


5/14/99  
27 MAY 2025 09:15  
R:\V\6-2025\0915\Proj\BR0090\_Pdy\_Typ.dgn  
R:\V\6-2025\0915\Proj\BR0090\_Pdy\_Typ.dgn


| FINAL PAVEMENT SCHEDULE<br>4-25-2024 |   |
|--------------------------------------|---|
| C1                                   | PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.   |
| C2                                   | PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.   |
| C3                                   | PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.   |
| C4                                   | PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 110 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 1½" IN DEPTH.                                   |
| C5                                   | PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH.                                    |
| D1                                   | PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.  |
| D2                                   | PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 2½" IN DEPTH OR GREATER THAN 4" IN DEPTH. |
| E1                                   | PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.  |
| E2                                   | PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.         |
| R1                                   | SHOULDER BERM GUTTER.   |
| T                                    | EARTH MATERIAL.   |
| U                                    | EXISTING PAVEMENT.  |
| V1                                   | INCIDENTAL MILLING  |
| V2                                   | MILLING ASPHALT PAVEMENT, 1½" DEPTH   |
| W                                    | VARIABLE DEPTH ASPHALT PAVEMENT (SEE STANDARD WEDGING DETAIL SHEET No. 2A-2)  |

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




USE INSET A WITH TYPICAL SECTION NO. 2

- L- STA 15+06.25 TO STA 15+34.83 LT
- L- STA 15+06.25 TO STA 15+34.83 RT
- L- STA 17+73.17 TO STA 17+99.75 LT
- L- STA 17+73.17 TO STA 17+99.75 RT




USE TYPICAL SECTION NO. 1

- L- STA 12+15.00 TO STA 14+49.00
- L- STA 18+59.00 TO STA 20+95.00



USE TYPICAL SECTION NO. 2

- L- STA 14+49.00 TO STA 15+49.00 BEGIN BRIDGE
- L- STA 17+59.00 END BRIDGE TO STA 18+59.00



USE TYPICAL SECTION NO. 3

- L- STA 15+49.00 TO STA 17+59.00
- NOTE: SEE STRUCTURE PLANS FOR STRUCTURE CONSTRUCTION DETAILS.