

REVISIONS

TIP PROJECT: BR-0153

CONTRACT:

\\\\\\benesch.com\\benesch\\projects\\2024\\BR-0153\\PMP_01.dgn
User: benesch\\lcf

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING PLAN
BERTIE COUNTY

LOCATION: BRIDGE 24 ON NC 11 OVER CASHIE RIVER

TYPE OF WORK: PAVEMENT MARKINGS FOR BRIDGE REPLACEMENT

INDEX

| SHEET NO. | DESCRIPTION |
|-------------|--|
| PMP-1 | INDEX, ROADWAY STANDARD DRAWINGS, PAVEMENT MARKING SCHEDULE, GENERAL |
| PMP-2 | REVISED ROADWAY STANDARD DRAWINGS |
| PMP-3, 4, 5 | PAVEMENT MARKING DETAILS |

PAVEMENT MARKING SCHEDULE

| SYMBOL | DESCRIPTION |
|-----------------------------|----------------------|
| THERMOPLASTIC (6", 90 MILS) | |
| T20 | WHITE EDGELINE |
| T31 | YELLOW SINGLE CENTER |
| T32 | 10 FT. YELLOW SKIP |
| T33 | YELLOW DOUBLE CENTER |
| SNOWPLOWABLE DELINEATION | |
| ME | YELLOW & YELLOW |

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|----------|---|
| 1205.01 | PAVEMENT MARKINGS - LINE TYPES AND OFFSETS |
| 1205.02 | PAVEMENT MARKINGS - TWO LANE AND MULTILANE ROADWAYS |
| 1205.12 | PAVEMENT MARKINGS - BRIDGES |
| 1250.01 | RAISED PAVEMENT MARKERS - INSTALLATION SPACING |
| 1250D01 | RAISED PAVEMENT MARKERS - INSTALLATION SPACING |
| 1261.01 | GUARDRAIL AND BARRIER DELINEATORS |
| 1261.02 | GUARDRAIL & BARRIER DELINEATORS |
| 1262.01 | GUARDRAIL END DELINEATION |


GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

- A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

| ROAD NAME | MARKING | MARKER |
|-----------|---------------|--|
| NC 11 | THERMOPLASTIC | SNOWPLOWABLE DELINEATION (POLYCARBONATE H-SHAPED MARKERS) (ALTERNATE 1 OF 5) |

- B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS.

| | |
|---|-----------|
| TIP NO. | SHEET NO. |
| BR-0153 | PMP-1 |
| APPROVED: _____ | |
| DATE: _____ | |
| SEAL | |
|  | |
| DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED | |

Prepared In the Office of:
benesch NC FIRM LICENSE No: F-1320
8000 REGENCY PARKWAY, STE 175
CARY, NC 27518
(984) 275-2490

| | |
|--------------------|-------------------------|
| LAURA C FISHER, PE | PROJECT ENGINEER |
| STEVEN W COX, PE | PROJECT DESIGN ENGINEER |