
<i>CONTROL (DITCHES)</i>	<i>MATTING FOR EE</i>
--------------------------	-----------------------

DATE	FROM	TO	USE
12/1/2011	...	...	...

[illegible]

DATE	FROM	TO	
11/1/2011	11/1/2011	11/1/2011	11/1/2011

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	11+50	20+50	L.T.	2,501
5	-L-	24+00	35+50	L.T.	3,617
6	-L-	39+00	43+00	L.T.	1,164
6	-L-	44+00	46+00	L.T.	861
6	-L-	47+50	52+50	L.T.	1,441
4	-L-	17+00	18+50	R.T.	308
4	-L-	21+50	23+50	R.T.	810
5	-L-	27+50	28+00	R.T.	119
5	-L-	30+00	31+00	R.T.	252
5	-L-	34+50	38+00	R.T.	1,643
6	-L-	39+00	40+00	R.T.	238
6	-L-	41+50	46+00	R.T.	1,211
6	-L-	47+00	49+50	R.T.	1,045
6	-L-	51+00	52+00	R.T.	272
7	-L-	52+00	54+00	R.T.	611
7	-L-	55+00	56+00	R.T.	222
7	-L-	57+00	58+50	R.T.	389
7	-L-	60+00	62+00	R.T.	444
8	-L-	67+00	68+00	R.T.	139
			SUBTOTAL		17,287
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE				ENGINEER	17,713
				TOTAL	35,000
				SAY	35,000