Approximate quantities only. Borrow excavation, shoulder borrow, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJECT NUMBER	SHEET
R-5863	X-1A

Station	Uncl. Exc.	Embt
Y3	(cu. yd.)	(cu. yd.)
10+16.00	0	0
10+50.00	320	0
11+00.00	496	0
11+50.00	308	0
12+00.00	63	0
12+08.59	2	0

Station	Uncl. Exc.	Embt
L RT	(cu. yd.)	(cu. yd.)
10+30.00	0	0
10+50.00	5	0
11+00.00	27	0
11+50.00	15	21
12+00.00	0	44
12+50.00	0	43
13+00.00	0	50
13+50.00	1	55
14+00.00	2	60
14+50.00	2	72
15+00.00	1	73
15+50.00	1	64
16+00.00	0	59
16+50.00	0	77
17+00.00	1	85
17+50.00	1	112
18+00.00	19	173
18+50.00	39	193
19+00.00	51	183
19+50.00	64	126
20+00.00	73	44
20+50.00	167	7
21+00.00	323	1
21+50.00	579	0
22+00.00	991	0
22+50.00	1161	0
23+00.00	853	0
23+50.00	515	0
24+00.00	363	0
24+50.00	250	1
25+00.00	160	1
25+50.00	100	0
26+00.00	70	0
26+50.00	70	1
27+00.00	181	1
27+50.00	280	1
28+00.00	275	1
28+50.00	154	0
29+00.00	69	0
29+50.00	134	2
30+00.00	167	7
30+50.00	185	9
31+00.00	187	11

31+50.00	120	14
32+00.00	37	14
32+50.00	27	11
33+00.00	37	13
33+50.00	39	11
34+00.00	103	3
34+50.00	237	2
35+00.00	384	3
35+50.00	460	3
36+00.00	576	2
36+50.00	838	1
37+00.00	985	1
37+50.00	909	1
38+00.00	705	2
38+50.00	354	3
39+00.00	73	198

Station	Uncl. Exc.	Embt
L RT	(cu. yd.)	(cu. yd.)
42+00.00	0	0
42+50.00	65	283
43+00.00	129	166
43+50.00	89	54
44+00.00	130	13
44+50.00	269	0
45+00.00	349	0
45+50.00	417	3
46+00.00	483	2
46+50.00	443	0
47+00.00	527	0
47+50.00	828	0
48+00.00	726	1
48+50.00	314	3
49+00.00	70	5

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
49+00.00	0	0
49+50.00	110	336
50+00.00	147	395
50+50.00	96	459
51+00.00	72	587
51+50.00	41	720
52+00.00	88	708
52+50.00	88	615
53+00.00	29	513
53+50.00	0	443
54+00.00	0	310

Station	Uncl. Exc.	Embt
L RT	(cu. yd.)	(cu. yd.)
54+00.00	0	0
54+50.00	34	65
55+00.00	155	1
55+50.00	250	0
56+00.00	221	0
56+50.00	119	0
57+00.00	30	25
57+50.00	3	171
58+00.00	0	243
58+50.00	1	121
59+00.00	3	27
59+50.00	3	42
60+00.00	4	131
60+50.00	3	196
61+00.00	3	133
61+50.00	3	69
62+00.00	1	64

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
62+00.00	0	0
62+50.00	0	128
63+00.00	0	204
63+50.00	0	262
63+63.54	0	82

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
64+94.29	0	0
65+00.00	20	8
65+50.00	113	62
66+00.00	55	35
66+50.00	50	11
67+00.00	38	11
67+50.00	30	19
68+00.00	49	19
68+10.00	15	3

Station	Uncl. Exc.	Embt
L RT	(cu. yd.)	(cu. yd.)
68+10.00	0	0
68+50.00	0	0
69+00.00	7	15
69+50.00	10	12
70+00.00	15	7
70+50.00	13	6
71+00.00	10	4
71+50.00	10	5
72+00.00	9	11
72+50.00	18	7
72+65.00	7	0

Station	Uncl. Exc.	Embt
Y3A	(cu. yd.)	(cu. yd.)
10+16.18	0	0
10+25.00	0	39
10+50.00	1	108
10+75.00	9	52
10+85.00	3	0

Station	Uncl. Exc.	Embt
Y5	(cu. yd.)	(cu. yd.)
10+25.00	0	0
10+50.00	15	2
11+00.00	141	4
11+50.00	319	0
11+64.15	117	0

Station	Uncl. Exc.	Embt
Y6	(cu. yd.)	(cu. yd.)
10+13.07	0	0
10+50.00	17	0
11+00.00	43	0
11+49.01	40	0

Station	Uncl. Exc.	Embt
Y7	(cu. yd.)	(cu. yd.)
10+65.02	0	0
11+00.00	0	258
11+50.00	0	185
12+00.00	0	21
12+50.00	16	23
12+70.00	7	1

Station	Uncl. Exc.	Embt
Y8	(cu. yd.)	(cu. yd.)
10+19.73	0	0
10+50.00	14	0
11+00.00	23	0
11+50.00	23	0
12+00.00	12	0
12+50.00	12	0
13+00.00	25	0
13+50.00	20	0
14+00.00	17	0
14+50.00	18	1
15+00.00	8	1
15+10.00	0	0

Station	Uncl. Exc.	Embt
Dwy6	(cu. yd.)	(cu. yd.)
10+27.00	0	0
10+50.00	42	0
10+90.00	35	0

Station	Uncl. Exc.	Embt
Dwy7	(cu. yd.)	(cu. yd.)
10+27.00	0	0
10+50.00	87	0
11+00.00	113	0
11+10.00	4	0

Station	Uncl. Exc.	Embt
Dwy4	(cu. yd.)	(cu. yd.)
10+17.00	0	0
10+50.00	121	0
11+00.00	89	28
11+50.00	4	35
11+90.00	3	6

Station	Uncl. Exc.	Embt
Roundabout	(cu. yd.)	(cu. yd.)
10+00.00	0	0
10+50.00	5	270
11+00.00	0	401
11+50.00	110	269
12+00.00	403	99
12+50.00	383	45
12+95.31	163	27

Station	Uncl. Exc.	Embt
L LT	(cu. yd.)	(cu. yd.)
10+30.00	0	0
10+50.00	1	13
11+00.00	4	54
11+50.00	5	94
12+00.00	3	119
12+50.00	0	53
13+00.00	0	188
13+50.00	1	512
14+00.00	2	412
14+50.00	3	200
15+00.00	2	280
15+50.00	1	362
16+00.00	0	421
16+50.00	0	423
17+00.00	0	373
17+50.00	0	347
18+00.00	1	316
18+50.00	2	264
19+00.00	3	151
19+50.00	6	66
20+00.00	5	54
20+50.00	3	37
21+00.00	6	20
21+50.00	11	28
22+00.00	11	37

22+50.00	7	27
23+00.00	5	15
23+50.00	6	0
24+00.00	4	67
24+50.00	2	154
25+00.00	3	226
25+50.00	1	299
26+00.00	1	420
26+50.00	0	465
27+00.00	0	353
27+50.00	0	329
28+00.00	1	374
28+50.00	0	425
29+00.00	0	388
29+50.00	1	219
30+00.00	2	81
30+50.00	2	31
31+00.00	2	74
31+50.00	1	165
32+00.00	0	233
32+50.00	1	243
33+00.00	1	263
33+50.00	1	275
34+00.00	1	244
34+50.00	1	149
35+00.00	0	67
35+50.00	0	51
36+00.00	1	24
36+50.00	4	18
37+00.00	32	16
37+50.00	59	14
38+00.00	57	13
38+50.00	27	7
39+00.00	1	1

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
39+00.00	0	0
39+50.00	5	496
40+00.00	9	493
40+50.00	5	96
41+00.00	102	344
41+50.00	136	430
42+00.00	59	459