

Approximate quantities only. Borrow excavation, fine grading, clearing and grubbing, removal of existing pavement will be paid for at the lump sum price for "Grading".			STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS			PROJECT NUMBER		SHEET	
						R-5863		X-1B	
NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT			CROSS-SECTION SUMMARY						
Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt				
L LT	(cu. yd.)	(cu. yd.)	Dwy1	(cu. yd.)	(cu. yd.)				
42+00.00	0	0	10+00.00	0	0				
42+50.00	8	151	10+50.00	4	1				
43+00.00	0	120	11+00.00	4	62				
43+50.00	0	108	11+50.00	0	152				
44+00.00	0	123	11+64.16	0	52				
44+50.00	0	112	Station	Uncl. Exc.	Embt				
45+00.00	0	76	Dwy2	(cu. yd.)	(cu. yd.)				
45+50.00	2	50	11+30.00	0	0				
46+00.00	13	30	11+50.00	1	1				
46+50.00	29	13	12+00.00	2	96				
47+00.00	34	9	12+50.00	0	175				
47+50.00	17	49	12+65.24	0	49				
48+00.00	1	152	Station	Uncl. Exc.	Embt				
48+50.00	0	252	Y1	(cu. yd.)	(cu. yd.)				
49+00.00	0	286	14+10.00	0	0				
Station	Uncl. Exc.	Embt	14+50.00	39	1				
L LT	(cu. yd.)	(cu. yd.)	14+90.09	79	1				
54+00.00	0	0	Station	Uncl. Exc.	Embt				
54+50.00	0	38	Y2	(cu. yd.)	(cu. yd.)				
55+00.00	0	30	23+18.00	0	0				
55+50.00	64	16	23+50.00	50	0				
56+00.00	129	0	23+82.60	101	0				
56+50.00	126	0	Station	Uncl. Exc.	Embt				
57+00.00	79	0	Y4	(cu. yd.)	(cu. yd.)				
57+50.00	18	15	41+35.00	0	0				
58+00.00	3	38	41+50.00	5	6				
58+50.00	3	24	42+00.00	21	53				
59+00.00	0	10	42+50.00	6	87				
59+50.00	0	15	42+98.44	5	89				
60+00.00	0	20	Station	Uncl. Exc.	Embt				
60+50.00	0	31	L LT	(cu. yd.)	(cu. yd.)				
61+00.00	0	28	68+10.00	0	0				
62+00.00	0	43	68+50.00	9	7				
Station	Uncl. Exc.	Embt	69+00.00	10	9				
L LT	(cu. yd.)	(cu. yd.)	69+50.00	10	9				
68+10.00	0	0	70+00.00	11	7				
68+50.00	9	7	70+50.00	12	6				
69+00.00	10	9	71+00.00	11	8				
69+50.00	10	9	71+50.00	8	8				
70+00.00	11	7	72+00.00	6	4				
70+50.00	12	6	72+50.00	9	2				
71+00.00	11	8	72+65.00	2	0				
71+50.00	8	8							
72+00.00	6	4							
72+50.00	9	2							
72+65.00	2	0							