STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SIGNING PLAN

MOORE COUNTY
LOCATION: NC 24–27 (MONROE STREET) FROM WEST OF NC 22 TO US 15 /501 IN CARTHAGE

PROJECT REFERENCE NO. U-3628 SIGN-1 APPROVED: David / Siars 7/3/2025

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.

<u>TITLE</u>

901.50

ARROWS AND SHIELDS

904.10

ORIENTATION OF GROUND MOUNTED SIGNS


904.50

MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

		SUMMARY OF QUANTITIES		
ITEM NO.		ITEM DESCRIPTION	QUANTITY	UNIT
DESC. NO.	SECT. NO.			
4025000000	901	CONTRACTOR FURNISHED, TYPE D SIGN	68	S.F.
4025000000	901	CONTRACTOR FURNISHED, TYPE E SIGN	137	S.F.
4025000000	901	CONTRACTOR FURNISHED, TYPE F SIGN	105	S.F.
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	662	L.F.
4096000000	904	SIGN ERECTION, TYPE D	5	EA.
4102000000	904	SIGN ERECTION, TYPE E	18	EA.
4108000000	904	SIGN ERECTION, TYPE F	6	EA.
4116100000	904	SIGN ERECTION, RELOCATE SIGN TYPE E	4	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	22	EA.
4192000000	907	DISPOSAL OF SUPPORT, U-CHANNEL	4	EA.
4238000000	907	DISPOSAL OF SIGN, D, E OR F	1	EA.

PLAN PREPARED FOR: N.C.D.O.T. DIVISION 8

Gregory S. Davis, PE DIVISION 8 UTILITY ENGINEER



GENERAL NOTES

- . SIGNS FURNISHED BY CONTRACTOR.
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON $^{\prime\prime}$ U $^{\prime\prime}$ CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.
- . PAVEMENT MARKING DESIGN DONE BY OTHERS.

INDEX

SHEET NO. DESCRIPTION SIGN-1 TITLE SHEET E AND F SHEET SIGN-2 SIGN DESIGNS SIGN-3-3A SIGN-4-11A SIGNING PLAN SHEETS

PLAN PREPARED BY: RK&K

David Sears, PE, PTOE Project Manager Allen Tutt Project Designer RKK 8601 Six Forks Road, Forum 1, Suite 700

www.rkk.com

Raleigh, North Carolina 27615-3960 NC License No. F-0112 Engineers | Construction Managers | Planners | Scientists

Responsive People | Creative Solutions