| PROJECT REFERENCE NO. | SHEET NO. |
|---|---|
| U-3628 | SIGN-2 |

APPROVED: DocuSigned by: David T Sears 069183F28E574E...

DATE: 7/3/2025

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 044558 ENGINEER DAVID T. SEARS

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

(401) QUANTITY REQ'D 1

24" X 30"
R5-2B

ONE "U" POST

(402) QUANTITY REQ'D 11

36" X 36"
R1-1

ONE "U" POST PER SIGN

(403) QUANTITY REQ'D 1

30" X 30"
W14-1

ONE "U" POST

(404) QUANTITY REQ'D 2

24" X 30"
R2-1

ONE "U" POST PER SIGN

(405) QUANTITY REQ'D 1

30" X 30"
W11-1

ONE "U" POST

(406) QUANTITY REQ'D 1

18" X 12"
W16-1P

MOUNT BELOW SIGN-405
IN ONE INSTALLATION

(407) QUANTITY REQ'D 1

36" X 36" X 36"
R1-2

ONE "U" POST

(501)

M3-4
24" X 12"

M1-5
24" X 24"

M1-5
24" X 24"

M6-3
21" X 15"

M3-3
24" X 12"

M1-5
24" X 24"

M6-1
21" X 15"

EXISTING
LIBRARY/ARROW
SIGNS TO BE
REMOUNTED
HERE

TWO "U" POSTS

(502)

M2-1
21" X 15"

M1-4
24" X 24"

M1-4
30" X 24"

ONE "U" POST

(503)

M3-1
24" X 12"

M1-4
24" X 24"

M1-4
30" X 24"

M6-3
21" X 15"




M3-3
24" X 12"

M1-4
24" X 24"

M1-4
30" X 24"

M6-1
21" X 15"

TWO "U" POSTS

(504)

M3-2
24" X 12"

M1-5
24" X 24"

M1-5
24" X 24"

M6-3
21" X 15"

MOUNT BELOW SIGN-303

(505)

M3-2
24" X 12"

M1-5
24" X 24"

M1-5
24" X 24"

M6-1
21" X 15"

M3-4
24" X 12"

M1-5
24" X 24"

M1-5
24" X 24"

M6-1
21" X 15"

TWO "U" POSTS

(506)

M2-1
21" X 15"

M1-5
24" X 24"

M1-5
24" X 24"

ONE "U" POST


RK&K
P: (919) 878-9560
8601 Six Forks Road, Forum 1,Suite 700
Raleigh, North Carolina 27615-3960
NC License No. F-0112
Engineers | Construction Managers | Planners | Scientists
www.rkk.com
Responsive People | Creative Solutions


06/26/25
U-3628_SGN_E_F_PSH02.dgn

# TYPE "E" & "F" SIGNS