

MAXTIME ALTERNATE PHASING ACTIVATION DETAIL

FLASHER CIRCUIT MODIFICATION DETAIL

1. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-4 AND TERMINATE ON T2-2.
2. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-5 AND TERMINATE ON T2-3.
3. REMOVE FLASHER UNIT 2.

<u>PHASING</u>	<u>OVERLAP PLAN</u>	<u>VEH DET PLAN</u>
ACTIVE PLAN REQUIRED TO <u>RUN DEFAULT PHASING</u>	1	1
ACTIVE PLAN REQUIRED TO <u>RUN ALTERNATE PHASING</u>	2	2

Disables phase 4 call on loop 7A and reduces delay time for phase 7 call on loop 7A to 3 seconds.

All Red Flash Exit Time
6



VHB Engineering NC, P.C. (C-3705)
 940 Main Campus Drive, Suite 500
 Raleigh, NC 27606
 919.829.0328

SEAL

NORTH CAROLINA
PROFESSIONAL
SEAL
033108
ENGINEER
JIANXIN MA

DocuSigned by:
Jianxin Ma
90767430384447

7/10/2025

SIGNATURE DATE

SIG. INVENTORY NO. 09-0367

SIG. INVENTORY NO. 09-0367