

PROJECT: 48647 REFERENCE: U-6187

SEE SHEET 3 FOR PLAN SHEET LAYOUT
AT TIME OF INVESTIGATION

CONTENTS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND (SOIL AND ROCK)
3	ROADWAY TITLE SHEET
4-12	PLAN SHEETS
13-16	PAVEMENT DATA SHEETS
17-32	DCP RAW DATA LOGS
33-42	PAVEMENT CORE PHOTOS

APPENDIX A

<u>TITLE</u>	<u>SHEETS</u>
SOIL TEST RESULTS	43-54

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

ROADWAY
SUBSURFACE INVESTIGATION

COUNTY DAVIE
PROJECT DESCRIPTION CONSTRUCT 2-LANE EXTENSION
OF SR 1630 (BALTIMORE ROAD) ON NEW LOCATION
FROM SOUTH OF US 158 TO I-40
PAVEMENT & SUBGRADE INVESTIGATION

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	U-6187	1	

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO PERFORM INDEPENDENT SUBSURFACE INVESTIGATIONS AND MAKE INTERPRETATIONS AS NECESSARY TO CONFIRM CONDITIONS ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

Q. HILL

CG2 EXPLORATION

R. MAFFIA


INVESTIGATED BY J. CRENSHAW

DRAWN BY Q. HILL


CHECKED BY J. CRENSHAW

SUBMITTED BY SCHNABEL ENG.

DATE APRIL 2024



Schnabel
ENGINEERING



DocuSigned by:

Jared Crenshaw

06/19/2024

F325B40D4C25483

SIGNATURE

DATE


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

09/08/99

TIP PROJECT: U-6187

CONTRACT: TBD

See Sheet 1A For Index of Sheets
See Sheet 1B For Conventional Plan Sheet Symbols



VICINITY MAP (NTS)

DESIGN RECOMMENDATION PLANS

(PLANS DEVELOPED USING
OPENROADS DESIGNER)


STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

DAVIE COUNTY

LOCATION: *REALIGNMENT AND EXTENSION OF SR 1630
(BALTIMORE ROAD) FROM SOUTH OF US 158
TO A NEW INTERCHANGE AT I-40*

TYPE OF WORK: *GRADING, PAVING, DRAINAGE, AND STRUCTURES*

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	U-6187	3	
STATE PROJ. NO.	F. A. PROJ. NO.	DESCRIPTION	
48647.1.1		PE	



BEGIN TIP PROJECT U-6187
-L- STA. 10+30.00

END TIP PROJECT U-6187
-L- STA. 72+80.54

END PROP. BRIDGE
-L- STA. 72+09 ±


PROPOSED BRIDGE

END CONSTRUCTION
-Y2- STA. 54+04.08 LT

THIS PROJECT IS NOT WITHIN A MUNICIPAL BOUNDARY.
THIS IS A CONTROL OF ACCESS PROJECT WITH ACCESS TO I-40 BEING LIMITED TO INTERCHANGES.
CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

DENOTES PROPOSED TRAFFIC SIGNAL

GRAPHIC SCALES



DESIGN DATA

ADT 2025 = 8,100
ADT 2045 = 21,200
K = 10 %
D = 55 %
T = 8 % *
V = 60 MPH
* TTST = 6% DUAL 2%
FUNC CLASS =
MAJOR COLLECTOR
STATE WIDE TIER

PROJECT LENGTH

PROJECT LENGTHS FOR TIP PROJECT U-6187:
LENGTH ROADWAY TIP PROJECT U-6187 = 1.139 MILES
LENGTH STRUCTURES TIP PROJECT U-6187 = 0.045 MILES
TOTAL LENGTH TIP PROJECT U-6187 = 1.184 MILES

NCDOT Contact: RYAN C. NEWCOMB, PE
Prepared in the Office of:



2024 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
JUNE 30, 2024

LETTING DATE:
JUNE 17, 2025

JONATHAN P. SOIKA, P.E.
PROJECT ENGINEER

JERRY B. JAVELLANA, P.E.
PROJECT DESIGN ENGINEER

HYDRAULICS ENGINEER

SIGNATURE: _____
ROADWAY DESIGN ENGINEER

SIGNATURE: _____
P.E.





-NONE- START 0+00.00

L_PC_1300_WB_LN		L_PC_1300_EB_LN	
PAVEMENT STRUCTURE		PAVEMENT STRUCTURE	
ASPHALT	8.5"	ASPHALT	10.0"
ABC	10.0"	ABC	12.0"

-NONE- PC 10+76.70

-NONE- N90°00'00.0"E

N69°55'21.1"E

Y4- START 10+00.00
= -L- POT 19+10.82

-Y4- PC 10+01.32

Y4_PC_1370_EB_LN	
PAVEMENT STRUCTURE	
ASPHALT	6.25"
ABC	14.75"

Y4_PC_1370_EB_LN

-Y4- PT 12+68.16

-Y4- -Y4
N01°58'12.9"E

MATCH LINE -L- STA 24+00.00 SEE SHEET 05

FOR -L- PROFILE SEE SHEET 13
FOR -Y4- PROFILE SEE SHEET 19

2RD104

NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DAVIE COUNTY

ROADWAY DESIGN UNIT
ROADWAY DESIGN
ENGINEER

HYDRAULICS
ENGINEER

PREPARED BY

vhb Engineering, Inc. P.C. (C-3705)
340 Main Campus Drive, Suite 500
Raleigh, NC 27605



2R01	05
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DAVIE COUNTY	
	
ROADWAY DESIGN UNIT ROADWAY DESIGN ENGINEER	
HYDRAULICS ENGINEER	
PREPARED BY  vhb VHB Engineering, Inc. P.C. (C-3705) 940 Main Campus Drive, Suite 500 Raleigh, NC 27605	

MATCH LINE -L- STA 38+00.00 SEE SHEET 05



FOR -L- PROFILE SEE SHEET 14

MATCH LINE -L- STA 52+00.00 SEE SHEET 07

U-6187	
2RD1	06
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DAVIE COUNTY	
	
ROADWAY DESIGN UNIT ROADWAY DESIGN ENGINEER	
HYDRAULICS ENGINEER	
PREPARED BY  vhb Engineering, Inc. P.C. (C-3705) 940 Main Campus Drive, Suite 500 Raleigh, NC 27606	



FOR -L- PROFILE SEE SHEETS 14 & 15

U-6187	
2RD1	07
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DAVIE COUNTY	
	
ROADWAY DESIGN UNIT ROADWAY DESIGN ENGINEER	
HYDRAULICS ENGINEER	
PREPARED BY	
 vhb Engineering, Inc. P.L.L.C. (C-3705) 940 Main Campus Drive, Suite 500 Raleigh, NC 27606	



FOR -Y1- PROFILE SEE SHEET 16

MATCH LINE -Y2- STA 27+00.00 SEE SHEET 11



MATCH LINE -Y2- STA 54+50.00 SEE SHEET 12

U-6187
2RDI 08

NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DAVIE COUNTY

ROADWAY DESIGN UNIT
ROADWAY DESIGN
ENGINEER

HYDRAULICS
ENGINEER

PREPARED BY

vhb
VHB Engineering, Inc. P.C. (C-3705)
940 Main Campus Drive, Suite 500
Raleigh, NC 27605

FOR -L- PROFILE SEE SHEET 15
FOR -LPB- PROFILE SEE SHEET 20
FOR -RPB- PROFILE SEE SHEET 21
FOR -RPC- PROFILE SEE SHEET 22
FOR -RPD- PROFILE SEE SHEET 23
FOR -Y2- EXISTING PROFILE SEE SHEETS 17 & 18

MATCH LINE -L- STA 63+75.00 SEE SHEET 07

MATCH LINE -Y1- STA 30+00.00 SEE SHEET 05



Y1_PC_3350_WB WDNG		Y1_PC_3350_CENTER LTL		Y1_PC_3350_EB LN WDNG	
PAVEMENT STRUCTURE		PAVEMENT STRUCTURE		PAVEMENT STRUCTURE	
ASPHALT	14.0"	ASPHALT	9.0"	ASPHALT	14.0"
		CONCRETE	7.5"		

FOR -Y1- PROFILE SEE SHEET 16

2R0110

NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DAVIE COUNTY

ROADWAY DESIGN UNIT
ROADWAY DESIGN
ENGINEER

HYDRAULICS
ENGINEER

PREPARED BY

vhb
VHB Engineering, Inc. P.C. (C-3705)
340 Main Campus Drive, Suite 500
Raleigh, NC 27605



FOR -Y2- EXISTING PROFILE SEE SHEET 17

MATCH LINE -Y2- STA 27+00.00 SEE SHEET 08

2R01

11

NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DAVIE COUNTY



ROADWAY DESIGN UNIT
ROADWAY DESIGN
ENGINEER

HYDRAULICS
ENGINEER

PREPARED BY



vhb
VHB Engineering, Inc. P.C. (C-3705)
340 Main Campus Drive, Suite 500
Raleigh, NC 27605

MATCH LINE -Y2- STA 54+50.00 SEE SHEET 08



FOR -Y2- EXISTING PROFILE SEE SHEET 18
FOR -RPD- PROFILE SEE SHEET 23

2RD1	12
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DAVIE COUNTY	
	
ROADWAY DESIGN UNIT ROADWAY DESIGN ENGINEER	
HYDRAULICS ENGINEER	
PREPARED BY  VHB Engineering, Inc. P.C. (C-3705) 340 Main Campus Drive, Suite 500 Raleigh, NC 27605	

PAVEMENT INVESTIGATION DATA SHEET

Project: 48647.1.1
TIP: U-6187

Route: SR 1630 (Baltimore Road)
County: Davie

Date: 02/23/24
Notes By: Q. Hill

Position (Sta., Lane, Shldr.)	Cut/Fill (Est. of Amount)	Width		Thickness								Subgrade					Asphalt Notes	State Plane Coordinates	
		Lane(s)	Shoulder(s)	Offset Distance (See Notes)	Crown "C" or Super "S"	Gross to Top of Soil	Asphalt	Concrete	ABC	Stabilized Subgrade Soil	Pavement Layering	Description	Sample Number	AASHTO Classification	Soil Moisture	Probe Depth		Northing	Easting
-L- STA 13+00																			
L_PC_1300_EB LN	FILL ± 0.5'	EB LN 11'	EB OSS 0.75'	4.5' FW	C	22.0"	10"	-	12.0"	-	Asphalt Concrete ABC	RE: Tan, brown, sandy SILT (1.3' - 1.9') RES: Reddish-brown, silty CLAY (1.9' - 5.0')	S-29	A-4 (1) A-6	9% M	5.0'	Moderate alligator cracking in vicinity	817,129	1,567,872
L_PC_1300_WB LN	AT GRADE ± 0.0'	WB LN 11'	WB OSS 1.5'	4.5' FW	C	18.5"	8.5"	-	10.0"	-	Asphalt ABC	RES: Brown, orange, CLAY, micaceous (1.5' - 5.0')	-	A-7	M	5.0'	Moderate alligator cracking in vicinity	817,127	1,567,862
-Y1- STA 14+00																			
Y1_PC_1100_WB LN WDNG	AT GRADE ± 0.0'	EBL 11'	WB OSS 2.5'	2.0' FW	S	23.5"	15.5"	8.0"	-	-	Asphalt Concrete	RES: Orange, silty CLAY (2.0' - 5.0')	S-27	A-7-5 (27)	32%	5.0'	No pavement distress observed	818,453	1,566,099
-Y1- STA 19+00																			
Y1_PC_1900_EB PS	CUT ± 2.0'	EBL 11'	EB OSS 1.5'	0.5' FW	C	17.0"	12.0"	-	5.0"	-	Asphalt ABC	RES: Orange, silty CLAY (1.4' - 5.0')	S-25	A-7-6 (19)	30%	5.0'	No pavement distress observed	818,628	1,566,871
Y1_PC_1900_EB LN	CUT ± 2.0'	EBL 11'	EB OSS 1.5'	5.5' FW	C	16.0"	8.0"	8.0"	-	-	Asphalt Concrete	RES: Brown, orange, sandy CLAY (1.4' - 5.0')	S-24	A-7-6 (13)	27%	5.0'	No pavement distress observed	818,635	1,566,871
Y1_PC_1900_WB LN	FILL ±1.0'	WBL 11'	WB OSS 1.5'	4.0' FW	C	17.5"	9.5"	8.0"	-	-	Asphalt Concrete	RES: Orange, silty CLAY (1.3' - 5.0')	-	A-7-6	M	5.0'	No pavement distress observed	818,649	1,566,868
-Y1- STA 28+50																			
Y12850HA	FILL ± 1.0'	-	-	20.0' LT	S	-	-	-	-	-	-	TOPSOIL (0.0' - 0.2') R.E.: Orange, brown, silty CLAY little fine to medium sand, little gravel (0.2' - 6.0')	BS-13	- A-7-6	26%	6.0'	No pavement distress observed	818,893	1,567,795

Notes:
 OSL = Outside Lane CTL = Center Turn Lane OSS = Outside Shoulder PS = Paved Shoulder RT = Right NB = Northbound
 ISL = Inside Lane RTL = Right Turn Lane ISS = Inside Shoulder RT LN = Right Lane LT = Left SB = Southbound
 CL = Center Lane DECEL = Deceleration Lane GM = Grass Median LT LN = Left Lane (I) = Inside FW = From White
 LTL = Left Turn Lane ACCEL = Acceleration Lane OGS = Outside Grass Shoulder COL = Collector Lane (O) = Outside FY = From Yellow

PAVEMENT INVESTIGATION DATA SHEET

Page 14

Project: 48647.1.1
TIP: U-6187

Route: SR 1630 (Baltimore Road)
County: Davie

Date: 02/23/24
Notes By: Q. Hill

Position (Sta., Lane, Shldr.)		Width		Thickness							Subgrade					State Plane Coordinates			
	Cut/Fill (Est. of Amount)	Lane(s)	Shoulder(s)	Offset Distance (See Notes)	Crown "C" or Super "S"	Gross to Top of Soil	Asphalt	Concrete	ABC	Stabilized Subgrade Soil	Pavement Layering	Description	Sample Number	AASHTO Classification	Soil Moisture	Probe Depth	Asphalt Notes	Northing	Easting
-Y1- STA 33+50																			
Y1_PC_3350_EB LN WDNG	FILL ± 1.0'	EBL 12.5'	EB OSS 1.5'	2.5' FW	C	14.0"	14.0"	-	-	-	Asphalt	R.E.: Brown, sandy CLAY, some silt (1.2' - 2.0') RES: Brown, sandy SILT (2.0' - 5.0')	- S-23	A-6 A-4 (2)	M 18%	5.0'	No pavement distress observed	819,073	1,568,275
Y1_PC_3350_CENTER LTL	AT GRADE ± 0.0'	LTL 11.5'	-	6.5' FW	C	16.5"	9.0"	7.5"	-	-	Asphalt Concrete	R.E.: Brown, sandy CLAY, some silt (1.4' - 2.5') RES: Orange, brown, sandy CLAY (2.5' - 5.0')	S-22 -	A-6 (4) A-6	15% M	5.0'	No pavement distress observed	819,085	1,568,265
Y1_PC_3350_WB WDNG	FILL ± 1.0'	WBL 12.0'	WB OSS 1.5'	2.5' FW	C	14.0"	14.0"	-	-	-	Asphalt	R.E.: Brown, sandy CLAY (1.2' - 1.9') RES: Orange, brown, sandy SILT (1.9' - 5.0')	- S-21	A-6 A-4 (2)	M 20%	5.0'	No pavement distress observed	819,100	1,568,257
-Y2- STA 30+00																			
Y2_PC_3000_EB ISS	AT GRADE ± 0.0'	ISL 12.0'	ISS 10.0'	5.5' FY	S	18.0"	18.0"	-	-	-	Asphalt	RES: Orange, brown, silty CLAY, micaceous (1.5' - 5.0')	-	A-6	M	5.0'	No pavement distress observed	822,146	1,566,054
Y2_PC_3000_EB OSL	AT GRADE ± 0.0'	OSL 13.0'	OSS 10.0'	5.5' FW	S	19.0"	6.0"	8.0"	5.0"	-	Asphalt Concrete ABC	RES: Orange, brown, clayey SILT, micaceous (1.6' - 5.0')	-	A-5	M	5.0'	No pavement distress observed	822,124	1,566,066
Y2_PC_3000_EB OSS	CUT ± 2.0'	OSL 13.0'	OSS 10.0'	6.0' FW	S	18.0"	18.0"	-	-	-	Asphalt	RES: Orange, brown, clayey SILT, micaceous (1.5' - 5.0')	-	A-5	M	5.0'	No pavement distress observed	822,112	1,566,070
-Y2- STA 35+00																			
Y2_PC_3500_EB ISS	AT GRADE ± 0.0'	ISL 12.0'	ISS 10.0'	5.5' FY	S	20.5"	17.0"	-	3.5"	-	Asphalt ABC	R.E.: Orange, brown, silty CLAY, micaceous (1.4' - 5.0')	-	A-6	M	5.0'	No pavement distress observed	822,311	1,566,531
Y2_PC_3500_EB OSS	AT GRADE ± 0.0'	OSL 12.5'	OSS 10.0'	6.0' FW	S	17.5"	17.5"	-	-	-	Asphalt	R.E.: Orange, silty CLAY, micaceous (1.5' - 5.0')	S-15	A-7-5 (15)	30%	5.0'	No pavement distress observed	822,279	1,566,540
-Y2- STA 40+00																			
Y2_AP_4000_EB GM	AT GRADE ± 0.0'	ISL 12.0'	ISS 10.5'	13.0' FY	S	-	-	-	-	-	-	TOPSOIL (0.0' - 0.25') RES: Orange, brown, CLAY (0.25' - 8.5') RES: Orange, clayey SILT, micaceous (8.5' - 10.0')	- SS-1015 -	- A-7-5 (25) A-5	M 26%	10.0'	No pavement distress observed	822,485	1,566,986
Y2_AP_4000_EB ISS	AT GRADE ± 0.0'	ISL 12.0'	ISS 10.5'	6.5' FY	S	18.0"	15.0"	-	3"	-	Asphalt ABC	RES: Reddish-brown, silty CLAY, micaceous (1.5' - 8.5") RES: Orange, SILT, micaceous, contains manganese oxide (8.5' - 10.0')	SS-523 -	A-7-6 (16) A-5	16% M	10.0'	No pavement distress observed	822,477	1,566,989
-Y2- STA 45+00																			
Y2_AP_4500_EB OGS	AT GRADE ± 0.0'	OSS 12.5'	OSS 10.0'	14.0' FW	S	-	-	-	-	-	Topsoil	TOPSOIL (0.0' - 0.8') R.E.: Orange, silty and sandy CLAY, micaceous (0.8' - 10.0')	SS-1010 SS-1011	- A-7-6 (20)(4)	M 32% 21%	10.0'	No pavement distress observed	822,590	1,567,479
-Y2- STA 50+00																			
Y2_AP_5000_EB GM	AT GRADE ± 0.0'	ISL 12.0'	ISS 10.5'	12.0' FY	S	-	-	-	-	-	Topsoil	TOPSOIL (0.0' - 0.3') RES: Orange, brown, clayey SILT (0.3' - 3.0') RES: Reddish brown, silty CLAY (3.0' - 10.0')	-	- A-5 A-7	M	10.0'	No pavement distress observed	822,816	1,567,929
Y2_AP_5000_EB ISS	AT GRADE ± 0.0'	ISL 12.0'	ISS 10.5'	6.5' FY	S	24.0"	18.0"	-	6.0"	-	Asphalt ABC	RES: Orange, brown, silty CLAY, trace sand, micaceous (2.0' - 10.0')	SS-519	A-7-5 (13)	21%	10.0'	No pavement distress observed	822,807	1,567,933

Notes:

OSL = Outside Lane
ISL = Inside Lane
CL = Center Lane
LTL = Left Turn Lane

CTL = Center Turn Lane
RTL = Right Turn Lane
DECEL = Deceleration Lane
ACCEL = Acceleration Lane

OSS = Outside Shoulder
ISS = Inside Shoulder
GM = Grass Median
OGS = Outside Grass Shoulder

PS = Paved Shoulder
RT LN = Right Lane
LT LN = Left Lane
COL = Collector Lane

RT = Right
LT = Left
(I) = Inside
(O) = Outside

NB = Northbound
SB = Southbound
FW = From White
FY = From Yellow

PAVEMENT INVESTIGATION DATA SHEET

Page 15

Project: 48647.1.1
TIP: U-6187

Route: SR 1630 (Baltimore Road)
County: Davie

Date: 02/23/24
Notes By: Q. Hill

		Width		Thickness							Subgrade					State Plane Coordinates			
Position (Sta., Lane, Shldr.)	Cut/Fill (Est. of Amount)	Lane(s)	Shoulder(s)	Offset Distance (See Notes)	Crown "C" or Super "S"	Gross to Top of Soil	Asphalt	Concrete	ABC	Stabilized Subgrade Soil	Pavement Layering	Description	Sample Number	AASHTO Classification	Soil Moisture	Probe Depth	Asphalt Notes	Northing	Easting
-Y2- STA 55+00																			
Y2_AP_5500_EB_ISS	AT GRADE ± 0.0'	ISL 11.5'	ISS 10.5'	6.0' FY	S	18.0"	18.0"	-	-	-	Asphalt	RES: Orange and tan, silty CLAY, micaceous, contains manganese oxide (1.5' - 10.0')	BS-07 SS-1022	A-7-5 (25) (13)	37% 29%	10.0'	No pavement distress observed	822,970	1,568,405
-Y2- STA 60+00																			
Y2_AP_6000_EB_ISS	AT GRADE ± 0.0'	ISL 12.0'	ISS 10.5'	5.5' FY	S	18.0"	18.0"	-	-	-	Asphalt	RES: Orange, tan, and black, clayey SILT, micaceous, contains manganese oxide (1.5' - 10.0')	-	A-5	M	10.0'	No pavement distress observed	823,121	1,568,881
-Y2- STA 64+00																			
Y2_PC_6400_EB ISS	AT GRADE ± 0.0'	ISL 11.5'	ISS 14'	6.0' FY	S	17.0"	17.0"	-	-	-	Asphalt	RES: Orange, brown, clayey SILT, micaceous (1.4' - 5.0')	-	A-5	M	5.0'	No pavement distress observed	823,238	1,569,261
Y2_PC_6400_EB OSL	AT GRADE ± 0.0'	OSL 11.25'	OSS 15.5'	4.5' FW	S	22.0"	22.0"	-	-	-	Asphalt	RES: Orange, silty CLAY, little fine to medium sand (1.8' - 5.0')	-	A-7-6	M	5.0'	No pavement distress observed	823,199	1,569,272
Y2_PC_6400_EB OSS	AT GRADE ± 0.0'	OSL 11.25'	OSS 15.5'	7.0' FW	S	21.25"	9.25"	-	12.0"	-	Asphalt ABC	RES: Orange, silty CLAY (1.8' - 5.0')	S-17	A-7-6 (19)	27%	5.0'	No pavement distress observed	823,186	1,569,274
-Y2- STA 20+00																			
Y2_PC_2000_WB ISS	AT GRADE ± 0.0'	ISL 12.0'	ISS 11.0'	5.5' FY	S	18.0"	18.0"	-	-	-	Asphalt	RES: Brown, orange, CLAY, some fine to medium sand (1.5' - 5.0')	S-12	A-7-6 (10)	25%	5.0'	No pavement distress observed	821,855	1,565,079
Y2_PC_2000_WB OSS	AT GRADE ± 0.0'	OSL 12.0'	OSS 11.0'	6.0' FW	S	19.5"	19.5"	-	-	-	Asphalt	RES: Brown, orange, silty CLAY (1.6' - 5.0')	S-06	A-7-5 (48)	54%	5.0'	No pavement distress observed	821,899	1,565,076
-Y2- STA 25+00																			
Y2_AP_2500_WB_GM	AT GRADE ± 0.0'	ISL 11.5'	ISS 11.0'	14.0' FY	S	-	-	-	-	-	-	TOPSOIL (0.0' - 0.25') RES: Brown, orange, SILT, micaceous (0.25' - 6.0') RES: Brown, tan, orange, clayey SILT, contains manganese oxide (6.0' - 10.0')	BS-03	- A-4 A-5	29%	10.0'	No pavement distress observed	822,009	1,565,563
Y2_PC_2500_WB ISS	AT GRADE ± 0.0'	ISL 11.5'	ISS 11.0'	6.5' FY	S	17.25"	17.25"	-	-	-	Asphalt	RES: Reddish brown, clayey SILT (1.4' - 5.0')	-	A-5	M	5.0'	No pavement distress observed	822,025	1,565,560
Y2_PC_2500_WB OSL	FILL ± 0.5'	ISL 11.5'	OSS 11.0'	3.0' FW	S	21.0"	6.0"	8.0"	7.0"	-	Asphalt Concrete ABC	RES: Brown, orange, silty CLAY, micaceous (1.8' - 5.0')	S-04	A-7-5 (28)	31%	5.0'	No pavement distress observed	822,045	1,565,553
Y2_PC_2500_WB OSS	FILL ± 1.0'	OSL 12.0'	OSS 11.0'	6.0' FW	S	18.0"	18.0"	-	-	-	Asphalt	RES: Brown, orange, silty CLAY, micaceous (1.5' - 5.0')	-	A-7-5	M	5.0'	No pavement distress observed	822,063	1,565,548
-Y2- STA 30+00																			
Y2_AP_3000_WB_GM	AT GRADE ± 0.0'	ISL 12.0'	ISS 11.0'	13.5' FY	S	-	-	-	-	-	-	TOPSOIL (0.0' - 0.3') R.E.: Brown, orange, silty CLAY, micaceous (0.3' - 10.0')	SS-9006	- A-7-5 (15)	M 33%	10.0'	No pavement distress observed	822,170	1,566,037
Y2_PC_3000_WB ISS	AT GRADE ± 0.0'	ISL 12.0'	ISS 11.0'	5.5' FY	S	18.0"	18.0"	-	-	-	Asphalt	R.E.: Brown, orange, silty CLAY (1.5' - 5.0')	S-10	A-7-5 (19)	31%	5.0'	No pavement distress observed	822,186	1,566,036
Y2_PC_3000_WB OSS	AT GRADE ± 0.0'	OSL 12.0'	OSS 11.0'	5.5' FW	S	17.0"	17.0"	-	-	-	Asphalt	R.E.: Brown, orange, clayey SILT, micaceous (1.4' - 5.0')	-	A-5	M	5.0'	No pavement distress observed	822,228	1,566,030
-Y2- STA 35+00																			
Y2_AP_3500_WB OGS	AT GRADE ± 0.0'	OSL 11.5'	OSS 11.5'	12.0' FW	S	-	-	-	-	-	-	TOPSOIL (0.0' - 0.3') R.E.: Brown, orange, silty CLAY (0.3' - 5.0') R.E.: Brown, orange, red, silty SAND, with clay lenses, trace rock fragments and manganese oxide (5.0' - 10.0')	BS-01	A-7-5 (4) A-2-4	27%	10.0'	No pavement distress observed	822,392	1,566,489

Notes:

OSL = Outside Lane
ISL = Inside Lane
CL = Center Lane
LTL = Left Turn Lane
CTL = Center Turn Lane
RTL = Right Turn Lane
DECEL = Deceleration Lane
ACCEL = Acceleration Lane
OSS = Outside Shoulder
ISS = Inside Shoulder
GM = Grass Median
OGS = Outside Grass Shoulder
PS = Paved Shoulder
RT LN = Right Lane
LT LN = Left Lane
COL = Collector Lane
RT = Right
LT = Left
(I) = Inside
(O) = Outside
NB = Northbound
SB = Southbound
FW = From White
FY = From Yellow

PAVEMENT INVESTIGATION DATA SHEET

Project: 48647.1.1
TIP: U-6187

Route: SR 1630 (Baltimore Road)
County: Davie

Date: 02/23/24
Notes By: Q. Hill

		Width		Thickness								Subgrade					State Plane Coordinates		
Position (Sta., Lane, Shldr.)	Cut/Fill (Est. of Amount)	Lane(s)	Shoulder(s)	Offset Distance (See Notes)	Crown "C" or Super "S"	Gross to Top of Soil	Asphalt	Concrete	ABC	Stabilized Subgrade Soil	Pavement Layering	Description	Sample Number	AASHTO Classification	Soil Moisture	Probe Depth	Asphalt Notes	Northing	Easting
-Y2- STA 45+00																			
Y2_PC_4500_WB ISS	AT GRADE ± 0.0'	ISL 11.5'	ISS 11.0'	5.5' FY	S	17.25"	17.25"	-	-	-	Asphalt	RES: Brown, orange, silty CLAY, micaceous (1.4' - 5.0')	-	A-7-5	M	5.0'	No pavement distress observed	822,685	1,567,462
Y2_PC_4500_WB ISL	AT GRADE ± 0.0'	ISL 11.5'	ISS 11.0'	3.5' FY	S	21.0"	6.5"	7.75"	6.75"	-	Asphalt Concrete ABC	RES: Brown, orange, silty CLAY (1.8' - 5.0')	S-08	A-7-5 (13)	31%	5.0'	No pavement distress observed	822,699	1,567,462
Y2_PC_4500_WB OSS	AT GRADE ± 0.0'	OSL 11.5'	OSS 12.0'	7.0' FW	S	13.25"	13.25"	-	-	-	Asphalt	RES: Brown, silty CLAY (1.5' - 5.0')	S-02	A-7-5 (17)	40%	5.0'	Previous pavement core patches observed, asphalt otherwise observed to be in good condition	822,723	1,567,452
-Y2- STA 50+00																			
Y2_PC_5000_WB ISS	AT GRADE ± 0.0'	ISL 11.5'	ISS 11.0'	6.0 FY	S	17.75"	17.75"	-	-	-	Asphalt	RES: Reddish-brown, CLAY (1.5' - 5.0')	S-07	A-7-6 (23)	24%	5.0'	No pavement distress observed	822,856	1,567,937
Y2_PC_5000_WB OSS	FILL ± 1.0'	OSL 11.0'	OSS 11.5'	6.5' FW	S	18.0"	18.0"	-	-	-	Asphalt	RES: Reddish-brown, silty CLAY (1.5' - 5.0')	-	A-7-6	M	5.0'	Previous pavement core patches observed, asphalt otherwise observed to be in good condition	822,887	1,567,924
-Y4- STA 13+70																			
Y4_PC_1370_EB LN	FILL ± 1.0'	EB LN 11.0'	OSS 1.25'	4.5' FW	C	21.0"	6.25"	-	14.75"	-	Asphalt ABC	R.E.: Brown, orange, CLAY (1.7' - 5.0')	S-31	A-7-6 (21)	30%	5.0'	Moderate alligator and vertical cracking in vicinity	818,008	1,567,814

Notes:

OSL = Outside Lane
ISL = Inside Lane
CL = Center Lane
LTL = Left Turn Lane
CTL = Center Turn Lane
RTL = Right Turn Lane
DECEL = Deceleration Lane
ACCEL = Acceleration Lane
OSS = Outside Shoulder
ISS = Inside Shoulder
GM = Grass Median
OGS = Outside Grass Shoulder
PS = Paved Shoulder
RT LN = Right Lane
LT LN = Left Lane
COL = Collector Lane
RT = Right
LT = Left
(I) = Inside
(O) = Outside
NB = Northbound
SB = Southbound
FW = From White
FY = From Yellow

CONE PENETROMETER RESULTS

Page 17


PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
GEOTECH(S)	J. Rose J. Crenshaw M. Brewer

L_PC_1300_EB LN

1


Datum = Top of subgrade 12/01/2023



L_PC_1300_WB LN

2

Datum = Top of subgrade 12/01/2023



CONE PENETROMETER RESULTS

Page 18

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y1_PC_1100_WB LN WDNG

3


Datum = Top of subgrade

12/01/2023

CBR Value

Interval	0.0 to 20.0
# of Values	30
Avg CBR	14.7
Wghtd Avg.	-
Max CBR	48.1
Min CBR	7.6

Interval	20.0 to 49.5
# of Values	102
Avg CBR	38.6
Wghtd Avg.	-
Max CBR	100+
Min CBR	9.6



Y1_PC_1900_EB PS

4


Datum = Top of subgrade

11/30/2023

CBR Value

Interval	0.0 to 5.0
# of Values	35
Avg CBR	100+
Wghtd Avg.	-
Max CBR	100+
Min CBR	14.1

Interval	5.0 to 57.7
# of Values	153
Avg CBR	45.0
Wghtd Avg.	-
Max CBR	100+
Min CBR	2.8



CONE PENETROMETER RESULTS

Page 19


PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y1_PC_1900_EB LN

5


Datum = Top of subgrade 11/30/2023



Y1_PC_1900_WB LN

6

Datum = Top of subgrade 12/01/2023



CONE PENETROMETER RESULTS

Page 20

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer


Y12850HA

7

Datum = Exstg Grd Lvl 01/04/2024

CBR Value

Interval	0.0 to 45.5
# of Values	47
Avg CBR	9.4
Wghtd Avg.	-
Max CBR	18.1
Min CBR	3.0



Y1_PC_3350_EB LN WDNG


8

Datum = Top of subgrade 11/30/2023

CBR Value

Interval	0.0 to 10.0
# of Values	14
Avg CBR	12.6
Wghtd Avg.	-
Max CBR	19.9
Min CBR	5.1

Interval	10.0 to 57.6
# of Values	111
Avg CBR	26.2
Wghtd Avg.	-
Max CBR	85.3
Min CBR	10.2



CONE PENETROMETER RESULTS

Page 21

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y1_PC_3350_CENTER LTL

9


Datum = Top of subgrade

11/30/2023

CBR Value

Interval	0.0 to 13.0
# of Values	23
Avg CBR	18.0
Wghtd Avg.	-
Max CBR	33.0
Min CBR	4.2

Interval	13.0 to 52.2
# of Values	41
Avg CBR	12.8
Wghtd Avg.	-
Max CBR	24.9
Min CBR	2.9



Y1_PC_3350_WB WDNG

10


Datum = Top of subgrade

11/30/2023

CBR Value

Interval	0.0 to 9.0
# of Values	22
Avg CBR	21.1
Wghtd Avg.	-
Max CBR	28.4
Min CBR	15.2

Interval	9.0 to 44.9
# of Values	142
Avg CBR	46.1
Wghtd Avg.	-
Max CBR	100+
Min CBR	11.5



CONE PENETROMETER RESULTS

Page 22

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer


Y2_PC_3000_EB ISS

11

Datum = Top of subgrade

11/29/2023

CBR Value



Interval	0.0 to 28.0
# of Values	29
Avg CBR	8.9
Wghtd Avg.	-
Max CBR	15.2
Min CBR	4.3

Interval	28.0 to 54.1
# of Values	82
Avg CBR	31.6
Wghtd Avg.	-
Max CBR	85.3
Min CBR	14.1


Y2_PC_3000_EB OSL

12

Datum = Top of subgrade

11/28/2023

CBR Value



Interval	0.0 to 10.0
# of Values	26
Avg CBR	33.7
Wghtd Avg.	-
Max CBR	100+
Min CBR	11.5

Interval	10.0 to 55.2
# of Values	132
Avg CBR	43.6
Wghtd Avg.	-
Max CBR	100+
Min CBR	6.7

CONE PENETROMETER RESULTS

Page 23

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer


Y2_PC_3000_EB OSS

13

Datum = Top of subgrade

11/28/2023

CBR Value



Interval	0.0 to 15.0
# of Values	14
Avg CBR	8.0
Wghtd Avg.	-
Max CBR	16.5
Min CBR	4.6

Interval	15.0 to 57.5
# of Values	148
Avg CBR	41.0
Wghtd Avg.	-
Max CBR	100+
Min CBR	9.2


Y2_PC_3500_EB ISS

14

Datum = Top of subgrade

11/29/2023

CBR Value



Interval	0.0 to 25.0
# of Values	38
Avg CBR	39.6
Wghtd Avg.	-
Max CBR	100+
Min CBR	3.4

Interval	25.0 to 58.2
# of Values	35
Avg CBR	14.2
Wghtd Avg.	-
Max CBR	39.3
Min CBR	3.2

CONE PENETROMETER RESULTS

Page 24

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y2_PC_3500_EB OSS

15


Datum = Top of subgrade

11/28/2023

CBR Value

Interval	0.0 to 19.0
# of Values	34
Avg CBR	21.7
Wghtd Avg.	-
Max CBR	100+
Min CBR	5.6

Interval	19.0 to 56.5
# of Values	154
Avg CBR	45.4
Wghtd Avg.	-
Max CBR	100+
Min CBR	14.1



Y2_PC_6400_EB ISS

16


Datum = Top of subgrade

11/29/2023

CBR Value

Interval	0.0 to 26.0
# of Values	39
Avg CBR	13.1
Wghtd Avg.	-
Max CBR	22.2
Min CBR	6.0

Interval	26.0 to 57.7
# of Values	112
Avg CBR	40.5
Wghtd Avg.	-
Max CBR	100+
Min CBR	9.6



CONE PENETROMETER RESULTS

Page 25

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer


Y2_PC_6400_EB OSL

17

Datum = Top of subgrade

11/29/2023

CBR Value




Y2_PC_6400_EB OSS

18

Datum = Top of subgrade

11/29/2023

CBR Value



CONE PENETROMETER RESULTS

Page 26

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y2_PC_2000_WB ISS

19


Datum = Top of subgrade

11/28/2023

CBR Value

Interval	0.0 to 25.0
# of Values	61
Avg CBR	23.9
Wghtd Avg.	-
Max CBR	48.1
Min CBR	8.7

Interval	25.0 to 46.9
# of Values	59
Avg CBR	29.6
Wghtd Avg.	-
Max CBR	100+
Min CBR	9.2



Y2_PC_2000_WB OSS


20

Datum = Top of subgrade

11/27/2024

CBR Value

Interval	0.0 to 48.0
# of Values	104
Avg CBR	26.5
Wghtd Avg.	-
Max CBR	85.3
Min CBR	3.4



CONE PENETROMETER RESULTS

Page 27

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y2_PC_2500_WB ISS


21

Datum = Top of subgrade

11/28/2023

CBR Value

Interval	0.0 to 46.5
# of Values	29
Avg CBR	5.5
Wghtd Avg.	-
Max CBR	13.1
Min CBR	2.6



Y2_PC_2500_WB OSL

22


Datum = Top of subgrade

11/28/2023

CBR Value

Interval	0.0 to 6.0
# of Values	16
Avg CBR	30.2
Wghtd Avg.	-
Max CBR	61.8
Min CBR	10.2

Interval	6.0 to 47.3
# of Values	34
Avg CBR	7.0
Wghtd Avg.	-
Max CBR	15.2
Min CBR	3.2



CONE PENETROMETER RESULTS

Page 28

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y2_PC_2500_WB OSS


23

Datum = Top of subgrade

11/28/2023

CBR Value

Interval	0.0 to 48.0
# of Values	32
Avg CBR	10.1
Wghtd Avg.	-
Max CBR	39.3
Min CBR	1.2



Y2_PC_3000_WB ISS


24

Datum = Top of subgrade

11/28/2023

CBR Value

Interval	0.0 to 46.8
# of Values	67
Avg CBR	15.6
Wghtd Avg.	-
Max CBR	33.0
Min CBR	4.7



CONE PENETROMETER RESULTS

Page 29

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer


Y2_PC_3000_WB OSS

25

Datum = Top of subgrade 11/27/2023

CBR Value

Interval	0.0 to 47.3
# of Values	94
Avg CBR	20.8
Wghtd Avg.	-
Max CBR	61.8
Min CBR	4.2




Y2_PC_4500_WB ISS

26

Datum = Top of subgrade 11/27/2023

CBR Value

Interval	0.0 to 46.8
# of Values	22
Avg CBR	3.8
Wghtd Avg.	-
Max CBR	9.2
Min CBR	1.9



CONE PENETROMETER RESULTS

Page 30

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y2_PC_4500_WB ISL


27

Datum = Top of subgrade

11/27/2024

CBR Value

Interval	0.0 to 46.7
# of Values	63
Avg CBR	28.4
Wghtd Avg.	-
Max CBR	100+
Min CBR	3.3



Y2_PC_4500_WB OSS


28

Datum = Top of subgrade

11/27/2023

CBR Value

Interval	0.0 to 48.1
# of Values	64
Avg CBR	18.0
Wghtd Avg.	-
Max CBR	39.3
Min CBR	1.5



CONE PENETROMETER RESULTS

Page 31


PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y2_PC_5000_WB ISS

29


Datum = Top of subgrade 11/27/2024



Y2_PC_5000_WB OSS

30

Datum = Top of subgrade 11/27/2023



CONE PENETROMETER RESULTS

Page 32

PROJECT NO.	U-6187
PROJECT NAME	2-Lane Extension of SR 1630
ROUTE	I 40, US 158, and SR 1630
COUNTY	Davie

GEOLOGIST	Quinton Hill
	J. Rose
GEOTECH(S)	J. Crenshaw
	M. Brewer

Y4_PC_1370_EB LN

42


Datum = Top of subgrade

12/01/2023

CBR Value

Interval		
0.0	to	15.0
# of Values	161	
Avg CBR	100+	
Wghtd Avg.	-	
Max CBR	100+	
Min CBR	4.4	

Interval		
15.0	to	49.5
# of Values	52	
Avg CBR	15.6	
Wghtd Avg.	-	
Max CBR	28.4	
Min CBR	3.8	



PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC

L_PC_1300_EB LN



TOP

BOTTOM


L_PC_1300_WB LN



TOP

BOTTOM

Y1_PC_1100_WB LN WDNG




TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC


Y1_PC_1900_EB PS



TOP

BOTTOM


Y1_PC_1900 EB LN



TOP

BOTTOM

Y1_PC_1900 WB LN



TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC

Y1_PC_3350_EB LN WDNG



TOP

BOTTOM


Y1_PC_3350_CENTER LTL



TOP

BOTTOM

Y1_PC_3350_WB WDNG




TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC

Y2_PC_3000_EB ISS



TOP

BOTTOM


Y2_PC_3000_EB OSL



TOP

BOTTOM

Y2_PC_3000_EB OSS




TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC


Y2_PC_3500_EB ISS



TOP

BOTTOM

Y2_PC_3500_EB OSS



TOP

BOTTOM

Y2_PC_6400_EB ISS




TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC

Y2_PC_6400_EB OSL



TOP

BOTTOM


Y2_PC_6400_EB OSS



TOP

BOTTOM

Y2_PC_2000_WB ISS




TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC

Y2_PC_2000_WB OSS



TOP

BOTTOM

Y2_PC_2500_WB ISS



TOP

BOTTOM

Y2_PC_2500_WB OSL



TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC


Y2_PC_2500_WB_OSS



TOP

BOTTOM


Y2_PC_3000_WB ISS



TOP

BOTTOM

Y2_PC_3000_WB OSS




TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC

Y2_PC_4500_WB ISS



TOP

BOTTOM


Y2_PC_4500_WB ISL



TOP

BOTTOM

Y2_PC_4500_WB OSS




TOP

BOTTOM

PAVEMENT CORE PHOTOGRAPHS
TIP No. U-6187|Davie County, NC

Y2_PC_5000_WB ISS



TOP

BOTTOM

Y2_PC_5000_WB OSS



TOP

BOTTOM

Y4_PC_1370_EB LN



TOP

BOTTOM

S:\GINT\PROJECTS\223294 SCHNABEL U6187 BALTIMORE RD EXTENSION.GPJ

LABORATORY SUMMARY SHEET

AASHTO Standard Specifications

(As modified by NCDOT, Material and Tests Unit, 2000.)

TEST RESULTS															
Proj. Sample Number	SS-37	SS-25	SS-15	SS-6	SS-1	SS-49	SS-55	SS-57	SS-62	SS-71	SS-82	SS-86	SS-100	SS-109	SS-112
Lab Sample Number	SS-37	SS-25	SS-15	SS-6	SS-1	SS-49	SS-55	SS-57	SS-62	SS-71	SS-82	SS-86	SS-100	SS-109	SS-112
Retained #4 Sieve %	0.1	0.1	0	0	3.0	0.1	0	0.5	0.8	0	0	0	0	0	0.1
Passing #10 Sieve %	99.5	99.7	100	99.9	94.8	99.9	100	98.8	98.6	99.9	100	100	100	100	99.8
Passing #40 Sieve %	92	91	98	98	84	99	89	92	92	96	96	98	90	94	94
Passing #200 Sieve %	66	36	85	78	50	91	53	65	73	85	61	83	48	56	67
MINUS NUMBER 10 FRACTION															
SOIL MORTAR - 100%															
Coarse Sand Ret.-#60 %	15.5	22.6	5.0	4.4	17.2	1.9	20.9	12.5	12.7	7.0	10.9	4.9	19.6	12.1	13.4
Fine Sand Ret.-#270 %	23.3	49.0	12.9	22.1	35.4	9.5	32.5	25.7	15.9	10.5	37.3	16.6	39.6	42.4	26.2
Silt 0.05 - 0.005mm %	18.9	16.6	16.1	23.5	25.1	17.1	18.2	18.6	19.7	10.7	20.3	23.2	22.1	28.3	26.4
Clay <0.005mm %	42.3	11.8	65.9	50.0	22.3	71.5	28.4	43.2	51.7	71.8	31.5	55.3	18.7	17.2	34.0
Liquid Limit (LL)	54	43	73	71	36	87	50	43	52	66	50	68	42	51	50
Plasticity Index (PI)	20	4	43	21	10	47	11	19	23	22	8	29	6	4	13
AASHTO Classification /Group Index	A-7-5(13)	A-5(0)	A-7-5(41)	A-7-5(23)	A-4(3)	A-7-5(52)	A-7-5(5)	A-7-6(11)	A-7-6(18)	A-7-5(25)	A-5(6)	A-7-5(29)	A-5(2)	A-5(3)	A-7-5(10)
Organic Content %	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	8.6	N/A	N/A	N/A	N/A	N/A	N/A
Station	18+00	20+50	22+50	26+50	28+50	33+00	35+00	37+00	39+00	43+00	47+00	49+00	51+00	53+00	55+00
Offset	0ft CL	0ft CL	0ft CL	0ft CL	0ft CL	0ft CL	0ft CL	0ft CL	0ft CL	0ft CL	30ft RT	30ft LT	30ft RT	30ft LT	30ft RT
Alignment															
Boring Identification	L-1800	L-2050	L-2250	L-2650	L-2850	L-3300	L-3500	L-3700	L-3900	L-4300	L-4700	L-4900	L-5100	L-5300	L-5500
Depth (FT)	3.7	13.5	3.5	3.4	0.0	3.5	6.5	0.0	0.0	3.5	8.5	3.5	8.5	18.5	3.5
to	5.2	15.0	5.0	4.9	1.5	5.0	8.0	1.5	1.5	5.0	10.0	5.0	10.0	20.0	5.0
Field Moist. Content %	13	40	29	37	18	42	35	19	29	24	22	27	30	24	22
Tested By	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON
Submitted By	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL
Date Submitted	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23

NP = Non-Plastic

NEM = Not Enough Material for Analysis

N/A = Not Applicable / Not Analyzed


Laboratory Manager

Report Date: 12/18/2023
Laboratory Report Page 1 of 3

S:\GINT\PROJECTS\223294 SCHNABEL U6187 BALTIMORE RD EXTENSION.GPJ

LABORATORY SUMMARY SHEET

AASHTO Standard Specifications

(As modified by NCDOT, Material and Tests Unit, 2000.)

TEST RESULTS															
Proj. Sample Number	SS-116	SS-125	SS-197	SS-130	SS-203	SS-205	SS-133	SS-145	SS-149	SS-151	SS-163	SS-207	SS-208	SS-211	SS-232
Lab Sample Number	SS-116	SS-125	SS-197	SS-130	SS-203	SS-205	SS-133	SS-145	SS-149	SS-151	SS-163	SS-207	SS-208	SS-211	SS-232
Retained #4 Sieve %	0	1.9	0.6	0	0.4	0.3	0.6	2.6	0	1.1	0.1	8.3	0	0	5.3
Passing #10 Sieve %	100	98.1	90.6	100	95.4	95.0	97.6	90.3	99.9	94.9	99.0	86.3	100	97.7	84.2
Passing #40 Sieve %	83	84	57	98	82	69	88	78	99	80	87	72	99	79	56
Passing #200 Sieve %	45	38	34	60	47	48	69	60	91	50	39	47	67	26	34
MINUS NUMBER 10 FRACTION															
SOIL MORTAR - 100%															
Coarse Sand Ret.-#60 %	27.7	29.1	46.5	6.4	22.4	35.1	14.9	19.1	2.3	23.8	29.7	25.9	4.9	37.9	44.0
Fine Sand Ret.-#270 %	34.4	39.6	20.9	44.1	37.1	20.3	17.5	18.1	9.3	30.4	38.6	22.9	37.6	41.4	18.6
Silt 0.05 - 0.005mm %	27.0	22.5	19.0	30.6	24.2	30.8	23.5	19.9	48.1	31.5	22.7	24.1	32.5	12.4	13.0
Clay <0.005mm %	10.9	8.8	13.6	19.0	16.3	13.8	44.2	42.9	40.3	14.4	9.1	27.1	25.0	8.3	24.4
Liquid Limit (LL)	36	NP	32	56	55	38	49	53	56	NP	31	NEM	58	NP	49
Plasticity Index (PI)	3	NP	3	11	9	4	19	26	18	NP	3	-	9	NP	23
AASHTO Classification /Group Index	A-4(0)	A-4(0)	A-4(0)	A-7-5(8)	A-5(4)	A-4(1)	A-7-5(14)	A-7-6(16)	A-7-5(22)	A-4(0)	A-4(0)	()	A-5(9)	A-2-4(0)	A-7-6(4)
Organic Content %	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	10.2	N/A	N/A	N/A
Station	55+00	57+00	58+50	59+00	59+50	59+50	61+00	63+00	63+00	63+00	65+00	67+00	67+00	67+00	69+00
Offset	30ft RT	30ft LT	0ft CL	0ft CL	0ft CL	0ft CL	40ft LT	30ft RT	30ft RT	30ft RT	10ft LT	80ft RT	80ft RT	80ft RT	70ft LT
Alignment															
Boring Identification	L-5500	L-5700	L-5850	L-5900	L-5950	L-5950	L-6100	L-6300	L-6300	L-6300	L-6500	L-6700	L-6700	L-6700	L-6900
Depth (FT)	18.5	18.5	13.5	6.5	8.5	18.5	0.0	0.0	13.5	23.5	43.5	0.0	3.5	13.5	8.5
to	20.0	20.0	15.0	8.0	10.0	20.0	1.5	1.5	15.0	25.0	45.0	1.5	5.0	15.0	10.0
Field Moist. Content %	21	29		40	26	57	25	24	40	37	23		56	55	22
Tested By	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON
Submitted By	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL
Date Submitted	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23

NP = Non-Plastic

NEM = Not Enough Material for Analysis

N/A = Not Applicable / Not Analyzed

Report Date: 12/18/2023

Laboratory Report Page 2 of 3

Laboratory Manager

LABORATORY SUMMARY SHEET

AASHTO Standard Specifications
(As modified by NCDOT, Material and Tests Unit, 2000.)

TEST RESULTS															
Proj. Sample Number	SS-165	SS-167	SS-172	SS-241	SS-246	SS-249									
Lab Sample Number	SS-165	SS-167	SS-172	SS-241	SS-246	SS-249									
Retained #4 Sieve %	0.2	0	0	1.0	0	7.8									
Passing #10 Sieve %	97.6	99.6	100	97.2	100	84.1									
Passing #40 Sieve %	87	82	98	87	92	56									
Passing #200 Sieve %	59	38	44	56	48	13									
MINUS NUMBER 10 FRACTION															
SOIL MORTAR - 100%															
Coarse Sand Ret.-#60 %	18.1	32.0	14.5	18.5	20.7	56.6									
Fine Sand Ret.-#270 %	25.4	37.2	49.1	29.3	40.9	31.7									
Silt 0.05 - 0.005mm %	23.9	21.8	23.0	21.8	29.4	9.4									
Clay <0.005mm %	32.6	8.9	13.4	30.4	9.0	2.4									
Liquid Limit (LL)	45	49	44	38	33	NP									
Plasticity Index (PI)	17	4	9	14	5	NP									
AASHTO Classification /Group Index	A-7-6(9)	A-5(0)	A-5(2)	A-6(6)	A-4(0)	A-2-4(0)									
Organic Content %	5.0	N/A	N/A	N/A	N/A	N/A									
Station	66+00	66+00	66+00	66+00	66+00	66+00									
Offset	120ft LT	120ft LT	120ft LT	120ft RT	120ft RT	120ft RT									
Alignment															
Boring Identification	LCULV1_LT	LCULV1_LT	LCULV1_LT	LCULV1_RT	LCULV1_RT	LCULV1_RT									
Depth (FT) to	0.0	6.5	28.5	0.0	18.5	33.5									
	1.5	8.0	30.0	1.5	20.0	33.9									
Field Moist. Content %	59	49	41	53	31	12									
Tested By	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON									
Submitted By	QHILL	QHILL	QHILL	QHILL	QHILL	QHILL									
Date Submitted	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23	11/22/23									

NP = Non-Plastic
NEM = Not Enough Material for Analysis
N/A = Not Applicable / Not Analyzed


Laboratory Manager

Report Date: 12/18/2023
Laboratory Report Page 3 of 3

S:\GINT\PROJECTS\223294 SCHNABEL U6187 BALTIMORE RD EXTENSION.GPJ

LABORATORY SUMMARY SHEET

AASHTO Standard Specifications
(As modified by NCDOT, Material and Tests Unit, 2000.)

TEST RESULTS															
Proj. Sample Number	SS-394	S-29	SS-1067	SS-360	SS-358	SS-405	SS-265	SS-106	S-27	S-24	S-25	S-22	S-23	S-21	SS-9006
Lab Sample Number	SS-394	S-29	SS-1067	SS-360	SS-358	SS-405	SS-265	SS-106	S-27	S-24	S-25	S-22	S-23	S-21	SS-9006
Retained #4 Sieve %	0	0.9	0	7.5	0.6	0	0	0	0.3	0.1	0	2.5	1.9	3.4	0.2
Passing #10 Sieve %	100	95.2	100	89.5	98.5	100	100	99.8	99.7	99.9	99.5	90.2	93.1	96.1	99.4
Passing #40 Sieve %	96	78	96	77	88	99	99	97	97	98	95	70	75	89	94
Passing #200 Sieve %	46	46	61	54	66	87	89	84	78	67	70	43	43	53	77
MINUS NUMBER 10 FRACTION															
SOIL MORTAR - 100%															
Coarse Sand Ret.-#60 %	16.2	28.2	12.8	21.2	15.1	2.5	2.8	5.9	7.5	6.6	8.7	28.9	27.6	17.2	10.1
Fine Sand Ret.-#270 %	46.2	29.0	34.0	21.7	22.3	16.8	10.6	22.3	18.9	58.1	26.0	28.4	32.2	34.4	15.5
Silt 0.05 - 0.005mm %	26.1	23.7	42.9	29.4	35.7	43.5	48.9	12.6	26.3	0.5	20.6	20.1	22.6	26.4	37.7
Clay <0.005mm %	11.5	19.2	10.3	27.7	26.8	37.2	37.8	59.2	47.3	34.8	44.8	22.6	17.6	22.0	36.7
Liquid Limit (LL)	54	23	53	47	66	63	72	73	61	43	55	31	26	27	50
Plasticity Index (PI)	5	8	8	20	26	16	33	35	31	21	27	17	10	7	16
AASHTO Classification /Group Index	A-5(1)	A-4(1)	A-5(6)	A-7-6(11)	A-7-5(19)	A-7-5(21)	A-7-5(36)	A-7-5(35)	A-7-5(27)	A-7-6(13)	A-7-6(19)	A-6(4)	A-4(2)	A-4(2)	A-7-5(15)
Organic Content %	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Station	72+09	13+00	10+50	13+50	15+50	21+50	20+00	12+50	11+00	19+00	19+00	33+50	33+50	35+00	30+00
Offset	21ft LT	5ft RT	20ft RT	30ft LT	35ft RT	25ft RT	15ft LT	25ft RT	2ft RT	6ft RT	1ft RT	7ft RT	3ft RT	7ft LT	14ft RT
Alignment															
Boring Identification	EB2_A	L_PC_1300_EB LN	LPB_1050	RPB_1350	RPB_1550	RPB_2150	RPD_2000	Y1_1250	Y1_PC_1100 WB LN WDNG	Y1_PC_1900 EB LN	Y1_PC_1900 EB PS	Y1_PC_3350 CENTER LTL	Y1_PC_3350 EB LN WDNG	Y1_PC_3500 WB WDNG	Y2_AP_3000 WB IGM
Depth (FT)	34.4	1.2	18.5	0.0	13.5	8.5	8.5	3.5	2.0	2.5	2.5	2.5	3.0	2.0	3.5
	to 35.9	2.0	20.0	1.5	15.0	10.0	10.0	5.0	2.5	3.0	3.0	3.0	3.5	2.3	5.0
Field Moist. Content %	66	9	58	40	62	50	70	31	32	27	30	15	18	20	33
Tested By	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON
Submitted By	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE
Date Submitted	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24

NP = Non-Plastic
NEM = Not Enough Material for Analysis
N/A = Not Applicable / Not Analyzed


Laboratory Manager

Report Date: 1/30/2024
Laboratory Report Page 1 of 3

S:\GINT\PROJECTS\223294 SCHNABEL U6187 BALTIMORE RD EXTENSION.GPJ

LABORATORY SUMMARY SHEET

AASHTO Standard Specifications
(As modified by NCDOT, Material and Tests Unit, 2000.)

TEST RESULTS															
Proj. Sample Number	SS-1015	SS-523	SS-1010	SS-1011	SS-519	SS-1022	S-12	S-06	S-04	S-10	S-15	S-08	S-02	S-07	S-17
Lab Sample Number	SS-1015	SS-523	SS-1010	SS-1011	SS-519	SS-1022	S-12	S-06	S-04	S-10	S-15	S-08	S-02	S-07	S-17
Retained #4 Sieve %	1.9	2.4	6.9	1.2	5.1	0	0	0	0.2	0.3	0.1	2.9	0	0.2	1.8
Passing #10 Sieve %	95.8	93.8	89.9	86.8	90.7	99.8	100	99.8	99.2	99.2	98.7	95.8	100	97.7	97.1
Passing #40 Sieve %	87	83	78	61	83	99	93	99	94	92	92	90	99	88	88
Passing #200 Sieve %	74	64	60	42	64	87	65	90	79	72	73	61	87	70	67
MINUS NUMBER 10 FRACTION															
SOIL MORTAR - 100%															
Coarse Sand Ret.-#60 %	12.7	17.3	20.4	38.1	13.5	2.6	15.1	2.7	9.1	11.7	10.8	12.2	3.2	15.2	15.5
Fine Sand Ret.-#270 %	12.8	19.1	15.4	17.7	21.7	15.9	25.7	10.2	15.8	21.0	20.6	30.7	15.4	16.1	19.7
Silt 0.05 - 0.005mm %	14.5	28.9	22.7	25.6	32.3	41.5	27.5	25.8	31.2	24.5	26.1	28.4	45.2	15.4	20.4
Clay <0.005mm %	59.9	34.8	41.5	18.7	32.5	40.0	31.7	61.3	43.9	42.8	42.5	28.7	36.2	53.3	44.4
Liquid Limit (LL)	67	52	59	42	51	62	42	87	65	58	55	60	54	58	52
Plasticity Index (PI)	28	24	30	13	18	22	18	41	31	24	18	19	14	31	28
AASHTO Classification /Group Index	A-7-5(25)	A-7-6(16)	A-7-6(20)	A-7-6(4)	A-7-5(13)	A-7-5(25)	A-7-6(10)	A-7-5(48)	A-7-5(28)	A-7-5(19)	A-7-5(15)	A-7-5(13)	A-7-5(17)	A-7-6(23)	A-7-6(19)
Organic Content %	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Station	40+00	40+00	45+00	45+00	50+00	55+00	20+00	20+00	25+00	30+00	35+00	45+00	45+00	50+00	64+00
Offset	13ft RT	7ft RT	14ft RT	14ft RT	7ft RT	6ft RT	6ft RT	6ft RT	3ft RT	6ft RT	6ft RT	4ft RT	7ft RT	6ft RT	7ft RT
Alignment															
Boring Identification	Y2_AP_4000 EB IGM	Y2_AP_4000 EB ISS	Y2_AP_4500 EB OGM	Y2_AP_4500 EB OGM	Y2_AP_5000 EB ISS	Y2_AP_5500 EB ISS	Y2_PC_2000 WB ISS	Y2_PC_2000 WB OSS	Y2_PC_2500 WB OSL	Y2_PC_3000 WB ISS	Y2_PC_3500 EB OSS	Y2_PC_4500 WB ISL	Y2_PC_4500 WB OSS	Y2_PC_5000 WB ISS	Y2_PC_6400 EB OSS
Depth (FT)	3.5	1.3	0.0	3.5	2.0	1.5	2.0	3.0	2.0	3.0	2.5	2.3	2.0	2.0	2.5
to	5.0	1.8	1.5	5.0	3.5	3.0	2.5	4.0	2.5	3.5	3.0	2.8	2.5	2.5	5.0
Field Moist. Content %	26	16	32	21	21	37	25	54	31	31	30	31	40	24	27
Tested By	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON	MDMASON
Submitted By	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE	JROSE
Date Submitted	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24	01/09/24

NP = Non-Plastic
NEM = Not Enough Material for Analysis
N/A = Not Applicable / Not Analyzed


Laboratory Manager

Report Date: 1/30/2024
Laboratory Report Page 2 of 3

LABORATORY

SUMMARY SHEET

AASHTO Standard Specifications

(As modified by NCDOT, Material and Tests Unit, 2000.)

TEST RESULTS															
Proj. Sample Number	SS-480	SS-487	SS-30	S-31											
Lab Sample Number	SS-480	SS-487	SS-30	S-31											
Retained #4 Sieve %	1.4	3.2	7.8	4.2											
Passing #10 Sieve %	97.0	93.4	86.9	92.4											
Passing #40 Sieve %	93	84	76	84											
Passing #200 Sieve %	52	59	56	67											
MINUS NUMBER 10 FRACTION															
SOIL MORTAR - 100%															
Coarse Sand Ret.-#60 %	10.0	16.7	19.8	14.5											
Fine Sand Ret.-#270 %	48.0	26.8	18.9	16.9											
Silt 0.05 - 0.005mm %	27.9	40.9	37.9	6.1											
Clay <0.005mm %	14.0	15.6	23.5	62.5											
Liquid Limit (LL)	33	39	55	55											
Plasticity Index (PI)	3	7	31	29											
AASHTO Classification /Group Index	A-4(0)	A-4(4)	A-7-6(19)	A-7-6(21)											
Organic Content %	N/A	N/A	N/A	N/A											
Station	29+55	32+05	11+50	13+70											
Offset	55ft RT	120ft RT	20ft LT	5ft RT											
Alignment															
Boring Identification	Y2CULV2_LT	Y2CULV2_RT	Y4_1150	Y4_PC_1370 EB LN											
Depth (FT) to	6.0	18.5	0.0	1.8											
	7.5	20.0	1.5	3.0											
Field Moist. Content %	42	41	22	30											
Tested By	MDMASON	MDMASON	MDMASON	MDMASON											
Submitted By	JROSE	JROSE	JROSE	JROSE											
Date Submitted	01/09/24	01/09/24	01/09/24	01/09/24											

NP = Non-Plastic

NEM = Not Enough Material for Analysis

N/A = Not Applicable / Not Analyzed

Signature

Laboratory Manager



PROJECT REFERENCE NO.	SHEET NO.
U-6187	-

County: Davie

Description: U-6187 Baltimore Road Extension

[illegible]

NP = Not Plastic
NT = Not Tested
ND = Not Determined

Henry Sanchez
Lab Manager, Certification No. 101-04-0603

W. Patrick Alton, P.E.
Soils Engineer




Project No: 66C-0009

Client: Schnabel Engineering South, PC

Project: U-6187 Baltimore Road Extension

City/State: Winston-Salem, NC



Sample	Depth (ft)	Classification	LL	PL	PI	% GRAVEL (+ #10)	% SAND (#10 - #200)	% FINES (- #200)
● BS-01	0.0' - 5.0'	A-7-5 (4)	46	30	16	8.6	46.4	45.0
☒ BS-03	0.0' - 5.0'	A-7-5 (13)	56	39	17	3.8	22.8	73.4
▲ BS-07	1.3' - 6.3'	A-7-5 (13)	55	36	19	4.8	27.2	68.0
★ BS-13	0.0' - 5.0'	A-7-6 (9)	42	24	18	6.2	31.2	62.6

Sample	Max Dry Density (pcf)	Optimum Moisture (%)	AASHTO	Sample Location	Natural Moisture (%)	Sample Notes
● BS-01	105.1	20.2	T-99 A	Y2_AP_3500_WB OGS	27.2	5.5 lb. Hammer, 12" Drop
☒ BS-03	95.9	25.1	T-99 A	Y2_AP_2500_WB GM	23.1	5.5 lb. Hammer, 12" Drop
▲ BS-07	96.9	23.0	T-99 A	Y2_AP_5500_EB ISS	29.1	5.5 lb. Hammer, 12" Drop
★ BS-13	104.9	22.0	T-99 A	Y12850HA	25.6	5.5 lb. Hammer, 12" Drop




Project No: 66C-0009

Client: Schnabel Engineering South, PC

Project: U-6187 Baltimore Road Extension

City/State: Winston-Salem, NC




Sample	Depth (ft)	Classification	LL	PL	PI	% GRAVEL (+ #10)	% SAND (#10 - #200)	% FINES (- #200)
● BS-01	0.0' - 5.0'	A-7-5 (4)	46	30	16	8.6	46.4	45.0
☒ BS-03	0.0' - 5.0'	A-7-5 (13)	56	39	17	3.8	22.8	73.4
▲ BS-07	1.3' - 6.3'	A-7-5 (13)	55	36	19	4.8	27.2	68.0
★ BS-13	0.0' - 5.0'	A-7-6 (9)	42	24	18	6.2	31.2	62.6

Sample	Max Dry Density (pcf)	Optimum Moisture (%)	AASHTO	Sample Location	Natural Moisture (%)	Sample Notes
● BS-01	110.2	17.3	T-134	Y2_AP_3500_WB OGS	27.2	10% Cement Added
☒ BS-03	95.2	26.0	T-134	Y2_AP_2500_WB GM	23.1	4% Lime Added
▲ BS-07	94.1	22.0	T-134	Y2_AP_5500_EB ISS	29.1	4% Lime Added
★ BS-13	99.8	21.1	T-134	Y12850HA	25.6	4% Lime Added



California Bearing Ratio Test Report - AASHTO T193

Load Penetration Curve



SOAKED CBR TEST RESULTS

Results		BS-01 (A)	BS-01 (B)	BS-03 (A)	BS-03 (B)			
0.1" Penetration		17.2	16.4	6.1	5.1			
0.2" Penetration		16.9	16.7	6.4	5.7			
Moisture Before Soaking (%)		20.1	20.1	27.0	27.0			
Dry Density Before Soaking (pcf)		104.7	104.4	95.5	95.6			
Moisture - Top 1" After Soaking (%)		22.6	22.5	29.3	30.2			
Surcharge Weight (lbs.)		10.0	10.0	10.0	10.0			
Project Information				Natural Moisture (%)				
Project Name:		Baltimore Road Extension (U-6187)			BS-01		27.2	
Client Name:		Schnabel Engineering South, PC			BS-03		23.1	
Project Number:		66C-0009			Percent Swell		A	B
Date Received:		1/12/2024			BS-01		0.070	0.120
Project Location:		Winston-Salem, NC			BS-03		0.420	0.200
Sample Information				Proctor Test Method (AASHTO T99)				
Sample Number		Description		Max. Dry Density (pcf)		Optimum Moisture %		
BS-01		A-7-5 (4)		105.1		20.2		
BS-03		A-7-5 (13)		95.9		25.1		
Sample Number		Sample Location		AASHTO (M145)		% - #200		% +19mm
BS-01		Y2_AP_3500_WB OGS		A-7-5		45.0		2.0
BS-03		Y2_AP_2500_WB GM		A-7-5		73.4		0.9
Specific Gravity		Remarks						
BS-01	2.753	BS-01	Specific Gravity Measured					
BS-03	2.746	BS-03	Specific Gravity Measured					

Performed By:

Henry Sanchez


Date:

2/20/2024



California Bearing Ratio Test Report - AASHTO T193

Load Penetration Curve



SOAKED CBR TEST RESULTS

Results		BS-07 (A)	BS-07 (B)	BS-13 (A)	BS-13 (B)		
0.1" Penetration		6.6	8.9	3.4	3.1		
0.2" Penetration		6.8	9.3	3.6	3.2		
Moisture Before Soaking (%)		22.8	22.8	24.5	24.5		
Dry Density Before Soaking (pcf)		98.0	99.3	100.8	99.8		
Moisture - Top 1" After Soaking (%)		32.5	30.0	24.5	25.3		
Surcharge Weight (lbs.)		10.0	10.0	10.0	10.0		
Project Information				Natural Moisture (%)			
Project Name:		Baltimore Road Extension (U-6187)		BS-07		29.1	
Client Name:		Schnabel Engineering South, PC		BS-13		25.6	
Project Number:		66C-0009		Percent Swell		A	B
Date Received:		2/20/2024		BS-07		1.280	1.080
Project Location:		Winston-Salem, NC		BS-13		0.050	0.360
Sample Information				Proctor Test Method (AASHTO T99)			
Sample Number		Description		Max. Dry Density (pcf)		Optimum Moisture %	
BS-07		A-7-5 (13)		96.9		23.0	
BS-13		A-7-6 (9)		104.9		22.0	
Sample Number		Sample Location		AASHTO (M145)		% - #200	% +19mm
BS-07		Y2_AP_5500_EB ISS		A-7-5		68.0	0.2
BS-13		Y12850HA		A-7-6		62.6	2.0
Specific Gravity		Remarks					
BS-07	2.677	BS-07	Specific Gravity Measured				
BS-13	2.776	BS-13	Specific Gravity Measured				

Performed By:

Henry Sanchez

Date:

2/20/2024

**Summary of Soil-Lime and Soil-Cement Unconfined Compression Testing****Baltimore Road Extension U-6187****F&R Project No. 66C-0009**

Sample	Location	Classification	Max Dry Density (pcf)	Optimum Moisture (%)	Additive (%)	Specimen	Unit Wt. (pcf)	Moisture (%)	Compaction (%)	Strength (psi)	Avg Strength (psi)
BS-01	Y2_AP_3500_WB OGS	A-7-5	110.2	17.3	Cement 8%	A	104.8	17.4	95.1	150	135
						B	104.0		94.4	120	
					Cement 10%	A	105.1	17.6	95.4	200	215
						B	107.7		97.7	230	
BS-03	Y2_AP_2500_WB GM	A-7-5	95.2	26.0	Lime 3%	A	94.0	25.3	98.7	30	35
						B	94.0		98.7	40	
					Lime 5%	A	92.3	26.9	97.0	40	40
						B	90.9		95.5	40	
BS-07	Y2_AP_5500_EB ISS	A-7-5	94.1	22.0	Lime 3%	A	95.4	24.4	101.4	50	50
						B	95.1		101.1	50	
					Lime 5%	A	93.3	26.9	99.1	50	45
						B	92.0		97.8	40	
BS-13	Y12850HA	A-7-6	99.8	21.1	Lime 3%	A	101.2	20.6	101.4	40	40
						B	99.8		100.0	40	
					Lime 5%	A	99.4	22.0	99.6	40	40
						B	98.9		99.1	40	