

STATION	STATION	UNCL. EXCAV.	ROCK	EMBANK. +%	BORROW	WASTE
-L-						
14+00	20+26.99	74		3,095	3,021	
-RPA-						
12+00	14+59.35	119		42		77
-RPB-						
11+50	16+15.95	158		1,372	1,214	
SUBTOTALS:		351		4,509	4,235	77
-L-						
21+65.15	27+00	81		2,806	2,725	
-RPC-						
12+00	15+59	122		155	33	
SUBTOTALS:		203		2,961	2,758	
-Y2- LT						
14+98	17+54	192		0		192
-Y2- MED						
13+75	18+13	4		185	181	
-Y2- RT						
14+96	17+12	77		0		77
SUBTOTALS:		273		185	181	269
TOTAL:		827		7,655	7,174	346
LOSS DUE TO CLEARING & GRUBBING		0		0	0	
WASTE IN LIEU OF BORROW					-346	-346
MATERIAL FOR SHOULDER CONSTRUCTION				660	660	
PROJECT TOTALS:		827		8,315	7,488	
EST 5% TO REPLACE TOP SOIL ON BORROW PIT					374	
GRAND TOTALS:		827		8,315	7,862	
SAY:		1,000			8,000	

SURVEY LINE	STATION	STATION	LOCATION LT/ RT/ CL	SY
-RPB- (CONC DITCH)	15+38	15+52	LT	7.56
			TOTAL:	7.56
			SAY:	10

SURVEY LINE	STATION	STATION	LENGTH	LENGTH (REMOVAL)	END ANCHOR UNIT	INTERMEDIATE ANCHOR UNIT	COMMENTS
-Y2-	12+36.00	14+69.45	233.45'		2		TIE TO EX. CABLE GUIDERAIL
-Y2-	17+63.95	18+13.00	49.05'		1		TIE TO EX. CABLE GUIDERAIL
REMOVAL							
-Y2-	12+60.00	14+95.29		235.30'			EX. CABLE GUIDERAIL REMOVAL
-Y2-	17+46.51	18+13.00		66.50'			EX. CABLE GUIDERAIL REMOVAL
		SUBTOTAL	282.50'	301.80'	3		
		LESS TERMINAL ANCHOR UNITS	72'				
		SUB TOTAL	210.50'	301.80'			
		SAY	220'.00	302.00'	3		

GUARDRAIL SUMMARY

\$\$\$\$SYTIME\$\$\$\$
Q:\RA\220307-04\20 CADD\BR-0098\Roadway\Sheets\BR-0098_RDY_3B-1.dgn
\$\$\$\$ISERNAME\$\$\$\$