

ADA SUMMARY OF QUANTITIES - TRINITY RD / TRENTON RD FROM NC 54 TO I-40

Municipality:	Cary
	Outside Municipality
WBS	2026CPT.05.02.20921.1,
Number:	2026CPT.05.02.20922.1
County:	Wake

Sheet No.
26

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2830000000-N (EA) Adjustment of Manholes	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2655000000-E (SY) 5" Monolithic Concrete Island (Keyed In)	2738000000-E (SY) Remove And Replace 5" Monolithic Concrete Islands (Keyed In)	2738000000-E (SY) Remove 5" Monolithic Concrete Islands (Keyed In)	2738000000-E (SY) Remove Driveway Apron	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2605000000-N (EA) Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps	Improvement Type
17061	1	SR-1655 (Trinity Rd)	Falcon Engineering (1210 Trinity Rd)															1			Type 1 Modified - 848.06
17062	1	SR-1655 (Trinity Rd)	Falcon Engineering (1210 Trinity Rd)															1			Type 1 Modified - 848.06
17065	2	SR-1655 (Trinity Rd)	All Saints Pl						6									1			Standard - 848.06
17066	2	SR-1655 (Trinity Rd)	All Saints Pl						6									1			Type 4B - 848D0610
17063	3	SR-1655 (Trinity Rd)	Trinity Grove Dr															1			Standard - 848.06
17064	3	SR-1655 (Trinity Rd)	Trinity Grove Dr						12									1			Type 4B - 848D0610
17067	4	SR-1655 (Trinity Rd)	Trinity Woods Dr						6									1			Type 1C - 848.06
17068	5	SR-1655 (Trinity Rd)	Brandywine Dr						6									1			Type 1C - 848.06
17069	5	SR-1655 (Trinity Rd)	Brandywine Dr						3									1			Type 3 Modified - 848D0609
-	-	-	-	-	-	-	36*	-	-	-	-	-	-	-	-	-	-	-	-	-	
Sub-Total for Trinity Rd / Trenton Rd From NC 54 To I-40				0	0	0	36	0	0	39	0	0	0	0	0	0	0	9	0	0	

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) *Contingency line item amount provided for adjustments outside of curb ramp pay limits.