

ADA SUMMARY OF QUANTITIES - HAMMOND RD FROM HOKE ST TO RUSH ST

Municipality:	Raleigh
WBS	2026CPT.05.02.20921.1,
Number:	2026CPT.05.02.20922.1
County:	Wake

Sheet No.
32

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2830000000-N (EA) Adjustment of Manholes	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2655000000-E (SY) 5" Monolithic Concrete Island (Keyed In)	2738000000-E (SY) Remove And Replace 5" Monolithic Concrete Islands (Keyed In)	2738000000-E (SY) Remove 5" Monolithic Concrete Islands (Keyed In)	2738000000-E (SY) Remove Driveway Apron	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2605000000-N (EA) Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps	Improvement Type
9553	1	SR-2026 (Hammond Rd)	Dead end (0.13 Mi North of Rush St)							6								1			Type 1C - 848.06
9554	1	SR-2026 (Hammond Rd)	Dead end (0.13 Mi North of Rush St)			15														1	Remove Ramp
6451	2	SR-2026 (Hammond Rd)	Rush St				10											1			Standard - 848.06
6452	2	SR-2026 (Hammond Rd)	Rush St															1			Standard - 848.06
6453	2	SR-2026 (Hammond Rd)	Rush St			15														1	Remove Ramp
6455	2	SR-2026 (Hammond Rd)	Rush St							3								1			Standard - 848.06
-	-	-	-	-	-	-	16*	-	-	-	-	-	-	-	-	-	-	-	-	-	
Sub-Total for Hammond Rd From Hoke St To Rush St				0	0	30	26	0	0	9	0	0	0	0	0	0	0	4	0	2	

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) *Contingency line item amount provided for adjustments outside of curb ramp pay limits.