

ADA SUMMARY OF QUANTITIES - LEAD MINE RD FROM BEGIN C&G TO SR 5147

Municipality:	Raleigh
WBS Number:	2026CPT.05.03.20921.1
County:	Wake

Sheet No.
24

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2535000000-E (LF) 8" X 12" Concrete Curb	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2830000000-N (EA) Adjustment of Manholes	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	4116100000-N (EA) Sign Erection, Relocate Type E (Ground Mounted)	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2605000000-N (EA) Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps	Improvement Type
18183	1	SR-1820 (Lead Mine Rd)	The Battery (7500 Lead Mine Rd) North Entrance			15												1	Remove Ramp
18184	1	SR-1820 (Lead Mine Rd)	The Battery (7500 Lead Mine Rd) North Entrance													1			Type 1C - 848.06
18185	1	SR-1820 (Lead Mine Rd)	The Battery (7500 Lead Mine Rd) North Entrance			15												1	Remove Ramp
18186	1	SR-1820 (Lead Mine Rd)	The Battery (7500 Lead Mine Rd) North Entrance													1			Type 1C - 848.06
18187	1	SR-1820 (Lead Mine Rd)	Greystone Baptist Church (7509 Lead Mine Rd)			15												1	Remove Ramp
18188	1	SR-1820 (Lead Mine Rd)	Greystone Baptist Church (7509 Lead Mine Rd)													1			Type 1C - 848.06
18189	1	SR-1820 (Lead Mine Rd)	Greystone Baptist Church (7509 Lead Mine Rd)			15												1	Remove Ramp
18190	1	SR-1820 (Lead Mine Rd)	Greystone Baptist Church (7509 Lead Mine Rd)								6					1			Type 1C - 848.06
18229	2	SR-1820 (Lead Mine Rd)	Sawmill Rd								6					1			Type 3 Modified - 848D0609
18230	2	SR-1820 (Lead Mine Rd)	Sawmill Rd								6					1			Type 3 Modified - 848D0609
18191	3	SR-1820 (Lead Mine Rd)	Greystone Village Shopping Center (7713 Lead Mine Rd) South Entrance			20												1	Remove Ramp
18192	3	SR-1820 (Lead Mine Rd)	Greystone Village Shopping Center (7713 Lead Mine Rd) South Entrance								6					1			Type 1C - 848.06
18193	3	SR-1820 (Lead Mine Rd)	Greystone Village Shopping Center (7713 Lead Mine Rd) South Entrance					18								1			Type 7 - 848.06
18194	3	SR-1820 (Lead Mine Rd)	Greystone Village Shopping Center (7713 Lead Mine Rd) South Entrance					18								1			Type 7 - 848.06
18195	3	SR-1820 (Lead Mine Rd)	Greystone Village Shopping Center (7713 Lead Mine Rd) South Entrance			20												1	Remove Ramp
18196	3	SR-1820 (Lead Mine Rd)	Greystone Village Shopping Center (7713 Lead Mine Rd) South Entrance								6					1			Type 1C - 848.06
-	-	-	-	-	-	-	-	40*	-	-	-	-	-	-	-	-	-	-	
Sub-Total for Lead Mine Rd From Begin C&G To SR 5147				0	0	100	0	76	0	0	30	0	0	0	0	10	0	6	

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) *Contingency line item amount provided for adjustments outside of curb ramp pay limits.