

20-AUG-2025 12:41
D:\w\p\dr\users\g01\HQR_LIS_East_01\Documents\NCDOT\NCDOT_L6170_R5600\NC170_US23BUS\6_0_CAD_BIM\6_2_Work\Lin_Progress\R-5600_NCDOT_File_Structure\Traffic\Signal\Design\Signal_Management\14-1333T1_Cherry_St-sm.ele.2024mdd.dgn
K Jones AT CHA-K JONES

MAXTIME STARTUP AND SOFTWARE FLASH
PROGRAMMING DETAIL

Front Panel
Main Menu >Controller >Unit

Web Interface
Home >Controller >Unit

Modify parameters as shown below and save changes.

Start Up Parameters	Unit Flash Parameters
StartUp Clearance Hold	All Red Flash Exit Time
6	6

OUTPUT CHANNEL CONFIGURATION

Front Panel
Main Menu >Controller >More>Channels>Channels Config

Web Interface
Home >Controller >Advanced IO>Channels>Channel Configuration

Channel Configuration

Channel	Control Type	Control Source	Flash Yellow	Flash Red	Flash Alt	MMU Channel
1	Phase Vehicle	1		X	X	1
2	Phase Vehicle	2		X		2
3	Phase Vehicle	3		X	X	3
4	Phase Vehicle	4		X		4
5	Phase Vehicle	5		X		5
6	Phase Vehicle	6		X	X	6
7	Phase Vehicle	7		X		7
8	Phase Vehicle	8		X	X	8
9	Overlap	1		X	X	9
10	Overlap	2		X	X	10
11	Overlap	3		X		11
12	Overlap	4		X		12
13	Phase Ped	2				13
14	Phase Ped	4				14
15	Phase Ped	6				15
16	Phase Ped	8				16
17	Overlap	5		X	X	17
18	Overlap	6		X		18

↑
NOTICE FLASH RED

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-1333T1
DESIGNED: Aug 2025
SEALED: 08/26/2025
REVISED:

Electrical Detail - Sheet 2 of 2
Temporary Design 1 - TMP Ph1, S4

Plans Prepared By:

**DRMP**

DRMP, INC.
8210 UNIVERSITY EXECUTIVE PARK DR.
SUITE 220
CHARLOTTE, NC 28262
NC LICENSE NO. F-1524 (704) 549-4260

Electrical and Programming
Details For:



750 N. Greenfield Pkwy, Garner, NC 27529

NC 107 (E. Main Street)
at
SR 1354 (Cherry Street)/
SR 1718 (E. Hall Heights)

Division 14 Jackson County Sylva

PLAN DATE: August 2025 REVIEWED BY: ZM Esposito

PREPARED BY: DJ White REVIEWED BY: BN Groome

REVISIONS INIT. DATE

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

SEAL
NORTH CAROLINA
PROFESSIONAL
SEAL
052936
ENGINEER
BRITTANY N. GROOME

Signed by:  8/26/2025
DATE
1E59340E1B64B4...

SIG. INVENTORY NO. 14-1333T1