

FLASHER CIRCUIT MODIFICATION DETAIL

IN ORDER TO INSURE THAT SIGNALS FLASH CONCURRENTLY ON THE SAME APPROACH, MAKE THE FOLLOWING FLASHER CIRCUIT CHANGES:

- 1. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-4 AND TERMINATE ON T2-2.
- 2. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-5 AND TERMINATE ON T2-3.
- 3. REMOVE FLASHER UNIT 2.

THE CHANGES LISTED ABOVE TIES ALL PHASES AND OVERLAPS TO FLASHER UNIT 1.

MAXTIME OVERLAP PROGRAMMING DETAIL

Front Panel
Main Menu >Controller >Overlap >Overlap Parameters/Overlap Timings

Web Interface
Home >Controller >Overlap Configuration >Overlaps

Overlap Plan 1

Overlap	3	4	6
Type	FYA 4 - Section	FYA 4 - Section	NORMAL
Included Phases	-	4,5	2
Modifier Phases	5	-	-
Modifier Overlap	-	-	-
Trail Green	0	0	0
Trail Yellow	0.0	0.0	0.0
Trail Red	0.0	0.0	0.0

OUTPUT CHANNEL CONFIGURATION

Front Panel
Main Menu >Controller >More>Channels>Channels Config

Web Interface
Home >Controller >Advanced IO>Channels>Channel Configuration

Channel Configuration

Channel	Control Type	Control Source	Flash Yellow	Flash Red	Flash Alt	MMU Channel
1	Phase Vehicle	1		X	X	1
2	Phase Vehicle	2		X		2
3	Overlap	7		X	X	3
4	Phase Vehicle	4		X		4
5	Phase Vehicle	5		X		5
6	Phase Vehicle	6		X	X	6
7	Phase Vehicle	7		X		7
8	Phase Vehicle	8		X	X	8
9	Overlap	1		X	X	9
10	Overlap	2		X	X	10
11	Overlap	3		X		11
12	Overlap	4		X		12
13	Phase Ped	2				13
14	Phase Ped	4				14
15	Phase Ped	6				15
16	Phase Ped	8				16
17	Overlap	5		X	X	17
18	Overlap	6		X		18

NOTICE OVERLAP 7
ASSIGNED TO CHANNEL 3 ➡

⬆
NNOTICE FLASHING RED

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-0790T2
DESIGNED: Oct 2025
SEALED: 10/1/2025
REVISED: N/A

MAXTIME STARTUP AND SOFTWARE FLASH
PROGRAMMING DETAIL

Front Panel
Main Menu>Controller>Unit

Web Interface
Home>Controller>Unit

Start Up Parameters
Startup Clearance Hold
6

Unit Flash Parameters
All Red Flash Exit Time
6

Electrical Detail - Sheet 2 of 2
Temporary Design 2 - TMP Ph1, S1A



NC 107 at SR 1724 (Fairview Road) / CVS Driveway Jackson County			
Division 14		Sylva	
PLAN DATE: October 2025	REVIEWED BY: ZM Esposito		
PREPARED BY: DS Griffith	REVIEWED BY: BN Groome		
REVISIONS	INIT.	DATE	

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

SEAL

Signed by:
Brittany N. Groome
1E09340E1064484...

10/1/2025
DATE

SIG. INVENTORY NO. 14-0790T2