

COMPUTED BY: Nick Moore DATE: 7/31/2024

CHECKED BY: Jinyoung Park DATE: 7/31/2024

(2-3-23)

STATE OF NORTH CAROLINA

DIVISION OF HIGHWAYS

PROJECT NO.

B-5985B

SHEET NO.

3G-1

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	Station	Station	Aggregate Type* ASU(1/2)/ AST	Aggregate Thickness INCHES [8" for ASU(2)]	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Subgrade Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
CONTINGENCY			ASU(1)	12"	50	100	150		
			TOTAL CY/TONS/SY:		50	100**	150**	0	0

*ASU(1/2) = Aggregate Subgrade (Type 1 or 2)
*AST = Aggregate Stabilization
**Total tons of "Class IV Subgrade Stabilization" and total square yards of "Geotextile for Subgrade Stabilization" are only the estimated quantities for ASU(1/2)/AST and may only represent a portion of the subgrade stabilization and geotextile quantities shown in the Item Sheets of the Proposal.