PROJECT NO.	SHEET NO.	TOTAL NO.	
2026CPT.10.13.10901, 2026CPT.10.13.20901	26		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 2" MILLING	1½" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1520000000-E LEVELING COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1524000000-E LEVELING COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775000000-E ASPHALT SURFACE TREATMENT, MATCOAT, #78M STONE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1838500000-N VACUUM TRUCK	1881000000-E CENTERLINE MILLED RUMBLE STRIPS (ASPHALT CONCRETE 18")	2143000000-E BLOTTING SAND	2612000000-E 6" DRIVEWAYS	2830000000-N ADJ. OF MANHOLES	2845000000-N ADJ. OF METER OR VALVE BOX	5255000000-N PORTABLE LIGHTING	7444000000-E INDUCTIVE LOOP
								MI	FT			TONS	SMI	TON	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	TONS	SY	GAL	WK	LF	TON	SY	EA	EA	LS	LF
2026CPT.10.13.10901	Union	1	US-74 WEST ROUTE ID 20600074090	FROM SR 1514 ROCKY RIVER RD TO SR 1379 HAYES RD (HAYES RD IMPROVEMENT PROJECT DJ0577) MP 19.2 TO 20.50	1,2,3,4	2	MD	1.3	28	19.2	20.5		2.60	481	22,548		3,460				3,190	150	253	1,170									0.40	268
TOTAL FOR MAP NO. 1								1.3					2.60	481	22,548		3,460				3,190	150	253	1,170									0.40	268
2026CPT.10.13.10901	Union	2	US-74 WEST ROUTE ID 20600074090	FROM SR 1379 HAYES RD (HAYES RD IPROVMENT PROJECT DJ00577) TO SR 1515 SARDIS CHURCH RD MP 20.68 TO MP 21.40	1,2,3,4,5	2	MD	0.72	28	20.68	21.4		1.44	266	13,799		3,161				2,026	90	156	648							2	2	0.40	
TOTAL FOR MAP NO. 2								0.72					1.44	266	13,799		3,161				2,026	90	156	648							2	2	0.40	
2026CPT.10.13.10901	Union	3	NC-207 ROUTE ID 30000207090	FROM SR 2152 W SANDY RIDGE RD TO SR 2150 JOE COLLINS RD MP 4.60 TO MP 6.00	6	2	2WU	1.4	20	4.6	6	95	2.80	388			767		1,583	350			156	630				7,392						
TOTAL FOR MAP NO. 3								1.4				95	2.80	388			767		1,583	350			156	630				7,392						
TOTAL FOR PROJ NO. 2026CPT.10.13.10901								3.42				95	6.84	1,135	36,347		7,388		1,583	350	5,216	240	565	2,448				7,392			2	2	0.80	268
2026CPT.10.13.20901	Union	4	SR-2394 / GRAY FOX RD ROUTE ID 40002394090	FROM US 74 WEST TO SR 1551 HELMSVILLE RD MP 0.00 TO MP .96	10,11	2	2WU	0.96	24	0	0.96					13,517					1,227		93	432										
TOTAL FOR MAP NO. 4								0.96								13,517					1,227		93	432										
2026CPT.10.13.20901	Union	5	SR-1315 / NEWTOWN RD ROUTE ID 40001315090	FROM PVMT JOINT (MP 14.9) TO SOUTH CARLOINA STATE LINE MP 14.9 TO MP 15.40	7	2	2WU	0.5	24	14.9	15.4	25	1.00	139			800		659	125			62	225										
TOTAL FOR MAP NO. 5								0.5				25	1.00	139			800		659	125			62	225										
2026CPT.10.13.20901	Union	6	SR-1315 / NEW TOWN RD ROUTE ID 40001315090	FROM SR 1307 WAXHAW MARVNN RD TO SR 1312 MARVIN RD MP 14.27 TO MP 14.55	7	2	2WU	0.28	24	14.27	14.55	25	0.56	78			800		398	70			36	126										
TOTAL FOR MAP NO. 6								0.28				25	0.56	78			800		398	70			36	126										
2026CPT.10.13.20901	Union	7	SR-1149 / DOSTER RD ROUTE 400011490090	FROM NC 200 TO SR 1007 ROCKY RIVER RD MP 0.00 TO 2.23	13	2	2WU	2.23	20	0	2.23	185	4.46	618			1,382	1,401	2,474	558			308	1,004						252				
TOTAL FOR MAP NO. 7								2.23				185	4.46	618			1,382	1,401	2,474	558			308	1,004						252				
2026CPT.10.13.20901	Union	8	SR-1107 / REHOBETH RD ROUTE ID 40001107090	FROM NC 75 TO PVMT JONT AT MP 4.67 (.59 MILES NORTH OF RICHARDSON KING RD) MP 4.67 TO MP 5.39	8,9	2	2WU	0.72	22	5.39	4.67	50	1.54	213		1,295	517				839	193	79	382										
TOTAL FOR MAP NO. 8								0.72				50	1.54	213		1,295	517				839	193	79	382										
2026CPT.10.13.20901	Union	9	SR-1162 / WESLEY CHAPEL RD ROUTE ID 40001162090	FROM SR 2515 MOLLIE IRENE DR TO NC 84 MP 7.66 TO MP 8.63	9	2	2WU	0.97	22	7.66	8.63	55	1.56	269			2,358				974	195	90	437									0.20	
TOTAL FOR MAP NO. 9								0.97				55	1.56	269			2,358				974	195	90	437									0.20	
2026CPT.10.13.20901	Union	10	SR-2115 / STACK RD ROUTE ID 40002115090	FROM SR 2133 SANDY RIDGE RD TO NC 207 MP 9.27 TO MP 11.29	12	2	2WU	2.02	20	9.27	11.29	70	4.04	560			1,667				3,000	505	250	909	23,704	5,930	1.00	9,611	60	216				
TOTAL FOR MAP NO. 10								2.02				70	4.04	560			1,667				3,000	505	250	909	23,704	5,930	1.00	9,611	60	216				
2026CPT.10.13.20901	Union	11	SR-1524 / STEVENS MILL RD ROUTE ID 40001524090	FROM SR 1365 STALLINGS RD TO MECKLENBURG COUNTY LINE MP 3.56 TO MP 4.31	7	2	2WU	0.75	20	3.56	4.31	65	1.52	211			962		859	190			85	342										
TOTAL FOR MAP NO. 11								0.75				65	1.52	211			962		859	190			85	342										
2026CPT.10.13.20901	Union	12	SR-1131 / NESBIT RD ROUTE ID 40001131090	FROM NC 200 S TO SR 1137 POTTERS RD S MP 4.05 TO MP 6.58	7	2	2WU	2.53	20	4.05	6.58	140	5.06	701			667		2,694	633			271	1,139										
TOTAL FOR MAP NO. 12								2.53				140	5.06	701			667		2,694	633			271	1,139										
TOTAL FOR PROJ NO. 2026CPT.10.13.20901								10.96				615	19.74	2,789		14,812	9,153	1,401	7,084	1,576	6,040	893	1,274	4,996	23,704	5,930	1.00	9,611	60	468			0.20	
GRAND TOTAL								14.38				710	26.58	3,924	36,347	14,812	16,541	1,401	8,667	1,926	11,256	1,133	1,839	7,444	23,704	5,930	1.00	17,003	60	468	2	2	1	268