PROPOSED ALIGNMENT CONTROL SHEET

PROJECT REFERENCE NO.	SHEET NO.
I-5898	RW02D-1

Location and Surveys

Dewberry®
Dewberry Engineers Inc.
551 PINEY FOREST ROAD
DANVILLE, VA 24540
PHONE: 434.797.4497
FAX: 434.797.4341
NCBELS #F-0929

PROJECT SURVEYOR

NORTH CAROLINA PROFESSIONAL SEAL L-5664 LAND SURVEYOR WILLIAM B. POWELL

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

I, William B. Powell, PLS, certify that the data compiled came from available surveys/mapping performed by others and provided to me by NCDOT and do not certify to the accuracy or quality of the individual data sources.

This 27th day of October, 2025.

Signed by: W. B. Powell A1C58B2AFAB4A40... 10/27/2025 | 11:40 AM EDT

Professional Land Surveyor L-5664

L

TYPE	STATION	NORTH	EAST
POT	100+00.00	968773.7710	1724069.5790
TS	132+51.23	972021.9143	1723927.8977
SC	135+88.73	972359.2718	1723921.3877
CS	150+28.13	973694.4306	1724393.9654
ST	153+65.63	973952.5753	1724611.2526
POT	173+34.04	975427.2769	1725915.0549

Y

TYPE	STATION	NORTH	EAST
POT	100+00.00	971162.9375	1722135.7716
PC	110+73.12	971516.7292	1723148.8913
PRC	115+05.62	971719.6360	1723528.9018
PT	117+41.13	971844.7443	1723728.1003
PC	120+94.49	972006.8780	1724042.0658
PRC	128+15.37	972111.9962	1724742.2721
PT	133+29.12	972117.9282	1725252.8970
POT	136+78.77	972188.0418	1725595.4419

Y2

TYPE	STATION	NORTH	EAST
POT	10+00.00	971509.2170	1723127.3793
POT	13+30.27	971179.9726	1723153.4060

Y3

TYPE	STATION	NORTH	EAST
POT	10+00.00	972409.1012	1724990.6669
POT	13+18.59	972090.5445	1724995.1928

Y4

TYPE	STATION	NORTH	EAST
POT	10+00.00	972090.5574	1724996.4760
POT	13+11.79	971782.7982	1725046.4313

RP_A

TYPE	STATION	NORTH	EAST
POT	10+00.00	972551.2714	1723843.5067
PC	16+43.02	971940.1784	1723643.3946
PT	17+90.11	971795.2400	1723640.1638

RP_B

TYPE	STATION	NORTH	EAST
PC	6+71.30	970545.4180	1723953.4537
PT	10+09.76	970878.7646	1723899.2580
POT	19+62.16	971795.2407	1723640.1650

RP_C

TYPE	STATION	NORTH	EAST
POT	10+00.00	971147.4077	1724075.9287
PC	15+51.50	971680.5083	1724217.1947
PT	19+11.42	972037.3268	1724233.1893
POT	19+56.32	972081.5757	1724225.6189

RP_D

TYPE	STATION	NORTH	EAST
PC	10+00.00	973212.1037	1724188.2849
PT	16+62.50	972557.2503	1724144.2379
POT	21+45.08	972081.5757	1724225.6189

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.

2. THE PROPOSED ALIGNMENT CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

REVISIONS

6/2/99

24-OCT-2025 (40)
P:\5010\0527\(40)Survey\microstation\d sheets\I5898.LS_RW02D-1.251016.dgn
codkins AT BFTYW94