Docusign Envelope ID: EAF16C8B-0353-4795-A48F-35630C2350B4

TIP NO.	SHEET NO.
HL-0008I	SIGN-2

APPROVED: DocuSigned by: Faith Jahnke 8D02B5BCE7C9466...

DATE: 9/29/2025

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 046981 ENGINEER FAITH E. JAHNKE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared in the Office of: SUMMIT DESIGN AND ENGINEERING SERVICES
NC FIRM LICENSE No: C-5176
320 Executive Ct.
Hillsborough, NC 27278
(919) 732-3883
(919) 732-6676 (FAX)

401 QUANTITY REQ'D: 5



W3-3
30'' X 30''
ONE "U" POST PER SIGN

402 QUANTITY REQ'D: 2

R3-4
36" X 36"
ONE "U" POST PER SIGN

403 QUANTITY REQ'D: 2

R6-1R
48" X 18"
TWO "U" POSTS PER SIGN
MOUNT ABOVE SIGN 407
IN 1 INSTALLATION

404 QUANTITY REQ'D: 4

R2-1
30" X 36"
ONE "U" POST PER SIGN

405 QUANTITY REQ'D: 8

R4-7
24" X 30"
ONE "U" POST PER SIGN

406 QUANTITY REQ'D: 1

M4-4
24" X 12"
MOUNT ABOVE SIGN 402
IN 1 INSTALLATION

407 QUANTITY REQ'D: 1

R1-1
30'' X 30''
ONE "U" POST PER SIGN

408 QUANTITY REQ'D: 1

W1-2L
36'' X 36''
ONE "U" POST PER SIGN

409 QUANTITY REQ'D: 1



W2-2
30'' X 30''
ONE "U" POST PER SIGN

410 QUANTITY REQ'D: 2

R3-7
36'' X 36''
ONE "U" POST PER SIGN

411 QUANTITY REQ'D: 1



W12-1
36'' X 36''
ONE "U" POST PER SIGN

412 QUANTITY REQ'D: 1



OM1-3
18" X 18"
MOUNT BELOW SIGN 405
IN 1 INSTALLATION

413 QUANTITY REQ'D: 3

R6-1L
48" X 18"
TWO "U" POSTS PER SIGN

414 QUANTITY REQ'D: 1

W13-1P
18" X 18"
ONE "U" POSTS PER SIGN
MOUNT BELOW SIGN 408
IN 1 INSTALLATION

TYPE "E" SIGNS

9/29/2025
N:\2019\19-0205.105 HL-0008I\Transportation\Design\Traffic\Signing\CADD\Signing Layout Plans\HL-0008I_SIGN_3.dgn
Usersteven.Coyle