



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

November 16, 2022

MEMORANDUM TO: Clark Morrison PhD, P.E.  
State Pavement Design Engineer

Tatia L. White, P.E., PLS  
State Roadway Design Engineer

Sean M. Epperson, P.E.  
Division Project Development Engineer

FROM: J. L. Pilipchuk, P.E., L.G.  
State Geotechnical Engineer

DS

DocuSigned by:  
*John Pilipchuk*  
52C44B94B8BE444...

STATE PROJECT: 46891.1.1 (U-5956)

COUNTY: Cabarrus

DESCRIPTION: Realign Union Cemetery Road to Intersect US 29 at Rock Hill Church Road and Construct Improvements Along US 29 from 0.6 Mile West of Rock Hill Church Road to just East of Rock Hill Church Road

SUBJECT: Pavement and Subgrade Investigation Report

The Geotechnical Engineering Unit has completed the evaluation of the pavement and subgrade investigation for this project and presents the following.

The proposed work consists of realigning Union Cemetery Road on New alignment and upgrades to US 29 and Cabarrus Ave.

The subgrade beneath the existing roadway primarily consists of silty sand (A-2-4), sandy silt (A-4), sandy clay (A-6), and silty clays (A-7-6).

Anticipated borrow will likely consist of soil types listed above.

The length of this project is 0.861 miles.

## AREAS OF SPECIAL GEOTECHNICAL INTEREST

### A. Highly Plastic Clays:

Locations of clays with a PI of 26 or greater

| LINE | STATION AND OFFSET    | PI |
|------|-----------------------|----|
| -Y1- | 4+74 LTL (RT)         | 26 |
| -Y1- | 51+16 LTLT (LT)       | 27 |
| -L-  | 17+33 ASPHALT LOT     | 31 |
| -L-  | 51+25 RT LN           | 35 |
| -L-  | 50+46 28' RT (BULK 2) | 31 |

### B. Trapped Water within the Pavement:

No trapped water was observed on site.

### C. Soils with a High Moisture Content:

In-situ moisture content exceeds the plastic limit (PL) at the following locations.

| LINE | STATION AND OFFSET | MOISTURE CONTENT |
|------|--------------------|------------------|
| -Y1- | 4+74 LTL RT        | 28.5%            |
| -Y1- | 26+62 LT ISL       | 34.3%            |
| -Y1- | 29+24 RTL (RT)     | 21.6%            |
| -Y1- | 35+27 LTL (RT)     | 23.2%            |
| -Y1- | 36+92 LT OSL       | 27.5%            |
| -Y1- | 36+92 ISL          | 20.6%            |
| -Y1- | 36+92 LTL (LT)     | 21.4%            |
| -Y1- | 49+29 RT OSL       | 22.8%            |
| -Y1- | 51+16 LTL (LT)     | 22.3%            |
| -L-  | 17+13 ASPHALT LOT  | 27.6%            |
| -L-  | 51+25 RT LN        | 30.1%            |

JLP/MJA/JBB

|               |                                 |    |
|---------------|---------------------------------|----|
| ATTACHMENT 1: | Pavement and Subgrade Inventory | 44 |
| ATTACHMENT 2: | DCP Graphs                      | 18 |
| ATTACHMENT 3: | Pavement Core Evaluation        | 5  |



DocuSigned by:

*Jeffrey Brian Barfield*

11/16/2022

09B33DEB8C824D1...

REFERENCE: U-5956

PROJECT: 46891

CONTENTS

| SHEET NO. | DESCRIPTION                         |
|-----------|-------------------------------------|
| 1         | TITLE SHEET                         |
| 2, 2A     | LEGEND (SOIL & ROCK), ABBREVIATIONS |
| 3         | ROADWAY TITLE SHEET                 |
| 4-14      | PLAN SHEETS                         |
| 15-17     | PAVEMENT INVESTIGATION DATA SHEETS  |
| 18-27     | DUAL MASS DCP DATA SHEETS           |
| 28-32     | PAVEMENT CORE PHOTOS                |
| 33-43     | LABORATORY TEST RESULTS             |

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
GEOTECHNICAL ENGINEERING UNIT

ROADWAY  
SUBSURFACE INVESTIGATION

COUNTY CABARRUS

PROJECT DESCRIPTION US 29 - REALIGN UNION  
CEMETERY RD. TO INTERSECT US 29 AT  
ROCK HILL CHURCH RD.

PAVEMENT AND SUBGRADE INVESTIGATION

| STATE | STATE PROJECT REFERENCE NO. | SHEET NO. | TOTAL SHEETS |
|-------|-----------------------------|-----------|--------------|
| N.C.  | U-5956                      | 1         | 43           |

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
  - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

|                 |
|-----------------|
| FIELD PERSONNEL |
| P. TOMASIC      |
| D. UNDERWOOD    |
| C. ODOM         |
| T. WENNER       |
| M. BREWER       |
| L. ARD          |
|                 |

INVESTIGATED BY CG2, PLLC.

DRAWN BY T. WENNER, P.G.

CHECKED BY M. BREWER, P.E.

SUBMITTED BY CG2, PLLC.

DATE OCTOBER 2022

Prepared in the Office of:



CAROLINAS  
GEOTECHNICAL  
GROUP

2400 CROWNPOINT EXECUTIVE DRIVE  
SUITE 800  
CHARLOTTE, NC 28227  
(980) 339-8684



DocuSigned by:

Matt Brewer 11/18/2022

386429C0A4C1462 SIGNATURE DATE

DOCUMENT NOT CONSIDERED FINAL  
UNLESS ALL SIGNATURES COMPLETED



Tip No. U-5956| WBS No. 46891.1.1| Cabarrus County

ABBREVIATIONS

|                           |                                     |
|---------------------------|-------------------------------------|
| RT LN = Right Lane        | CR = Crown                          |
| LT LN = Left Lane         | S = Super                           |
| OSL = Outside Lane        | C = Cut                             |
| ISL = Inside Lane         | F = Fill                            |
| OSML = Outside Mid-Lane   | DCP = Dynamic Cone Penetrometer     |
| ISML = Inside Mid-Lane    | M = Moist                           |
| PS = Paved Shoulder       | W = Wet                             |
| LTL = Left Turn Lane      | N/A = Not Observed                  |
| RTL = Right Turn Lane     | NSR = No Sample Recovered           |
| MID = Middle Lane         | S- = Soil Grab Sample               |
| CTL = Center Turn Lane    | Ref- = Soil Reference Sample        |
| ISWP = Inside Wheel Path  | SS- = Split Spoon Sample            |
| OSWP = Outside Wheel Path | RE = Roadway Embankment             |
| PS = Paved Shoulder       | F. = Fine                           |
| FW = From White Line      | Cse. = Coarse                       |
| FY = From Yellow Line     | ABC = Aggregate Base Course         |
| RT = Right                | STBC = Soil Type Base Course        |
| LT = Left                 | CSS = Cement Stabilized Soil        |
| (I) = Inside              | SG = Subgrade                       |
| (O) = Outside             | AF= Artificial Fill                 |
| BOC = Back of Curb        | S# = Grass Shoulder Boring with DCP |
| C&G = Curb and Gutter     | BGS = Below Ground Surface          |
| EOP = Edge of Pavement    | WOD = Weight of DCP                 |


\$FILE\$

\$DATE\$

PROJECT: 46891

TIP PROJECT: U-5956

SEE SHEET 1A FOR INDEX OF SHEETS  
SEE SHEET 1B FOR CONVENTIONAL PLAN SHEET SYMBOLS




Note: Not to Scale

ROW PLANS

# STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS CABARRUS COUNTY


LOCATION: REALIGN UNION CEMETERY ROAD TO INTERSECT US 29 AT  
ROCK HILL CHURCH ROAD AND CONSTRUCT IMPROVEMENTS  
ALONG US 29 FROM 0.6 MILE WEST OF ROCK HILL CHURCH  
ROAD TO JUST EAST OF ROCK HILL CHURCH ROAD

TYPE OF WORK: GRADING, DRAINAGE, PAVING, SIGNALS, AND SIGNING



★ TRAFFIC SIGNAL  
CLEARING ON THIS PROJECT FROM -L- STA 18+50 TO -L- STA 51+83.57 SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.  
CLEARING FOR THE REMAINDER OF -L- AND ALL Y LINES SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.  
THIS PROJECT IS WITHIN THE MUNICIPAL BOUNDARIES OF THE CITY OF CONCORD.

## GRAPHIC SCALES



## DESIGN DATA

AADT 2020 = 14,900  
AADT 2040 = 18,400  
K = 9%  
D = 55%  
T = 8%\*  
V = 40 MPH  
CLASSIFICATION:  
URBAN COLLECTOR  
\* 1% TTST 7% DUAL  
SUB-REGIONAL TIER

## PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT U-5956 = 0.861 MILES  
TOTAL LENGTH TIP PROJECT U-5956 = 0.861 MILES

PLANS PREPARED FOR  
THE NCDOT BY:

2018 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:  
JUNE 17, 2022

LETTING DATE:  
NOVEMBER 17, 2023

Kimley»Horn

NC LICENSE #F-2102  
200 SOUTH TRYON STREET, SUITE 200  
CHARLOTTE, NORTH CAROLINA 28202  
PHONE: (704) 333-5131

JASON D. LAWING, P.E.  
PROJECT ENGINEER


ANDREW J. WEEKS, E.I.  
PROJECT DESIGN ENGINEER

SEAN EPPERSON, P.E.  
PROJECT ENGINEER  
NCDOT HIGHWAY DIVISION 10

HYDRAULICS ENGINEER


SIGNATURE: \_\_\_\_\_ P.E.  
ROADWAY DESIGN ENGINEER

SIGNATURE: \_\_\_\_\_ P.E.



| STATE           | STATE PROJECT REFERENCE NO. | SHEET NO.   | TOTAL SHEETS |
|-----------------|-----------------------------|-------------|--------------|
| N.C.            | U-5956                      | 3           | 43           |
| STATE PROJ. NO. | P.A. PROJ. NO.              | DESCRIPTION |              |
| 46891.1.1       |                             | PE          |              |
| 46891.2.1       |                             | UTILITIES   |              |
| 46891.2.2       |                             | R/W         |              |
|                 |                             |             |              |
|                 |                             |             |              |

DOCUMENT NOT CONSIDERED FINAL  
UNLESS ALL SIGNATURES COMPLETED




| PROJECT REFERENCE NO.                                  | SHEET NO. |
|--------------------------------------------------------|-----------|
| U-5956                                                 | 4         |
| <div><div></div><div>050100</div><div>FEET</div></div> |           |


|                    |          |                     |          |
|--------------------|----------|---------------------|----------|
| C-2 -Y1- STA. 6+64 |          | C-3 -Y1- STA. 6+64  |          |
| LT PS 1.0 FT RT FW |          | LT ISL 1.0 FT RT FY |          |
| PAVEMENT SECTION   |          | PAVEMENT SECTION    |          |
| ASPHALT            | 12.75 in | ASPHALT             | 12.00 in |
| ABC                | YES      | CONCRETE            | 8.00 in  |
| UTILITY PRESENT    |          | ASPHALT             | 0.75 in  |
|                    |          | CONCRETE            | 8.25 in  |



|                     |          |                    |          |
|---------------------|----------|--------------------|----------|
| C-4 -Y1- STA. 6+64  |          | C-5 -Y1- STA. 6+64 |          |
| RT ISL 1.8 FT RT FY |          | RT PS 1.8 FT RT FW |          |
| PAVEMENT SECTION    |          | PAVEMENT SECTION   |          |
| ASPHALT             | 14.25 in | ASPHALT            | 14.25 in |
| ABC                 | 10.75 in |                    |          |

|                       |          |
|-----------------------|----------|
| C-1 -Y1- STA. 4+74    |          |
| LTL (RT) 5.0 FT RT FY |          |
| PAVEMENT SECTION      |          |
| ASPHALT               | 14.25 in |
| ABC                   | 11.75 in |



|                       |          |
|-----------------------|----------|
| C-6 -Y1- STA. 18+03   |          |
| LTL (LT) 5.0 FT RT FY |          |
| PAVEMENT SECTION      |          |
| ASPHALT               | 18.00 in |
| ABC                   | 13.00 in |





|                      |          |                       |          |
|----------------------|----------|-----------------------|----------|
| C-12 -Y1- STA. 26+62 |          | C-13 -Y1- STA. 26+62  |          |
| LT PS 1.0 FT RT FW   |          | LT OSL 5.0 FT LT FW   |          |
| PAVEMENT SECTION     |          | PAVEMENT SECTION      |          |
| ASPHALT              | 12.00 in | ASPHALT               | 10.50 in |
| ABC                  | YES      | CONCRETE              | 7.00 in  |
| UTILITY PRESENT      |          | ASPHALT               |          |
| C-14 -Y1- STA. 26+62 |          | CONCRETE              |          |
| LT ISL 6.0 FT RT FW  |          | C-15 -Y1- STA. 26+62  |          |
| PAVEMENT SECTION     |          | LTL (LT) 7.0 FT RT FY |          |
| ASPHALT              | 11.00 in | PAVEMENT SECTION      |          |
| CONCRETE             | 5.75 in. | ASPHALT               | 19.00 in |
| ASPHALT              | 0.75 in  |                       |          |
| CONCRETE             | 6.50 in  |                       |          |


|                       |          |
|-----------------------|----------|
| C-16 -Y1- STA. 29+24  |          |
| RTL (RT) 9.0 FT LT FW |          |
| PAVEMENT SECTION      |          |
| ASPHALT               | 16.25 in |
| ABC                   | 7.75 in  |

|                       |          |
|-----------------------|----------|
| C-7 -Y1- STA. 22+32   |          |
| LTL (LT) 7.0 FT RT FY |          |
| PAVEMENT SECTION      |          |
| ASPHALT               | 6.50 in  |
| ABC                   | 11.00 in |

|                       |          |                      |          |
|-----------------------|----------|----------------------|----------|
| C-8 -Y1- STA. 24+65   |          | C-9 -Y1- STA. 24+65  |          |
| LTL (RT) 8.5 FT RT FY |          | RT ISL 8.0 FT RT FW  |          |
| PAVEMENT SECTION      |          | PAVEMENT SECTION     |          |
| ASPHALT               | 19.00 in | ASPHALT              | 13.50 in |
| ABC                   | 11.50 in | ABC                  | 11.50 in |
| C-10 -Y1- STA. 24+65  |          | C-11 -Y1- STA. 24+65 |          |
| RT OSL 7.0 FT LT FW   |          | RT PS 1.0 FT RT FW   |          |
| PAVEMENT SECTION      |          | PAVEMENT SECTION     |          |
| ASPHALT               | 12.75 in | ASPHALT              | 15.25 in |
| ABC                   | 12.25 in | ABC                  | YES      |
|                       |          | UTILITY PRESENT      |          |

TEST LOCATIONS S1, S2, S3, AND S4 WERE PERFORMED IN THE GRASS SHOULDER 3.5' RT FW.






|                       |          |                      |          |
|-----------------------|----------|----------------------|----------|
| C-24 -Y1- STA. 39+65  |          | C-25 -Y1- STA. 39+65 |          |
| LTL (RT) 4.0 FT RT FY |          | RT ISL 7.0 FT RT FW  |          |
| PAVEMENT SECTION      |          | PAVEMENT SECTION     |          |
| ASPHALT               | 8.00 in  | ASPHALT              | 13.00 in |
| ABC                   | 16.00 in | ABC                  | 12.00 in |
| C-26 -Y1- STA. 39+65  |          | C-27 -Y1- STA. 39+65 |          |
| RT OSL 4.5 FT LT FW   |          | RT PS 0.2 FT RT FW   |          |
| PAVEMENT SECTION      |          | PAVEMENT SECTION     |          |
| ASPHALT               | 13.00 in | ASPHALT              | 14.00 in |
| ABC                   | 13.00 in | ABC                  | 11.00 in |

|                       |          |                       |          |
|-----------------------|----------|-----------------------|----------|
| C-28 -Y1- STA. 42+44  |          | C-29 -Y1- STA. 42+44  |          |
| RTL (LT) 7.0 FT LT FW |          | LTL (LT) 5.0 FT RT FY |          |
| PAVEMENT SECTION      |          | PAVEMENT SECTION      |          |
| ASPHALT               | 13.00 in | ASPHALT               | 10.75 in |
| ABC                   | 3.00 in  | ABC                   | 12.25 in |

|                     |         |
|---------------------|---------|
| C-35 -L- STA. 15+81 |         |
| CONCRETE LOT        |         |
| PAVEMENT SECTION    |         |
| CONCRETE            | 8.75 in |
| ABC                 | 9.25 in |



| PROJECT REFERENCE NO. | SHEET NO. |
|-----------------------|-----------|
| U-5956                | 10        |
| 0 50 100<br>FEET      |           |





N  
NC GRID  
NAD 83 N.A. 2011

| PROJECT REFERENCE NO. | SHEET NO. |
|-----------------------|-----------|
| U-5956                | 11        |
| 0 50 100<br>FEET      |           |

|                       |          |
|-----------------------|----------|
| C-34 -Y1- Sta. 51+16  |          |
| LTL (LT) 7.0 FT RT FY |          |
| PAVEMENT SECTION      |          |
| ASPHALT               | 8.00 in  |
| ABC                   | 17.00 in |

|                       |          |                      |          |
|-----------------------|----------|----------------------|----------|
| C-31 -Y1- STA. 49+29  |          | C-32 -Y1- Sta. 49+29 |          |
| LTL (RT) 5.5 FT RT FY |          | RT OSL 3.0 FT LT FW  |          |
| PAVEMENT SECTION      |          | PAVEMENT SECTION     |          |
| ASPHALT               | 4.00 in  | ASPHALT              | 9.50 in  |
| ABC                   | 16.00 in | ABC                  | 12.50 in |

|                      |         |
|----------------------|---------|
| C-33 -Y1- STA. 49+29 |         |
| RT PS 1.0 FT RT FW   |         |
| PAVEMENT SECTION     |         |
| ASPHALT              | 8.75 in |
| ABC                  | YES     |
| UTILITY PRESENT      |         |

|                       |          |
|-----------------------|----------|
| C-30 -Y1- STA. 46+45  |          |
| RTL (RT) 5.0 FT LT FW |          |
| PAVEMENT SECTION      |          |
| ASPHALT               | 11.25 in |


END GRADE  
-Y1- POT Sta. 50+10.00



NC GRID  
NAD 83 NA 2011

|                     |          |
|---------------------|----------|
| C-38-Y3-STA. 12+84  |          |
| LT LN 3.0 FT RT C&G |          |
| PAVEMENT SECTION    |          |
| ASPHALT             | 9.25 in  |
| ABC                 | 11.75 in |

|                     |          |                     |          |
|---------------------|----------|---------------------|----------|
| C-39 -L- STA. 51+25 |          | C-40 -L- STA. 51+25 |          |
| RT LN 4.0 FT LT EOP |          | RT PS 1.0 FT LT EOP |          |
| PAVEMENT SECTION    |          | PAVEMENT SECTION    |          |
| ASPHALT             | 11.00 in | ASPHALT             | 10.75 in |



PAVEMENT INVESTIGATION DATA SHEET

|          |           |
|----------|-----------|
| Project: | 46891.1.1 |
| TIP:     | U-5956    |

|         |                                                                               |
|---------|-------------------------------------------------------------------------------|
| Route:  | US 29 - Realign Union Cemetary Rd. to Intersect US 29 at Rock Hill Church Rd. |
| County: | Cabarrus                                                                      |

|                  |                                                                 |
|------------------|-----------------------------------------------------------------|
| Date Performed:  | 8/7 to 8/9, 9/18/22                                             |
| Field Personnel: | M. Brewer, T. Wenner, D. Underwood, C. Odom, P. Tomasic, L. Ard |

|                                     |                                | Width (ft) |                    | (ft)                        | (in)                   | Thickness (in)       |               |       |                     |              |                                      | Subgrade                                                                                                                               |                    |                       |               |                   |                                                                                                             | GPS Coordinates |           |
|-------------------------------------|--------------------------------|------------|--------------------|-----------------------------|------------------------|----------------------|---------------|-------|---------------------|--------------|--------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|--------------------|-----------------------|---------------|-------------------|-------------------------------------------------------------------------------------------------------------|-----------------|-----------|
| Test Location                       | Cut/Fill (Est. of Amount) (ft) | Lane       | Shoulder           | Offset Distance (See Notes) | Crown "C" or Super "S" | Gross to Top of Soil | Asphalt       | ABC   | Stabilized Subgrade | Concrete     | Pavement Layering                    | Description (Depth - ft)                                                                                                               | Soil Sample Number | AASHTO Classification | Soil Moisture | Boring Depth (ft) | Asphalt Notes                                                                                               | Northing        | Easting   |
| C-1<br>-Y1- Sta. 4+74<br>LTL (RT)   | Fill<br>5.0                    | 12.0       | -                  | 5.0 RT<br>FY                | Cr.                    | 26.00                | 14.25         | 11.75 |                     |              | Asphalt<br>ABC<br>SG                 | 2.2-5.0: RE - Brown-Gray, Silty CLAY, Highly Plastic, Trace Organics                                                                   | S-1                | A-7-6(6)              | M             | 5                 | Low to Moderate Severity Fatigue Cracking                                                                   | 601,091         | 1,515,095 |
| C-2<br>-Y1- Sta. 6+64<br>LT PS      | Fill<br>5.0                    | 12.0       | 3.0 PS             | 1.0 RT<br>FW                | Cr.                    | N/A                  | 12.75         | Yes   |                     |              | Asphalt<br>ABC                       | Unmarked gas line at test location. No Auger/DCP Performed                                                                             | -                  | -                     | -             | -                 | No Distress Observed                                                                                        | 601,214         | 1,515,247 |
| C-3<br>-Y1- Sta. 6+64<br>LT ISL     | Fill<br>5.0                    | 12.0       | 1.0 PS             | 1.0 RT<br>FY                | Cr.                    | 29.00                | 12.00<br>0.75 |       |                     | 8.00<br>8.25 | Asphalt/Conc.<br>Asphalt/Conc.<br>SG | 2.4-5.0: RE - Gray-Brown, Silty Fine to Coarse SAND<br>Trace Organics                                                                  | S-3                | A-2-4                 | M             | 5                 | No Distress Observed                                                                                        | 601,193         | 1,515,257 |
| C-4<br>-Y1- Sta. 6+64<br>RT ISL     | Fill<br>5.0                    | 12.0       | -                  | 1.8 RT<br>FY                | Cr.                    | 25.00                | 14.25         | 10.75 |                     |              | Asphalt<br>ABC<br>SG                 | 2.1-5.0: RE - Brown, Fine to Coarse Sandy SILT                                                                                         | S-4                | A-4(0)                | M             | 5                 | Low Severity Trasnverse Cracking                                                                            | 601,169         | 1,515,269 |
| C-5<br>-Y1- Sta. 6+64<br>RT PS      | Fill<br>5.0                    | 12.0       | 3.0 PS             | 1.8 RT<br>FW                | Cr.                    | 14.25                | 14.25         |       |                     |              | Asphalt<br>SG                        | 1.2-3.0: RE - Brown, Fine to Coarse Sandy SILT<br>3.0: Auger Refusal                                                                   | Ref-4              | A-4                   | M             | 3<br>AR           | Low Severity Longitudinal Cracking                                                                          | 601,150         | 1,515,279 |
| C-6<br>-Y1- Sta.18+03<br>LTL (LT)   | Fill<br>5.0                    | 12.0       | 2.0 PS             | 5.0 RT<br>FY                | Cr.                    | 31.00                | 18.00         | 13.00 |                     |              | Asphalt<br>ABC<br>SG                 | 2.6-3.0: RE - Tan, Silty Fine to Coarse SAND<br>3.0-5.0: RE - Red-Brown, Fine to Coarse Sandy CLAY, Petroleum Odor, Moderately Plastic | S-6A<br>S-6B       | A-2-4<br>A-6(7)       | M<br>M        | 5                 | No Distress Observed                                                                                        | 601,693         | 1,516,280 |
| C-7<br>-Y1- Sta.22+32<br>LTL (LT)   | Fill<br>5.0                    | 12.0       | Concrete<br>Median | 7.0 RT<br>FY                | Cr.                    | 17.50                | 6.50          | 11.00 |                     |              | Asphalt<br>ABC<br>SG                 | 1.5-5.0: RE - Tan, Fine to Coarse Sandy SILT                                                                                           | S-7                | A-4(0)                | M             | 5                 | Low to Moderate Severity Transverse and Longitudinal Cracking,<br><b>Full Depth Bottom-Up Crack in Core</b> | 601,883         | 1,516,665 |
| C-8<br>-Y1- Sta. 24+65<br>LTL (RT)  | At<br>Grade                    | 12.0       | Concrete<br>Median | 8.5 RT<br>FY                | Cr.                    | 19.00                | 19.00         |       |                     |              | Asphalt<br>SG                        | 1.6-5.0: RES - Orange-Brown, Fine to Coarse Sandy SILT                                                                                 | Ref-7              | A-4                   | M             | 5                 | Low Severity Transverse Cracking                                                                            | 601,974         | 1,516,880 |
| C-9<br>-Y1- Sta. 24+65<br>RT ISL    | At<br>Grade                    | 12.0       | Concrete<br>Median | 8.0 RT<br>FW                | Cr.                    | 25.00                | 13.50         | 11.50 |                     |              | Asphalt<br>ABC<br>SG                 | 2.1-5.0: RES - Tan-Orange, Fine to Coarse Sandy SILT                                                                                   | S-9                | A-4(1)                | M             | 5                 | Low Severity Transverse Cracking                                                                            | 601,965         | 1,516,885 |
| C-10<br>-Y1- Sta. 24+65<br>RT OSL   | At<br>Grade                    | 12.0       | 3.0 PS             | 7.0 LT<br>FW                | Cr.                    | 25.00                | 12.75         | 12.25 |                     |              | Asphalt<br>ABC<br>SG                 | 2.2-5.0: RES - Tan-Orange, Fine to Coarse Sandy SILT, trace mica                                                                       | S-10               | A-4(3)                | M             | 5                 | No Distress Observed                                                                                        | 601,958         | 1,516,888 |
| C-11<br>-Y1- Sta. 24+65<br>RT PS    | At<br>Grade                    | 12.0       | 3.0 PS             | 1.0 RT<br>FW                | Cr.                    | N/A                  | 15.25         | Yes   |                     |              | Asphalt<br>ABC                       | Water line within 2.0 feet of test location. No Auger/DCP Performed                                                                    | -                  | -                     | -             | -                 | No Distress Observed                                                                                        | 601,951         | 1,516,892 |
| C-12<br>-Y1- Sta. 26+62<br>LT PS    | Fill<br>5.0                    | 12.0       | 2.0 PS             | 1.0 RT<br>FW                | Cr.                    | N/A                  | 12.00         | Yes   |                     |              | Asphalt<br>ABC                       | Unmarked gas line within 5.0 feet of test location. No Auger/DCP Performed                                                             | -                  | -                     | -             | -                 | Low Severity Transverse Cracking                                                                            | 602,104         | 1,517,036 |
| C-13<br>-Y1- Sta. 26+62<br>LT OSL   | Fill<br>5.0                    | 12.0       | 2.0 PS             | 5.0 LT<br>FW                | Cr.                    | 25.00                | 10.50<br>0.50 |       |                     | 7.00<br>7.00 | Asphalt<br>Concrete<br>Asphalt/Conc. | 2.1-5.0: RE - Red-Brown, Silty CLAY, with F. to Cse, Sand, Mod. Plastic                                                                | Ref-14             | A-7-6                 | -             | 5                 | Low Severity Transverse Cracking                                                                            | 602,098         | 1,517,039 |
| C-14<br>-Y1- Sta. 26+62<br>LT ISL   | Fill<br>5.0                    | 12.0       | -                  | 6.0 RT<br>FW                | Cr.                    | 24.00                | 11.00<br>0.75 |       |                     | 5.75<br>6.50 | Asphalt/Conc.<br>Asphalt/Conc.<br>SG | 2.0-5.0: RE - Red-Brown, Silty CLAY, with F. to Cse, Sand, Mod. Plastic                                                                | S-14               | A-7-6(9)              | M             | 5                 | Low to Moderate Severity Transverse and Longitudinal Cracking                                               | 602,086         | 1,517,044 |
| C-15<br>-Y1- Sta. 26+62<br>LTL (LT) | Fill<br>5.0                    | 12.0       | 1.0 PS             | 7.0 RT<br>FY                | Cr.                    | 19.00                | 19.00         |       |                     |              | Asphalt<br>SG                        | 1.6-5.0: RE - Red-Brown, Silty CLAY, with Fine to Coarse Sand, Moderately Plastic                                                      | Ref-14             | A-7-6                 | M             | 5                 | Low to Moderate Severity Transverse and Longitudinal Cracking                                               | 602,076         | 1,517,049 |

Notes:

Offset Distance: Left and Right Relative to the Direction of Travel

Prepared by: CTW  
Reviewed by: DMB

PAVEMENT INVESTIGATION DATA SHEET

|          |           |
|----------|-----------|
| Project: | 46891.1.1 |
| TIP:     | U-5956    |

|         |                                                                               |
|---------|-------------------------------------------------------------------------------|
| Route:  | US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd. |
| County: | Cabarrus                                                                      |

|                  |                                                                 |
|------------------|-----------------------------------------------------------------|
| Date Performed:  | 8/7 to 8/9, 9/18/22                                             |
| Field Personnel: | M. Brewer, T. Wenner, D. Underwood, C. Odom, P. Tomasic, L. Ard |

|                                     |                                | Width (ft) |                                  | (ft)                        | (in)                   | Thickness (in)       |               |       |                     |              |                                      | Subgrade                                                                              |                    |                       |               |                   |                                                                          | GPS Coordinates |           |
|-------------------------------------|--------------------------------|------------|----------------------------------|-----------------------------|------------------------|----------------------|---------------|-------|---------------------|--------------|--------------------------------------|---------------------------------------------------------------------------------------|--------------------|-----------------------|---------------|-------------------|--------------------------------------------------------------------------|-----------------|-----------|
| Test Location                       | Cut/Fill (Est. of Amount) (ft) | Lane       | Shoulder                         | Offset Distance (See Notes) | Crown "C" or Super "S" | Gross to Top of Soil | Asphalt       | ABC   | Stabilized Subgrade | Concrete     | Pavement Layering                    | Description (Depth - ft)                                                              | Soil Sample Number | AASHTO Classification | Soil Moisture | Boring Depth (ft) | Asphalt Notes                                                            | Northing        | Easting   |
| C-16<br>-Y1- Sta. 29+24<br>RTL (RT) | Fill<br>5.0                    | 12.0       | -                                | 9.0 LT<br>FW                | Cr.                    | 24.00                | 16.25         | 7.75  |                     |              | Asphalt<br>ABC<br>SG                 | 2.0-5.0: RE - Tan-Orange, Clayey Fine to Coarse SAND, Moderately Plastic              | S-16               | A-2-6(1)              | M             | 5                 | No Distress Observed                                                     | 602,152         | 1,517,304 |
| C-17<br>-Y1- Sta. 30+66<br>LTL (LT) | Fill<br>5.0                    | 12.0       | 1.0 PS                           | 5.0 RT<br>FY                | Cr.                    | 37.00                | 18.25         | 18.75 |                     |              | Asphalt<br>ABC<br>SG                 | 3.1-5.0: RE - Gray, Silty, Fine to Coarse SAND, with little gravel                    | S-17               | A-2-4                 | M             | 5                 | Low Severity Transverse Cracking<br><b>6 inch Top-Down Crack in Core</b> | 602,255         | 1,517,412 |
| C-18<br>-Y1- Sta. 35+27<br>LTL (RT) | Fill<br>5.0                    | 10.0       | 1.0 PS                           | 6.0 RT<br>FY                | Cr.                    | 25.00                | 9.00          | 16.00 |                     |              | Asphalt<br>ABC<br>SG                 | 2.1-5.0: RE - Red-Brown, Silty CLAY, Moderately Plastic                               | S-18               | A-7-6(11)             | M             | 5                 | No Distress Observed                                                     | 602,435         | 1,517,836 |
| C-19<br>-Y1- Sta. 35+27<br>RTL (RT) | Fill<br>6.0                    | 12.0       | 2.0 PS                           | 9.0 LT<br>FW                | Cr.                    | 27.00                | 16.00         | 11.00 |                     |              | Asphalt<br>ABC<br>SG                 | 2.3-5.0: RE - Tan-Orange, Fine to Coarse Sandy CLAY, Moderately Plastic               | S-19               | A-6(2)                | M             | 5                 | No Distress Observed, Small Patch Over Water Line (~2.0' x 2.0')         | 602,405         | 1,517,847 |
| C-20<br>-Y1- Sta. 36+92<br>RTL (LT) | Fill<br>5.0                    | 12.0       | 2.0 PS                           | 6.0 LT<br>FW                | Cr.                    | N/A                  | 14.25         | Yes   |                     |              | Asphalt<br>ABC                       | Gas line within 5.0 feet of test location. No Auger/DCP Performed                     | -                  | -                     | -             | -                 | No Distress Observed                                                     | 602,537         | 1,517,975 |
| C-21<br>-Y1- Sta. 36+92<br>LT OSL   | Fill<br>5.0                    | 12.0       | -                                | 8.0 LT<br>FW                | Cr.                    | 25.50                | 11.25         |       |                     | 14.25        | Asphalt<br>Concrete<br>SG            | 2.2-5.0: RE - Tan-Orange, Fine to Coarse Sandy CLAY, trace gravel, Moderately Plastic | S-21               | A-6(12)               | M             | 5                 | No Distress Observed                                                     | 602,524         | 1,517,980 |
| C-22<br>-Y1- Sta. 36+92<br>LT ISL   | Fill<br>5.0                    | 12.0       | 1.0 PS                           | 1.0 RT<br>FW                | Cr.                    | 28.00                | 12.25<br>2.50 |       |                     | 6.25<br>7.00 | Asphalt/Conc.<br>Asphalt/Conc.<br>SG | 2.3-5.0: RE - Tan-Orange, Fine to Coarse Sandy CLAY, Moderately Plastic               | S-22               | A-6(12)               | M             | 5                 | No Distress Observed                                                     | 602,510         | 1,517,984 |
| C-23<br>-Y1- Sta. 36+92<br>LTL (LT) | Fill<br>5.0                    | 12.0       | 1.0 PS                           | 1.0 RT<br>FY                | Cr.                    | 26.00                | 11.00         | 15.00 |                     |              | Asphalt<br>ABC<br>SG                 | 2.2-5.0: RE - Brown, Fine to Coarse Sandy CLAY, Moderately Plastic                    | S-23               | A-6(6)                | M             | 5                 | No Distress Observed                                                     | 602,499         | 1,517,988 |
| C-24<br>-Y1- Sta. 39+65<br>LTL (RT) | Fill<br>5.0                    | 12.0       | -                                | 4.0 RT<br>FY                | Cr.                    | 24.00                | 8.00          | 16.00 |                     |              | Asphalt<br>ABC<br>SG                 | 2.0-5.0: RE - Tan-Orange, Fne to Coarse Sandy CLAY, Moderately Plastic                | Ref-26             | A-6                   | M             | 5                 | Low to Moderate Severity Longitudinal and Transverse Cracking            | 602,573         | 1,518,251 |
| C-25<br>-Y1- Sta. 39+65<br>RT ISL   | Fill<br>5.0                    | 12.0       | -                                | 7.0 RT<br>FW                | Cr.                    | 25.00                | 13.00         | 12.00 |                     |              | Asphalt<br>ABC<br>SG                 | 2.2-5.0: RE - Tan, Silty Fine to Coarse SAND                                          | S-25               | A-2-4                 | M             | 5                 | Low to Moderate Severity Longitudinal and Transverse Cracking            | 602,558         | 1,518,255 |
| C-26<br>-Y1- Sta. 39+65<br>RT OSL   | Fill<br>5.0                    | 12.0       | 3.0 PS                           | 4.5 LT<br>FW                | Cr.                    | 25.00                | 14.00         | 11.00 |                     |              | Asphalt<br>ABC<br>SG                 | 2.2-5.0: RE - Tan-Orange, Fine to Coarse Sandy CLAY, Moderately Plastic               | S-26               | A-6(5)                | M             | 5                 | No Distress Observed                                                     | 602,547         | 1,518,258 |
| C-27<br>-Y1- Sta. 39+65<br>RT PS    | Fill<br>5.0                    | 12.0       | 3.0 PS                           | 0.2 RT<br>FW                | Cr.                    | 26.00                | 13.50         | 12.50 |                     |              | Asphalt<br>ABC<br>SG                 | 2.2-5.0: RE -Tan-Orange, Fine to Coarse Sandy CLAY                                    | S-27               | A-6(2)                | M             | 5                 | No Distress Observed<br><b>5 inch Bottom-Up Crack in Core</b>            | 602,543         | 1,518,259 |
| C-28<br>-Y1- Sta. 42+44<br>RTL (LT) | Fill<br>5.0                    | 12.0       | 3.0 Concrete<br>Curb &<br>Gutter | 7.0 LT<br>FW                | Cr.                    | 16.00                | 13.00         | 3.00  |                     |              | Asphalt<br>ABC<br>SG                 | 1.3-5.0: RE - Red-Brown, Fine to Coarse Sandy CLAY                                    | S-28               | A-6(6)                | M             | 5                 | Low to Moderate Severity Transverse and Longitudinal Cracking            | 602,678         | 1,518,515 |
| C-29<br>-Y1- Sta. 42+44<br>LTL (LT) | Fill<br>5.0                    | 10.0       | 1.0 PS                           | 5.0 RT<br>FY                | Cr.                    | 23.00                | 10.75         | 12.25 |                     |              | Asphalt<br>ABC<br>SG                 | 1.9-5.0: RE - Red-Brown, Fine to Coarse Sandy CLAY, Moderately Plastic                | S-29               | A-6(7)                | M             | 5                 | Moderate to High Severity Transverse and Longitudinal Cracking           | 602,643         | 1,518,521 |
| C-30<br>-Y1- Sta. 46+45<br>RTL (RT) | At<br>Grade                    | 10.0       | -                                | 5.0 LT<br>FW                | Cr.                    | 11.25                | 11.25         |       |                     |              | Asphalt<br>SG                        | Gas line within 5.0 feet of test location. No Auger/DCP Performed                     | -                  | -                     | -             | -                 | Low to Moderate Severity Transverse and Longitudinal Cracking            | 602,664         | 1,518,925 |

Notes:

Offset Distance: Left and Right Relative to the Direction of Travel

Prepared by: CTW  
Reviewed by: DMB

PAVEMENT INVESTIGATION DATA SHEET

|          |           |
|----------|-----------|
| Project: | 46891.1.1 |
| TIP:     | U-5956    |

|         |                                                                               |
|---------|-------------------------------------------------------------------------------|
| Route:  | US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd. |
| County: | Cabarrus                                                                      |

|                  |                                                                 |
|------------------|-----------------------------------------------------------------|
| Date Performed:  | 8/7 to 8/9, 9/18/22                                             |
| Field Personnel: | M. Brewer, T. Wenner, D. Underwood, C. Odom, P. Tomasic, L. Ard |

|                                         |                                | Width (ft) |                               | (ft)                        | (in)                   | Thickness (in)       |         |       |                     |          |                       | Subgrade                                                                |                    |                       |               |                   |                                                                                                                        | GPS Coordinates |           |
|-----------------------------------------|--------------------------------|------------|-------------------------------|-----------------------------|------------------------|----------------------|---------|-------|---------------------|----------|-----------------------|-------------------------------------------------------------------------|--------------------|-----------------------|---------------|-------------------|------------------------------------------------------------------------------------------------------------------------|-----------------|-----------|
| Test Location                           | Cut/Fill (Est. of Amount) (ft) | Lane       | Shoulder                      | Offset Distance (See Notes) | Crown "C" or Super "S" | Gross to Top of Soil | Asphalt | ABC   | Stabilized Subgrade | Concrete | Pavement Layering     | Description (Depth - ft)                                                | Soil Sample Number | AASHTO Classification | Soil Moisture | Boring Depth (ft) | Asphalt Notes                                                                                                          | Northing        | Easting   |
| C-31<br>-Y1- Sta. 49+29<br>LTL (RT)     | At Grade                       | 12.0       | 2.0 PS                        | 5.5 RT<br>FY                | Cr.                    | 20.00                | 4.00    | 16.00 |                     |          | Asphalt<br>ABC<br>SG  | 1.7-5.0: RES - Tan-Orange, Silty CLAY, Moderately Plastic               | S-31               | A-7-6(9)              | M             | 5                 | Low to Moderate Severity Transverse and Longitudinal Cracking<br><b>Full Depth Crack in Core</b>                       | 602,745         | 1,519,199 |
| C-32<br>-Y1- Sta. 49+29<br>RT OSL       | Fill<br>5.0                    | 12.0       | 3.0 PS                        | 3.0 LT<br>FW                | Cr.                    | 22.00                | 9.50    | 12.50 |                     |          | Asphalt<br>ABC<br>SG  | 1.8-5.0: RE - Tan-Orange, Fine to Coarse Sandy CLAY, Moderately Plastic | S-32               | A-6(8)                | M             | 5                 | Low to Moderate Severity Transverse and Longitudinal Cracking                                                          | 602,720         | 1,519,203 |
| C-33<br>-Y1- Sta. 49+29<br>RT PS        | Fill<br>5.0                    | 12.0       | 3.0 PS                        | 1.0 RT<br>FW                | Cr.                    | N/A                  | 8.75    | Yes   |                     |          | Asphalt<br>ABC        | Gas line within 5.0 feet of test location. No Auger/DCP Performed       | -                  | -                     | -             | -                 | Low to Moderate Severity Transverse and Longitudinal Cracking                                                          | 602,716         | 1,519,204 |
| C-34<br>-Y1- Sta. 51+16<br>LTL (LT)     | At Grade                       | 12.0       | 2.0 PS<br>Concrete Median     | 7.0 RT<br>FY                | Cr.                    | 25.00                | 8.00    | 17.00 |                     |          | Asphalt<br>ABC<br>SG  | 2.1-5.0: RES - Red-Brown, Silty CLAY, Highly Plastic                    | S-34               | A-7-6(13)             | M             | 5                 | Moderate Severity Transverse Cracking                                                                                  | 602,793         | 1,519,382 |
| C-35<br>-L- Sta. 15+81<br>CONCRETE LOT  | Fill<br>10.0                   | -          | -                             | -                           | -                      | 18.00                |         | 9.25  |                     | 8.75     | Concrete<br>ABC<br>SG | 1.5-5.0: AF - Red-Brown, Fine to Coarse Sandy CLAY                      | S-35               | A-6(7)                | M             | 5                 | No Distress Observed                                                                                                   | 602,371         | 1,518,485 |
| C-36<br>-L- Sta. 17+33<br>ASPHALT LOT   | Fill<br>10.0                   | -          | -                             | -                           | -                      | 15.00                | 3.50    | 11.50 |                     |          | Asphalt<br>ABC<br>SG  | 1.3-5.0: AF - Red-Brown, Silty CLAY, Highly Plastic                     | S-36               | A-7-6(20)             | M             | 5                 | Low to Moderate Severity Longitudinal Cracking                                                                         | 602,219         | 1,518,502 |
| C-39<br>-L- Sta. 51+25<br>RT LN         | At Grade                       | 12.0       | -                             | 4.0 LT<br>EOP               | Cr.                    | 11.00                | 11.00   |       |                     |          | Asphalt<br>SG         | 0.9-5.0: RES - Tan-Orange, Silty CLAY, Highly Plastic                   | S-39               | A-7-6(20)             | M             | 5                 | Moderate to High Severity Transverse and Longitudinal Cracking, Cracks Sealed                                          | 600,658         | 1,521,061 |
| C-40<br>-L- Sta. 51+25<br>RT PS         | At Grade                       | 12.0       | -                             | 1.0 LT<br>EOP               | Cr.                    | 10.75                | 10.75   |       |                     |          | Asphalt<br>SG         | 0.9-5.0: RES - Tan-Orange, Fine to Coarse Sandy CLAY                    | S-40               | A-6(8)                | M             | 5                 | Moderate to High Severity Transverse and Longitudinal Cracking, Cracks Sealed                                          | 600,657         | 1,521,058 |
| C-37<br>-Y2- Sta. 23+62<br>RT LN        | Fill<br>5.0                    | 12.0       | 2.0 PS                        | 1.0 LT<br>FW                | Cr.                    | 17.00                | 7.25    | 9.75  |                     |          | Asphalt<br>ABC<br>SG  | 1.4-5.0: RE - Red-Brown, Fine to Coarse Sandy CLAY                      | S-37               | A-6(2)                | M             | 5                 | Low to Moderate Severity Transverse and Longitudinal Cracking, Cracks Sealed<br><b>2 Inch Bottom-Up Crack in Core</b>  | 602,609         | 1,520,179 |
| C-38<br>-Y3- Sta. 12+84<br>LT LN        | At Grade                       | 12.0       | 3.0 Concrete<br>Curb & Gutter | 3.0 RT<br>C&G               | Cr.                    | 21.00                | 9.25    | 11.75 |                     |          | Asphalt<br>ABC<br>SG  | 1.8-5.0: RE - Red-Brown, Fine to Coarse Sandy SILT                      | S-38               | A-4(2)                | M             | 5                 | Moderate to High Severity Transverse and Longitudinal Cracking, Cracks Sealed<br><b>6 Inch Bottom-Up Crack in Core</b> | 601,478         | 1,520,827 |
| S1<br>-Y1- Sta. 26+47<br>Grass Shoulder | Fill<br>5.0                    | -          | -                             | 3.5 RT<br>FW                | Cr.                    | -                    | -       | -     | -                   | -        | Grass<br>Shoulder     | 1.0-1.5: RE - Red-Brown, Silty CLAY, with F. to Cse, Sand, Mod. Plastic | Ref-14             | A-7-6                 | -             | 1.5               | No Distress Observed                                                                                                   | 602,099         | 1,517,021 |
| S2<br>-Y1- Sta. 26+55<br>Grass Shoulder | Fill<br>5.0                    | -          | -                             | 3.5 RT<br>FW                | Cr.                    | -                    | -       | -     | -                   | -        | Grass<br>Shoulder     | 1.0-1.5: RE - Red-Brown, Silty CLAY, with F. to Cse, Sand, Mod. Plastic | Ref-14             | A-7-6                 | -             | 1.5               | No Distress Observed                                                                                                   | 602,102         | 1,517,028 |
| S3<br>-Y1- Sta. 26+62<br>Grass Shoulder | Fill<br>5.0                    | -          | -                             | 3.5 RT<br>FW                | Cr.                    | -                    | -       | -     | -                   | -        | Grass<br>Shoulder     | 1.0-1.5: RE - Red-Brown, Silty CLAY, with F. to Cse, Sand, Mod. Plastic | Ref-14             | A-7-6                 | -             | 1.5               | No Distress Observed                                                                                                   | 602,105         | 1,517,034 |
| S4<br>-Y1- Sta. 26+79<br>Grass Shoulder | Fill<br>5.0                    | -          | -                             | 3.5 RT<br>FW                | Cr.                    | -                    | -       | -     | -                   | -        | Grass<br>Shoulder     | 1.0-1.5: RE - Red-Brown, Silty CLAY, with F. to Cse, Sand, Mod. Plastic | Ref-14             | A-7-6                 | -             | 1.5               | No Distress Observed                                                                                                   | 602,113         | 1,517,049 |
|                                         |                                |            |                               |                             |                        |                      |         |       |                     |          |                       |                                                                         |                    |                       |               |                   |                                                                                                                        |                 |           |

Notes:

Offset Distance: Left and Right Relative to the Direction of Travel

Prepared by: CTW  
Reviewed by: DMB

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |       |          |  |       |  |             | WBS NO.         |        | PROJECT TIP I.D.                      |  |                                   |  | ROUTE                                                                            |  |               |  |
|------------------------------------------------|------------------------|-------|----------|--|-------|--|-------------|-----------------|--------|---------------------------------------|--|-----------------------------------|--|----------------------------------------------------------------------------------|--|---------------|--|
|                                                |                        |       |          |  |       |  |             | 46891.1.1       |        | U-5956                                |  |                                   |  | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |  |               |  |
|                                                |                        |       |          |  |       |  |             | COUNTY          |        | FIELD PROFESSIONAL                    |  |                                   |  | FIELD CREW                                                                       |  |               |  |
| Cabarrus                                       |                        |       |          |  |       |  |             | T. Wenner, P.G. |        |                                       |  | C. Odom, D. Underwood, P. Tomasic |  |                                                                                  |  |               |  |
| Test Location                                  |                        |       |          |  |       |  |             | Date Run        |        | Test Location                         |  |                                   |  |                                                                                  |  | Date Run      |  |
| C-4 -Y1- Sta. 6+64 RT ISL 1.8 FT RT FY         |                        |       |          |  |       |  |             | 8/7 to 8/9/22   |        | C-5 -Y1- Sta. 6+64 RT PS 1.8 FT RT FW |  |                                   |  |                                                                                  |  | 8/7 to 8/9/22 |  |
| Type                                           | Test Interval          |       |          |  | Datum |  | Cut/Fill    |                 | Type   | Test Interval                         |  |                                   |  | Datum                                                                            |  | Cut/Fill      |  |
| DCP                                            | Cumulative cm per blow |       |          |  | ABC   |  | 5.0 ft Fill |                 | DCP    | Cumulative cm per blow                |  |                                   |  | SG (A-4)                                                                         |  | 5.0 ft Fill   |  |
| 1.10                                           | 1.50                   | 13.80 | 48.15    |  |       |  |             | 3.90            | 100.00 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 1.90                                           | 1.70                   | 14.00 | 48.30    |  |       |  |             | 7.40            | 100.40 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 2.40                                           | 1.90                   | 14.30 | 48.43    |  |       |  |             | 10.60           | 101.20 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 2.70                                           | 2.10                   | 14.60 | 48.56    |  |       |  |             | 13.60           | 101.50 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 3.00                                           | 2.30                   | 14.80 | 48.69    |  |       |  |             | 15.80           | 102.30 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 3.30                                           | 2.50                   | 15.10 | 48.82    |  |       |  |             | 18.70           | 103.40 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 3.47                                           | 2.68                   | 15.40 | 48.95    |  |       |  |             | 21.80           | 104.00 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 3.65                                           | 2.86                   | 15.80 | 49.08    |  |       |  |             | 25.30           | 104.30 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 3.82                                           | 3.04                   | 16.10 | 49.21    |  |       |  |             | 29.80           | 105.10 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 3.99                                           | 3.22                   | 16.50 | 49.34    |  |       |  |             | 34.50           | 105.60 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 4.16                                           | 3.40                   | 16.80 | 49.47    |  |       |  |             | 38.10           | 106.10 |                                       |  |                                   |  |                                                                                  |  |               |  |
| 4.34                                           | 3.60                   | 17.30 | 49.60    |  |       |  |             | 41.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 4.51                                           | 3.80                   | 17.70 | 49.75    |  |       |  |             | 44.80           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 4.68                                           | 4.10                   | 18.20 | 49.90    |  |       |  |             | 47.80           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 4.85                                           | 4.30                   | 18.60 | 50.05    |  |       |  |             | 51.20           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 5.03                                           | 4.50                   | 19.10 | 50.20    |  |       |  |             | 53.80           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 5.20                                           | 4.68                   | 19.50 | 50.35    |  |       |  |             | 55.80           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 5.32                                           | 4.86                   | 20.00 | 50.50    |  |       |  |             | 57.90           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 5.44                                           | 5.04                   | 20.40 | 50.65    |  |       |  |             | 59.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 5.56                                           | 5.22                   | 20.90 | 50.80    |  |       |  |             | 60.90           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 5.68                                           | 5.40                   | 21.30 | 50.95    |  |       |  |             | 62.20           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 5.80                                           | 5.60                   | 22.00 | 51.10    |  |       |  |             | 63.20           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 5.92                                           | 5.80                   | 22.60 | 51.24    |  |       |  |             | 64.10           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 6.04                                           | 6.10                   | 23.30 | 51.39    |  |       |  |             | 65.30           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 6.16                                           | 6.30                   | 23.90 | 51.53    |  |       |  |             | 66.30           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 6.28                                           | 6.50                   | 24.60 | 51.68    |  |       |  |             | 67.50           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 6.40                                           | 6.70                   | 26.00 | 51.82    |  |       |  |             | 68.60           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 6.52                                           | 6.90                   | 27.40 | 51.97    |  |       |  |             | 69.70           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 6.64                                           | 7.20                   | 28.80 | 52.11    |  |       |  |             | 71.10           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 6.76                                           | 7.40                   | 30.20 | 52.26    |  |       |  |             | 72.30           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 6.88                                           | 7.60                   | 31.60 | 52.40    |  |       |  |             | 73.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.00                                           | 7.90                   | 33.60 | DCP REF. |  |       |  |             | 74.60           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.12                                           | 8.10                   | 35.40 | 50/3.0"  |  |       |  |             | 75.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.24                                           | 8.40                   | 36.10 |          |  |       |  |             | 76.50           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.36                                           | 8.60                   | 37.30 |          |  |       |  |             | 77.30           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.48                                           | 8.90                   | 37.90 |          |  |       |  |             | 78.20           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.60                                           | 8.99                   | 38.70 |          |  |       |  |             | 79.50           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.66                                           | 9.08                   | 39.40 |          |  |       |  |             | 80.30           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.71                                           | 9.17                   | 40.10 |          |  |       |  |             | 81.30           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.77                                           | 9.26                   | 41.10 |          |  |       |  |             | 82.10           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.82                                           | 9.35                   | 41.90 |          |  |       |  |             | 82.70           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.88                                           | 9.44                   | 42.70 |          |  |       |  |             | 83.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.93                                           | 9.53                   | 43.50 |          |  |       |  |             | 83.90           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 7.99                                           | 9.62                   | 44.00 |          |  |       |  |             | 84.60           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.04                                           | 9.71                   | 44.40 |          |  |       |  |             | 85.60           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.10                                           | 9.80                   | 44.80 |          |  |       |  |             | 86.70           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.15                                           | 10.00                  | 45.30 |          |  |       |  |             | 88.60           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.21                                           | 10.20                  | 45.45 |          |  |       |  |             | 89.20           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.26                                           | 10.50                  | 45.60 |          |  |       |  |             | 89.70           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.32                                           | 10.70                  | 45.75 |          |  |       |  |             | 90.20           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.37                                           | 10.90                  | 45.90 |          |  |       |  |             | 91.50           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.43                                           | 11.05                  | 46.05 |          |  |       |  |             | 92.50           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.48                                           | 11.20                  | 46.20 |          |  |       |  |             | 92.90           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.54                                           | 11.35                  | 46.35 |          |  |       |  |             | 93.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.59                                           | 11.50                  | 46.50 |          |  |       |  |             | 94.20           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.65                                           | 11.65                  | 46.65 |          |  |       |  |             | 94.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 8.70                                           | 11.80                  | 46.80 |          |  |       |  |             | 95.10           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| DCP REF.                                       | 11.95                  | 46.95 |          |  |       |  |             | 95.80           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| AUGER 12.9                                     | 12.10                  | 47.10 |          |  |       |  |             | 96.10           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| TO 21.6 CM                                     | 12.25                  | 47.25 |          |  |       |  |             | 96.80           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 0.00                                           | 12.40                  | 47.40 |          |  |       |  |             | 97.30           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 0.30                                           | 12.70                  | 47.55 |          |  |       |  |             | 97.80           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 0.60                                           | 12.90                  | 47.70 |          |  |       |  |             | 98.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 0.90                                           | 13.20                  | 47.85 |          |  |       |  |             | 99.10           |        |                                       |  |                                   |  |                                                                                  |  |               |  |
| 1.20                                           | 13.50                  | 48.00 |          |  |       |  |             | 99.40           |        |                                       |  |                                   |  |                                                                                  |  |               |  |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |          |       |  |             |  | WBS NO.       |                        | PROJECT TIP I.D.                          |       |          |             | ROUTE                                                                         |  |  |  |
|------------------------------------------------|------------------------|----------|-------|--|-------------|--|---------------|------------------------|-------------------------------------------|-------|----------|-------------|-------------------------------------------------------------------------------|--|--|--|
|                                                |                        |          |       |  |             |  | 46891.1.1     |                        | U-5956                                    |       |          |             | US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd. |  |  |  |
|                                                |                        |          |       |  |             |  | COUNTY        |                        | FIELD PROFESSIONAL                        |       |          |             | FIELD CREW                                                                    |  |  |  |
|                                                |                        |          |       |  |             |  | Cabarrus      |                        | T. Wenner, P.G.                           |       |          |             | C. Odom, D. Underwood, P. Tomasic                                             |  |  |  |
| Test Location                                  |                        |          |       |  |             |  | Date Run      |                        | Test Location                             |       |          |             | Date Run                                                                      |  |  |  |
| C-6 -Y1- Sta. 18+03 LTL (LT) 5.0 FT RT FY      |                        |          |       |  |             |  | 8/7 to 8/9/22 |                        | C-7 -Y1- Sta. 22+32 LTL (LT) 7.0 FT RT FY |       |          |             | 8/7 to 8/9/22                                                                 |  |  |  |
| Type                                           | Test Interval          |          | Datum |  | Cut/Fill    |  | Type          | Test Interval          |                                           | Datum |          | Cut/Fill    |                                                                               |  |  |  |
| DCP                                            | Cumulative cm per blow |          | ABC   |  | 5.0 ft Fill |  | DCP           | Cumulative cm per blow |                                           | ABC   |          | 5.0 ft Fill |                                                                               |  |  |  |
| 0.50                                           | DCP REF.               | 54.20    |       |  |             |  | 0.50          | 3.20                   | 31.80                                     | 65.00 | 83.68    |             |                                                                               |  |  |  |
| 1.00                                           | AUGER 14.6             | 54.70    |       |  |             |  | 1.10          | 3.50                   | 32.10                                     | 65.70 | 83.77    |             |                                                                               |  |  |  |
| 1.50                                           | TO 33.0 CM             | 55.20    |       |  |             |  | 1.18          | 3.90                   | 32.30                                     | 66.50 | 83.86    |             |                                                                               |  |  |  |
| 2.00                                           | 2.90                   | 55.70    |       |  |             |  | 1.25          | 4.20                   | 32.60                                     | 67.10 | 83.95    |             |                                                                               |  |  |  |
| 2.50                                           | 5.70                   | 56.10    |       |  |             |  | 1.33          | 4.60                   | 32.90                                     | 68.10 | 84.04    |             |                                                                               |  |  |  |
| 3.10                                           | 8.20                   | 56.50    |       |  |             |  | 1.41          | 4.90                   | 33.20                                     | 69.10 | 84.13    |             |                                                                               |  |  |  |
| 3.70                                           | 11.90                  | 56.90    |       |  |             |  | 1.48          | 5.30                   | 33.80                                     | 70.30 | 84.22    |             |                                                                               |  |  |  |
| 4.30                                           | 14.80                  | 57.30    |       |  |             |  | 1.56          | 6.00                   | 34.10                                     | 71.10 | 84.31    |             |                                                                               |  |  |  |
| 4.90                                           | 16.10                  | 57.70    |       |  |             |  | 1.63          | 6.60                   | 34.60                                     | 72.10 | 84.40    |             |                                                                               |  |  |  |
| 5.50                                           | 17.60                  | 57.83    |       |  |             |  | 1.71          | 7.30                   | 35.30                                     | 72.60 | 84.43    |             |                                                                               |  |  |  |
| 6.80                                           | 18.70                  | 57.96    |       |  |             |  | 1.79          | 7.90                   | 36.10                                     | 73.10 | 84.45    |             |                                                                               |  |  |  |
| 8.00                                           | 20.00                  | 58.09    |       |  |             |  | 1.86          | 8.60                   | 36.90                                     | 73.50 | 84.48    |             |                                                                               |  |  |  |
| 9.30                                           | 21.00                  | 58.22    |       |  |             |  | 1.94          | 9.70                   | 38.00                                     | 74.00 | 84.50    |             |                                                                               |  |  |  |
| 10.50                                          | 21.20                  | 58.35    |       |  |             |  | 2.02          | 10.80                  | 39.00                                     | 74.50 | 84.53    |             |                                                                               |  |  |  |
| 12.30                                          | 21.40                  | 58.48    |       |  |             |  | 2.09          | 12.00                  | 40.00                                     | 74.80 | 84.55    |             |                                                                               |  |  |  |
| 12.60                                          | 21.60                  | 58.61    |       |  |             |  | 2.17          | 13.10                  | 40.80                                     | 75.10 | 84.58    |             |                                                                               |  |  |  |
| 12.80                                          | 21.80                  | 58.74    |       |  |             |  | 2.25          | 14.20                  | 41.50                                     | 75.30 | 84.60    |             |                                                                               |  |  |  |
| 13.10                                          | 22.00                  | 58.87    |       |  |             |  | 2.32          | 15.20                  | 42.40                                     | 75.60 | 84.63    |             |                                                                               |  |  |  |
| 13.30                                          | 22.30                  | 59.00    |       |  |             |  | 2.40          | 16.40                  | 43.20                                     | 75.90 | 84.65    |             |                                                                               |  |  |  |
| 13.60                                          | 22.60                  | 59.02    |       |  |             |  | 2.47          | 17.50                  | 44.00                                     | 76.10 | 84.68    |             |                                                                               |  |  |  |
| 13.90                                          | 23.00                  | 59.03    |       |  |             |  | 2.55          | 18.00                  | 44.90                                     | 76.40 | 84.70    |             |                                                                               |  |  |  |
| 14.10                                          | 23.30                  | 59.05    |       |  |             |  | 2.63          | 18.60                  | 45.90                                     | 76.60 | 84.73    |             |                                                                               |  |  |  |
| 14.40                                          | 23.60                  | 59.06    |       |  |             |  | 2.70          | 19.00                  | 46.30                                     | 76.90 | 84.75    |             |                                                                               |  |  |  |
| 14.60                                          | 24.00                  | 59.08    |       |  |             |  | 2.78          | 19.40                  | 47.40                                     | 77.10 | 84.78    |             |                                                                               |  |  |  |
| 14.90                                          | 24.40                  | 59.09    |       |  |             |  | 2.86          | 19.70                  | 48.00                                     | 77.30 | 84.80    |             |                                                                               |  |  |  |
| 15.05                                          | 24.70                  | 59.11    |       |  |             |  | 2.93          | 20.00                  | 48.70                                     | 77.50 | 84.83    |             |                                                                               |  |  |  |
| 15.20                                          | 25.10                  | 59.12    |       |  |             |  | 3.01          | 20.20                  | 49.00                                     | 77.70 | 84.85    |             |                                                                               |  |  |  |
| 15.35                                          | 25.50                  | 59.14    |       |  |             |  | 3.09          | 20.50                  | 50.20                                     | 77.90 | 84.88    |             |                                                                               |  |  |  |
| 15.50                                          | 26.20                  | 59.15    |       |  |             |  | 3.16          | 20.80                  | 50.70                                     | 78.10 | 84.90    |             |                                                                               |  |  |  |
| 15.65                                          | 26.90                  | 59.17    |       |  |             |  | 3.24          | 21.10                  | 51.00                                     | 78.28 | DCP REF. |             |                                                                               |  |  |  |
| 15.80                                          | 27.50                  | 59.18    |       |  |             |  | 3.31          | 21.40                  | 51.20                                     | 78.46 | 50/1.0"  |             |                                                                               |  |  |  |
| 15.95                                          | 28.20                  | 59.20    |       |  |             |  | 3.39          | 21.70                  | 51.50                                     | 78.64 |          |             |                                                                               |  |  |  |
| 16.10                                          | 28.90                  | 59.21    |       |  |             |  | 3.47          | 22.00                  | 52.00                                     | 78.82 |          |             |                                                                               |  |  |  |
| 16.25                                          | 29.60                  | 59.23    |       |  |             |  | 3.54          | 22.30                  | 52.20                                     | 79.00 |          |             |                                                                               |  |  |  |
| 16.40                                          | 30.30                  | 59.24    |       |  |             |  | 3.62          | 22.60                  | 52.40                                     | 79.18 |          |             |                                                                               |  |  |  |
| 16.57                                          | 30.90                  | 59.26    |       |  |             |  | 3.70          | 23.10                  | 52.60                                     | 79.36 |          |             |                                                                               |  |  |  |
| 16.74                                          | 31.60                  | 59.27    |       |  |             |  | 3.77          | 23.70                  | 52.80                                     | 79.54 |          |             |                                                                               |  |  |  |
| 16.91                                          | 32.30                  | 59.29    |       |  |             |  | 3.85          | 24.90                  | 53.00                                     | 79.72 |          |             |                                                                               |  |  |  |
| 17.08                                          | 33.20                  | 59.30    |       |  |             |  | 3.93          | 25.90                  | 53.20                                     | 79.90 |          |             |                                                                               |  |  |  |
| 17.25                                          | 34.20                  | 59.32    |       |  |             |  | 4.00          | 26.80                  | 53.40                                     | 80.10 |          |             |                                                                               |  |  |  |
| 17.42                                          | 35.10                  | 59.33    |       |  |             |  | 4.08          | 27.50                  | 53.60                                     | 80.30 |          |             |                                                                               |  |  |  |
| 17.59                                          | 36.10                  | 59.35    |       |  |             |  | 4.15          | 27.90                  | 53.80                                     | 80.50 |          |             |                                                                               |  |  |  |
| 17.76                                          | 37.00                  | 59.36    |       |  |             |  | 4.23          | 28.40                  | 54.00                                     | 80.70 |          |             |                                                                               |  |  |  |
| 17.93                                          | 38.40                  | 59.38    |       |  |             |  | 4.31          | 28.90                  | 54.18                                     | 80.90 |          |             |                                                                               |  |  |  |
| 18.10                                          | 39.30                  | 59.39    |       |  |             |  | 4.38          | 29.10                  | 54.36                                     | 81.08 |          |             |                                                                               |  |  |  |
| 18.12                                          | 40.50                  | 59.41    |       |  |             |  | 4.46          | 29.30                  | 54.54                                     | 81.26 |          |             |                                                                               |  |  |  |
| 18.13                                          | 42.60                  | 59.42    |       |  |             |  | 4.54          | 29.60                  | 54.72                                     | 81.44 |          |             |                                                                               |  |  |  |
| 18.15                                          | 43.40                  | 59.44    |       |  |             |  | 4.61          | 29.80                  | 54.90                                     | 81.62 |          |             |                                                                               |  |  |  |
| 18.16                                          | 44.60                  | 59.45    |       |  |             |  | 4.69          | 30.00                  | 55.30                                     | 81.80 |          |             |                                                                               |  |  |  |
| 18.18                                          | 45.60                  | 59.47    |       |  |             |  | 4.77          | 30.06                  | 55.70                                     | 81.98 |          |             |                                                                               |  |  |  |
| 18.19                                          | 46.60                  | 59.48    |       |  |             |  | 4.84          | 30.12                  | 56.20                                     | 82.16 |          |             |                                                                               |  |  |  |
| 18.21                                          | 47.80                  | 59.50    |       |  |             |  | 4.92          | 30.18                  | 56.60                                     | 82.34 |          |             |                                                                               |  |  |  |
| 18.22                                          | 49.10                  | 59.51    |       |  |             |  | 4.99          | 30.24                  | 57.00                                     | 82.52 |          |             |                                                                               |  |  |  |
| 18.24                                          | 50.30                  | 59.53    |       |  |             |  | 5.07          | 30.30                  | 57.60                                     | 82.70 |          |             |                                                                               |  |  |  |
| 18.25                                          | 50.60                  | 59.54    |       |  |             |  | 5.15          | 30.36                  | 58.10                                     | 82.78 |          |             |                                                                               |  |  |  |
| 18.27                                          | 50.80                  | 59.56    |       |  |             |  | 5.22          | 30.42                  | 58.70                                     | 82.86 |          |             |                                                                               |  |  |  |
| 18.28                                          | 51.10                  | 59.57    |       |  |             |  | 5.30          | 30.48                  | 59.20                                     | 82.94 |          |             |                                                                               |  |  |  |
| 18.30                                          | 51.30                  | 59.59    |       |  |             |  | DCP REF       | 30.54                  | 59.80                                     | 83.02 |          |             |                                                                               |  |  |  |
| 18.31                                          | 51.60                  | 59.60    |       |  |             |  | AUGER 21.9    | 30.60                  | 60.40                                     | 83.10 |          |             |                                                                               |  |  |  |
| 18.33                                          | 51.90                  | DCP REF. |       |  |             |  | TO 27.2 CM    | 30.74                  | 61.00                                     | 83.18 |          |             |                                                                               |  |  |  |
| 18.34                                          | 52.20                  | 50/1.0"  |       |  |             |  | 0.90          | 30.88                  | 61.50                                     | 83.26 |          |             |                                                                               |  |  |  |
| 18.36                                          | 52.60                  |          |       |  |             |  | 1.80          | 31.02                  | 62.10                                     | 83.34 |          |             |                                                                               |  |  |  |
| 18.37                                          | 52.90                  |          |       |  |             |  | 2.10          | 31.16                  | 62.70                                     | 83.42 |          |             |                                                                               |  |  |  |
| 18.39                                          | 53.20                  |          |       |  |             |  | 2.50          | 31.30                  | 63.50                                     | 83.50 |          |             |                                                                               |  |  |  |
| 18.40                                          | 53.70                  |          |       |  |             |  | 2.80          | 31.60                  | 64.20                                     | 83.59 |          |             |                                                                               |  |  |  |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |  |  |  |          |  |  | WBS NO.       |  | PROJECT TIP I.D.                        |                        |       |       | ROUTE                                                                            |       |               |          |  |
|------------------------------------------------|------------------------|--|--|--|----------|--|--|---------------|--|-----------------------------------------|------------------------|-------|-------|----------------------------------------------------------------------------------|-------|---------------|----------|--|
|                                                |                        |  |  |  |          |  |  | 46891.1.1     |  | U-5956                                  |                        |       |       | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |       |               |          |  |
|                                                |                        |  |  |  |          |  |  | COUNTY        |  | FIELD PROFESSIONAL                      |                        |       |       | FIELD CREW                                                                       |       |               |          |  |
|                                                |                        |  |  |  |          |  |  | Cabarrus      |  | T. Wenner, P.G.                         |                        |       |       | C. Odom, D. Underwood, P. Tomasic                                                |       |               |          |  |
| Test Location                                  |                        |  |  |  |          |  |  | Date Run      |  | Test Location                           |                        |       |       |                                                                                  |       | Date Run      |          |  |
| C-8 -Y1- Sta. 24+65 LTL (RT) 8.5 FT RT FY      |                        |  |  |  |          |  |  | 8/7 to 8/9/22 |  | C-9 -Y1- Sta. 24+65 RT ISL 8.0 FT RT FW |                        |       |       |                                                                                  |       | 8/7 to 8/9/22 |          |  |
| Type                                           | Test Interval          |  |  |  | Datum    |  |  | Cut/Fill      |  | Type                                    | Test Interval          |       |       |                                                                                  | Datum |               | Cut/Fill |  |
| DCP                                            | Cumulative cm per blow |  |  |  | SG (A-4) |  |  | At Grade      |  | DCP                                     | Cumulative cm per blow |       |       |                                                                                  | ABC   |               | At Grade |  |
| 3.20                                           | 76.06                  |  |  |  |          |  |  |               |  | 0.20                                    | 2.10                   | 18.00 | 78.10 |                                                                                  |       |               |          |  |
| 4.60                                           | 76.40                  |  |  |  |          |  |  |               |  | 0.40                                    | 2.40                   | 19.00 | 78.70 |                                                                                  |       |               |          |  |
| 5.60                                           | 77.00                  |  |  |  |          |  |  |               |  | 0.60                                    | 2.60                   | 20.00 | 79.20 |                                                                                  |       |               |          |  |
| 6.10                                           | 77.60                  |  |  |  |          |  |  |               |  | 0.80                                    | 2.90                   | 21.20 | 79.80 |                                                                                  |       |               |          |  |
| 6.50                                           | 78.20                  |  |  |  |          |  |  |               |  | 1.00                                    | 3.20                   | 22.30 | 80.40 |                                                                                  |       |               |          |  |
| 7.00                                           | 78.80                  |  |  |  |          |  |  |               |  | 1.20                                    | 3.34                   | 23.20 | 81.00 |                                                                                  |       |               |          |  |
| 7.40                                           | 79.40                  |  |  |  |          |  |  |               |  | 1.40                                    | 3.48                   | 24.10 | 81.60 |                                                                                  |       |               |          |  |
| 7.90                                           | 79.60                  |  |  |  |          |  |  |               |  | 1.70                                    | 3.62                   | 25.10 | 82.30 |                                                                                  |       |               |          |  |
| 8.50                                           | 79.90                  |  |  |  |          |  |  |               |  | 1.90                                    | 3.76                   | 26.10 | 83.10 |                                                                                  |       |               |          |  |
| 9.20                                           | 80.10                  |  |  |  |          |  |  |               |  | 2.10                                    | 3.90                   | 27.00 | 83.80 |                                                                                  |       |               |          |  |
| 9.80                                           | 80.40                  |  |  |  |          |  |  |               |  | 2.21                                    | 4.04                   | 27.90 | 84.50 |                                                                                  |       |               |          |  |
| 10.50                                          | 80.60                  |  |  |  |          |  |  |               |  | 2.32                                    | 4.18                   | 29.10 | 85.40 |                                                                                  |       |               |          |  |
| 11.10                                          | 81.20                  |  |  |  |          |  |  |               |  | 2.43                                    | 4.32                   | 30.30 | 86.00 |                                                                                  |       |               |          |  |
| 11.80                                          | 81.70                  |  |  |  |          |  |  |               |  | 2.54                                    | 4.46                   | 31.60 | 86.50 |                                                                                  |       |               |          |  |
| 12.40                                          | 82.30                  |  |  |  |          |  |  |               |  | 2.65                                    | 4.60                   | 32.80 | 87.40 |                                                                                  |       |               |          |  |
| 13.10                                          | 82.80                  |  |  |  |          |  |  |               |  | 2.76                                    | 4.72                   | 34.10 | 88.10 |                                                                                  |       |               |          |  |
| 13.70                                          | 83.40                  |  |  |  |          |  |  |               |  | 2.87                                    | 4.84                   | 35.30 | 88.60 |                                                                                  |       |               |          |  |
| 14.40                                          | 84.10                  |  |  |  |          |  |  |               |  | 2.98                                    | 4.96                   | 36.20 | 89.70 |                                                                                  |       |               |          |  |
| 15.20                                          | 84.90                  |  |  |  |          |  |  |               |  | 3.09                                    | 5.08                   | 37.30 | 91.00 |                                                                                  |       |               |          |  |
| 16.00                                          | 85.50                  |  |  |  |          |  |  |               |  | 3.20                                    | 5.20                   | 38.30 | 92.20 |                                                                                  |       |               |          |  |
| 16.80                                          | 86.40                  |  |  |  |          |  |  |               |  | 3.38                                    | 5.40                   | 39.40 |       |                                                                                  |       |               |          |  |
| 17.60                                          | 87.00                  |  |  |  |          |  |  |               |  | 3.56                                    | 5.60                   | 40.60 |       |                                                                                  |       |               |          |  |
| 18.40                                          | 87.30                  |  |  |  |          |  |  |               |  | 3.74                                    | 5.90                   | 41.50 |       |                                                                                  |       |               |          |  |
| 19.90                                          | 88.10                  |  |  |  |          |  |  |               |  | 3.92                                    | 6.10                   | 42.90 |       |                                                                                  |       |               |          |  |
| 21.10                                          | 89.80                  |  |  |  |          |  |  |               |  | 4.10                                    | 6.30                   | 43.80 |       |                                                                                  |       |               |          |  |
| 22.60                                          | 90.50                  |  |  |  |          |  |  |               |  | 4.28                                    | 6.48                   | 45.00 |       |                                                                                  |       |               |          |  |
| 24.00                                          | 91.40                  |  |  |  |          |  |  |               |  | 4.46                                    | 6.66                   | 46.10 |       |                                                                                  |       |               |          |  |
| 25.60                                          | 92.30                  |  |  |  |          |  |  |               |  | 4.64                                    | 6.84                   | 47.20 |       |                                                                                  |       |               |          |  |
| 27.50                                          | 93.40                  |  |  |  |          |  |  |               |  | 4.82                                    | 7.02                   | 48.30 |       |                                                                                  |       |               |          |  |
| 29.10                                          | 94.80                  |  |  |  |          |  |  |               |  | 5.00                                    | 7.20                   | 49.80 |       |                                                                                  |       |               |          |  |
| 30.60                                          | 95.30                  |  |  |  |          |  |  |               |  | 5.08                                    | 7.36                   | 50.70 |       |                                                                                  |       |               |          |  |
| 31.60                                          | 96.50                  |  |  |  |          |  |  |               |  | 5.15                                    | 7.52                   | 52.00 |       |                                                                                  |       |               |          |  |
| 32.70                                          | 97.30                  |  |  |  |          |  |  |               |  | 5.23                                    | 7.68                   | 53.10 |       |                                                                                  |       |               |          |  |
| 34.30                                          | 98.10                  |  |  |  |          |  |  |               |  | 5.30                                    | 7.84                   | 54.20 |       |                                                                                  |       |               |          |  |
| 35.50                                          | 98.80                  |  |  |  |          |  |  |               |  | 5.38                                    | 8.00                   | 55.20 |       |                                                                                  |       |               |          |  |
| 36.70                                          |                        |  |  |  |          |  |  |               |  | 5.45                                    | 8.15                   | 56.00 |       |                                                                                  |       |               |          |  |
| 37.80                                          |                        |  |  |  |          |  |  |               |  | 5.53                                    | 8.30                   | 57.00 |       |                                                                                  |       |               |          |  |
| 39.50                                          |                        |  |  |  |          |  |  |               |  | 5.60                                    | 8.45                   | 57.90 |       |                                                                                  |       |               |          |  |
| 41.00                                          |                        |  |  |  |          |  |  |               |  | 5.68                                    | 8.60                   | 58.60 |       |                                                                                  |       |               |          |  |
| 43.30                                          |                        |  |  |  |          |  |  |               |  | 5.75                                    | 8.75                   | 59.00 |       |                                                                                  |       |               |          |  |
| 45.70                                          |                        |  |  |  |          |  |  |               |  | 5.83                                    | 8.90                   | 59.50 |       |                                                                                  |       |               |          |  |
| 48.10                                          |                        |  |  |  |          |  |  |               |  | 5.90                                    | 9.05                   | 59.90 |       |                                                                                  |       |               |          |  |
| 50.40                                          |                        |  |  |  |          |  |  |               |  | 5.98                                    | 9.20                   | 60.40 |       |                                                                                  |       |               |          |  |
| 52.40                                          |                        |  |  |  |          |  |  |               |  | 6.05                                    | 9.35                   | 61.00 |       |                                                                                  |       |               |          |  |
| 54.40                                          |                        |  |  |  |          |  |  |               |  | 6.13                                    | 9.50                   | 61.70 |       |                                                                                  |       |               |          |  |
| 56.00                                          |                        |  |  |  |          |  |  |               |  | 6.20                                    | 9.70                   | 62.40 |       |                                                                                  |       |               |          |  |
| 57.60                                          |                        |  |  |  |          |  |  |               |  | 6.28                                    | 9.90                   | 62.80 |       |                                                                                  |       |               |          |  |
| 59.30                                          |                        |  |  |  |          |  |  |               |  | 6.35                                    | 10.20                  | 63.30 |       |                                                                                  |       |               |          |  |
| 60.70                                          |                        |  |  |  |          |  |  |               |  | 6.43                                    | 10.40                  | 65.50 |       |                                                                                  |       |               |          |  |
| 61.80                                          |                        |  |  |  |          |  |  |               |  | 6.50                                    | 10.60                  | 66.70 |       |                                                                                  |       |               |          |  |
| 63.00                                          |                        |  |  |  |          |  |  |               |  | 6.65                                    | 10.80                  | 67.80 |       |                                                                                  |       |               |          |  |
| 64.20                                          |                        |  |  |  |          |  |  |               |  | 6.80                                    | 11.00                  | 68.50 |       |                                                                                  |       |               |          |  |
| 65.20                                          |                        |  |  |  |          |  |  |               |  | 6.95                                    | 11.30                  | 68.90 |       |                                                                                  |       |               |          |  |
| 66.50                                          |                        |  |  |  |          |  |  |               |  | 7.10                                    | 11.50                  | 69.70 |       |                                                                                  |       |               |          |  |
| 67.30                                          |                        |  |  |  |          |  |  |               |  | 7.25                                    | 11.70                  | 70.60 |       |                                                                                  |       |               |          |  |
| 68.10                                          |                        |  |  |  |          |  |  |               |  | 7.40                                    | 12.00                  | 72.10 |       |                                                                                  |       |               |          |  |
| 68.70                                          |                        |  |  |  |          |  |  |               |  | 7.55                                    | 12.40                  | 73.00 |       |                                                                                  |       |               |          |  |
| 69.90                                          |                        |  |  |  |          |  |  |               |  | 7.70                                    | 12.70                  | 73.70 |       |                                                                                  |       |               |          |  |
| 71.00                                          |                        |  |  |  |          |  |  |               |  | 7.85                                    | 13.10                  | 74.30 |       |                                                                                  |       |               |          |  |
| 72.40                                          |                        |  |  |  |          |  |  |               |  | 8.00                                    | 13.40                  | 74.90 |       |                                                                                  |       |               |          |  |
| 73.00                                          |                        |  |  |  |          |  |  |               |  | DGP REF.                                | 14.20                  | 75.40 |       |                                                                                  |       |               |          |  |
| 75.00                                          |                        |  |  |  |          |  |  |               |  | AUGER 19.3                              | 15.20                  | 75.90 |       |                                                                                  |       |               |          |  |
| 75.40                                          |                        |  |  |  |          |  |  |               |  | TO 27.3 CM                              | 15.90                  | 76.50 |       |                                                                                  |       |               |          |  |
| 75.70                                          |                        |  |  |  |          |  |  |               |  | 1.10                                    | 16.50                  | 77.00 |       |                                                                                  |       |               |          |  |
| 76.10                                          |                        |  |  |  |          |  |  |               |  | 1.80                                    | 17.10                  | 77.50 |       |                                                                                  |       |               |          |  |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |       |  |       |  | WBS NO.       | PROJECT TIP I.D.                         | ROUTE                                                                            |       |  |            |  |             |
|------------------------------------------------|------------------------|-------|--|-------|--|---------------|------------------------------------------|----------------------------------------------------------------------------------|-------|--|------------|--|-------------|
|                                                |                        |       |  |       |  | 46891.1.1     | U-5956                                   | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |       |  |            |  |             |
|                                                |                        |       |  |       |  | COUNTY        | FIELD PROFESSIONAL                       | FIELD CREW                                                                       |       |  |            |  |             |
|                                                |                        |       |  |       |  | Cabarrus      | T. Wenner/M. Brewer                      | C. Odom, L. Ard, P. Tomasic, D. Underwood                                        |       |  |            |  |             |
| Test Location                                  |                        |       |  |       |  | Date Run      | Test Location                            |                                                                                  |       |  |            |  | Date Run    |
| C-10 -Y1- Sta. 24+65 RT OSL 7.0 FT LT FW       |                        |       |  |       |  | 8/7 to 8/9/22 | C-13 -Y1- Sta. 26+62 LT OSL 5.0 FT LT FW |                                                                                  |       |  |            |  | 9/18/2022   |
| Type                                           | Test Interval          |       |  | Datum |  | Cut/Fill      | Type                                     | Test Interval                                                                    |       |  | Datum      |  | Cut/Fill    |
| DCP                                            | Cumulative cm per blow |       |  | ABC   |  | At Grade      | DCP                                      | Cumulative cm per blow                                                           |       |  | SG (A-7-6) |  | 5.0 ft Fill |
| 0.20                                           | 1.30                   | 56.60 |  |       |  |               | 4 (WOD)                                  | 79.45                                                                            |       |  |            |  |             |
| 0.50                                           | 1.50                   | 57.60 |  |       |  |               |                                          | 21.20                                                                            | 79.50 |  |            |  |             |
| 0.80                                           | 1.80                   | 58.50 |  |       |  |               |                                          | 36.50                                                                            | 79.58 |  |            |  |             |
| 1.00                                           | 2.00                   | 59.00 |  |       |  |               |                                          | 59.90                                                                            | 79.66 |  |            |  |             |
| 1.30                                           | 2.20                   | 59.60 |  |       |  |               |                                          | 65.50                                                                            | 79.74 |  |            |  |             |
| 1.60                                           | 2.40                   | 60.10 |  |       |  |               |                                          | 68.50                                                                            | 79.82 |  |            |  |             |
| 1.90                                           | 2.60                   | 60.70 |  |       |  |               |                                          | 69.70                                                                            | 79.90 |  |            |  |             |
| 2.20                                           | 2.80                   | 61.30 |  |       |  |               |                                          | 70.80                                                                            | 79.98 |  |            |  |             |
| 2.40                                           | 3.00                   | 61.90 |  |       |  |               |                                          | 71.60                                                                            | 80.06 |  |            |  |             |
| 2.70                                           | 3.20                   | 62.40 |  |       |  |               |                                          | 72.10                                                                            | 80.14 |  |            |  |             |
| 3.00                                           | 3.36                   | 63.00 |  |       |  |               |                                          | 72.60                                                                            | 80.22 |  |            |  |             |
| 3.20                                           | 3.52                   | 63.60 |  |       |  |               |                                          | 73.10                                                                            | 80.30 |  |            |  |             |
| 3.40                                           | 3.68                   | 64.20 |  |       |  |               |                                          | 74.00                                                                            |       |  |            |  |             |
| 3.60                                           | 3.84                   | 64.90 |  |       |  |               |                                          | 74.30                                                                            |       |  |            |  |             |
| 3.80                                           | 4.00                   | 65.60 |  |       |  |               |                                          | 74.50                                                                            |       |  |            |  |             |
| 4.00                                           | 4.30                   | 66.20 |  |       |  |               |                                          | 75.00                                                                            |       |  |            |  |             |
| 4.20                                           | 4.60                   | 66.80 |  |       |  |               |                                          | 76.50                                                                            |       |  |            |  |             |
| 4.40                                           | 4.90                   | 67.10 |  |       |  |               |                                          | 76.61                                                                            |       |  |            |  |             |
| 4.60                                           | 5.20                   | 67.70 |  |       |  |               |                                          | 76.72                                                                            |       |  |            |  |             |
| 4.80                                           | 5.50                   | 68.20 |  |       |  |               |                                          | 76.83                                                                            |       |  |            |  |             |
| 5.00                                           | 5.90                   | 68.90 |  |       |  |               |                                          | 76.94                                                                            |       |  |            |  |             |
| 5.18                                           | 6.20                   | 69.30 |  |       |  |               |                                          | 77.05                                                                            |       |  |            |  |             |
| 5.36                                           | 6.60                   | 69.90 |  |       |  |               |                                          | 77.16                                                                            |       |  |            |  |             |
| 5.54                                           | 7.00                   | 70.30 |  |       |  |               |                                          | 77.27                                                                            |       |  |            |  |             |
| 5.72                                           | 7.70                   | 70.70 |  |       |  |               |                                          | 77.38                                                                            |       |  |            |  |             |
| 5.90                                           | 8.20                   | 71.30 |  |       |  |               |                                          | 77.49                                                                            |       |  |            |  |             |
| 6.06                                           | 8.90                   | 72.60 |  |       |  |               |                                          | 77.60                                                                            |       |  |            |  |             |
| 6.22                                           | 9.50                   | 73.40 |  |       |  |               |                                          | 77.65                                                                            |       |  |            |  |             |
| 6.38                                           | 10.20                  | 73.90 |  |       |  |               |                                          | 77.70                                                                            |       |  |            |  |             |
| 6.54                                           | 11.40                  | 74.80 |  |       |  |               |                                          | 77.75                                                                            |       |  |            |  |             |
| 6.70                                           | 13.00                  | 75.40 |  |       |  |               |                                          | 77.80                                                                            |       |  |            |  |             |
| 6.78                                           | 14.40                  | 76.00 |  |       |  |               |                                          | 77.85                                                                            |       |  |            |  |             |
| 6.86                                           | 15.90                  | 76.50 |  |       |  |               |                                          | 77.90                                                                            |       |  |            |  |             |
| 6.94                                           | 17.30                  | 77.00 |  |       |  |               |                                          | 77.95                                                                            |       |  |            |  |             |
| 7.02                                           | 18.80                  | 77.70 |  |       |  |               |                                          | 78.00                                                                            |       |  |            |  |             |
| 7.10                                           | 20.10                  | 78.30 |  |       |  |               |                                          | 78.05                                                                            |       |  |            |  |             |
| 7.18                                           | 21.60                  | 79.10 |  |       |  |               |                                          | 78.10                                                                            |       |  |            |  |             |
| 7.26                                           | 23.30                  | 79.80 |  |       |  |               |                                          | 78.15                                                                            |       |  |            |  |             |
| 7.34                                           | 25.00                  | 80.60 |  |       |  |               |                                          | 78.20                                                                            |       |  |            |  |             |
| 7.42                                           | 26.80                  | 81.50 |  |       |  |               |                                          | 78.25                                                                            |       |  |            |  |             |
| 7.50                                           | 28.50                  | 82.00 |  |       |  |               |                                          | 78.30                                                                            |       |  |            |  |             |
| 7.60                                           | 30.30                  | 82.40 |  |       |  |               |                                          | 78.35                                                                            |       |  |            |  |             |
| 7.70                                           | 32.00                  | 83.20 |  |       |  |               |                                          | 78.40                                                                            |       |  |            |  |             |
| 7.80                                           | 33.40                  | 83.40 |  |       |  |               |                                          | 78.45                                                                            |       |  |            |  |             |
| 7.90                                           | 34.70                  | 83.60 |  |       |  |               |                                          | 78.50                                                                            |       |  |            |  |             |
| 8.00                                           | 35.80                  | 83.80 |  |       |  |               |                                          | 78.55                                                                            |       |  |            |  |             |
| 8.10                                           | 36.90                  | 84.00 |  |       |  |               |                                          | 78.60                                                                            |       |  |            |  |             |
| 8.20                                           | 37.70                  | 84.20 |  |       |  |               |                                          | 78.64                                                                            |       |  |            |  |             |
| 8.30                                           | 38.50                  | 84.40 |  |       |  |               |                                          | 78.68                                                                            |       |  |            |  |             |
| 8.40                                           | 39.30                  | 84.60 |  |       |  |               |                                          | 78.72                                                                            |       |  |            |  |             |
| 8.50                                           | 40.30                  | 84.80 |  |       |  |               |                                          | 78.76                                                                            |       |  |            |  |             |
| 8.61                                           | 41.10                  | 85.00 |  |       |  |               |                                          | 78.80                                                                            |       |  |            |  |             |
| 8.72                                           | 42.10                  | 85.20 |  |       |  |               |                                          | 78.84                                                                            |       |  |            |  |             |
| 8.83                                           | 43.00                  | 85.36 |  |       |  |               |                                          | 78.88                                                                            |       |  |            |  |             |
| 8.94                                           | 44.00                  | 85.52 |  |       |  |               |                                          | 78.92                                                                            |       |  |            |  |             |
| 9.05                                           | 45.60                  | 85.68 |  |       |  |               |                                          | 78.96                                                                            |       |  |            |  |             |
| 9.16                                           | 47.10                  | 85.84 |  |       |  |               |                                          | 79.00                                                                            |       |  |            |  |             |
| 9.27                                           | 48.50                  | 86.00 |  |       |  |               |                                          | 79.05                                                                            |       |  |            |  |             |
| 9.38                                           | 49.60                  | 86.12 |  |       |  |               |                                          | 79.10                                                                            |       |  |            |  |             |
| 9.49                                           | 50.50                  | 86.24 |  |       |  |               |                                          | 79.15                                                                            |       |  |            |  |             |
| 9.60                                           | 51.50                  | 86.36 |  |       |  |               |                                          | 79.20                                                                            |       |  |            |  |             |
| DOP REF.                                       | 52.60                  | 86.48 |  |       |  |               |                                          | 79.25                                                                            |       |  |            |  |             |
| AUGER 13.7                                     | 53.90                  | 86.60 |  |       |  |               |                                          | 79.30                                                                            |       |  |            |  |             |
| TO 23.3 CM                                     | 54.90                  |       |  |       |  |               |                                          | 79.35                                                                            |       |  |            |  |             |
| 1.10                                           | 55.90                  |       |  |       |  |               |                                          | 79.40                                                                            |       |  |            |  |             |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |  |  |            |  |  | WBS NO.     | PROJECT TIP I.D.    |                                            |                        |  | ROUTE                                                                            |            |  |               |             |  |
|------------------------------------------------|------------------------|--|--|------------|--|--|-------------|---------------------|--------------------------------------------|------------------------|--|----------------------------------------------------------------------------------|------------|--|---------------|-------------|--|
|                                                |                        |  |  |            |  |  | 46891.1.1   | U-5956              |                                            |                        |  | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |            |  |               |             |  |
|                                                |                        |  |  |            |  |  | COUNTY      | FIELD PROFESSIONAL  |                                            |                        |  | FIELD CREW                                                                       |            |  |               |             |  |
|                                                |                        |  |  |            |  |  | Cabarrus    | T. Wenner/M. Brewer |                                            |                        |  | C. Odom, L. Ard, P. Tomasic, D. Underwood                                        |            |  |               |             |  |
| Test Location                                  |                        |  |  |            |  |  | Date Run    |                     | Test Location                              |                        |  |                                                                                  |            |  | Date Run      |             |  |
| C-14 -Y1- Sta. 26+62 LT ISL 6.0 FT RT FW       |                        |  |  |            |  |  | 9/18/2022   |                     | C-15 -Y1- Sta. 26+62 LTL (LT) 7.0 FT RT FY |                        |  |                                                                                  |            |  | 8/7 to 8/9/22 |             |  |
| Type                                           | Test Interval          |  |  | Datum      |  |  | Cut/Fill    |                     | Type                                       | Test Interval          |  |                                                                                  | Datum      |  |               | Cut/Fill    |  |
| DCP                                            | Cumulative cm per blow |  |  | SG (A-7-6) |  |  | 5.0 ft Fill |                     | DCP                                        | Cumulative cm per blow |  |                                                                                  | SG (A-7-6) |  |               | 5.0 ft Fill |  |
| 6.10                                           |                        |  |  |            |  |  |             |                     | 1.80                                       | 91.50                  |  |                                                                                  |            |  |               |             |  |
| 9.90                                           |                        |  |  |            |  |  |             |                     | 3.50                                       | 92.80                  |  |                                                                                  |            |  |               |             |  |
| 12.80                                          |                        |  |  |            |  |  |             |                     | 5.40                                       | 93.70                  |  |                                                                                  |            |  |               |             |  |
| 15.80                                          |                        |  |  |            |  |  |             |                     | 7.00                                       | 95.20                  |  |                                                                                  |            |  |               |             |  |
| 19.10                                          |                        |  |  |            |  |  |             |                     | 8.10                                       | 96.50                  |  |                                                                                  |            |  |               |             |  |
| 22.60                                          |                        |  |  |            |  |  |             |                     | 9.30                                       | 97.50                  |  |                                                                                  |            |  |               |             |  |
| 31.20                                          |                        |  |  |            |  |  |             |                     | 10.30                                      | 98.40                  |  |                                                                                  |            |  |               |             |  |
| 36.60                                          |                        |  |  |            |  |  |             |                     | 11.80                                      | 99.60                  |  |                                                                                  |            |  |               |             |  |
| 38.00                                          |                        |  |  |            |  |  |             |                     | 13.10                                      | 100.40                 |  |                                                                                  |            |  |               |             |  |
| 40.00                                          |                        |  |  |            |  |  |             |                     | 14.50                                      |                        |  |                                                                                  |            |  |               |             |  |
| 42.50                                          |                        |  |  |            |  |  |             |                     | 16.00                                      |                        |  |                                                                                  |            |  |               |             |  |
| 45.60                                          |                        |  |  |            |  |  |             |                     | 17.80                                      |                        |  |                                                                                  |            |  |               |             |  |
| 48.70                                          |                        |  |  |            |  |  |             |                     | 19.60                                      |                        |  |                                                                                  |            |  |               |             |  |
| 52.30                                          |                        |  |  |            |  |  |             |                     | 21.20                                      |                        |  |                                                                                  |            |  |               |             |  |
| 56.50                                          |                        |  |  |            |  |  |             |                     | 22.30                                      |                        |  |                                                                                  |            |  |               |             |  |
| 59.50                                          |                        |  |  |            |  |  |             |                     | 23.30                                      |                        |  |                                                                                  |            |  |               |             |  |
| 62.50                                          |                        |  |  |            |  |  |             |                     | 24.50                                      |                        |  |                                                                                  |            |  |               |             |  |
| 66.80                                          |                        |  |  |            |  |  |             |                     | 25.80                                      |                        |  |                                                                                  |            |  |               |             |  |
| 71.30                                          |                        |  |  |            |  |  |             |                     | 26.40                                      |                        |  |                                                                                  |            |  |               |             |  |
| 76.50                                          |                        |  |  |            |  |  |             |                     | 26.80                                      |                        |  |                                                                                  |            |  |               |             |  |
| 79.60                                          |                        |  |  |            |  |  |             |                     | 27.20                                      |                        |  |                                                                                  |            |  |               |             |  |
| 82.50                                          |                        |  |  |            |  |  |             |                     | 27.70                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 28.10                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 28.50                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 29.50                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 30.00                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 30.90                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 31.80                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 32.80                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 34.50                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 36.40                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 38.10                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 39.90                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 42.10                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 44.20                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 46.40                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 48.40                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 50.10                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 52.00                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 53.60                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 55.50                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 57.20                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 59.30                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 61.50                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 63.30                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 65.00                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 66.50                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 68.10                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 69.50                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 71.10                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 72.60                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 73.70                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 74.30                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 76.70                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 78.20                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 79.60                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 80.90                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 82.30                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 83.80                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 84.80                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 86.00                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 87.20                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 88.20                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 89.50                                      |                        |  |                                                                                  |            |  |               |             |  |
|                                                |                        |  |  |            |  |  |             |                     | 90.70                                      |                        |  |                                                                                  |            |  |               |             |  |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |  |  |       |  |  |  | WBS NO.       | PROJECT TIP I.D.                           | ROUTE                                                                            |       |  |       |  |  |  |               |
|------------------------------------------------|------------------------|--|--|-------|--|--|--|---------------|--------------------------------------------|----------------------------------------------------------------------------------|-------|--|-------|--|--|--|---------------|
|                                                |                        |  |  |       |  |  |  | 46891.1.1     | U-5956                                     | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |       |  |       |  |  |  |               |
|                                                |                        |  |  |       |  |  |  | COUNTY        | FIELD PROFESSIONAL                         | FIELD CREW                                                                       |       |  |       |  |  |  |               |
|                                                |                        |  |  |       |  |  |  | Cabarrus      | T. Wenner, P.G.                            | C. Odom, D. Underwood, P. Tomasic                                                |       |  |       |  |  |  |               |
| Test Location                                  |                        |  |  |       |  |  |  | Date Run      | Test Location                              |                                                                                  |       |  |       |  |  |  | Date Run      |
| C-16 -Y1- Sta. 29+24 RTL (RT) 9.0 FT LT FW     |                        |  |  |       |  |  |  | 8/7 to 8/9/22 | C-17 -Y1- Sta. 30+66 LTL (LT) 5.0 FT RT FY |                                                                                  |       |  |       |  |  |  | 8/7 to 8/9/22 |
| Type                                           | Test Interval          |  |  | Datum |  |  |  | Cut/Fill      | Type                                       | Test Interval                                                                    |       |  | Datum |  |  |  | Cut/Fill      |
| DCP                                            | Cumulative cm per blow |  |  | ABC   |  |  |  | 5.0 ft Fill   | DCP                                        | Cumulative cm per blow                                                           |       |  | ABC   |  |  |  | 5.0 ft Fill   |
| 1.40                                           | 94.10                  |  |  |       |  |  |  |               | 1.80                                       | 22.20                                                                            | 70.20 |  |       |  |  |  |               |
| 2.50                                           | 95.40                  |  |  |       |  |  |  |               | 2.50                                       | 22.60                                                                            | 71.40 |  |       |  |  |  |               |
| 3.04                                           | 97.60                  |  |  |       |  |  |  |               | 2.70                                       | 23.00                                                                            | 72.10 |  |       |  |  |  |               |
| 3.58                                           | 98.90                  |  |  |       |  |  |  |               | 3.00                                       | 23.30                                                                            | 73.00 |  |       |  |  |  |               |
| 4.12                                           | 100.60                 |  |  |       |  |  |  |               | 4.10                                       | 23.60                                                                            | 74.00 |  |       |  |  |  |               |
| 4.66                                           |                        |  |  |       |  |  |  |               | 4.50                                       | 23.90                                                                            | 75.10 |  |       |  |  |  |               |
| 5.20                                           |                        |  |  |       |  |  |  |               | 5.00                                       | 24.20                                                                            | 76.70 |  |       |  |  |  |               |
| 5.54                                           |                        |  |  |       |  |  |  |               | 5.40                                       | 24.50                                                                            | 77.50 |  |       |  |  |  |               |
| 5.88                                           |                        |  |  |       |  |  |  |               | 5.80                                       | 24.90                                                                            | 79.30 |  |       |  |  |  |               |
| 6.22                                           |                        |  |  |       |  |  |  |               | 6.10                                       | 25.40                                                                            | 81.00 |  |       |  |  |  |               |
| 6.56                                           |                        |  |  |       |  |  |  |               | 6.50                                       | 25.80                                                                            | 84.30 |  |       |  |  |  |               |
| 6.90                                           |                        |  |  |       |  |  |  |               | 6.80                                       | 26.30                                                                            | 87.00 |  |       |  |  |  |               |
| 7.38                                           |                        |  |  |       |  |  |  |               | 7.40                                       | 26.70                                                                            | 89.50 |  |       |  |  |  |               |
| 7.86                                           |                        |  |  |       |  |  |  |               | 7.70                                       | 27.10                                                                            | 91.90 |  |       |  |  |  |               |
| 8.34                                           |                        |  |  |       |  |  |  |               | 8.00                                       | 27.50                                                                            | 94.10 |  |       |  |  |  |               |
| 8.82                                           |                        |  |  |       |  |  |  |               | 8.30                                       | 28.00                                                                            | 96.00 |  |       |  |  |  |               |
| 9.30                                           |                        |  |  |       |  |  |  |               | 8.60                                       | 28.40                                                                            | 98.60 |  |       |  |  |  |               |
| 9.90                                           |                        |  |  |       |  |  |  |               | 8.90                                       | 28.80                                                                            |       |  |       |  |  |  |               |
| 10.50                                          |                        |  |  |       |  |  |  |               | 9.20                                       | 29.20                                                                            |       |  |       |  |  |  |               |
| 10.90                                          |                        |  |  |       |  |  |  |               | 9.50                                       | 29.60                                                                            |       |  |       |  |  |  |               |
| 11.50                                          |                        |  |  |       |  |  |  |               | 9.80                                       | 29.90                                                                            |       |  |       |  |  |  |               |
| 11.90                                          |                        |  |  |       |  |  |  |               | 10.10                                      | 30.30                                                                            |       |  |       |  |  |  |               |
| 12.30                                          |                        |  |  |       |  |  |  |               | 10.40                                      | 30.70                                                                            |       |  |       |  |  |  |               |
| 12.90                                          |                        |  |  |       |  |  |  |               | 10.80                                      | 31.20                                                                            |       |  |       |  |  |  |               |
| 13.60                                          |                        |  |  |       |  |  |  |               | 11.10                                      | 31.80                                                                            |       |  |       |  |  |  |               |
| 14.30                                          |                        |  |  |       |  |  |  |               | 11.50                                      | 32.30                                                                            |       |  |       |  |  |  |               |
| 14.70                                          |                        |  |  |       |  |  |  |               | 11.80                                      | 32.90                                                                            |       |  |       |  |  |  |               |
| 15.30                                          |                        |  |  |       |  |  |  |               | 12.20                                      | 33.40                                                                            |       |  |       |  |  |  |               |
| 16.00                                          |                        |  |  |       |  |  |  |               | 12.50                                      | 34.00                                                                            |       |  |       |  |  |  |               |
| 16.90                                          |                        |  |  |       |  |  |  |               | 12.80                                      | 34.60                                                                            |       |  |       |  |  |  |               |
| 18.90                                          |                        |  |  |       |  |  |  |               | 13.10                                      | 35.40                                                                            |       |  |       |  |  |  |               |
| 20.50                                          |                        |  |  |       |  |  |  |               | 13.40                                      | 36.00                                                                            |       |  |       |  |  |  |               |
| 24.10                                          |                        |  |  |       |  |  |  |               | 13.70                                      | 36.70                                                                            |       |  |       |  |  |  |               |
| 29.40                                          |                        |  |  |       |  |  |  |               | 13.86                                      | 37.20                                                                            |       |  |       |  |  |  |               |
| 34.10                                          |                        |  |  |       |  |  |  |               | 14.02                                      | 37.70                                                                            |       |  |       |  |  |  |               |
| 36.60                                          |                        |  |  |       |  |  |  |               | 14.18                                      | 38.10                                                                            |       |  |       |  |  |  |               |
| 42.70                                          |                        |  |  |       |  |  |  |               | 14.34                                      | 38.60                                                                            |       |  |       |  |  |  |               |
| 46.00                                          |                        |  |  |       |  |  |  |               | 14.50                                      | 39.10                                                                            |       |  |       |  |  |  |               |
| 49.40                                          |                        |  |  |       |  |  |  |               | 14.70                                      | 39.80                                                                            |       |  |       |  |  |  |               |
| 52.30                                          |                        |  |  |       |  |  |  |               | 14.90                                      | 40.50                                                                            |       |  |       |  |  |  |               |
| 54.50                                          |                        |  |  |       |  |  |  |               | 15.10                                      | 41.10                                                                            |       |  |       |  |  |  |               |
| 56.00                                          |                        |  |  |       |  |  |  |               | 15.30                                      | 41.80                                                                            |       |  |       |  |  |  |               |
| 57.60                                          |                        |  |  |       |  |  |  |               | 15.50                                      | 42.50                                                                            |       |  |       |  |  |  |               |
| 59.00                                          |                        |  |  |       |  |  |  |               | 15.70                                      | 43.40                                                                            |       |  |       |  |  |  |               |
| 60.40                                          |                        |  |  |       |  |  |  |               | 15.90                                      | 44.30                                                                            |       |  |       |  |  |  |               |
| 61.90                                          |                        |  |  |       |  |  |  |               | 16.20                                      | 45.30                                                                            |       |  |       |  |  |  |               |
| 63.20                                          |                        |  |  |       |  |  |  |               | 16.40                                      | 46.20                                                                            |       |  |       |  |  |  |               |
| 64.30                                          |                        |  |  |       |  |  |  |               | 16.60                                      | 47.10                                                                            |       |  |       |  |  |  |               |
| 65.40                                          |                        |  |  |       |  |  |  |               | 16.80                                      | 48.70                                                                            |       |  |       |  |  |  |               |
| 66.60                                          |                        |  |  |       |  |  |  |               | 17.00                                      | 50.20                                                                            |       |  |       |  |  |  |               |
| 68.50                                          |                        |  |  |       |  |  |  |               | 17.20                                      | 51.60                                                                            |       |  |       |  |  |  |               |
| 70.10                                          |                        |  |  |       |  |  |  |               | 17.40                                      | 53.40                                                                            |       |  |       |  |  |  |               |
| 72.10                                          |                        |  |  |       |  |  |  |               | 17.60                                      | 54.70                                                                            |       |  |       |  |  |  |               |
| 73.80                                          |                        |  |  |       |  |  |  |               | 17.90                                      | 56.50                                                                            |       |  |       |  |  |  |               |
| 75.50                                          |                        |  |  |       |  |  |  |               | 18.30                                      | 57.90                                                                            |       |  |       |  |  |  |               |
| 76.90                                          |                        |  |  |       |  |  |  |               | 18.60                                      | 58.90                                                                            |       |  |       |  |  |  |               |
| 78.80                                          |                        |  |  |       |  |  |  |               | 19.00                                      | 59.50                                                                            |       |  |       |  |  |  |               |
| 81.10                                          |                        |  |  |       |  |  |  |               | 19.30                                      | 60.60                                                                            |       |  |       |  |  |  |               |
| 84.20                                          |                        |  |  |       |  |  |  |               | 19.60                                      | 61.70                                                                            |       |  |       |  |  |  |               |
| 86.70                                          |                        |  |  |       |  |  |  |               | 20.00                                      | 62.80                                                                            |       |  |       |  |  |  |               |
| 88.10                                          |                        |  |  |       |  |  |  |               | 20.30                                      | 64.00                                                                            |       |  |       |  |  |  |               |
| 89.40                                          |                        |  |  |       |  |  |  |               | 20.70                                      | 65.40                                                                            |       |  |       |  |  |  |               |
| 90.90                                          |                        |  |  |       |  |  |  |               | 21.00                                      | 66.70                                                                            |       |  |       |  |  |  |               |
| 91.70                                          |                        |  |  |       |  |  |  |               | 21.40                                      | 67.80                                                                            |       |  |       |  |  |  |               |
| 93.00                                          |                        |  |  |       |  |  |  |               | 21.80                                      | 69.20                                                                            |       |  |       |  |  |  |               |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |        |  |       |  |  |             | WBS NO.       |       | PROJECT TIP I.D.                           |        |  |       | ROUTE                                                                            |  |               |  |
|------------------------------------------------|------------------------|--------|--|-------|--|--|-------------|---------------|-------|--------------------------------------------|--------|--|-------|----------------------------------------------------------------------------------|--|---------------|--|
|                                                |                        |        |  |       |  |  |             | 46891.1.1     |       | U-5956                                     |        |  |       | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |  |               |  |
|                                                |                        |        |  |       |  |  |             | COUNTY        |       | FIELD PROFESSIONAL                         |        |  |       | FIELD CREW                                                                       |  |               |  |
|                                                |                        |        |  |       |  |  |             | Cabarrus      |       | T. Wenner, P.G.                            |        |  |       | C. Odom, D. Underwood, P. Tomasic                                                |  |               |  |
| Test Location                                  |                        |        |  |       |  |  |             | Date Run      |       | Test Location                              |        |  |       |                                                                                  |  | Date Run      |  |
| C-18 -Y1- Sta. 35+27 LTL (RT) 6.0 FT RT FY     |                        |        |  |       |  |  |             | 8/7 to 8/9/22 |       | C-19 -Y1- Sta. 35+27 RTL (RT) 9.0 FT LT FW |        |  |       |                                                                                  |  | 8/7 to 8/9/22 |  |
| Type                                           | Test Interval          |        |  | Datum |  |  | Cut/Fill    |               | Type  | Test Interval                              |        |  | Datum |                                                                                  |  | Cut/Fill      |  |
| DCP                                            | Cumulative cm per blow |        |  | ABC   |  |  | 5.0 ft Fill |               | DCP   | Cumulative cm per blow                     |        |  | ABC   |                                                                                  |  | 6.0 ft Fill   |  |
| 1.40                                           | 19.30                  | 58.50  |  |       |  |  |             |               | 2.40  | 21.30                                      | 102.90 |  |       |                                                                                  |  |               |  |
| 2.20                                           | 19.60                  | 60.30  |  |       |  |  |             |               | 3.50  | 21.70                                      | 104.30 |  |       |                                                                                  |  |               |  |
| 2.60                                           | 19.80                  | 61.80  |  |       |  |  |             |               | 4.10  | 22.10                                      | 105.70 |  |       |                                                                                  |  |               |  |
| 2.80                                           | 20.10                  | 63.30  |  |       |  |  |             |               | 4.50  | 22.50                                      | 106.60 |  |       |                                                                                  |  |               |  |
| 3.30                                           | 20.30                  | 64.50  |  |       |  |  |             |               | 5.10  | 22.90                                      | 108.00 |  |       |                                                                                  |  |               |  |
| 3.60                                           | 20.50                  | 66.00  |  |       |  |  |             |               | 5.40  | 23.30                                      | 109.20 |  |       |                                                                                  |  |               |  |
| 3.90                                           | 20.80                  | 67.20  |  |       |  |  |             |               | 5.58  | 23.80                                      | 110.70 |  |       |                                                                                  |  |               |  |
| 4.20                                           | 21.00                  | 68.40  |  |       |  |  |             |               | 5.76  | 24.20                                      |        |  |       |                                                                                  |  |               |  |
| 4.50                                           | 21.30                  | 69.60  |  |       |  |  |             |               | 5.94  | 24.70                                      |        |  |       |                                                                                  |  |               |  |
| 4.80                                           | 21.50                  | 70.70  |  |       |  |  |             |               | 6.12  | 25.10                                      |        |  |       |                                                                                  |  |               |  |
| 5.10                                           | 21.70                  | 71.50  |  |       |  |  |             |               | 6.30  | 25.60                                      |        |  |       |                                                                                  |  |               |  |
| 5.40                                           | 22.00                  | 72.30  |  |       |  |  |             |               | 6.50  | 26.10                                      |        |  |       |                                                                                  |  |               |  |
| 5.70                                           | 22.20                  | 73.30  |  |       |  |  |             |               | 6.70  | 26.60                                      |        |  |       |                                                                                  |  |               |  |
| 6.00                                           | 22.50                  | 74.10  |  |       |  |  |             |               | 6.90  | 27.10                                      |        |  |       |                                                                                  |  |               |  |
| 6.30                                           | 22.70                  | 75.10  |  |       |  |  |             |               | 7.10  | 27.60                                      |        |  |       |                                                                                  |  |               |  |
| 6.60                                           | 22.90                  | 76.10  |  |       |  |  |             |               | 7.30  | 28.10                                      |        |  |       |                                                                                  |  |               |  |
| 6.90                                           | 23.20                  | 77.20  |  |       |  |  |             |               | 7.50  | 28.60                                      |        |  |       |                                                                                  |  |               |  |
| 7.20                                           | 23.40                  | 78.00  |  |       |  |  |             |               | 7.70  | 29.10                                      |        |  |       |                                                                                  |  |               |  |
| 7.50                                           | 23.70                  | 80.10  |  |       |  |  |             |               | 7.90  | 29.80                                      |        |  |       |                                                                                  |  |               |  |
| 7.80                                           | 23.90                  | 81.20  |  |       |  |  |             |               | 8.10  | 30.30                                      |        |  |       |                                                                                  |  |               |  |
| 8.10                                           | 24.20                  | 82.50  |  |       |  |  |             |               | 8.30  | 30.90                                      |        |  |       |                                                                                  |  |               |  |
| 8.40                                           | 24.50                  | 83.70  |  |       |  |  |             |               | 8.48  | 31.60                                      |        |  |       |                                                                                  |  |               |  |
| 8.70                                           | 24.70                  | 84.60  |  |       |  |  |             |               | 8.66  | 32.50                                      |        |  |       |                                                                                  |  |               |  |
| 9.00                                           | 25.00                  | 85.70  |  |       |  |  |             |               | 8.84  | 33.30                                      |        |  |       |                                                                                  |  |               |  |
| 9.30                                           | 25.30                  | 86.60  |  |       |  |  |             |               | 9.02  | 34.00                                      |        |  |       |                                                                                  |  |               |  |
| 9.60                                           | 25.60                  | 87.40  |  |       |  |  |             |               | 9.20  | 34.90                                      |        |  |       |                                                                                  |  |               |  |
| 9.90                                           | 25.90                  | 88.70  |  |       |  |  |             |               | 9.40  | 35.80                                      |        |  |       |                                                                                  |  |               |  |
| 10.30                                          | 26.30                  | 89.80  |  |       |  |  |             |               | 9.60  | 36.80                                      |        |  |       |                                                                                  |  |               |  |
| 10.60                                          | 26.60                  | 90.50  |  |       |  |  |             |               | 9.90  | 37.90                                      |        |  |       |                                                                                  |  |               |  |
| 10.90                                          | 26.90                  | 91.50  |  |       |  |  |             |               | 10.10 | 38.70                                      |        |  |       |                                                                                  |  |               |  |
| 11.20                                          | 27.10                  | 92.30  |  |       |  |  |             |               | 10.30 | 39.60                                      |        |  |       |                                                                                  |  |               |  |
| 11.50                                          | 27.40                  | 93.40  |  |       |  |  |             |               | 10.60 | 40.80                                      |        |  |       |                                                                                  |  |               |  |
| 11.70                                          | 27.60                  | 94.50  |  |       |  |  |             |               | 10.90 | 42.70                                      |        |  |       |                                                                                  |  |               |  |
| 12.00                                          | 27.90                  | 95.40  |  |       |  |  |             |               | 11.10 | 44.20                                      |        |  |       |                                                                                  |  |               |  |
| 12.30                                          | 28.10                  | 96.10  |  |       |  |  |             |               | 11.40 | 49.00                                      |        |  |       |                                                                                  |  |               |  |
| 12.50                                          | 28.50                  | 96.80  |  |       |  |  |             |               | 11.70 | 53.40                                      |        |  |       |                                                                                  |  |               |  |
| 12.70                                          | 28.80                  | 97.40  |  |       |  |  |             |               | 11.90 | 56.80                                      |        |  |       |                                                                                  |  |               |  |
| 13.00                                          | 29.20                  | 97.80  |  |       |  |  |             |               | 12.20 | 60.10                                      |        |  |       |                                                                                  |  |               |  |
| 13.20                                          | 29.50                  | 98.30  |  |       |  |  |             |               | 12.40 | 63.20                                      |        |  |       |                                                                                  |  |               |  |
| 13.40                                          | 29.90                  | 98.70  |  |       |  |  |             |               | 12.70 | 65.50                                      |        |  |       |                                                                                  |  |               |  |
| 13.60                                          | 30.20                  | 99.40  |  |       |  |  |             |               | 12.90 | 67.80                                      |        |  |       |                                                                                  |  |               |  |
| 13.80                                          | 30.50                  | 99.90  |  |       |  |  |             |               | 13.20 | 70.00                                      |        |  |       |                                                                                  |  |               |  |
| 14.10                                          | 30.80                  | 100.50 |  |       |  |  |             |               | 13.50 | 71.90                                      |        |  |       |                                                                                  |  |               |  |
| 14.30                                          | 31.10                  | 101.00 |  |       |  |  |             |               | 13.90 | 73.70                                      |        |  |       |                                                                                  |  |               |  |
| 14.50                                          | 31.40                  | 101.80 |  |       |  |  |             |               | 14.20 | 75.50                                      |        |  |       |                                                                                  |  |               |  |
| 14.80                                          | 31.80                  | 102.90 |  |       |  |  |             |               | 14.50 | 76.90                                      |        |  |       |                                                                                  |  |               |  |
| 15.10                                          | 32.20                  | 104.70 |  |       |  |  |             |               | 14.80 | 78.50                                      |        |  |       |                                                                                  |  |               |  |
| 15.30                                          | 32.60                  | 106.20 |  |       |  |  |             |               | 15.10 | 79.80                                      |        |  |       |                                                                                  |  |               |  |
| 15.60                                          | 33.00                  | 107.00 |  |       |  |  |             |               | 15.40 | 81.00                                      |        |  |       |                                                                                  |  |               |  |
| 15.90                                          | 33.40                  | 108.40 |  |       |  |  |             |               | 15.70 | 82.30                                      |        |  |       |                                                                                  |  |               |  |
| 16.10                                          | 33.90                  | 109.70 |  |       |  |  |             |               | 16.00 | 83.60                                      |        |  |       |                                                                                  |  |               |  |
| 16.40                                          | 34.50                  | 110.60 |  |       |  |  |             |               | 16.40 | 85.00                                      |        |  |       |                                                                                  |  |               |  |
| 16.60                                          | 35.00                  | 111.40 |  |       |  |  |             |               | 16.80 | 86.50                                      |        |  |       |                                                                                  |  |               |  |
| 16.90                                          | 35.60                  | 112.40 |  |       |  |  |             |               | 17.10 | 87.40                                      |        |  |       |                                                                                  |  |               |  |
| 17.10                                          | 36.10                  | 113.20 |  |       |  |  |             |               | 17.50 | 88.90                                      |        |  |       |                                                                                  |  |               |  |
| 17.30                                          | 38.50                  | 113.90 |  |       |  |  |             |               | 17.90 | 90.10                                      |        |  |       |                                                                                  |  |               |  |
| 17.50                                          | 41.10                  | 114.60 |  |       |  |  |             |               | 18.20 | 91.40                                      |        |  |       |                                                                                  |  |               |  |
| 17.70                                          | 43.30                  | 116.00 |  |       |  |  |             |               | 18.60 | 92.60                                      |        |  |       |                                                                                  |  |               |  |
| 17.90                                          | 46.40                  | 117.80 |  |       |  |  |             |               | 18.90 | 93.90                                      |        |  |       |                                                                                  |  |               |  |
| 18.10                                          | 48.70                  | 119.30 |  |       |  |  |             |               | 19.30 | 95.40                                      |        |  |       |                                                                                  |  |               |  |
| 18.30                                          | 51.10                  |        |  |       |  |  |             |               | 19.60 | 96.70                                      |        |  |       |                                                                                  |  |               |  |
| 18.50                                          | 52.80                  |        |  |       |  |  |             |               | 19.90 | 98.00                                      |        |  |       |                                                                                  |  |               |  |
| 18.70                                          | 54.50                  |        |  |       |  |  |             |               | 20.30 | 99.40                                      |        |  |       |                                                                                  |  |               |  |
| 18.90                                          | 56.90                  |        |  |       |  |  |             |               | 20.60 | 100.50                                     |        |  |       |                                                                                  |  |               |  |
| 19.10                                          | 57.10                  |        |  |       |  |  |             |               | 21.00 | 101.40                                     |        |  |       |                                                                                  |  |               |  |



| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |         |  |       |  |             |  | WBS NO.       |                        | PROJECT TIP I.D.                           |  |       |  | ROUTE                                                                            |  |               |  |
|------------------------------------------------|------------------------|---------|--|-------|--|-------------|--|---------------|------------------------|--------------------------------------------|--|-------|--|----------------------------------------------------------------------------------|--|---------------|--|
|                                                |                        |         |  |       |  |             |  | 46891.1.1     |                        | U-5956                                     |  |       |  | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |  |               |  |
|                                                |                        |         |  |       |  |             |  | COUNTY        |                        | FIELD PROFESSIONAL                         |  |       |  | FIELD CREW                                                                       |  |               |  |
|                                                |                        |         |  |       |  |             |  | Cabarrus      |                        | T. Wenner, P.G.                            |  |       |  | C. Odom, D. Underwood, P. Tomasic                                                |  |               |  |
| Test Location                                  |                        |         |  |       |  |             |  | Date Run      |                        | Test Location                              |  |       |  |                                                                                  |  | Date Run      |  |
| C-27 -Y1- Sta. 39+65 RT PS 0.2 FT RT FW        |                        |         |  |       |  |             |  | 8/7 to 8/9/22 |                        | C-28 -Y1- Sta. 42+44 RTL (LT) 7.0 FT LT FW |  |       |  |                                                                                  |  | 8/7 to 8/9/22 |  |
| Type                                           | Test Interval          |         |  | Datum |  | Cut/Fill    |  | Type          | Test Interval          |                                            |  | Datum |  | Cut/Fill                                                                         |  |               |  |
| DCP                                            | Cumulative cm per blow |         |  | ABC   |  | 5.0 ft Fill |  | DCP           | Cumulative cm per blow |                                            |  | ABC   |  | 5.0 ft Fill                                                                      |  |               |  |
| 0.40                                           | 17.90                  | 71.20   |  |       |  |             |  | 1.10          | 60.50                  |                                            |  |       |  |                                                                                  |  |               |  |
| 0.70                                           | 18.60                  | 71.20   |  |       |  |             |  | 1.90          | 62.20                  |                                            |  |       |  |                                                                                  |  |               |  |
| 1.10                                           | 19.80                  | 71.20   |  |       |  |             |  | 2.40          | 64.10                  |                                            |  |       |  |                                                                                  |  |               |  |
| 1.40                                           | 21.40                  | 71.20   |  |       |  |             |  | 2.70          | 65.80                  |                                            |  |       |  |                                                                                  |  |               |  |
| 1.80                                           | 22.10                  | 71.20   |  |       |  |             |  | 3.10          | 67.30                  |                                            |  |       |  |                                                                                  |  |               |  |
| 2.00                                           | 22.60                  | 71.20   |  |       |  |             |  | 3.40          | 69.30                  |                                            |  |       |  |                                                                                  |  |               |  |
| 2.30                                           | 23.20                  | 71.20   |  |       |  |             |  | 3.80          | 71.10                  |                                            |  |       |  |                                                                                  |  |               |  |
| 2.50                                           | 23.90                  | 71.20   |  |       |  |             |  | 4.10          | 72.70                  |                                            |  |       |  |                                                                                  |  |               |  |
| 2.80                                           | 24.70                  | 71.20   |  |       |  |             |  | 5.00          | 74.70                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.00                                           | 25.20                  | 71.20   |  |       |  |             |  | 5.50          | 76.20                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.06                                           | 25.80                  | 71.20   |  |       |  |             |  | 5.90          | 78.00                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.12                                           | 26.60                  | 71.20   |  |       |  |             |  | 6.60          | 79.80                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.18                                           | 27.50                  | 71.20   |  |       |  |             |  | 7.10          | 81.60                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.24                                           | 28.70                  | 71.20   |  |       |  |             |  | 7.70          | 83.20                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.30                                           | 30.90                  | 71.20   |  |       |  |             |  | 8.00          | 84.80                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.42                                           | 33.10                  | 71.20   |  |       |  |             |  | 8.40          | 86.80                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.54                                           | 35.30                  | 71.20   |  |       |  |             |  | 8.70          | 88.30                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.66                                           | 37.00                  | 71.20   |  |       |  |             |  | 9.10          | 89.70                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.78                                           | 38.60                  | 71.20   |  |       |  |             |  | 9.40          | 91.60                  |                                            |  |       |  |                                                                                  |  |               |  |
| 3.90                                           | 39.60                  | 71.20   |  |       |  |             |  | 9.80          | 93.00                  |                                            |  |       |  |                                                                                  |  |               |  |
| 4.04                                           | 41.90                  | 71.20   |  |       |  |             |  | 10.40         | 94.70                  |                                            |  |       |  |                                                                                  |  |               |  |
| 4.18                                           | 43.50                  | 71.20   |  |       |  |             |  | 11.00         | 96.10                  |                                            |  |       |  |                                                                                  |  |               |  |
| 4.32                                           | 44.20                  | 71.20   |  |       |  |             |  | 11.60         | 97.60                  |                                            |  |       |  |                                                                                  |  |               |  |
| 4.46                                           | 44.90                  | 71.20   |  |       |  |             |  | 12.20         | 99.20                  |                                            |  |       |  |                                                                                  |  |               |  |
| 4.60                                           | 45.40                  | 71.20   |  |       |  |             |  | 12.80         | 100.70                 |                                            |  |       |  |                                                                                  |  |               |  |
| 4.90                                           | 46.00                  | 71.20   |  |       |  |             |  | 13.80         | 102.20                 |                                            |  |       |  |                                                                                  |  |               |  |
| 5.20                                           | 46.70                  | 71.20   |  |       |  |             |  | 14.60         | 103.80                 |                                            |  |       |  |                                                                                  |  |               |  |
| 5.50                                           | 47.60                  | 71.20   |  |       |  |             |  | 15.10         | 105.80                 |                                            |  |       |  |                                                                                  |  |               |  |
| 5.80                                           | 48.60                  | 71.20   |  |       |  |             |  | 15.70         | 107.40                 |                                            |  |       |  |                                                                                  |  |               |  |
| 6.10                                           | 49.50                  | 71.20   |  |       |  |             |  | 16.10         | 109.20                 |                                            |  |       |  |                                                                                  |  |               |  |
| 6.40                                           | 50.70                  | 71.20   |  |       |  |             |  | 16.60         | 110.60                 |                                            |  |       |  |                                                                                  |  |               |  |
| 6.60                                           | 51.50                  | 71.20   |  |       |  |             |  | 17.10         | 112.10                 |                                            |  |       |  |                                                                                  |  |               |  |
| 6.90                                           | 51.90                  | 71.20   |  |       |  |             |  | 17.60         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 7.10                                           | 52.50                  | 71.20   |  |       |  |             |  | 18.10         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 7.40                                           | 53.10                  | 71.20   |  |       |  |             |  | 18.60         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 7.60                                           | 53.50                  | 71.20   |  |       |  |             |  | 19.10         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 7.80                                           | 54.20                  | 71.20   |  |       |  |             |  | 19.70         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 8.10                                           | 55.30                  | 71.20   |  |       |  |             |  | 20.30         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 8.30                                           | 56.90                  | 71.20   |  |       |  |             |  | 21.00         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 8.50                                           | 58.20                  | 71.20   |  |       |  |             |  | 21.80         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 8.90                                           | 59.20                  | 71.20   |  |       |  |             |  | 22.60         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 9.20                                           | 60.30                  | 71.20   |  |       |  |             |  | 23.50         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 9.60                                           | 61.00                  | 71.20   |  |       |  |             |  | 24.30         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 9.90                                           | 61.40                  | 71.20   |  |       |  |             |  | 25.30         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 10.30                                          | 61.90                  | 71.20   |  |       |  |             |  | 26.50         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 10.50                                          | 62.60                  | 71.20   |  |       |  |             |  | 27.60         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 10.80                                          | 63.80                  | DCP REF |  |       |  |             |  | 28.90         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 11.00                                          | 65.60                  | 80/0"   |  |       |  |             |  | 30.20         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 11.30                                          | 67.20                  |         |  |       |  |             |  | 31.50         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 11.50                                          | 69.10                  |         |  |       |  |             |  | 32.50         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 11.80                                          | 70.30                  |         |  |       |  |             |  | 33.70         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 12.10                                          | 70.39                  |         |  |       |  |             |  | 34.90         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 12.40                                          | 70.48                  |         |  |       |  |             |  | 36.20         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 12.70                                          | 70.57                  |         |  |       |  |             |  | 37.80         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 13.00                                          | 70.66                  |         |  |       |  |             |  | 39.10         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 13.30                                          | 70.75                  |         |  |       |  |             |  | 40.80         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 13.60                                          | 70.84                  |         |  |       |  |             |  | 42.30         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 14.00                                          | 70.93                  |         |  |       |  |             |  | 45.20         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 14.30                                          | 71.02                  |         |  |       |  |             |  | 46.90         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 14.60                                          | 71.11                  |         |  |       |  |             |  | 49.10         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 15.20                                          | 71.20                  |         |  |       |  |             |  | 51.40         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 15.70                                          | 71.20                  |         |  |       |  |             |  | 53.40         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 16.30                                          | 71.20                  |         |  |       |  |             |  | 55.10         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 16.80                                          | 71.20                  |         |  |       |  |             |  | 56.90         |                        |                                            |  |       |  |                                                                                  |  |               |  |
| 17.40                                          | 71.20                  |         |  |       |  |             |  | 58.80         |                        |                                            |  |       |  |                                                                                  |  |               |  |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |  |  |       |  |             |  | WBS NO.       |                        | PROJECT TIP I.D.                           |  |       |  | ROUTE                                                                            |  |               |  |
|------------------------------------------------|------------------------|--|--|-------|--|-------------|--|---------------|------------------------|--------------------------------------------|--|-------|--|----------------------------------------------------------------------------------|--|---------------|--|
|                                                |                        |  |  |       |  |             |  | 46891.1.1     |                        | U-5956                                     |  |       |  | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |  |               |  |
|                                                |                        |  |  |       |  |             |  | COUNTY        |                        | FIELD PROFESSIONAL                         |  |       |  | FIELD CREW                                                                       |  |               |  |
|                                                |                        |  |  |       |  |             |  | Cabarrus      |                        | T. Wenner, P.G.                            |  |       |  | C. Odom, D. Underwood, P. Tomasic                                                |  |               |  |
| Test Location                                  |                        |  |  |       |  |             |  | Date Run      |                        | Test Location                              |  |       |  |                                                                                  |  | Date Run      |  |
| C-29 -Y1- Sta. 42+44 LTL (LT) 5.0 FT RT FY     |                        |  |  |       |  |             |  | 8/7 to 8/9/22 |                        | C-31 -Y1- Sta. 49+29 LTL (RT) 5.5 FT RT FY |  |       |  |                                                                                  |  | 8/7 to 8/9/22 |  |
| Type                                           | Test Interval          |  |  | Datum |  | Cut/Fill    |  | Type          | Test Interval          |                                            |  | Datum |  | Cut/Fill                                                                         |  |               |  |
| DCP                                            | Cumulative cm per blow |  |  | ABC   |  | 5.0 ft Fill |  | DCP           | Cumulative cm per blow |                                            |  | ABC   |  | At Grade                                                                         |  |               |  |
| 1.10                                           | 72.80                  |  |  |       |  |             |  | 1.30          | 13.30                  | 40.80                                      |  |       |  |                                                                                  |  |               |  |
| 3.00                                           | 73.70                  |  |  |       |  |             |  | 1.50          | 13.50                  | 42.80                                      |  |       |  |                                                                                  |  |               |  |
| 3.90                                           | 75.00                  |  |  |       |  |             |  | 1.70          | 13.70                  | 43.90                                      |  |       |  |                                                                                  |  |               |  |
| 4.50                                           | 76.70                  |  |  |       |  |             |  | 1.90          | 13.90                  | 45.10                                      |  |       |  |                                                                                  |  |               |  |
| 5.20                                           | 78.80                  |  |  |       |  |             |  | 2.10          | 14.10                  | 46.40                                      |  |       |  |                                                                                  |  |               |  |
| 6.10                                           | 80.70                  |  |  |       |  |             |  | 2.30          | 14.30                  | 47.80                                      |  |       |  |                                                                                  |  |               |  |
| 6.50                                           | 82.10                  |  |  |       |  |             |  | 2.50          | 14.60                  | 48.70                                      |  |       |  |                                                                                  |  |               |  |
| 7.40                                           | 83.70                  |  |  |       |  |             |  | 2.70          | 14.80                  | 49.90                                      |  |       |  |                                                                                  |  |               |  |
| 8.20                                           | 86.00                  |  |  |       |  |             |  | 2.90          | 15.10                  | 51.20                                      |  |       |  |                                                                                  |  |               |  |
| 8.70                                           | 88.10                  |  |  |       |  |             |  | 3.10          | 15.30                  | 53.40                                      |  |       |  |                                                                                  |  |               |  |
| 9.30                                           | 90.00                  |  |  |       |  |             |  | 3.30          | 15.60                  | 55.30                                      |  |       |  |                                                                                  |  |               |  |
| 9.80                                           | 91.60                  |  |  |       |  |             |  | 3.46          | 15.80                  | 57.60                                      |  |       |  |                                                                                  |  |               |  |
| 11.00                                          | 92.80                  |  |  |       |  |             |  | 3.62          | 16.00                  | 59.80                                      |  |       |  |                                                                                  |  |               |  |
| 11.60                                          | 94.10                  |  |  |       |  |             |  | 3.78          | 16.20                  | 62.90                                      |  |       |  |                                                                                  |  |               |  |
| 12.20                                          | 95.50                  |  |  |       |  |             |  | 3.94          | 16.40                  | 65.70                                      |  |       |  |                                                                                  |  |               |  |
| 12.90                                          | 96.40                  |  |  |       |  |             |  | 4.10          | 16.60                  | 68.50                                      |  |       |  |                                                                                  |  |               |  |
| 13.50                                          | 98.40                  |  |  |       |  |             |  | 4.40          | 16.78                  | 71.10                                      |  |       |  |                                                                                  |  |               |  |
| 14.10                                          | 100.00                 |  |  |       |  |             |  | 4.70          | 16.96                  | 73.70                                      |  |       |  |                                                                                  |  |               |  |
| 14.70                                          | 101.10                 |  |  |       |  |             |  | 4.90          | 17.14                  | 76.10                                      |  |       |  |                                                                                  |  |               |  |
| 15.30                                          | 102.80                 |  |  |       |  |             |  | 5.20          | 17.32                  | 78.40                                      |  |       |  |                                                                                  |  |               |  |
| 15.90                                          | 104.10                 |  |  |       |  |             |  | 5.50          | 17.50                  | 80.50                                      |  |       |  |                                                                                  |  |               |  |
| 16.50                                          | 105.30                 |  |  |       |  |             |  | 5.60          | 17.80                  | 82.50                                      |  |       |  |                                                                                  |  |               |  |
| 17.10                                          | 106.70                 |  |  |       |  |             |  | 5.70          | 18.10                  | 84.80                                      |  |       |  |                                                                                  |  |               |  |
| 17.60                                          | 107.90                 |  |  |       |  |             |  | 5.90          | 18.30                  | 87.10                                      |  |       |  |                                                                                  |  |               |  |
| 18.00                                          | 109.80                 |  |  |       |  |             |  | 6.00          | 18.60                  | 89.10                                      |  |       |  |                                                                                  |  |               |  |
| 18.50                                          | 111.40                 |  |  |       |  |             |  | 6.10          | 18.90                  | 91.00                                      |  |       |  |                                                                                  |  |               |  |
| 18.90                                          |                        |  |  |       |  |             |  | 6.19          | 19.10                  | 93.40                                      |  |       |  |                                                                                  |  |               |  |
| 19.40                                          |                        |  |  |       |  |             |  | 6.28          | 19.40                  | 95.10                                      |  |       |  |                                                                                  |  |               |  |
| 20.50                                          |                        |  |  |       |  |             |  | 6.37          | 19.60                  | 97.00                                      |  |       |  |                                                                                  |  |               |  |
| 21.20                                          |                        |  |  |       |  |             |  | 6.46          | 19.90                  | 98.70                                      |  |       |  |                                                                                  |  |               |  |
| 23.30                                          |                        |  |  |       |  |             |  | 6.55          | 20.10                  | 100.70                                     |  |       |  |                                                                                  |  |               |  |
| 24.10                                          |                        |  |  |       |  |             |  | 6.64          | 20.30                  | 102.50                                     |  |       |  |                                                                                  |  |               |  |
| 24.70                                          |                        |  |  |       |  |             |  | 6.73          | 20.60                  | 104.20                                     |  |       |  |                                                                                  |  |               |  |
| 25.60                                          |                        |  |  |       |  |             |  | 6.82          | 20.80                  | 105.90                                     |  |       |  |                                                                                  |  |               |  |
| 26.40                                          |                        |  |  |       |  |             |  | 6.91          | 21.10                  | 107.50                                     |  |       |  |                                                                                  |  |               |  |
| 27.20                                          |                        |  |  |       |  |             |  | 7.00          | 21.30                  | 109.10                                     |  |       |  |                                                                                  |  |               |  |
| 27.80                                          |                        |  |  |       |  |             |  | 7.14          | 21.50                  | 111.20                                     |  |       |  |                                                                                  |  |               |  |
| 29.30                                          |                        |  |  |       |  |             |  | 7.28          | 21.70                  | 112.80                                     |  |       |  |                                                                                  |  |               |  |
| 31.30                                          |                        |  |  |       |  |             |  | 7.42          | 22.00                  | 114.50                                     |  |       |  |                                                                                  |  |               |  |
| 33.80                                          |                        |  |  |       |  |             |  | 7.56          | 22.20                  | 116.10                                     |  |       |  |                                                                                  |  |               |  |
| 36.10                                          |                        |  |  |       |  |             |  | 7.70          | 22.40                  | 117.40                                     |  |       |  |                                                                                  |  |               |  |
| 38.10                                          |                        |  |  |       |  |             |  | 7.84          | 22.70                  | 118.70                                     |  |       |  |                                                                                  |  |               |  |
| 39.40                                          |                        |  |  |       |  |             |  | 7.98          | 23.00                  | 120.00                                     |  |       |  |                                                                                  |  |               |  |
| 40.90                                          |                        |  |  |       |  |             |  | 8.12          | 23.30                  | 121.00                                     |  |       |  |                                                                                  |  |               |  |
| 42.90                                          |                        |  |  |       |  |             |  | 8.26          | 23.60                  | 122.00                                     |  |       |  |                                                                                  |  |               |  |
| 44.60                                          |                        |  |  |       |  |             |  | 8.40          | 23.90                  | 123.30                                     |  |       |  |                                                                                  |  |               |  |
| 46.30                                          |                        |  |  |       |  |             |  | 8.60          | 24.10                  | 124.70                                     |  |       |  |                                                                                  |  |               |  |
| 47.90                                          |                        |  |  |       |  |             |  | 8.80          | 24.40                  | 126.20                                     |  |       |  |                                                                                  |  |               |  |
| 50.20                                          |                        |  |  |       |  |             |  | 9.00          | 24.60                  | 127.70                                     |  |       |  |                                                                                  |  |               |  |
| 51.30                                          |                        |  |  |       |  |             |  | 9.20          | 24.90                  | 129.20                                     |  |       |  |                                                                                  |  |               |  |
| 53.50                                          |                        |  |  |       |  |             |  | 9.50          | 25.10                  | 131.00                                     |  |       |  |                                                                                  |  |               |  |
| 54.40                                          |                        |  |  |       |  |             |  | 9.70          | 25.40                  | 132.60                                     |  |       |  |                                                                                  |  |               |  |
| 55.50                                          |                        |  |  |       |  |             |  | 9.90          | 25.70                  | 134.40                                     |  |       |  |                                                                                  |  |               |  |
| 57.00                                          |                        |  |  |       |  |             |  | 10.10         | 25.90                  | 135.70                                     |  |       |  |                                                                                  |  |               |  |
| 58.20                                          |                        |  |  |       |  |             |  | 10.30         | 26.20                  | 137.50                                     |  |       |  |                                                                                  |  |               |  |
| 59.20                                          |                        |  |  |       |  |             |  | 10.50         | 26.50                  |                                            |  |       |  |                                                                                  |  |               |  |
| 60.20                                          |                        |  |  |       |  |             |  | 10.80         | 27.60                  |                                            |  |       |  |                                                                                  |  |               |  |
| 61.40                                          |                        |  |  |       |  |             |  | 11.10         | 29.10                  |                                            |  |       |  |                                                                                  |  |               |  |
| 62.80                                          |                        |  |  |       |  |             |  | 11.30         | 30.80                  |                                            |  |       |  |                                                                                  |  |               |  |
| 64.10                                          |                        |  |  |       |  |             |  | 11.60         | 32.90                  |                                            |  |       |  |                                                                                  |  |               |  |
| 65.20                                          |                        |  |  |       |  |             |  | 11.90         | 35.10                  |                                            |  |       |  |                                                                                  |  |               |  |
| 66.40                                          |                        |  |  |       |  |             |  | 12.20         | 36.20                  |                                            |  |       |  |                                                                                  |  |               |  |
| 68.20                                          |                        |  |  |       |  |             |  | 12.50         | 37.40                  |                                            |  |       |  |                                                                                  |  |               |  |
| 70.10                                          |                        |  |  |       |  |             |  | 12.70         | 38.50                  |                                            |  |       |  |                                                                                  |  |               |  |
| 71.20                                          |                        |  |  |       |  |             |  | 13.00         | 39.70                  |                                            |  |       |  |                                                                                  |  |               |  |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |  |  |  |       |  |  | WBS NO.       |  | PROJECT TIP I.D.                           |                        |  |  | ROUTE                                                                            |       |               |          |  |
|------------------------------------------------|------------------------|--|--|--|-------|--|--|---------------|--|--------------------------------------------|------------------------|--|--|----------------------------------------------------------------------------------|-------|---------------|----------|--|
|                                                |                        |  |  |  |       |  |  | 46891.1.1     |  | U-5956                                     |                        |  |  | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |       |               |          |  |
|                                                |                        |  |  |  |       |  |  | COUNTY        |  | FIELD PROFESSIONAL                         |                        |  |  | FIELD CREW                                                                       |       |               |          |  |
|                                                |                        |  |  |  |       |  |  | Cabarrus      |  | T. Wenner, P.G.                            |                        |  |  | C. Odom, D. Underwood, P. Tomasic                                                |       |               |          |  |
| Test Location                                  |                        |  |  |  |       |  |  | Date Run      |  | Test Location                              |                        |  |  |                                                                                  |       | Date Run      |          |  |
| C-32 -Y1- Sta. 49+29 RT OSL 3.0 FT LT FW       |                        |  |  |  |       |  |  | 8/7 to 8/9/22 |  | C-34 -Y1- Sta. 51+16 LTL (LT) 7.0 FT RT FY |                        |  |  |                                                                                  |       | 8/7 to 8/9/22 |          |  |
| Type                                           | Test Interval          |  |  |  | Datum |  |  | Cut/Fill      |  | Type                                       | Test Interval          |  |  |                                                                                  | Datum |               | Cut/Fill |  |
| DCP                                            | Cumulative cm per blow |  |  |  | ABC   |  |  | 5.0 ft Fill   |  | DCP                                        | Cumulative cm per blow |  |  |                                                                                  | ABC   |               | At Grade |  |
| 1.90                                           | 38.40                  |  |  |  |       |  |  |               |  | 2.40                                       | 74.10                  |  |  |                                                                                  |       |               |          |  |
| 2.90                                           | 40.00                  |  |  |  |       |  |  |               |  | 3.60                                       | 75.70                  |  |  |                                                                                  |       |               |          |  |
| 3.60                                           | 41.80                  |  |  |  |       |  |  |               |  | 4.30                                       | 77.30                  |  |  |                                                                                  |       |               |          |  |
| 3.90                                           | 44.10                  |  |  |  |       |  |  |               |  | 5.10                                       | 78.50                  |  |  |                                                                                  |       |               |          |  |
| 4.20                                           | 46.10                  |  |  |  |       |  |  |               |  | 6.40                                       | 79.80                  |  |  |                                                                                  |       |               |          |  |
| 4.50                                           | 47.90                  |  |  |  |       |  |  |               |  | 7.20                                       | 81.10                  |  |  |                                                                                  |       |               |          |  |
| 4.80                                           | 49.90                  |  |  |  |       |  |  |               |  | 7.60                                       | 82.10                  |  |  |                                                                                  |       |               |          |  |
| 5.10                                           | 51.80                  |  |  |  |       |  |  |               |  | 8.20                                       | 84.30                  |  |  |                                                                                  |       |               |          |  |
| 5.50                                           | 53.50                  |  |  |  |       |  |  |               |  | 8.70                                       | 85.60                  |  |  |                                                                                  |       |               |          |  |
| 5.80                                           | 55.10                  |  |  |  |       |  |  |               |  | 9.40                                       | 87.10                  |  |  |                                                                                  |       |               |          |  |
| 6.20                                           | 56.50                  |  |  |  |       |  |  |               |  | 10.00                                      | 88.20                  |  |  |                                                                                  |       |               |          |  |
| 6.50                                           | 57.80                  |  |  |  |       |  |  |               |  | 10.50                                      | 89.40                  |  |  |                                                                                  |       |               |          |  |
| 6.90                                           | 59.40                  |  |  |  |       |  |  |               |  | 11.00                                      | 91.10                  |  |  |                                                                                  |       |               |          |  |
| 7.30                                           | 60.80                  |  |  |  |       |  |  |               |  | 11.80                                      | 92.90                  |  |  |                                                                                  |       |               |          |  |
| 7.60                                           | 62.20                  |  |  |  |       |  |  |               |  | 12.50                                      | 94.90                  |  |  |                                                                                  |       |               |          |  |
| 8.00                                           | 63.70                  |  |  |  |       |  |  |               |  | 13.20                                      | 96.40                  |  |  |                                                                                  |       |               |          |  |
| 8.30                                           | 65.30                  |  |  |  |       |  |  |               |  | 14.00                                      | 96.90                  |  |  |                                                                                  |       |               |          |  |
| 8.70                                           | 66.60                  |  |  |  |       |  |  |               |  | 14.60                                      | 97.90                  |  |  |                                                                                  |       |               |          |  |
| 9.00                                           | 68.00                  |  |  |  |       |  |  |               |  | 15.20                                      | 98.60                  |  |  |                                                                                  |       |               |          |  |
| 9.30                                           | 69.50                  |  |  |  |       |  |  |               |  | 15.80                                      | 99.00                  |  |  |                                                                                  |       |               |          |  |
| 9.50                                           | 70.60                  |  |  |  |       |  |  |               |  | 16.30                                      | 99.30                  |  |  |                                                                                  |       |               |          |  |
| 9.80                                           | 71.70                  |  |  |  |       |  |  |               |  | 17.00                                      | 99.70                  |  |  |                                                                                  |       |               |          |  |
| 10.10                                          | 73.60                  |  |  |  |       |  |  |               |  | 18.60                                      | 100.00                 |  |  |                                                                                  |       |               |          |  |
| 10.30                                          | 75.40                  |  |  |  |       |  |  |               |  | 20.70                                      | 100.40                 |  |  |                                                                                  |       |               |          |  |
| 10.50                                          | 76.80                  |  |  |  |       |  |  |               |  | 22.10                                      | 100.60                 |  |  |                                                                                  |       |               |          |  |
| 10.70                                          | 78.20                  |  |  |  |       |  |  |               |  | 22.90                                      | 100.80                 |  |  |                                                                                  |       |               |          |  |
| 10.90                                          | 79.60                  |  |  |  |       |  |  |               |  | 23.40                                      | 101.10                 |  |  |                                                                                  |       |               |          |  |
| 11.10                                          | 81.10                  |  |  |  |       |  |  |               |  | 24.40                                      | 101.30                 |  |  |                                                                                  |       |               |          |  |
| 11.40                                          | 82.60                  |  |  |  |       |  |  |               |  | 25.40                                      | 101.50                 |  |  |                                                                                  |       |               |          |  |
| 11.80                                          | 84.10                  |  |  |  |       |  |  |               |  | 26.00                                      | 101.70                 |  |  |                                                                                  |       |               |          |  |
| 12.10                                          | 85.70                  |  |  |  |       |  |  |               |  | 27.20                                      | 101.90                 |  |  |                                                                                  |       |               |          |  |
| 12.50                                          | 87.00                  |  |  |  |       |  |  |               |  | 27.80                                      | 102.10                 |  |  |                                                                                  |       |               |          |  |
| 12.80                                          | 88.60                  |  |  |  |       |  |  |               |  | 28.50                                      | 102.30                 |  |  |                                                                                  |       |               |          |  |
| 12.96                                          | 90.40                  |  |  |  |       |  |  |               |  | 29.20                                      | 102.50                 |  |  |                                                                                  |       |               |          |  |
| 13.12                                          | 92.40                  |  |  |  |       |  |  |               |  | 30.30                                      | 102.70                 |  |  |                                                                                  |       |               |          |  |
| 13.28                                          | 93.90                  |  |  |  |       |  |  |               |  | 30.90                                      | 102.90                 |  |  |                                                                                  |       |               |          |  |
| 13.44                                          | 95.40                  |  |  |  |       |  |  |               |  | 31.40                                      | 103.20                 |  |  |                                                                                  |       |               |          |  |
| 13.60                                          | 95.80                  |  |  |  |       |  |  |               |  | 31.70                                      | 103.40                 |  |  |                                                                                  |       |               |          |  |
| 13.90                                          | 97.10                  |  |  |  |       |  |  |               |  | 34.40                                      | 103.60                 |  |  |                                                                                  |       |               |          |  |
| 14.10                                          | 98.50                  |  |  |  |       |  |  |               |  | 35.50                                      | 103.80                 |  |  |                                                                                  |       |               |          |  |
| 14.40                                          | 99.70                  |  |  |  |       |  |  |               |  | 36.50                                      | 104.10                 |  |  |                                                                                  |       |               |          |  |
| 14.60                                          | 100.80                 |  |  |  |       |  |  |               |  | 37.60                                      | 104.30                 |  |  |                                                                                  |       |               |          |  |
| 14.90                                          | 101.60                 |  |  |  |       |  |  |               |  | 38.60                                      | 104.60                 |  |  |                                                                                  |       |               |          |  |
| 15.20                                          | 103.20                 |  |  |  |       |  |  |               |  | 39.70                                      | 104.80                 |  |  |                                                                                  |       |               |          |  |
| 15.50                                          | 104.50                 |  |  |  |       |  |  |               |  | 41.00                                      | 105.10                 |  |  |                                                                                  |       |               |          |  |
| 15.90                                          | 105.80                 |  |  |  |       |  |  |               |  | 42.40                                      | 105.30                 |  |  |                                                                                  |       |               |          |  |
| 16.20                                          | 107.00                 |  |  |  |       |  |  |               |  | 44.30                                      | 105.60                 |  |  |                                                                                  |       |               |          |  |
| 16.50                                          | 107.70                 |  |  |  |       |  |  |               |  | 45.00                                      | 105.80                 |  |  |                                                                                  |       |               |          |  |
| 17.00                                          | 108.80                 |  |  |  |       |  |  |               |  | 47.00                                      | 106.10                 |  |  |                                                                                  |       |               |          |  |
| 17.40                                          | 110.30                 |  |  |  |       |  |  |               |  | 48.40                                      | 106.50                 |  |  |                                                                                  |       |               |          |  |
| 17.90                                          | 112.10                 |  |  |  |       |  |  |               |  | 49.60                                      | 107.00                 |  |  |                                                                                  |       |               |          |  |
| 18.30                                          | 113.40                 |  |  |  |       |  |  |               |  | 51.20                                      | 107.40                 |  |  |                                                                                  |       |               |          |  |
| 18.80                                          |                        |  |  |  |       |  |  |               |  | 52.40                                      | 107.90                 |  |  |                                                                                  |       |               |          |  |
| 19.70                                          |                        |  |  |  |       |  |  |               |  | 54.00                                      | 108.30                 |  |  |                                                                                  |       |               |          |  |
| 20.40                                          |                        |  |  |  |       |  |  |               |  | 55.40                                      | 108.80                 |  |  |                                                                                  |       |               |          |  |
| 21.00                                          |                        |  |  |  |       |  |  |               |  | 57.00                                      | 109.10                 |  |  |                                                                                  |       |               |          |  |
| 21.60                                          |                        |  |  |  |       |  |  |               |  | 58.30                                      | 109.60                 |  |  |                                                                                  |       |               |          |  |
| 22.40                                          |                        |  |  |  |       |  |  |               |  | 60.10                                      | 110.00                 |  |  |                                                                                  |       |               |          |  |
| 23.00                                          |                        |  |  |  |       |  |  |               |  | 61.70                                      | 110.60                 |  |  |                                                                                  |       |               |          |  |
| 24.10                                          |                        |  |  |  |       |  |  |               |  | 63.80                                      | 110.90                 |  |  |                                                                                  |       |               |          |  |
| 25.40                                          |                        |  |  |  |       |  |  |               |  | 65.50                                      | 111.40                 |  |  |                                                                                  |       |               |          |  |
| 27.10                                          |                        |  |  |  |       |  |  |               |  | 67.00                                      |                        |  |  |                                                                                  |       |               |          |  |
| 29.70                                          |                        |  |  |  |       |  |  |               |  | 68.90                                      |                        |  |  |                                                                                  |       |               |          |  |
| 32.90                                          |                        |  |  |  |       |  |  |               |  | 71.00                                      |                        |  |  |                                                                                  |       |               |          |  |
| 35.60                                          |                        |  |  |  |       |  |  |               |  | 73.00                                      |                        |  |  |                                                                                  |       |               |          |  |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |  |  |            |  | WBS NO.       |  | PROJECT TIP I.D.                        |                        |  |  | ROUTE                                                                            |  |               |  |
|------------------------------------------------|------------------------|--|--|------------|--|---------------|--|-----------------------------------------|------------------------|--|--|----------------------------------------------------------------------------------|--|---------------|--|
|                                                |                        |  |  |            |  | 46891.1.1     |  | U-5956                                  |                        |  |  | US 29 - Realign Union Cemetery Rd. to<br>Intersect US 29 at Rock Hill Church Rd. |  |               |  |
|                                                |                        |  |  |            |  | COUNTY        |  | FIELD PROFESSIONAL                      |                        |  |  | FIELD CREW                                                                       |  |               |  |
|                                                |                        |  |  |            |  | Cabarrus      |  | T. Wenner, P.G.                         |                        |  |  | C. Odom, D. Underwood, P. Tomasic                                                |  |               |  |
| Test Location                                  |                        |  |  |            |  | Date Run      |  | Test Location                           |                        |  |  |                                                                                  |  | Date Run      |  |
| C-39 -L- Sta. 51+25 RT LN 4.0 FT LT EOP        |                        |  |  |            |  | 8/7 to 8/9/22 |  | C-40 -L- Sta. 51+25 RT PS 1.0 FT LT EOP |                        |  |  |                                                                                  |  | 8/7 to 8/9/22 |  |
| Type                                           | Test Interval          |  |  | Datum      |  | Cut/Fill      |  | Type                                    | Test Interval          |  |  | Datum                                                                            |  | Cut/Fill      |  |
| DCP                                            | Cumulative cm per blow |  |  | SG (A-7-6) |  | At Grade      |  | DCP                                     | Cumulative cm per blow |  |  | SG (A-6)                                                                         |  | At Grade      |  |
| 2.70                                           |                        |  |  |            |  |               |  | 5.40                                    |                        |  |  |                                                                                  |  |               |  |
| 4.80                                           |                        |  |  |            |  |               |  | 7.60                                    |                        |  |  |                                                                                  |  |               |  |
| 6.40                                           |                        |  |  |            |  |               |  | 9.70                                    |                        |  |  |                                                                                  |  |               |  |
| 7.80                                           |                        |  |  |            |  |               |  | 11.70                                   |                        |  |  |                                                                                  |  |               |  |
| 9.60                                           |                        |  |  |            |  |               |  | 13.70                                   |                        |  |  |                                                                                  |  |               |  |
| 11.50                                          |                        |  |  |            |  |               |  | 16.50                                   |                        |  |  |                                                                                  |  |               |  |
| 13.50                                          |                        |  |  |            |  |               |  | 20.20                                   |                        |  |  |                                                                                  |  |               |  |
| 15.60                                          |                        |  |  |            |  |               |  | 23.50                                   |                        |  |  |                                                                                  |  |               |  |
| 17.70                                          |                        |  |  |            |  |               |  | 27.60                                   |                        |  |  |                                                                                  |  |               |  |
| 19.20                                          |                        |  |  |            |  |               |  | 30.70                                   |                        |  |  |                                                                                  |  |               |  |
| 21.10                                          |                        |  |  |            |  |               |  | 33.80                                   |                        |  |  |                                                                                  |  |               |  |
| 23.30                                          |                        |  |  |            |  |               |  | 36.80                                   |                        |  |  |                                                                                  |  |               |  |
| 25.40                                          |                        |  |  |            |  |               |  | 40.60                                   |                        |  |  |                                                                                  |  |               |  |
| 27.70                                          |                        |  |  |            |  |               |  | 46.90                                   |                        |  |  |                                                                                  |  |               |  |
| 29.30                                          |                        |  |  |            |  |               |  | 93.40                                   |                        |  |  |                                                                                  |  |               |  |
| 30.80                                          |                        |  |  |            |  |               |  | 97.30                                   |                        |  |  |                                                                                  |  |               |  |
| 32.60                                          |                        |  |  |            |  |               |  | 100.20                                  |                        |  |  |                                                                                  |  |               |  |
| 34.60                                          |                        |  |  |            |  |               |  | 102.60                                  |                        |  |  |                                                                                  |  |               |  |
| 36.30                                          |                        |  |  |            |  |               |  | 105.00                                  |                        |  |  |                                                                                  |  |               |  |
| 38.20                                          |                        |  |  |            |  |               |  | 107.30                                  |                        |  |  |                                                                                  |  |               |  |
| 40.00                                          |                        |  |  |            |  |               |  | 109.80                                  |                        |  |  |                                                                                  |  |               |  |
| 42.30                                          |                        |  |  |            |  |               |  | 111.90                                  |                        |  |  |                                                                                  |  |               |  |
| 43.90                                          |                        |  |  |            |  |               |  | 113.70                                  |                        |  |  |                                                                                  |  |               |  |
| 45.60                                          |                        |  |  |            |  |               |  | 115.50                                  |                        |  |  |                                                                                  |  |               |  |
| 47.10                                          |                        |  |  |            |  |               |  | 117.40                                  |                        |  |  |                                                                                  |  |               |  |
| 49.20                                          |                        |  |  |            |  |               |  | 119.00                                  |                        |  |  |                                                                                  |  |               |  |
| 51.40                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 53.40                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 55.30                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 57.30                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 58.90                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 60.40                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 62.30                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 64.00                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 65.50                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 66.70                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 68.70                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 70.50                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 72.60                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 74.20                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 76.20                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 78.60                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 81.20                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 83.30                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 85.70                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 87.70                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 88.90                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 91.00                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 93.40                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 95.00                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 97.30                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 99.50                                          |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 101.50                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 103.80                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 105.90                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 107.60                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 109.20                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 111.30                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 113.50                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 115.80                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 117.80                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 119.40                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |
| 121.20                                         |                        |  |  |            |  |               |  |                                         |                        |  |  |                                                                                  |  |               |  |

| DUAL MASS DYNAMIC CONE PENETROMETER DATA SHEET |                        |  |  |       |  | WBS NO.       |  | PROJECT TIP I.D.                         |                        |  |  | ROUTE                                                                         |  |               |  |
|------------------------------------------------|------------------------|--|--|-------|--|---------------|--|------------------------------------------|------------------------|--|--|-------------------------------------------------------------------------------|--|---------------|--|
|                                                |                        |  |  |       |  | 46891.1.1     |  | U-5956                                   |                        |  |  | US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd. |  |               |  |
|                                                |                        |  |  |       |  | COUNTY        |  | FIELD PROFESSIONAL                       |                        |  |  | FIELD CREW                                                                    |  |               |  |
|                                                |                        |  |  |       |  | Cabarrus      |  | T. Wenner, P.G.                          |                        |  |  | C. Odom, D. Underwood, P. Tomasic                                             |  |               |  |
| Test Location                                  |                        |  |  |       |  | Date Run      |  | Test Location                            |                        |  |  |                                                                               |  | Date Run      |  |
| C-37 -Y2- Sta. 23+62 RT LN 1.0 FT LT FW        |                        |  |  |       |  | 8/7 to 8/9/22 |  | C-38 -Y3- Sta. 12+84 LT LN 3.0 FT RT C&G |                        |  |  |                                                                               |  | 8/7 to 8/9/22 |  |
| Type                                           | Test Interval          |  |  | Datum |  | Cut/Fill      |  | Type                                     | Test Interval          |  |  | Datum                                                                         |  | Cut/Fill      |  |
| DCP                                            | Cumulative cm per blow |  |  | ABC   |  | 5.0 ft Fill   |  | DCP                                      | Cumulative cm per blow |  |  | ABC                                                                           |  | At Grade      |  |
| 2.30                                           |                        |  |  |       |  |               |  | 1.50                                     | 53.80                  |  |  |                                                                               |  |               |  |
| 5.40                                           |                        |  |  |       |  |               |  | 2.20                                     | 56.20                  |  |  |                                                                               |  |               |  |
| 9.20                                           |                        |  |  |       |  |               |  | 3.00                                     | 58.40                  |  |  |                                                                               |  |               |  |
| 11.20                                          |                        |  |  |       |  |               |  | 3.70                                     | 60.80                  |  |  |                                                                               |  |               |  |
| 14.40                                          |                        |  |  |       |  |               |  | 4.30                                     | 62.80                  |  |  |                                                                               |  |               |  |
| 17.70                                          |                        |  |  |       |  |               |  | 5.10                                     | 65.00                  |  |  |                                                                               |  |               |  |
| 20.60                                          |                        |  |  |       |  |               |  | 5.60                                     | 66.90                  |  |  |                                                                               |  |               |  |
| 23.00                                          |                        |  |  |       |  |               |  | 6.10                                     | 69.00                  |  |  |                                                                               |  |               |  |
| 24.50                                          |                        |  |  |       |  |               |  | 6.50                                     | 70.50                  |  |  |                                                                               |  |               |  |
| 25.60                                          |                        |  |  |       |  |               |  | 7.00                                     | 72.40                  |  |  |                                                                               |  |               |  |
| 27.10                                          |                        |  |  |       |  |               |  | 7.40                                     | 74.40                  |  |  |                                                                               |  |               |  |
| 28.80                                          |                        |  |  |       |  |               |  | 7.70                                     | 76.00                  |  |  |                                                                               |  |               |  |
| 30.50                                          |                        |  |  |       |  |               |  | 8.10                                     | 77.60                  |  |  |                                                                               |  |               |  |
| 32.10                                          |                        |  |  |       |  |               |  | 8.40                                     | 79.40                  |  |  |                                                                               |  |               |  |
| 33.80                                          |                        |  |  |       |  |               |  | 8.80                                     | 81.00                  |  |  |                                                                               |  |               |  |
| 35.70                                          |                        |  |  |       |  |               |  | 9.10                                     | 82.40                  |  |  |                                                                               |  |               |  |
| 37.30                                          |                        |  |  |       |  |               |  | 9.40                                     | 84.20                  |  |  |                                                                               |  |               |  |
| 39.10                                          |                        |  |  |       |  |               |  | 9.80                                     | 85.90                  |  |  |                                                                               |  |               |  |
| 41.10                                          |                        |  |  |       |  |               |  | 10.10                                    | 87.50                  |  |  |                                                                               |  |               |  |
| 44.10                                          |                        |  |  |       |  |               |  | 10.50                                    | 89.30                  |  |  |                                                                               |  |               |  |
| 46.90                                          |                        |  |  |       |  |               |  | 10.80                                    | 90.60                  |  |  |                                                                               |  |               |  |
| 49.80                                          |                        |  |  |       |  |               |  | 10.96                                    | 91.60                  |  |  |                                                                               |  |               |  |
| 52.90                                          |                        |  |  |       |  |               |  | 11.12                                    | 93.00                  |  |  |                                                                               |  |               |  |
| 56.40                                          |                        |  |  |       |  |               |  | 11.28                                    | 94.50                  |  |  |                                                                               |  |               |  |
| 60.40                                          |                        |  |  |       |  |               |  | 11.44                                    | 95.90                  |  |  |                                                                               |  |               |  |
| 63.80                                          |                        |  |  |       |  |               |  | 11.60                                    | 97.40                  |  |  |                                                                               |  |               |  |
| 67.10                                          |                        |  |  |       |  |               |  | 11.76                                    | 98.50                  |  |  |                                                                               |  |               |  |
| 70.20                                          |                        |  |  |       |  |               |  | 11.92                                    | 99.60                  |  |  |                                                                               |  |               |  |
| 75.10                                          |                        |  |  |       |  |               |  | 12.08                                    | 100.80                 |  |  |                                                                               |  |               |  |
| 79.40                                          |                        |  |  |       |  |               |  | 12.24                                    | 102.00                 |  |  |                                                                               |  |               |  |
| 83.70                                          |                        |  |  |       |  |               |  | 12.40                                    | 103.20                 |  |  |                                                                               |  |               |  |
| 87.40                                          |                        |  |  |       |  |               |  | 12.53                                    | 104.40                 |  |  |                                                                               |  |               |  |
| 90.20                                          |                        |  |  |       |  |               |  | 12.66                                    | 105.60                 |  |  |                                                                               |  |               |  |
| 92.40                                          |                        |  |  |       |  |               |  | 12.79                                    | 106.60                 |  |  |                                                                               |  |               |  |
| 94.90                                          |                        |  |  |       |  |               |  | 12.92                                    | 108.00                 |  |  |                                                                               |  |               |  |
| 96.50                                          |                        |  |  |       |  |               |  | 13.05                                    | 109.10                 |  |  |                                                                               |  |               |  |
| 97.80                                          |                        |  |  |       |  |               |  | 13.18                                    | 110.20                 |  |  |                                                                               |  |               |  |
| 99.40                                          |                        |  |  |       |  |               |  | 13.31                                    | 111.90                 |  |  |                                                                               |  |               |  |
| 101.50                                         |                        |  |  |       |  |               |  | 13.44                                    | 113.20                 |  |  |                                                                               |  |               |  |
| 103.60                                         |                        |  |  |       |  |               |  | 13.57                                    | 114.70                 |  |  |                                                                               |  |               |  |
| 106.30                                         |                        |  |  |       |  |               |  | 13.70                                    | 115.70                 |  |  |                                                                               |  |               |  |
| 110.30                                         |                        |  |  |       |  |               |  | 14.10                                    | 116.60                 |  |  |                                                                               |  |               |  |
| 114.00                                         |                        |  |  |       |  |               |  | 14.40                                    | 117.30                 |  |  |                                                                               |  |               |  |
| 117.90                                         |                        |  |  |       |  |               |  | 14.80                                    | 118.30                 |  |  |                                                                               |  |               |  |
| 122.00                                         |                        |  |  |       |  |               |  | 15.20                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 15.60                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 15.90                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 16.30                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 16.70                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 17.00                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 17.40                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 18.40                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 19.60                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 21.30                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 24.40                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 27.30                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 29.80                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 32.90                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 35.40                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 38.40                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 41.20                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 43.50                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 46.20                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 49.00                                    |                        |  |  |                                                                               |  |               |  |
|                                                |                        |  |  |       |  |               |  | 51.50                                    |                        |  |  |                                                                               |  |               |  |




**U-5956: US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd.**

**Pavement Core Photographs**


**C-1 - Y1- Sta. 4+74 LTL (RT)**




**C-2 - Y1- Sta. 6+64 LT PS**



**C-3 - Y1- Sta. 6+64 LT ISL**




**C-4 - Y1- Sta. 6+64 RT ISL**



**C-5 - Y1- Sta. 6+64 RT PS**




**C-6 - Y1- Sta. 18+03 LTL (LT)**



**C-7 -Y1- Sta. 22+32 LTL (LT)**







**C-8 -Y1- Sta. 24+65 LTL (RT)**



U-5956: US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd.

Pavement Core Photographs




**U-5956: US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd.**

**Pavement Core Photographs**

**C-17 -Y1- Sta. 30+66 LTL (LT)**




**C-18 - L- Sta. 35+27 LTL (RT)**




**C-19 -Y1- Sta. 35+27 RTL (RT)**



**C-20 -Y1- Sta. 36+92 RTL (LT)**




**C-21 - Y1- Sta. 36+92 LT OSL**



**C-22 - Y1- Sta. 36+92 LT ISL**






**C-23 - Y1- Sta. 36+92 LTL (LT)**





**U-5956: US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd.**

**Pavement Core Photographs**



U-5956: US 29 - Realign Union Cemetery Rd. to Intersect US 29 at Rock Hill Church Rd.

Pavement Core Photographs



F&ME CONSULTANTS, INC.  
3112 DEVINE STREET, COLUMBIA SC 29205  
(CERT No.: 130-0212)

US-29 Realign Union Cemetery Rd.  
to Intersect US 29 at Rock Hill  
Church Rd.

T.I.P. No. U-5956

County Cabarrus

F&ME Job No. C8806 - Task 00016

Date Received 8/16/2022

Date Reported 8/30/2022

Tested By F&ME

CERT No.: 130-04-0212

| SOIL TEST RESULTS |              |                 |                      |              |      |      |             |         |       |       |                    |       |       |          |         |
|-------------------|--------------|-----------------|----------------------|--------------|------|------|-------------|---------|-------|-------|--------------------|-------|-------|----------|---------|
| SAMPLE NO.        | OFFSET       | STATION         | DEPTH INTERVAL (ft.) | AASHTO CLASS | L.L. | P.I. | % BY WEIGHT |         |       |       | % PASSING (SIEVES) |       |       | %        | %       |
|                   |              |                 |                      |              |      |      | C. SAND     | F. SAND | SILT  | CLAY  | 10                 | 40    | 200   | MOISTURE | ORGANIC |
| S-1               | LTL (RT)     | -Y1- Sta.4+74   | 2.2 - 5.0            | A-7-6(6)     | 46   | 26   | 27.8%       | 21.2%   | 18.1% | 32.9% | 78.1%              | 61.0% | 42.9% | 28.5%    | ND      |
| S-3               | LT ISL       | -Y1- Sta.6+64   | 2.4 - 5.0            | A-2-4        | 25   | 5    | 35.1%       | 33.0%   | 21.8% | 10.1% | 87.2%              | 68.3% | 32.0% | 18.9%    | ND      |
| S-4               | RT ISL       | -Y1- Sta.6+64   | 2.1 - 5.0            | A-4(0)       | 31   | 2    | 27.6%       | 29.3%   | 24.7% | 18.4% | 82.6%              | 67.3% | 39.6% | 16.2%    | ND      |
| S-6A              | LTL (LT)     | -Y1- Sta.18+03  | 2.6 - 3.0            | A-2-4        | 22   | 6    | 37.9%       | 28.2%   | 21.8% | 12.1% | 67.8%              | 48.5% | 26.2% | 7.0%     | ND      |
| S-6B              | LTL (LT)     | -Y1- Sta.18+03  | 3.0 - 5.0            | A-6(7)       | 40   | 22   | 25.3%       | 22.9%   | 27.3% | 24.5% | 87.8%              | 72.8% | 49.1% | 16.2%    | ND      |
| S-7               | LTL (LT)     | -Y1- Sta.22+32  | 1.5 - 5.0            | A-4(0)       | NP   | NP   | 21.8%       | 42.7%   | 25.4% | 10.1% | 95.9%              | 84.0% | 40.7% | 12.8%    | ND      |
| S-9               | RT ISL       | -Y1- Sta.24+65  | 2.1 - 5.0            | A-4(1)       | 30   | 8    | 13.3%       | 39.4%   | 26.8% | 20.5% | 88.5%              | 83.5% | 47.5% | 19.9%    | ND      |
| S-10              | RT OSL       | -Y1- Sta.24+65  | 2.2 - 5.0            | A-4(3)       | 35   | 8    | 12.9%       | 29.1%   | 25.3% | 32.7% | 86.8%              | 79.8% | 55.3% | 25.4%    | ND      |
| S-14              | LT ISL       | -Y1- Sta.26+62  | 2.0 - 5.0            | A-7-6(9)     | 44   | 21   | 24.5%       | 21.7%   | 21.4% | 32.4% | 99.0%              | 83.0% | 57.1% | 34.3%    | ND      |
| S-16              | RTL (RT)     | -Y1- Sta.29+24  | 2.0 - 5.0            | A-2-6(1)     | 32   | 17   | 33.4%       | 27.5%   | 22.8% | 16.3% | 69.1%              | 53.4% | 30.2% | 21.6%    | ND      |
| S-17              | LTL (LT)     | -Y1- Sta.30+66  | 3.1 - 5.0            | A-2-4        | 24   | 7    | 38.3%       | 25.4%   | 26.2% | 10.1% | 55.0%              | 39.6% | 22.6% | 5.7%     | ND      |
| S-18              | LTL (RT)     | -Y1- Sta.35+27  | 2.1 - 5.0            | A-7-6(11)    | 45   | 24   | 18.9%       | 18.4%   | 23.9% | 38.8% | 85.7%              | 73.5% | 57.0% | 23.2%    | ND      |
| S-19              | RTL (RT)     | -Y1- Sta.35+27  | 2.3 - 5.0            | A-6(2)       | 32   | 16   | 24.3%       | 22.1%   | 25.3% | 28.3% | 67.5%              | 56.1% | 39.0% | 12.9%    | ND      |
| S-21              | LT OSL       | -Y1- Sta.36+92  | 2.2 - 5.0            | A-6(12)      | 40   | 22   | 13.1%       | 19.3%   | 26.8% | 40.8% | 92.3%              | 84.8% | 66.0% | 27.5%    | ND      |
| S-22              | LT ISL       | -Y1- Sta.36+92  | 2.3 - 5.0            | A-6(12)      | 40   | 22   | 15.7%       | 22.2%   | 23.5% | 38.6% | 96.6%              | 87.0% | 63.8% | 20.6%    | ND      |
| S-23              | LTL (LT)     | -Y1- Sta.36+92  | 2.2 - 5.0            | A-6(6)       | 39   | 21   | 22.2%       | 20.5%   | 21.0% | 36.3% | 79.0%              | 67.0% | 48.3% | 21.4%    | ND      |
| S-25              | RT ISL       | -Y1- Sta.39+65  | 2.2 - 5.0            | A-2-4        | NP   | NP   | 36.8%       | 30.4%   | 20.7% | 12.1% | 81.1%              | 60.6% | 30.9% | 7.3%     | ND      |
| S-26              | RT OSL       | -Y1- Sta.39+65  | 2.2 - 5.0            | A-6(5)       | 35   | 17   | 24.6%       | 19.6%   | 23.4% | 32.4% | 82.0%              | 67.5% | 48.8% | 14.6%    | ND      |
| S-27              | RT PS        | -Y1- Sta.39+65  | 2.2 - 5.0            | A-6(2)       | 33   | 15   | 27.5%       | 18.6%   | 11.5% | 42.4% | 72.3%              | 57.3% | 41.4% | 10.3%    | ND      |
| S-28              | RTL (LT)     | -Y1- Sta.42+44  | 1.3 - 5.0            | A-6(6)       | 33   | 15   | 20.0%       | 20.6%   | 23.1% | 36.3% | 89.7%              | 76.9% | 56.8% | 15.6%    | ND      |
| S-29              | LTL (LT)     | -Y1- Sta.42+44  | 1.9 - 5.0            | A-6(7)       | 37   | 16   | 14.3%       | 17.1%   | 26.0% | 42.6% | 84.3%              | 76.6% | 60.5% | 17.5%    | ND      |
| S-31              | LTL (RT)     | -Y1- Sta.49+29  | 1.7 - 5.0            | A-7-6(9)     | 42   | 16   | 12.5%       | 28.7%   | 18.1% | 40.7% | 96.5%              | 91.0% | 62.2% | 25.1%    | ND      |
| S-32              | RT OSL       | -Y1- Sta.49+29  | 1.8 - 5.0            | A-6(8)       | 38   | 17   | 18.4%       | 22.3%   | 25.0% | 34.3% | 93.5%              | 82.4% | 59.7% | 22.8%    | ND      |
| S-34              | LTL (LT)     | -Y1- Sta. 51+16 | 2.1 - 5.0            | A-7-6(13)    | 49   | 27   | 17.3%       | 15.3%   | 22.9% | 44.5% | 81.8%              | 71.8% | 57.6% | 22.3%    | ND      |
| S-35              | CONCRETE LOT | -L- Sta. 15+81  | 1.5 - 5.0            | A-6(7)       | 32   | 15   | 16.2%       | 19.7%   | 29.6% | 34.5% | 93.4%              | 83.2% | 63.2% | 16.2%    | ND      |
| S-36              | ASPHALT LOT  | -L- Sta. 17+33  | 1.3 - 5.0            | A-7-6(20)    | 57   | 31   | 12.1%       | 14.9%   | 21.8% | 51.2% | 91.5%              | 83.8% | 69.5% | 27.6%    | ND      |
| S-39              | RT LN        | -L- Sta. 51+25  | 0.9 - 5.0            | A-7-6(20)    | 64   | 35   | 5.1%        | 16.8%   | 27.1% | 51.0% | 99.7%              | 97.9% | 81.8% | 30.1%    | ND      |
| S-40              | RT PS        | -L- Sta. 51+25  | 0.9 - 5.0            | A-6(8)       | 37   | 15   | 14.4%       | 24.0%   | 35.2% | 26.4% | 96.0%              | 88.0% | 64.0% | 21.3%    | ND      |
| S-37              | LT LN        | -Y2- Sta.23+62  | 1.4 - 5.0            | A-6(2)       | 34   | 15   | 29.1%       | 21.7%   | 22.9% | 26.3% | 73.8%              | 57.7% | 39.3% | 14.7%    | ND      |
| S-38              | LT LN        | -Y3- Sta.12+84  | 1.8 - 5.0            | A-4(2)       | 28   | 9    | 22.1%       | 20.6%   | 31.1% | 26.2% | 85.0%              | 71.9% | 52.0% | 17.5%    | ND      |

Prepared in the Office of:  
F&ME CONSULTANTS, INC.  
COLUMBIA, SOUTH CAROLINA  
NCDOT LAB CERT. NO. 130-0212

F&ME CONSULTANTS, INC.  
3112 DEVINE STREET, COLUMBIA SC 29205  
(CERT No.: 130-0212)

Project

US-29 Relain Union Cemetery Rd

T.I.P. No.

U-5956

County

Cabarrus

F&ME Job No.

C8806 - Task 00016

Date Received

8/16/2022 - 10/20/2022

Date Reported

11/7/2022


Tested By

F&ME

CERT No.:

130-04-0212

| SOIL TEST RESULTS |        |            |                      |              |      |      |             |         |       |       |                    |       |       |          |         |
|-------------------|--------|------------|----------------------|--------------|------|------|-------------|---------|-------|-------|--------------------|-------|-------|----------|---------|
| SAMPLE NO.        | OFFSET | STATION    | DEPTH INTERVAL (ft.) | AASHTO CLASS | L.L. | P.I. | % BY WEIGHT |         |       |       | % PASSING (SIEVES) |       |       | %        | %       |
|                   |        |            |                      |              |      |      | C. SAND     | F. SAND | SILT  | CLAY  | 10                 | 40    | 200   | MOISTURE | ORGANIC |
| Bulk-1            | 14' LT | -L- 25+93  | 1.0 - 3.0            | A-6(10)      | 35   | 17   | 11.5%       | 16.2%   | 36.0% | 36.3% | 96.7%              | 90.4% | 70.1% | 14.5%    | ND      |
| Bulk-2            | 28' RT | - L- 50+46 | 1.0 - 3.0            | A-7-6(20)    | 55   | 31   | 12.4%       | 19.8%   | 21.2% | 46.6% | 95.7%              | 89.3% | 68.6% | 21.6%    | ND      |
| Bulk-3            | CL     | -L- 41+00  | 1.0 - 3.0            | A-7-6(20)    | 49   | 24   | 1.9%        | 3.4%    | 37.8% | 56.9% | 99.1%              | 97.9% | 95.2% | 17.9%    | ND      |



REV 08/2021

CALIFORNIA BEARING RATIO (CBR)  
AASHTO T193


SAMPLE INFORMATION

|                  |                                                        |                |         |               |           |
|------------------|--------------------------------------------------------|----------------|---------|---------------|-----------|
| Project Name     | US-29 - Realign Union Cemetery Road to Intersect US 29 |                |         | Project No.   | U-5956    |
| Sample Location  | Bulk-1 (Specimen A)                                    |                |         | FME Lab ID    | 22-2333   |
| Soil Description | A-6(10)                                                |                |         | Depth/Elev.   | 1.0 - 3.0 |
| Date Sampled     | --                                                     | Sampled By:    | CG2     | Date Received | 8/5/22    |
| Date Test Began  | 8/22/22                                                | Date Completed | 8/26/22 | Tested By     | JJW       |

MOLDING CHARACTERISTICS

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Retained on 3/4" Sieve     | 0%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 110.6                 | Optimum Moisture Content (%) | 17.2 |
| Soak Time (hr)                        | 96                    | Surcharge Weight (lb)        | 10.0 |

TESTING RESULTS



ADDITIONAL COMMENTS

Desired Percent Compaction = 100%



F&ME Consultants, Inc.  
3112 Devine Street, Columbia, SC 29205

*Jerry P. Davis*

Reviewed By

9/2/22  
Date

This report shall not be reproduced, except in full,  
without the written approval of F&ME Consultants, Inc.

REV 08/2021

CALIFORNIA BEARING RATIO (CBR)  
AASHTO T193


SAMPLE INFORMATION

|                  |                                                        |                |         |               |           |
|------------------|--------------------------------------------------------|----------------|---------|---------------|-----------|
| Project Name     | US-29 - Realign Union Cemetery Road to Intersect US 29 |                |         | Project No.   | U-5956    |
| Sample Location  | Bulk-1 (Specimen B)                                    |                |         | FME Lab ID    | 22-2333   |
| Soil Description | A-6(10)                                                |                |         | Depth/Elev.   | 1.0 - 3.0 |
| Date Sampled     | --                                                     | Sampled By:    | CG2     | Date Received | 8/5/22    |
| Date Test Began  | 8/22/22                                                | Date Completed | 8/26/22 | Tested By     | JJW       |

MOLDING CHARACTERISTICS

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Retained on 3/4" Sieve     | 0%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 110.6                 | Optimum Moisture Content (%) | 17.2 |
| Soak Time (hr)                        | 96                    | Surcharge Weight (lb)        | 10.0 |

TESTING RESULTS



ADDITIONAL COMMENTS

Desired Percent Compaction = 100%




F&ME Consultants, Inc.  
3112 Devine Street, Columbia, SC 29205

*Jerry P. Davis*

Reviewed By

9/2/22  
Date

This report shall not be reproduced, except in full,  
without the written approval of F&ME Consultants, Inc.



REV 08/2021

CALIFORNIA BEARING RATIO (CBR)  
AASHTO T193


SAMPLE INFORMATION

|                  |                                                        |                |         |               |           |
|------------------|--------------------------------------------------------|----------------|---------|---------------|-----------|
| Project Name     | US-29 - Realign Union Cemetery Road to Intersect US 29 |                |         | Project No.   | U-5956    |
| Sample Location  | Bulk-2 (Specimen A)                                    |                |         | FME Lab ID    | 22-2334   |
| Soil Description | A-7-6(20)                                              |                |         | Depth/Elev.   | 1.0 - 3.0 |
| Date Sampled     | --                                                     | Sampled By:    | CG2     | Date Received | 8/5/22    |
| Date Test Began  | 8/22/22                                                | Date Completed | 8/26/22 | Tested By     | JJW       |

MOLDING CHARACTERISTICS

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Retained on 3/4" Sieve     | 0%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 96.3                  | Optimum Moisture Content (%) | 23.3 |
| Soak Time (hr)                        | 96                    | Surcharge Weight (lb)        | 10.0 |

TESTING RESULTS



ADDITIONAL COMMENTS

Desired Percent Compaction = 100%



F&ME Consultants, Inc.  
3112 Devine Street, Columbia, SC 29205

*Jerry P. Davis*

Reviewed By

9/2/22  
Date

This report shall not be reproduced, except in full,  
without the written approval of F&ME Consultants, Inc.

REV 08/2021

CALIFORNIA BEARING RATIO (CBR)  
AASHTO T193


SAMPLE INFORMATION

|                  |                                                        |                |         |               |           |
|------------------|--------------------------------------------------------|----------------|---------|---------------|-----------|
| Project Name     | US-29 - Realign Union Cemetery Road to Intersect US 29 |                |         | Project No.   | U-5956    |
| Sample Location  | Bulk-2 (Specimen B)                                    |                |         | FME Lab ID    | 22-2334   |
| Soil Description | A-7-6(20)                                              |                |         | Depth/Elev.   | 1.0 - 3.0 |
| Date Sampled     | --                                                     | Sampled By:    | CG2     | Date Received | 8/5/22    |
| Date Test Began  | 8/22/22                                                | Date Completed | 8/26/22 | Tested By     | JJW       |

MOLDING CHARACTERISTICS

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Retained on 3/4" Sieve     | 0%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 96.3                  | Optimum Moisture Content (%) | 23.3 |
| Soak Time (hr)                        | 96                    | Surcharge Weight (lb)        | 10.0 |

TESTING RESULTS



ADDITIONAL COMMENTS

Desired Percent Compaction = 100%




F&ME Consultants, Inc.  
3112 Devine Street, Columbia, SC 29205

*Jerry P. Davis*

Reviewed By

9/7/22  
Date

This report shall not be reproduced, except in full,  
without the written approval of F&ME Consultants, Inc.



REV 08/2021

CALIFORNIA BEARING RATIO (CBR)  
AASHTO T193


SAMPLE INFORMATION

|                  |                                                        |                |          |               |           |
|------------------|--------------------------------------------------------|----------------|----------|---------------|-----------|
| Project Name     | US-29 - Realign Union Cemetery Road to Intersect US 29 |                |          | Project No.   | U-5956    |
| Sample Location  | Bulk-3 (Specimen A)                                    |                |          | FME Lab ID    | 22-2953   |
| Soil Description | A-7-6(20)                                              |                |          | Depth/Elev.   | 1.0 - 3.0 |
| Date Sampled     | --                                                     | Sampled By:    | CG2      | Date Received | 10/20/22  |
| Date Test Began  | 10/24/22                                               | Date Completed | 10/28/22 | Tested By     | NR & CM   |

MOLDING CHARACTERISTICS

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Retained on 3/4" Sieve     | 0%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 93.4                  | Optimum Moisture Content (%) | 24.6 |
| Soak Time (hr)                        | 96                    | Surcharge Weight (lb)        | 10.0 |

TESTING RESULTS



ADDITIONAL COMMENTS

Desired Percent Compaction = 100%



F&ME Consultants, Inc.  
3112 Devine Street, Columbia, SC 29205

*Jerry P. Davis*

Reviewed By

11/1/22  
Date

This report shall not be reproduced, except in full,  
without the written approval of F&ME Consultants, Inc.

REV 08/2021

CALIFORNIA BEARING RATIO (CBR)  
AASHTO T193


SAMPLE INFORMATION

|                  |                                                        |                |          |               |           |
|------------------|--------------------------------------------------------|----------------|----------|---------------|-----------|
| Project Name     | US-29 - Realign Union Cemetery Road to Intersect US 29 |                |          | Project No.   | U-5956    |
| Sample Location  | Bulk-3 (Specimen B)                                    |                |          | FME Lab ID    | 22-2953   |
| Soil Description | A-7-6(20)                                              |                |          | Depth/Elev.   | 1.0 - 3.0 |
| Date Sampled     | --                                                     | Sampled By:    | CG2      | Date Received | 10/20/22  |
| Date Test Began  | 10/24/22                                               | Date Completed | 10/28/22 | Tested By     | NR & CM   |

MOLDING CHARACTERISTICS

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Retained on 3/4" Sieve     | 0%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 93.4                  | Optimum Moisture Content (%) | 24.6 |
| Soak Time (hr)                        | 96                    | Surcharge Weight (lb)        | 10.0 |

TESTING RESULTS



ADDITIONAL COMMENTS

Desired Percent Compaction = 100%



F&ME Consultants, Inc.  
3112 Devine Street, Columbia, SC 29205

*Jerry P. Davis*

Reviewed By

11/1/22  
Date

This report shall not be reproduced, except in full,  
without the written approval of F&ME Consultants, Inc.

REV 08/2021

COMPRESSIVE STRENGTH OF MOLDED SOIL-CEMENT CYLINDERS  
ASTM D-1633

SAMPLE INFORMATION

|                  |                                   |             |          |               |               |
|------------------|-----------------------------------|-------------|----------|---------------|---------------|
| Project Name     | US-29 Realign Union Cemetery Road |             |          | NCDOT STIP #  | U-5956        |
| Sample Location  | Bulk-1                            |             |          | FME Lab ID    | 22-2951       |
| Soil Description | A-6(10)                           |             |          | Depth/Elev.   | 1.0 - 3.0 ft. |
| Station          | -L- 25+93                         |             |          | Offset        | 14' LT        |
| Date Sampled     | --                                | Sampled By: | CG2      | Date Received | 10/20/22      |
| Date Molded      | 10/27/21                          | Date Tested | 11/04/22 | Tested By     | A. Abernethy  |

MOLDING CHARACTERISTICS

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Cement Added to Proctor    | 9%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 106.7                 | Optimum Moisture Content (%) | 19.3 |

TESTING RESULTS

| % Cement | Age (Days) | Moisture Content | Height (in.) | Diameter (in.) | Area (in. <sup>2</sup> ) | Maximum Load (lbf) | Compressive Strength (psi) | Average Compressive Strength (psi) |
|----------|------------|------------------|--------------|----------------|--------------------------|--------------------|----------------------------|------------------------------------|
| 8%       | 8          | 19.2%            | 4.589        | 3.986          | 12.48                    | 3,343              | 270                        | 280                                |
| 8%       | 8          | 18.9%            | 4.574        | 3.986          | 12.48                    | 3,697              | 295                        |                                    |
| 10%      | 8          | 19.2%            | 4.867        | 3.985          | 12.47                    | 3,798              | 305                        | 300                                |
| 10%      | 8          | 18.9%            | 4.906        | 3.986          | 12.48                    | 3,582              | 285                        |                                    |

ADDITIONAL COMMENTS

|                                                                                       |                                                                  |                                                                                       |                                             |
|---------------------------------------------------------------------------------------|------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------|
|  | F&ME Consultants, Inc.<br>3112 Devine Street, Columbia, SC 29205 |  | 130-04-0212                                 |
|                                                                                       |                                                                  |                                                                                       | NCDOT Certification No.<br>11/07/22<br>Date |

This report shall not be reproduced, except in full,  
without the written approval of F&ME Consultants, Inc.




MOISTURE-DENSITY RELATIONSHIP

PROJECT ID U-5956

PROJECT NAME US 29 - Realign Union Cemetery Road to Intersect US 29

PROJECT LOCATION Cabarrus County - North Carolina



REV 08/2021

COMPRESSIVE STRENGTH OF MOLDED SOIL-LIME CYLINDERS  
ASTM D-1633

SAMPLE INFORMATION

|                  |                                   |               |               |
|------------------|-----------------------------------|---------------|---------------|
| Project Name     | US-29 Realign Union Cemetery Road | NCDOT STIP #  | U-5956        |
| Sample Location  | Bulk-2                            | FME Lab ID    | 22-2952       |
| Soil Description | A-7-6(20)                         | Depth/Elev.   | 1.0 - 3.0 ft. |
| Station          | -L- 50+46                         | Offset        | 28' RT        |
| Date Sampled     | --                                | Sampled By:   | CG2           |
| Date Molded      | 10/27/21                          | Date Received | 10/20/22      |
|                  |                                   | Date Tested   | 11/04/22      |
|                  |                                   | Tested By     | A. Abernethy  |

MOLDING CHARACTERISTICS

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Lime Added to Proctor      | 5%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 96.9                  | Optimum Moisture Content (%) | 23.8 |


TESTING RESULTS

| % Lime | Age (Days) | Moisture Content | Height (in.) | Diameter (in.) | Area (in. <sup>2</sup> ) | Maximum Load (lbf) | Compressive Strength (psi) | Average Compressive Strength (psi) |
|--------|------------|------------------|--------------|----------------|--------------------------|--------------------|----------------------------|------------------------------------|
| 4%     | 8          | 23.9%            | 5.164        | 3.983          | 12.46                    | 798                | 65                         | 65                                 |
| 4%     | 8          | 23.6%            | 5.146        | 3.982          | 12.45                    | 723                | 60                         |                                    |
| 6%     | 8          | 23.3%            | 5.568        | 3.988          | 12.49                    | 1127               | 90                         | 100                                |
| 6%     | 8          | 23.5%            | 4.751        | 3.984          | 12.47                    | 1328               | 105                        |                                    |

ADDITIONAL COMMENTS

|                                                                                       |                                                                  |                                                                                       |                                             |
|---------------------------------------------------------------------------------------|------------------------------------------------------------------|---------------------------------------------------------------------------------------|---------------------------------------------|
|  | F&ME Consultants, Inc.<br>3112 Devine Street, Columbia, SC 29205 |  | 130-04-0212                                 |
|                                                                                       |                                                                  |                                                                                       | NCDOT Certification No.<br>11/07/22<br>Date |

This report shall not be reproduced, except in full,  
without the written approval of F&ME Consultants, Inc.



## COMPRESSIVE STRENGTH OF MOLDED SOIL-LIME CYLINDERS ASTM D-1633

|                  |                                   |             |          |               |               |
|------------------|-----------------------------------|-------------|----------|---------------|---------------|
| Project Name     | US-29 Realign Union Cemetery Road |             |          | NCDOT STIP #  | U-5956        |
| Sample Location  | Bulk-3                            |             |          | FME Lab ID    | 22-2953       |
| Soil Description | A-7-6(20)                         |             |          | Depth/Elev.   | 1.0 - 3.0 ft. |
| Station          | -L- 41+00                         |             |          | Offset        | CL            |
| Date Sampled     | --                                | Sampled By: | CG2      | Date Received | 10/20/22      |
| Date Molded      | 10/27/21                          | Date Tested | 11/04/22 | Tested By     | A. Abernethy  |

|                                       |                       |                              |      |
|---------------------------------------|-----------------------|------------------------------|------|
| Method                                | AASHTO T99 - Method A | % Lime Added to Proctor      | 5%   |
| Max Dry Density (lb/ft <sup>3</sup> ) | 94.9                  | Optimum Moisture Content (%) | 23.9 |

| % Lime | Age (Days) | Moisture Content | Height (in.) | Diameter (in.) | Area (in. <sup>2</sup> ) | Maximum Load (lbf) | Compressive Strength (psi) | Average Compressive Strength (psi) |
|--------|------------|------------------|--------------|----------------|--------------------------|--------------------|----------------------------|------------------------------------|
| 4%     | 8          | 24.8%            | 4.565        | 3.810          | 11.40                    | 416                | 35                         | 40                                 |
| 4%     | 8          | 24.9%            | 4.756        | 3.979          | 12.43                    | 585                | 45                         |                                    |
| 6%     | 8          | 24.4%            | 4.853        | 3.981          | 12.45                    | 708                | 55                         | 65                                 |
| 6%     | 8          | 24.7%            | 4.752        | 3.991          | 12.51                    | 925                | 75                         |                                    |

|                                                                                       |                                                                             |                                                                                                   |
|---------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|
|  |                                                                             | 130-04-0212                                                                                       |
|                                                                                       |                                                                             | NCDOT Certification No.                                                                           |
|  | <b>F&amp;ME Consultants, Inc.</b><br>3112 Devine Street, Columbia, SC 29205 | 11/07/22                                                                                          |
|                                                                                       |                                                                             | Date                                                                                              |
|                                                                                       |                                                                             | Reviewed By  |

**F&ME CONSULTANTS**

**PROJECT ID** U-5956 **PROJECT NAME** US 29 - Realign Union Cemetery Road to Intersect US 29 **PROJECT LOCATION** Cabarrus County - North Carolina

**Source of Material** Bulk-3  
**Description of Material** A-7-6(20) (5% Lime Added)  
**Test Method** AASHTO T99 - Method A

**TEST RESULTS**  
Maximum Dry Density **94.9 PCF**  
Optimum Water Content **23.9 %**

**Curves of 100% Saturation for Specific Gravity Equal to:**  
2.80  
2.70  
2.60

**DRY DENSITY, pcf**

**WATER CONTENT, %**

The graph plots Dry Density (pcf) on the y-axis (75 to 135) against Water Content (%) on the x-axis (0 to 45). Three saturation curves for specific gravities of 2.60, 2.70, and 2.80 are shown. Test data points are plotted and connected by a smooth curve, showing a peak at approximately 23.9% water content and 94.9 pcf dry density.

| Water Content (%) | Dry Density (pcf) |
|-------------------|-------------------|
| 19.5              | 91.0              |
| 21.5              | 93.5              |
| 23.5              | 94.5              |
| 25.0              | 94.5              |
| 26.5              | 91.5              |

**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **1**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|

C-1 -Y1- Sta. 4+74 LTL (RT)

Datum = ABC


RAW

FILL

08/07/22

| Interval<br>0.0 to 11.0 |      |
|-------------------------|------|
| # of Values             | 36   |
| Avg CBR                 | 53.7 |
| Wghtd Avg.              | 44.3 |
| Max CBR                 | 100+ |
| Min CBR                 | 19.2 |

| Interval<br>11.0 to 43.5 |      |
|--------------------------|------|
| # of Values              | 81   |
| Avg CBR                  | 44.6 |
| Wghtd Avg.               | 33.2 |
| Max CBR                  | 100+ |
| Min CBR                  | 7.9  |



C-3 -Y1- Sta. 6+64 LT ISL

Datum = SG


RAW

FILL

08/07/22

| Interval<br>0.0 to 0.0 |         |
|------------------------|---------|
| # of Values            | 0       |
| Avg CBR                | #DIV/0! |
| Wghtd Avg.             | #DIV/0! |
| Max CBR                | 0.0     |
| Min CBR                | 0.0     |

| Interval<br>0.0 to 7.2 |      |
|------------------------|------|
| # of Values            | 75   |
| Avg CBR                | 100+ |
| Wghtd Avg.             | 100+ |
| Max CBR                | 100+ |
| Min CBR                | 9.2  |



**CONE PENETROMETER RESULTS**  
**NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **2**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|

C-4 -Y1- Sta. 6+64 RT ISL

Datum = ABC


RAW

FILL

08/07/22

| Interval    |         |
|-------------|---------|
| 8.5         | to 16.7 |
| # of Values | 89      |
| Avg CBR     | 100+    |
| Wghtd Avg.  | 100+    |
| Max CBR     | 100+    |
| Min CBR     | 70.9    |

| Interval    |         |
|-------------|---------|
| 16.7        | to 29.1 |
| # of Values | 76      |
| Avg CBR     | 100+    |
| Wghtd Avg.  | 86.6    |
| Max CBR     | 100+    |
| Min CBR     | 16.2    |



C-5 -Y1- Sta. 6+64 RT PS

Datum = SG


RAW

FILL

08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 0.0  |
| # of Values | 0       |
| Avg CBR     | #DIV/0! |
| Wghtd Avg.  | #DIV/0! |
| Max CBR     | 0.0     |
| Min CBR     | 0.0     |

| Interval    |         |
|-------------|---------|
| 0.0         | to 41.8 |
| # of Values | 76      |
| Avg CBR     | 42.7    |
| Wghtd Avg.  | 23.7    |
| Max CBR     | 100+    |
| Min CBR     | 6.5     |



**CONE PENETROMETER RESULTS**  
**NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **3**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|

C-6 -Y1- Sta. 18+03 LTL (LT)

**5**

Datum = ABC


RAW

FILL

08/07/22

|                         |         |
|-------------------------|---------|
| Interval<br>13.0 to 0.0 |         |
| # of Values             | 0       |
| Avg CBR                 | #DIV/0! |
| Wghtd Avg.              | #DIV/0! |
| Max CBR                 | 0.0     |
| Min CBR                 | 0.0     |

|                          |      |
|--------------------------|------|
| Interval<br>13.0 to 36.5 |      |
| # of Values              | 121  |
| Avg CBR                  | 100+ |
| Wghtd Avg.               | 72.1 |
| Max CBR                  | 100+ |
| Min CBR                  | 8.4  |



C-7 -Y1- Sta. 22+32 LTL (LT)

**6**

Datum = ABC


RAW

FILL

08/07/22

|                        |         |
|------------------------|---------|
| Interval<br>0.0 to 0.0 |         |
| # of Values            | 0       |
| Avg CBR                | #DIV/0! |
| Wghtd Avg.             | #DIV/0! |
| Max CBR                | 0.0     |
| Min CBR                | 0.0     |

|                          |      |
|--------------------------|------|
| Interval<br>10.7 to 44.1 |      |
| # of Values              | 229  |
| Avg CBR                  | 100+ |
| Wghtd Avg.               | 97.6 |
| Max CBR                  | 100+ |
| Min CBR                  | 27.9 |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **4**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |


|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|

C-8 -Y1- Sta. 24+65 LTL (RT)

Datum = SG  
RAW  
GRADE  
08/07/22

|                        |         |
|------------------------|---------|
| Interval<br>0.0 to 0.0 |         |
| # of Values            | 0       |
| Avg CBR                | #DIV/0! |
| Wghtd Avg.             | #DIV/0! |
| Max CBR                | 0.0     |
| Min CBR                | 0.0     |

|                         |      |
|-------------------------|------|
| Interval<br>0.0 to 38.9 |      |
| # of Values             | 100  |
| Avg CBR                 | 50.4 |
| Wghtd Avg.              | 34.3 |
| Max CBR                 | 100+ |
| Min CBR                 | 9.8  |




C-9 -Y1- Sta. 24+65 RT ISL

Datum = ABC  
RAW  
GRADE  
08/07/22

|                          |         |
|--------------------------|---------|
| Interval<br>10.7 to 14.2 |         |
| # of Values              | 42      |
| Avg CBR                  | 49.6    |
| Wghtd Avg.               | #DIV/0! |
| Max CBR                  | 100+    |
| Min CBR                  | 13.3    |

|                          |      |
|--------------------------|------|
| Interval<br>14.2 to 47.0 |      |
| # of Values              | 110  |
| Avg CBR                  | 69.3 |
| Wghtd Avg.               | 45.5 |
| Max CBR                  | 100+ |
| Min CBR                  | 14.6 |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **5**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|

C-10 -Y1- Sta. 24+65 RT OSL

**9**

Datum = ABC


RAW

GRADE

08/07/22

| Interval<br>0.0 to 14.8 |      |
|-------------------------|------|
| # of Values             | 49   |
| Avg CBR                 | 97.5 |
| Wghtd Avg.              | 44.8 |
| Max CBR                 | 100+ |
| Min CBR                 | 18.1 |

| Interval<br>14.8 to 34.1 |      |
|--------------------------|------|
| # of Values              | 80   |
| Avg CBR                  | 97.9 |
| Wghtd Avg.               | 57.3 |
| Max CBR                  | 100+ |
| Min CBR                  | 20.5 |



C-13 -Y1- Sta. 26+62 LT OSL

**10**

Datum = SG


RAW

CUT

8/7/2022

| Interval<br>0.0 to 30.5 |      |
|-------------------------|------|
| # of Values             | 26   |
| Avg CBR                 | 100+ |
| Wghtd Avg.              | 10.6 |
| Max CBR                 | 100+ |
| Min CBR                 | 1.2  |

| Interval<br>30.5 to 31.6 |      |
|--------------------------|------|
| # of Values              | 51   |
| Avg CBR                  | 100+ |
| Wghtd Avg.               | 100+ |
| Max CBR                  | 100+ |
| Min CBR                  | 100+ |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **6**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|


C-14 -Y1- Sta. 26+62 LT ISL

**11**

Datum = 9IN BELOW SG  
RAW  
FILL  
08/07/22

| Interval<br>0.0 to 18.5 |      |
|-------------------------|------|
| # of Values             | 7    |
| Avg CBR                 | 9.6  |
| Wghtd Avg.              | 9.1  |
| Max CBR                 | 13.3 |
| Min CBR                 | 6.5  |

| Interval<br>18.5 to 30.8 |      |
|--------------------------|------|
| # of Values              | 9    |
| Avg CBR                  | 11.5 |
| Wghtd Avg.               | 9.0  |
| Max CBR                  | 22.0 |
| Min CBR                  | 4.7  |




C-15 -Y1- Sta. 26+62 LTL (LT)

**12**

Datum = SG  
RAW  
FILL  
08/07/22

| Interval<br>0.0 to 0.0 |         |
|------------------------|---------|
| # of Values            | 0       |
| Avg CBR                | #DIV/0! |
| Wghtd Avg.             | #DIV/0! |
| Max CBR                | 0.0     |
| Min CBR                | 0.0     |

| Interval<br>0.0 to 39.5 |      |
|-------------------------|------|
| # of Values             | 74   |
| Avg CBR                 | 30.2 |
| Wghtd Avg.              | 24.5 |
| Max CBR                 | 90.0 |
| Min CBR                 | 13.3 |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **7**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|

C-16 -Y1- Sta. 29+24 RTL (RT)

**13**

Datum = ABC


RAW

FILL

08/07/22

| Interval<br>0.0 to 7.4 |      |
|------------------------|------|
| # of Values            | 31   |
| Avg CBR                | 69.1 |
| Wghtd Avg.             | 57.4 |
| Max CBR                | 100+ |
| Min CBR                | 16.2 |

| Interval<br>7.4 to 39.6 |      |
|-------------------------|------|
| # of Values             | 39   |
| Avg CBR                 | 19.4 |
| Wghtd Avg.              | 15.4 |
| Max CBR                 | 43.0 |
| Min CBR                 | 4.9  |



C-17 -Y1- Sta. 30+66 LTL (LT)

**14**

Datum = ABC


RAW

FILL

08/07/22

| Interval<br>0.0 to 18.5 |      |
|-------------------------|------|
| # of Values             | 113  |
| Avg CBR                 | 100+ |
| Wghtd Avg.              | 86.1 |
| Max CBR                 | 100+ |
| Min CBR                 | 18.1 |

| Interval<br>18.5 to 38.8 |      |
|--------------------------|------|
| # of Values              | 34   |
| Avg CBR                  | 25.7 |
| Wghtd Avg.               | 21.8 |
| Max CBR                  | 58.4 |
| Min CBR                  | 9.5  |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **8**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|

C-18 -Y1- Sta. 35+27 LTL (RT)

**15**

Datum = ABC


RAW

FILL

08/07/22

| Interval<br>0.0 to 16.2 |      |
|-------------------------|------|
| # of Values             | 122  |
| Avg CBR                 | 100+ |
| Wghtd Avg.              | 100+ |
| Max CBR                 | 100+ |
| Min CBR                 | 12.2 |

| Interval<br>16.2 to 47.0 |      |
|--------------------------|------|
| # of Values              | 68   |
| Avg CBR                  | 37.7 |
| Wghtd Avg.               | 29.2 |
| Max CBR                  | 100+ |
| Min CBR                  | 10.1 |



C-19 -Y1- Sta. 35+27 RTL (RT)

**16**

Datum = ABC


RAW

FILL

08/07/22

| Interval<br>0.0 to 10.9 |      |
|-------------------------|------|
| # of Values             | 80   |
| Avg CBR                 | 100+ |
| Wghtd Avg.              | 100+ |
| Max CBR                 | 100+ |
| Min CBR                 | 13.3 |

| Interval<br>10.9 to 43.6 |      |
|--------------------------|------|
| # of Values              | 57   |
| Avg CBR                  | 29.9 |
| Wghtd Avg.               | 22.7 |
| Max CBR                  | 70.9 |
| Min CBR                  | 6.4  |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **9**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|


C-21 -Y1- Sta. 36+92 LT OSL

**17**

Datum = SG  
RAW  
FILL  
08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 0.0  |
| # of Values | 0       |
| Avg CBR     | #DIV/0! |
| Wghtd Avg.  | #DIV/0! |
| Max CBR     | 0.0     |
| Min CBR     | 0.0     |

| Interval    |         |
|-------------|---------|
| 0.0         | to 32.7 |
| # of Values | 14      |
| Avg CBR     | 5.7     |
| Wghtd Avg.  | 5.1     |
| Max CBR     | 8.4     |
| Min CBR     | 2.7     |




C-22 -Y1- Sta. 36+92 LT ISL

**18**

Datum = SG  
RAW  
FILL  
08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 0.0  |
| # of Values | 0       |
| Avg CBR     | #DIV/0! |
| Wghtd Avg.  | #DIV/0! |
| Max CBR     | 0.0     |
| Min CBR     | 0.0     |

| Interval    |         |
|-------------|---------|
| 0.0         | to 28.9 |
| # of Values | 30      |
| Avg CBR     | 16.7    |
| Wghtd Avg.  | 13.1    |
| Max CBR     | 33.9    |
| Min CBR     | 5.7     |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page 10

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 1 |
|------|--------------------|

C-23 -Y1- Sta. 36+92 LTL (LT)

19

Datum = ABC


RAW

FILL

08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 14.9 |
| # of Values | 75      |
| Avg CBR     | 99.0    |
| Wghtd Avg.  | 70.3    |
| Max CBR     | 100+    |
| Min CBR     | 20.5    |

| Interval    |         |
|-------------|---------|
| 14.9        | to 44.6 |
| # of Values | 55      |
| Avg CBR     | 26.9    |
| Wghtd Avg.  | 24.2    |
| Max CBR     | 58.4    |
| Min CBR     | 13.9    |



C-24 -Y1- Sta. 29+65 LTL (RT)

20

Datum = ABC


RAW

FILL

08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 16.0 |
| # of Values | 139     |
| Avg CBR     | 100+    |
| Wghtd Avg.  | #DIV/0! |
| Max CBR     | 100+    |
| Min CBR     | 16.2    |

| Interval    |         |
|-------------|---------|
| 16.0        | to 38.7 |
| # of Values | 135     |
| Avg CBR     | 100+    |
| Wghtd Avg.  | 84.0    |
| Max CBR     | 100+    |
| Min CBR     | 6.0     |



**CONE PENETROMETER RESULTS**  
**NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **1**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 2 |
|------|--------------------|

C-25 -Y1- Sta. 39+65 RT ISL

Datum = ABC


RAW

FILL

08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 13.0 |
| # of Values | 110     |
| Avg CBR     | 100+    |
| Wghtd Avg.  | 100+    |
| Max CBR     | 100+    |
| Min CBR     | 9.2     |

| Interval    |          |
|-------------|----------|
| 13.0        | to ##### |
| # of Values | 71       |
| Avg CBR     | #VALUE!  |
| Wghtd Avg.  | #VALUE!  |
| Max CBR     | #VALUE!  |
| Min CBR     | #VALUE!  |



C-26 -Y1- Sta. 39+65 RT OSL

Datum = ABC


RAW

FILL

08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 13.0 |
| # of Values | 116     |
| Avg CBR     | 100+    |
| Wghtd Avg.  | 100+    |
| Max CBR     | 100+    |
| Min CBR     | 43.0    |

| Interval    |          |
|-------------|----------|
| 13.0        | to ##### |
| # of Values | 103      |
| Avg CBR     | #VALUE!  |
| Wghtd Avg.  | #VALUE!  |
| Max CBR     | #VALUE!  |
| Min CBR     | #VALUE!  |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **2**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |


|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 2 |
|------|--------------------|

C-27 -Y1- Sta. 39+65 RT PS

Datum = ABC  
RAW  
FILL  
08/07/22

| Interval<br>0.0 to 12.2 |      |
|-------------------------|------|
| # of Values             | 80   |
| Avg CBR                 | 100+ |
| Wghtd Avg.              | 93.4 |
| Max CBR                 | 100+ |
| Min CBR                 | 14.6 |

| Interval<br>12.2 to 28.0 |      |
|--------------------------|------|
| # of Values              | 46   |
| Avg CBR                  | 100+ |
| Wghtd Avg.               | 39.0 |
| Max CBR                  | 100+ |
| Min CBR                  | 13.9 |




C-28 -Y1- Sta. 42+44 RTL (LT)

Datum = ABC  
RAW  
FILL  
08/07/22

| Interval<br>0.0 to 3.0 |      |
|------------------------|------|
| # of Values            | 14   |
| Avg CBR                | 76.4 |
| Wghtd Avg.             | 64.1 |
| Max CBR                | 100+ |
| Min CBR                | 30.6 |

| Interval<br>3.0 to 44.1 |      |
|-------------------------|------|
| # of Values             | 83   |
| Avg CBR                 | 37.6 |
| Wghtd Avg.              | 26.5 |
| Max CBR                 | 100+ |
| Min CBR                 | 10.9 |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **3**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |


|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 2 |
|------|--------------------|

C-29 -Y1- Sta. 42+44 LTL (LT)

Datum = ABC  
RAW  
FILL  
08/07/22

| Interval<br>0.0 to 12.3 |      |
|-------------------------|------|
| # of Values             | 39   |
| Avg CBR                 | 51.7 |
| Wghtd Avg.              | 42.8 |
| Max CBR                 | 90.0 |
| Min CBR                 | 15.4 |

| Interval<br>12.3 to 43.9 |      |
|--------------------------|------|
| # of Values              | 52   |
| Avg CBR                  | 23.2 |
| Wghtd Avg.               | 21.4 |
| Max CBR                  | 37.9 |
| Min CBR                  | 12.8 |




C-31 -Y1- Sta. 49+29 LTL (RT)

Datum = ABC  
RAW  
GRADE  
08/07/22

| Interval<br>0.0 to 16.1 |      |
|-------------------------|------|
| # of Values             | 131  |
| Avg CBR                 | 100+ |
| Wghtd Avg.              | 100+ |
| Max CBR                 | 100+ |
| Min CBR                 | 14.6 |

| Interval<br>16.1 to 54.1 |      |
|--------------------------|------|
| # of Values              | 54   |
| Avg CBR                  | 19.8 |
| Wghtd Avg.               | 18.2 |
| Max CBR                  | 37.9 |
| Min CBR                  | 10.1 |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **4**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |


|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 2 |
|------|--------------------|

C-32 -Y1- Sta. 49+29 RT OS�

Datum = ABC  
RAW  
FILL  
08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 13.0 |
| # of Values | 64      |
| Avg CBR     | 100+    |
| Wghtd Avg.  | 68.9    |
| Max CBR     | 100+    |
| Min CBR     | 9.8     |

| Interval    |         |
|-------------|---------|
| 13.0        | to 44.6 |
| # of Values | 53      |
| Avg CBR     | 24.1    |
| Wghtd Avg.  | 21.7    |
| Max CBR     | 90.0    |
| Min CBR     | #VALUE! |




C-34 -Y1- Sta. 51+16 LTL (LT)

Datum = ABC  
RAW  
GRADE  
08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 16.7 |
| # of Values | 46      |
| Avg CBR     | 100+    |
| Wghtd Avg.  | 68.9    |
| Max CBR     | 100+    |
| Min CBR     | 9.8     |

| Interval    |         |
|-------------|---------|
| 16.7        | to 43.9 |
| # of Values | 80      |
| Avg CBR     | 84.2    |
| Wghtd Avg.  | 39.7    |
| Max CBR     | 100+    |
| Min CBR     | 14.6    |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **5**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |


|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 2 |
|------|--------------------|

C-35 -L- Sta. 15+81

Datum = ABC  
RAW  
FILL  
08/07/22

| Interval<br>0.0 to 9.2 |      |
|------------------------|------|
| # of Values            | 53   |
| Avg CBR                | 100+ |
| Wghtd Avg.             | 81.0 |
| Max CBR                | 100+ |
| Min CBR                | 23.7 |

| Interval<br>9.2 to 48.7 |      |
|-------------------------|------|
| # of Values             | 95   |
| Avg CBR                 | 55.3 |
| Wghtd Avg.              | 32.0 |
| Max CBR                 | 100+ |
| Min CBR                 | 9.5  |




C-36 -L- Sta. 17+33

Datum = ABC  
RAW  
FILL  
8/7/2022

| Interval<br>0.0 to 11.8 |      |
|-------------------------|------|
| # of Values             | 46   |
| Avg CBR                 | 72.0 |
| Wghtd Avg.              | 53.4 |
| Max CBR                 | 100+ |
| Min CBR                 | 11.8 |

| Interval<br>11.8 to 52.8 |      |
|--------------------------|------|
| # of Values              | 84   |
| Avg CBR                  | 30.2 |
| Wghtd Avg.               | 27.0 |
| Max CBR                  | 90.0 |
| Min CBR                  | 8.9  |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **6**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 2 |
|------|--------------------|


C-37 -Y2- Sta. 23+62 RT LN

**11**

Datum = ABC  
RAW  
FILL  
08/07/22

|                        |      |
|------------------------|------|
| Interval<br>0.0 to 9.6 |      |
| # of Values            | 9    |
| Avg CBR                | 12.7 |
| Wghtd Avg.             | 11.7 |
| Max CBR                | 22.0 |
| Min CBR                | 8.2  |

|                         |      |
|-------------------------|------|
| Interval<br>9.6 to 48.0 |      |
| # of Values             | 36   |
| Avg CBR                 | 13.9 |
| Wghtd Avg.              | 11.7 |
| Max CBR                 | 30.6 |
| Min CBR                 | 6.2  |




C-38 -Y3- Sta. 12+84 LT LN

**12**

Datum = ABC  
RAW  
GRADE  
08/07/22

|                         |      |
|-------------------------|------|
| Interval<br>0.0 to 11.7 |      |
| # of Values             | 57   |
| Avg CBR                 | 100+ |
| Wghtd Avg.              | 67.6 |
| Max CBR                 | 100+ |
| Min CBR                 | 10.1 |

|                          |      |
|--------------------------|------|
| Interval<br>11.7 to 46.6 |      |
| # of Values              | 52   |
| Avg CBR                  | 21.9 |
| Wghtd Avg.               | 19.2 |
| Max CBR                  | 49.6 |
| Min CBR                  | 10.1 |



**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **7**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |


|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 2 |
|------|--------------------|

C-39 -L- Sta. 51+25 RT LN

Datum = SG  
RAW  
GRADE  
08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 0.0  |
| # of Values | 0       |
| Avg CBR     | #DIV/0! |
| Wghtd Avg.  | #DIV/0! |
| Max CBR     | 0.0     |
| Min CBR     | 0.0     |

| Interval    |         |
|-------------|---------|
| 0.0         | to 47.7 |
| # of Values | 63      |
| Avg CBR     | 17.4    |
| Wghtd Avg.  | 16.9    |
| Max CBR     | 27.9    |
| Min CBR     | 11.8    |




**13**

C-40 -L- Sta. 51+25 RT PS

Datum = SG  
RAW  
GRADE  
08/07/22

| Interval    |         |
|-------------|---------|
| 0.0         | to 0.0  |
| # of Values | 0       |
| Avg CBR     | #DIV/0! |
| Wghtd Avg.  | #DIV/0! |
| Max CBR     | 0.0     |
| Min CBR     | 0.0     |

| Interval    |         |
|-------------|---------|
| 0.0         | to 46.9 |
| # of Values | 26      |
| Avg CBR     | 11.9    |
| Wghtd Avg.  | 6.7     |
| Max CBR     | 20.5    |
| Min CBR     | 0.6     |



**14**

**CONE PENETROMETER RESULTS  
NCDOT, GEOTECHNICAL ENGINEERING UNIT**

Page **8**

|             |           |
|-------------|-----------|
| PROJECT NO. | 46891.1.1 |
| PROJECT ID  | U-5956    |
| ROUTE       | US 29     |
| COUNTY      | Cabarrus  |

|           |           |
|-----------|-----------|
| GEOLOGIST | LM Howard |
| GEOTECHS  | CG2       |

|      |                    |
|------|--------------------|
| FILE | U5956 DCP Graphs 2 |
|------|--------------------|


C-37 -Y2- Sta. 23+62 RT LN

**15**

Datum = ABC  
RAW  
FILL  
08/07/22

| Interval<br>0.0 to 9.6 |      |
|------------------------|------|
| # of Values            | 9    |
| Avg CBR                | 12.7 |
| Wghtd Avg.             | 11.7 |
| Max CBR                | 22.0 |
| Min CBR                | 8.2  |

| Interval<br>9.6 to 48.0 |      |
|-------------------------|------|
| # of Values             | 35   |
| Avg CBR                 | 13.8 |
| Wghtd Avg.              | 11.4 |
| Max CBR                 | 30.6 |
| Min CBR                 | 5.0  |




C-38 -Y3- Sta. 12+64 LT LN

**16**

Datum = ABC  
RAW  
GRADE  
08/07/22

| Interval<br>0.0 to 11.7 |      |
|-------------------------|------|
| # of Values             | 57   |
| Avg CBR                 | 100+ |
| Wghtd Avg.              | 67.6 |
| Max CBR                 | 100+ |
| Min CBR                 | 10.1 |

| Interval<br>11.7 to 46.6 |      |
|--------------------------|------|
| # of Values              | 50   |
| Avg CBR                  | 21.7 |
| Wghtd Avg.               | 18.4 |
| Max CBR                  | 49.6 |
| Min CBR                  | 8.6  |



PAVEMENT CORE EVALUATION  
46891.1.1 (U-5956) Cabarrus County

| LINE | STATION        | ABC<br>(in) | LAYER<br>THICKNESS<br>(in) | LAYER | LIFT(S) | REMARKS                                                                                        |
|------|----------------|-------------|----------------------------|-------|---------|------------------------------------------------------------------------------------------------|
| -Y1- | 4+74 LTL (RT)  | 11.75       | 2.00                       | S     | 2       |                                                                                                |
|      | Asphalt 14.25" |             | 0.75                       | B/MS  | 1       | appears similar to mat seal, possibly consolidation of large aggregate, some missing aggregate |
|      |                |             | 1.00                       | S     | 1       | low oxidation                                                                                  |
|      |                |             | 3.50                       | B     | 1       | low oxidation                                                                                  |
|      |                |             | 1.00                       | S     | 1       | low to moderate oxidation, thin hairline crack between upper lift                              |
|      |                |             | 6.00                       | B     | 1       | low to moderate oxidation                                                                      |
| -Y1- | 6+64 LT PS     | Y           | 2.25                       | S     | 1-2     | lifts indistinguishable                                                                        |
|      | Asphalt 12.75" |             | 7.50                       | I     | 3       | lift 2 delaminated from 3, lift one looks like old surface lift                                |
|      |                |             | 0.50                       | MS    | 1       | flattened and elongated aggregate (FLA)                                                        |
|      |                |             | 1.75                       | I     | 1       |                                                                                                |
|      |                |             | 1.00                       | S     | 1       | some ABC/large aggregate crumbling off                                                         |
| -Y1- | 6+64 LT ISL    | -           | 3.50                       | S     | 2       | oxidation at lift boundaries                                                                   |
|      | Asphalt 12.75" |             | 5.50                       | I     | 3       | low to moderate oxidation, lift 3 delaminated from upper and lower lifts                       |
|      |                |             | 1.25                       | S     | 1       |                                                                                                |
|      |                |             | 1.25                       | I     | 1       | moderate oxidation and stripping, flattened and elongated aggregate                            |
|      |                |             | 0.50                       | S     | 1       | moderate oxidation                                                                             |
|      |                |             | 8.00                       | C     | 1       |                                                                                                |
|      |                |             | 0.75                       | S     | 1       | moderate oxidation and stripping                                                               |
|      |                |             | 8.25                       | C     | 1       | piece missing from upper corner, about 2" long, 1" wide, possibly mechanical                   |
| -Y1- | 6+64 RT ISL    | 16.75       | 3.75                       | S     | 2       | low oxidation                                                                                  |
|      | Asphalt 8.25"  |             | 3.50                       | I/B   | 1       | low oxidation                                                                                  |
|      |                |             | 4.75                       | S     | 3       | lift 2 different mix, FLA, low to moderate stripping and oxidation, delaminated                |
|      |                |             | 2.50                       | I     | 1       | low oxidation                                                                                  |
| -Y1- | 6+64 RT PS     | -           | 2.00                       | S     | 1       |                                                                                                |
|      | Asphalt 14.25" |             | 3.50                       | I     | 2       |                                                                                                |
|      |                |             | 8.75                       | B     | 2       | low oxidation and stripping                                                                    |
| -Y1- | 18+03 LTL (LT) | 13.00       | 2.00                       | S     | 1       |                                                                                                |
|      | Asphalt 18"    |             | 3.25                       | I     | 2       |                                                                                                |
|      |                |             | 12.75                      | B     | 2       | possibly 3 lifts, mechanical break 8" into lift, low oxidation and stripping                   |
| -Y1- | 22+32 LTL (LT) | 11.00       | 1.00                       | S     | 1       | full-depth crack through core but still attached                                               |
|      | Asphalt 6.5"   |             | 0.50                       | MS    | 1       | , low to moderate oxidation and stripping                                                      |
|      |                |             | 1.00                       | S     | 1       |                                                                                                |
|      |                |             | 2.50                       | B     | 1       | missing 1.5" of lift or was measured incorrectly in PIDS                                       |
| -Y1- | 24+65 LTL (RT) | -           | 3.00                       | S/MS  | 2       | mat seal lift at bottom of lift 1                                                              |
|      | Asphalt 19"    |             | 3.50                       | I     | 1       |                                                                                                |
|      |                |             | 2.50                       | S     | 1       | delaminated from upper and lower lifts                                                         |
|      |                |             | 10.00                      | B     | 1       |                                                                                                |

PAVEMENT CORE EVALUATION  
46891.1.1 (U-5956) Cabarrus County

| LINE | STATION        | ABC<br>(in) | LAYER<br>THICKNESS<br>(in) | LAYER | LIFT(S) | REMARKS                                                                                       |
|------|----------------|-------------|----------------------------|-------|---------|-----------------------------------------------------------------------------------------------|
| -Y1- | 24+65 RT ISL   | 14.25       | 3.50                       | S     | 2       | lift 2 possibly intermediate mix                                                              |
|      | Asphalt 11"    |             | 3.00                       | B     | 1       | low to moderate oxidation                                                                     |
|      |                |             | 1.00                       | S     | 1       | delaminated from upper and lower lift                                                         |
|      |                |             | 1.50                       | I     | 1       | moderate oxidation                                                                            |
|      |                |             | 1.25                       | S     | 1       | low oxidation                                                                                 |
|      |                |             | 3.00                       | B     | 1       | low oxidation                                                                                 |
| -Y1- | 24+65 RT OSL   | 15.00       | 3.50                       | S     | 2       | lift 2 possibly intermediate mix                                                              |
|      | Asphalt 10.75" |             | 3.00                       | B     | 1       | low to moderate oxidation                                                                     |
|      |                |             | 0.75                       | S     | 1       | delaminated from upper and lower lift                                                         |
|      |                |             | 1.25                       | I     | 1       | moderate oxidation                                                                            |
|      |                |             | 1.50                       | S     | 1       | low oxidation                                                                                 |
|      |                |             | 3.00                       | B     | 1       | low oxidation                                                                                 |
| -Y1- | 24+65 RT PS    | Y           | 1.50                       | S     | 1       |                                                                                               |
|      | Asphalt 15.25" |             | 4.00                       | I     | 3       |                                                                                               |
|      |                |             | 5.00                       | B     | 1       | delaminated from upper and lower lift                                                         |
|      |                |             | 1.25                       | S     | 1       | bleeding at break, low to moderate oxidation                                                  |
|      |                |             | 2.00                       | I     | 1       | low to moderate oxidation                                                                     |
|      |                |             | 1.50                       | B     | 1       | flat and elongated aggregate (FLA) aggregate, low to moderate oxidation                       |
| -Y1- | 26+62 LT PS    | Y           | 2.00                       | S     | 1       |                                                                                               |
|      | Asphalt 12"    |             | 4.25                       | I     | 2       |                                                                                               |
|      |                |             | 3.25                       | S     | 3       | delaminated from upper lift                                                                   |
|      |                |             | 2.50                       | I/B   | 1       | moderate oxidation                                                                            |
| -Y1- | 26+62 LT OSL   | -           | 2.00                       | S     | 1       |                                                                                               |
|      | Asphalt 10.25" |             | 3.25                       | I     | 3       |                                                                                               |
|      |                |             | 2.00                       | B     | 1       |                                                                                               |
|      |                |             | 2.50                       | S     | 1       | delaminated from upper lift                                                                   |
|      |                |             | 1.00                       | I/B   | 1       | low bleeding                                                                                  |
|      |                |             | 11.00                      | C     | 1       | at 6", lift 1 delaminated, very thin asphalt layer in between at one point but high oxidation |
| -Y1- | 26+62 LT ISL   | -           | 2.00                       | S     | 1       |                                                                                               |
|      | Asphalt 10.5"  |             | 3.25                       | I     | 3       |                                                                                               |
|      |                |             | 2.00                       | B     | 1       |                                                                                               |
|      |                |             | 2.50                       | S     | 1       | delaminated from upper lift                                                                   |
|      |                |             | 1.75                       | I/B   | 1       | delaminated from upper and lower lift                                                         |
|      |                |             | 11.00                      | C     | 1       | at 6", lift 1 delaminated, very thin asphalt layer in between at one point but high oxidation |
| -Y1- | 26+62 LTL (LT) | -           | 1.75                       | S/MS  | 1       | mat seal lift at bottom of lift 1                                                             |
|      | Asphalt 19"    |             | 4.50                       | I     | 2       |                                                                                               |
|      |                |             | 1.75                       | S     | 3       |                                                                                               |
|      |                |             | 11.00                      | B     | 1       | mechanical break after possible lift 2                                                        |

PAVEMENT CORE EVALUATION  
46891.1.1 (U-5956) Cabarrus County

| LINE | STATION        | ABC<br>(in) | LAYER<br>THICKNESS<br>(in) | LAYER | LIFT(S) | REMARKS                                                                                       |
|------|----------------|-------------|----------------------------|-------|---------|-----------------------------------------------------------------------------------------------|
| -Y1- | 29+24 RTL RT   | 7.75        | 2.25                       | S     | 2       |                                                                                               |
|      | Asphalt 16.25" |             | 4.75                       | I     | 2       |                                                                                               |
|      |                |             | 1.75                       | S     | 1       | delaminated from upper lift, low oxidation                                                    |
|      |                |             | 2.00                       | I     | 1       |                                                                                               |
|      |                |             | 5.50                       | B     | 1       |                                                                                               |
| -Y1- | 30+66 LTL LT   | 18.75       | 5.00                       | S     | 3       | lift 1 bottom has large aggregate, crack through lifts, moderate oxidation, crumbling, L1&2 I |
|      | Asphalt 18.25" |             | 1.75                       | I     | 1       | crack through lift, moderate oxidation                                                        |
|      |                |             | 3.75                       | S     | 2       | 1" top-down crack through lift, lift 1 delaminated from upper and lower lifts                 |
|      |                |             | 2.00                       | I     | 1       | low to moderate stripping and oxidation                                                       |
|      |                |             | 5.75                       | B     | 1       | low oxidation, low to moderate stripping                                                      |
| -Y1- | 35+27 LTL (RT) | 16.00       | 2.25                       | S     | 1-2     | lifts indistinguishable, lift 1 bottom has large aggregate, oxidized at boundary              |
|      | Asphalt 9"     |             | 1.50                       | I     | 1       | oxidized at boundaries                                                                        |
|      |                |             | 3.00                       | B     | 1-2     | moderate oxidation and stripping                                                              |
|      |                |             | 2.25                       | S     | 1       | delaminated, low to moderated oxidation and stripping                                         |
| -Y1- | 35+27 RTL RT   | 11.00       | 2.00                       | S     | 1       | last .75" possible mat seal, low oxidation                                                    |
|      | Asphalt 16"    |             | 4.00                       | I     | 3       | low oxidation                                                                                 |
|      |                |             | 2.25                       | S     | 1       | delaminated from upper lift, low oxidation                                                    |
|      |                |             | 7.75                       | B     | 2       | lift 2 different aggregate, low oxidation                                                     |
| -Y1- | 36+92 RTL (LT) | Yes         | 1.50                       | I     | 1       |                                                                                               |
|      | Asphalt 14.25" |             | 2.00                       | S     | 1       |                                                                                               |
|      |                |             | 4.25                       | I     | 2       | lift 1 delaminated from 2                                                                     |
|      |                |             | 6.50                       | B     | 1-2     | lifts indistinguishable, low oxidation                                                        |
| -Y1- | 36+92 LT OSL   | -           | 1.75                       | I     | 1       |                                                                                               |
|      | Asphalt 12.25" |             | 1.75                       | S     | 1       |                                                                                               |
|      |                |             | 3.25                       | I/B   | 1       |                                                                                               |
|      |                |             | 3.00                       | S     | 3       |                                                                                               |
|      |                |             | 1.75                       | I     | 1       | low to moderate oxidation                                                                     |
|      |                |             | 14.00                      | C     | 2       |                                                                                               |
| -Y1- | 36+92 LT ISL   | -           | 1.00                       | S     | 2       |                                                                                               |
|      | Asphalt 14.75  |             | 1.25                       | I/B   | 1       |                                                                                               |
|      |                |             | 2.00                       | S     | 1       |                                                                                               |
|      |                |             | 3.00                       | I     | 1       | delaminated from lower lift                                                                   |
|      |                |             | 3.00                       | S     | 2       |                                                                                               |
|      |                |             | 2.00                       | I     | 1       | delaminated from lower lift                                                                   |
|      |                |             | 6.25                       | C     | 1       | delaminated                                                                                   |
|      |                |             | 1.75                       | S     | 1       | delaminated, moderate oxidation                                                               |
|      |                |             | 7.00                       | C     | 1       | delaminated                                                                                   |

PAVEMENT CORE EVALUATION  
46891.1.1 (U-5956) Cabarrus County

| LINE | STATION        | ABC<br>(in) | LAYER<br>THICKNESS<br>(in) | LAYER | LIFT(S) | REMARKS                                                                                                                                                                    |
|------|----------------|-------------|----------------------------|-------|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| -Y1- | 36+92 LTL (LT) | 15.00       | 2.00                       | S/I   | 1       |                                                                                                                                                                            |
|      | Asphalt 11"    |             | 3.25                       | I     | 3       | low oxidation                                                                                                                                                              |
|      |                |             | 12.75                      | S     | 2       | low oxidation, delaminated                                                                                                                                                 |
| -Y1- | 39+65 LTL (RT) | 16.00       | 2.00                       | S/I   | 1       |                                                                                                                                                                            |
|      | Asphalt 8"     |             | 3.25                       | I/B   | 1       |                                                                                                                                                                            |
|      |                |             | 12.75                      | S     | 3       | low to moderate oxidation                                                                                                                                                  |
| -Y1- | 39+65 RT ISL   | 13.00       | 3.25                       | S     | 2       | low oxidation                                                                                                                                                              |
|      | 13" Asphalt    |             | 3.25                       | I     | 1       | low oxidation and stripping, few small voids                                                                                                                               |
|      |                |             | 2.00                       | S     | 2       | Moderate oxidation, low stripping, 2nd lift FLA, some small voids                                                                                                          |
|      |                |             | 3.25                       | I     | 2       | low oxidation                                                                                                                                                              |
|      |                |             | 1.25                       | B     | 1       | moderate oxidation, low stripping, numerous small voids, FLA                                                                                                               |
| -Y1- | 39+65 RT OSL   | 13.00       | 2.75                       | S     | 2       |                                                                                                                                                                            |
|      | 13.00" Asphalt |             | 3.75                       | I     | 2       | low oxidation                                                                                                                                                              |
|      |                |             | 2.00                       | S     | 2       | moderate oxidation, low stripping, 2nd lift FLA, some small voids                                                                                                          |
|      |                |             | 3.25                       | I     | 2       | 1st lift moderate oxidation, low stripping, 2nd lift low oxidation and stripping                                                                                           |
|      |                |             | 1.25                       | B     | 1       | moderate oxidation, low stripping, FLA                                                                                                                                     |
| -Y1- | 39+65 RT PS    | 12.50       | 3.50                       | S     | 2       |                                                                                                                                                                            |
|      | 13" Asphalt    |             | 3.00                       | I     | 1       | low stripping, few small voids                                                                                                                                             |
|      |                |             | 2+                         | S     | 1       | high oxidation, moderate stripping, loss of asphalt matrix, FLA, delaminated top and bottom<br>remainder of the core in multiple pieces, high stripping 5" bottom up crack |
| -Y1- | 42+42 RTL (LT) | 3.00        | 1.75                       | S     | 1       |                                                                                                                                                                            |
|      | 13" Asphalt    |             | 4.00                       | I     | 2       |                                                                                                                                                                            |
|      |                |             | 2.25                       | S     | 2       | low oxidation, 2nd lift small FLA                                                                                                                                          |
|      |                |             | 5.00                       | I     | 2       | low oxidation, FLA, bottom 1" moderate oxidation and stripping with some material missing                                                                                  |
| -Y1- | 42+44 LTL (LT) | 12.25       | 2.25                       | S     | 1       |                                                                                                                                                                            |
|      | 10.75" Asphalt |             | 4.75                       | I     | 2       |                                                                                                                                                                            |
|      |                |             | 3.75                       | S     | 3       |                                                                                                                                                                            |
| -Y1- | 46+45 RTL (RT) | -           | 2.25                       | S     | 1       |                                                                                                                                                                            |
|      | 11.25" Asphalt |             | 3.50                       | I     | 1       |                                                                                                                                                                            |
|      |                |             | 5.50                       | B     | 1       | moderate oxidation, low stripping                                                                                                                                          |
| -Y1- | 49+29 LTL (RT) | 16.00       | 1.25                       | S     | 1       |                                                                                                                                                                            |
|      | 4" Asphalt     |             | 1.5+                       | I     | 1       | Low oxidation, missing 0.5", full depth crack                                                                                                                              |
| -Y1- | 49+29 RT OSL   | 13.00       | 1.50                       | S     | 1       | low oxidation                                                                                                                                                              |
|      | 8.5" Asphalt   |             | 1.75                       | I     | 1       | low oxidation, delaminated from bottom                                                                                                                                     |
|      |                |             | 2.75                       | S     | 2       | 2nd lift low oxidation and stripping, small FLA                                                                                                                            |
|      |                |             | 1.25                       | I     | 1       | low oxidation                                                                                                                                                              |
|      |                |             | 1.25                       | B     | 1       | moderate oxidation, low stripping, FLA                                                                                                                                     |

PAVEMENT CORE EVALUATION  
46891.1.1 (U-5956) Cabarrus County

| LINE | STATION            | ABC<br>(in) | LAYER<br>THICKNESS<br>(in) | LAYER | LIFT(S) | REMARKS                                                                                                  |
|------|--------------------|-------------|----------------------------|-------|---------|----------------------------------------------------------------------------------------------------------|
| -Y1- | 49+29 RT PS        | Yes         | 1.50                       | S     | 1       |                                                                                                          |
|      | 8.75" Asphalt      |             | 2.00                       | I     | 1       | low oxidation and stripping, delaminated bottom                                                          |
|      |                    |             | 5.25                       | S     | 3       | low oxidation and stripping, 1st lift small FLA, 2nd-3rd lift low-moderate stripping loss of some matrix |
| -Y1- | 51+16 LTL (LT)     | 17.00       | 1.50                       | S     | 1       |                                                                                                          |
|      | 8" Asphalt         |             | 3.00                       | I     | 1       | low oxidation, delaminated at bottom, milled surface                                                     |
|      |                    |             | 3.50                       | S     | 2       | low oxidation, moderate stripping                                                                        |
| -L-  | 15+81 Concrete Lot | 9.25        | 8.75                       | C     | 1       | good condition, some small air voids                                                                     |
| -L-  | 17+33              | 11.50       | 1.25                       | S     | 1       |                                                                                                          |
|      | Asphalt Lot        |             | 2.25                       | I     | 1       |                                                                                                          |
| -L-  | 51+25 RT LN        | -           | 6.00                       | S     | 4       | Low oxidation and stripping                                                                              |
|      | 11" Asphalt        |             | 5.00                       | B     | 1       | low oxidation                                                                                            |
| -L   | 51+25 RT PS        | -           | 5.00                       | S     | 3       | low oxidation and stripping 2nd and 3rd lifts delaminated                                                |
|      | 10.75" Asphalt     |             | 5.75                       | B     | 1       | low oxidation and stripping, few large voids                                                             |
| -Y2- | 23+62 RT LN        | 9.75        | 2.00                       | S     | 1       |                                                                                                          |
|      | 7.25 Asphalt       |             | 2.75                       | B     | 1       |                                                                                                          |
|      |                    |             | 2.50                       | S     | 1       | multiple pieces high stripped, possible old saw cut 2.5+ inches                                          |
| -Y3- | 12+84 LT LN        | 11.75       | 5.25                       | S     | 3       | low oxidation and stripping, 2nd and 3rd lift delaminated                                                |
|      | 9.25" Asphalt      |             | 6.50                       | B     | 1       | low oxidation and stripping, few large voids                                                             |