

PRELIMINARY SITE ASSESSMENT

**SR 1997 (FAYETTEVILLE ROAD) WIDENING
TIP NO. U-5797, WBS NO. 44367.1.1**

PARCEL NO. 14

OWNER: RT & DT ENTERPRISES LLC

2500 FAYETTEVILLE ROAD

LUMBERTON, ROBESON COUNTY, NORTH CAROLINA



PREPARED FOR:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
C/O STV ENGINEERS, INC.
1600 PERIMETER PARK DRIVE, SUITE 225
MORRISVILLE, NC 2756002

PREPARED BY:
FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
CARY, NC 27513

**PROJECT NUMBER: G19011.00
JUNE 9, 2020**





June 9, 2020

Mr. Patrick Livingston, PE
STV Engineers, Inc.
900 W. Trade St, Suite 715
Charlotte, NC 28202

Re: **Preliminary Site Assessment**
SR 1997 (Fayetteville Road) Widening
TIP No. U-5797, WBS No. 44367.1.1
NCDOT Parcel No. 14
Owner: RT & DT Enterprises LLC
2500 Fayetteville Road
Lumberton, Robeson County, North Carolina

Dear Mr. Livingston:

Falcon is pleased to present the following Preliminary Site Assessment in support of the above-mentioned Project. Specifically, Falcon sampled soil in proximity to the project limits on this parcel in general accordance with the approved scope of work. Soils requiring remediation or special handling during construction were not identified.

Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

Please review this report and advise us if you have any questions or concerns. We appreciate this opportunity to provide services to you and look forward to partnering with you on future projects. If you have any questions, please give Falcon a call at (919) 871-0800.

Sincerely,

FALCON ENGINEERING, INC.

A handwritten signature in blue ink, reading "Christopher J. Burkhardt".

Christopher J. Burkhardt
Environmental Services Manager

A handwritten signature in blue ink, reading "Jeremy R. Hamm".

Jeremy R. Hamm, PE
Geotechnical Services Manager

TABLE OF CONTENTS

SECTION 1: INTRODUCTION	5
1.1 DESCRIPTION	5
1.2 SCOPE OF WORK.....	5
SECTION 2: HISTORY	6
2.1 PARCEL USAGE.....	6
2.2 FACILITY IDENTIFICATION NUMBER	6
2.3 GROUNDWATER INCIDENT NUMBER.....	6
SECTION 3: SITE OBSERVATIONS	7
3.1 GROUNDWATER MONITORING WELLS.....	7
3.2 ACTIVE USTS	7
3.3 FEATURES APPARENT BEYOND ROW/EASEMENT	7
SECTION 4: METHODOLOGY	8
4.1 GEOPHYSICS.....	8
4.2 BORINGS	8
4.3 SAMPLE PROTOCOL.....	8
SECTION 5: RESULTS.....	10
5.1 GEOPHYSICS	10
5.2 SAMPLE DATA	10
TABLE NO. 1 BORING COORDINATES.....	10
TABLE NO. 2 PID READINGS	11
TABLE NO. 3 SUMMARY OF UVF SOIL SAMPLING RESULTS	11
5.3 SAMPLE OBSERVATIONS	11
TABLE NO. 4 SOIL OBSERVATIONS.....	11
5.4 QUANTITIES CALCULATIONS	11
SECTION 6: CONCLUSIONS	12
6.1 INTERPRETATION OF RESULTS	12
6.2 GEOPHYSICS.....	12
6.3 SAMPLING	12
6.4 QUANTITIES	12
SECTION 7: RECOMMENDATIONS	13
7.1 ADDITIONAL SAMPLING	13
7.2 SPECIAL HANDLING OF IMPACTED SOIL.....	13



LIST OF FIGURES AND ATTACHMENTS

VICINITY MAP

USGS TOPOGRAPHIC MAP

PARCEL LOCATION MAP

BORING LOCATION MAP

SITE PHOTOGRAPHS

LABORATORY RESULTS

GEOPHYSICAL SURVEY

SECTION 1: INTRODUCTION

1.1 DESCRIPTION

Falcon Engineering, Inc. (Falcon) has completed a Preliminary Site Assessment of NCDOT TIP Project U-5797 Parcel No. 14. Parcel No. 14 is addressed as 2500 Fayetteville Road, Lumberton Robeson County, North Carolina. NCDOT is proposing to widen Fayetteville Road (SR 1997) from Farringdom Street to 22nd Street. The limits of the assessment are between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). Boring locations were placed in the vicinity of proposed excavations for drainage features, utilities, and roadway/ditch cuts to determine if soils requiring remediation or special handling were present where excavation was planned to take place.

1.2 SCOPE OF WORK

Falcon's scope of work included coordination of; public and private utility location near the proposed borings, geophysical surveys, collecting soil samples using direct push methods, and laboratory analysis. Samples were analyzed for petroleum Hydrocarbons via UVF technology.

SECTION 2: HISTORY

2.1 PARCEL USAGE

Falcon performed a Phase I Environmental Site Assessment (ESA) for U-5797 under Project No. G17057 dated April 2018. The ESA identified this parcel as a Recognized Environmental Condition (REC) based on Lumberton Oil Co Bulk Plant being identified in historic City Directories at 2500-02 Fayetteville Road. This Parcel is considered a REC based on the likely use/storage of petroleum products and/or other hazardous chemicals prior to current environmental policies and best practices and the potential for an unreported or undiscovered release.

2.2 FACILITY IDENTIFICATION NUMBER

A Facility Identification Number was not identified for this parcel.

2.3 GROUNDWATER INCIDENT NUMBER

A Groundwater Incident Number was not identified for this parcel.



SECTION 3: SITE OBSERVATIONS

3.1 GROUNDWATER MONITORING WELLS

Groundwater monitoring wells (MWs) were not observed on this parcel.

3.2 ACTIVE USTS

Active USTs were not observed within the project limits or registered at this parcel.

3.3 FEATURES APPARENT BEYOND ROW/EASEMENT

USTs, monitoring wells, remediation systems, or hydraulic lifts were not observed.

SECTION 4: METHODOLOGY

4.1 GEOPHYSICS

Pyramid Geophysical Services (Pyramid) was subcontracted to perform a geophysical survey of the assessment area. The assessment area is between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). The survey was used to locate private utility lines, as well as possible indications of USTs, and/or their pits.

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is georeferenced and can be overlain on aerial photographs and CADD drawings.

GPR data was acquired across select EM anomalies (where identified), using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Pyramid marked their findings on the surface with paint. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and to obtain adequate coverage. A copy of the full Geophysical Report is included in the Attachments.

4.2 BORINGS

Regional Probing was subcontracted to advance soil borings using direct push technology. Regional Probing used a truck-mounted Geoprobe® 5410 unit mounted on an off-road modified Ford F350 Diesel 4x4. The unit has auger-capabilities and is equipped with a GH-42 soil-probing hammer, with 21,700 pounds of down force and 28,900 pounds of retraction force. The unit has an on-board tank for decontaminating the geoprobe rods before advancing the probe at each sample location.

4.3 SAMPLE PROTOCOL

Prior to initiating sample collection Falcon contacted NC One Call and requested public utility locations be marked around the proposed sample locations. Sampling was in general accordance with the NC Department of Environmental Quality (DEQ) Division of Waste Management's (DWM) "Guidelines for Site Checks, Tank Closure, and Initial Response and Abatement for UST Releases" (March 1, 2007 Version Change 9 – February 1, 2019) guidance document. Sampling strategy was derived based upon the project scope and objectives as outlined above. Red Lab, LLC was selected to perform the UVF laboratory analytical analysis. Appropriate sterile containers were received by Falcon from Red Lab prior to beginning the fieldwork. The containers were labeled appropriately.

A Minirae 3000 photoionization detector (PID) was used to field screen samples for volatile organics to determine if a release had occurred. The instrument was calibrated per manufacturer instructions prior to use. Falcon staff bagged composite soil samples of each boring in approximately two-foot sections. Representative samples were placed in a sealed plastic bag for approximately 10 minutes to allow soil hydrocarbons to reach equilibrium within the headspace prior to scanning with the PID. One sample per boring was collected from the depth of the proposed cut or from the section above the depth of cut with the highest PID reading.

To avoid cross contamination, a new unused pair of non-powdered nitrile gloves was worn while extracting each sample. Samples were placed in the appropriate laboratory provided containers. The labels on each container were then completed so that each provided the date and time of sampling, method of analysis, sample collector, preservative used and sampling location identification. Samples were placed in an ice filled cooler and transported to the lab. Appropriate chain-of-custody procedures, including the completion of necessary forms, were followed.

SECTION 5: RESULTS

5.1 GEOPHYSICS

The geophysical investigation was performed between March 18 and March 26, 2019 to investigate for metallic underground storage tanks (USTs) were present beneath the survey area. A total of three EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. One EM anomaly was associated with interference from a car and was further investigated with GPR. The GPR transects did not record any evidence of buried structures, such as USTs.

5.2 SAMPLE DATA

Falcon and our subcontractor advanced one boring (B-14) to the proposed excavation depth of the drainage features, utilities, or roadway/ditch cut being assessed. Groundwater was not observed. Please see the Boring Location Plan in the attachments for a visual depiction of the sample locations. The coordinates (latitude and longitude) that correspond to the sample locations are shown below in Table No. 1 Boring Coordinates.

TABLE NO. 1 BORING COORDINATES

Boring	Latitude	Longitude
B-14	34.6366127	-79.0021424

Borings were field screened with a PID in sections for evidence of volatile organics. The PID screening results are presented in Table No. 2 PID Readings. Falcon selected soil samples based on the field screening results and the needs of the project. Red Lab analyzed the selected samples and their full analytical report is attached. The results of the laboratory analysis are shown in Table No. 3 Summary of UVF Soil Sampling Results.

Petroleum hydrocarbons above State Action Levels were not detected in the samples.

TABLE NO. 2 PID READINGS

Boring	Depth BGS*	PID**
B-14	0-3.0	1.8
	3.0-6.0	3.3

*BGS = Depth below ground surface in feet

**PID readings are in parts per million

Samples shown in **bold** were selected for analysis

TABLE NO. 3 SUMMARY OF UVF SOIL SAMPLING RESULTS

Sample ID	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Finger-print Match
								% light	% mid	% heavy	
<0.27	0.71	34	34.7	16.4	1.8	0.035	4.7	86.6	8.8	Road Tar 95.4%,(FCM),(BO)	<0.27

Results reported in mg/kg (milligrams per kilogram)

5.3 SAMPLE OBSERVATIONS

Obvious visual indications of a release (stained soils, odors, or oily sheen) were not observed. Table No. 4 Soil Observations lists visual soil observations of color and texture.

TABLE NO. 4 SOIL OBSERVATIONS

Sample ID	Depth	Color	Soil Type
B-14	0-3.0	Brown Gray	Sandy Clay (A-6)
	3.0-6.0	Brown	Clayey Sand (A-2-6)

Depth is in feet below ground surface

5.4 QUANTITIES CALCULATIONS

Soils requiring quantity calculations were not identified.

SECTION 6: CONCLUSIONS

6.1 INTERPRETATION OF RESULTS

This Preliminary Site Assessment was performed to evaluate the soils in proximity to the project limits on this parcel for the presence of petroleum hydrocarbons. The findings are as follows:

- Soil sampling completed on the parcel did not identify contaminants in the soil at levels requiring remediation.

6.2 GEOPHYSICS

The geophysical data did not record evidence of unknown metallic USTs within the geophysical survey area at Parcel No. 14. Falcon does not anticipate USTs will be encountered within the project limits on this parcel during construction.

6.3 SAMPLING

Sampling results did not identify contaminants in the soil which require remediation in the areas sampled. Based on past project experience, Falcon does not anticipate soil remediation or special handling and disposal will be required during construction on this parcel.

6.4 QUANTITIES

Soils requiring quantities calculations were not identified.



SECTION 7: RECOMMENDATIONS


7.1 ADDITIONAL SAMPLING

Contaminants above the Industrial / Commercial Soil Cleanup Levels were not identified; therefore, additional assessment is not warranted at this time. Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

7.2 SPECIAL HANDLING OF IMPACTED SOIL

Soils requiring special handling were not identified. If suspect contaminated soils are encountered during construction Falcon and the NCDOT GeoEnvironmental Group should be contacted for proper handling instructions.

NCDOT U-5797 (SR 1997 Widening) Parcel 14
Preliminary Site Assessment
Vicinity Map




Project No.: G19011.00
Date: September 2019
Source: Google Maps

NCDOT U-5797 (SR 1997 Widening) Parcel 14

Preliminary Site Assessment

USGS Topographic Maps



Project No.: G19011.00
Date: September 2019
Source: "NW, NE, SW, and SE Lumberton, NC" 2019



NCDOT U-5797 (SR 1997 Widening) Parcel 14


Preliminary Site Assessment

Parcel Location Map




September 5, 2019

-  County Line
-  City Limits
-  Streets
-  Parcels



Esri, HERE, Garmin, (c) OpenStreetMap contributors, and the GIS user community
Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Project No.: G19011.00
Date: September 2019
Source: Robeson County GIS



NOTES:

- BGS = BELOW GROUND SURFACE



FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
RALEIGH, NC 27607
PHONE: 919.871.0800
FAX: 919.871.0803

BORING LOCATION PLAN

NCDOT U-5797 (SR 1997 WIDENING)
PARCEL 14 - RT & DT ENTERPRISES LLC
ROBESON / LUMBERTON, NC
WBS NO.: 44367.1.1 & TIP NO.: U-5797
FALCON PROJECT NO. G19011.00

NCDOT U-5797 (SR 1997 Widening) Parcel 14
Preliminary Site Assessment
Site Photographs



Photograph No. 1: General view of Boring B-14.

**Project:** G19011 U5797[illegible]

Concentration values in mg/kg for soil samples and mg/L for water samples. Soil values uncorrected for moisture or stone content. Fingerprints provide a tentative hydrocarbon identification.

Abbreviations :- FCM = Results calculated using Fundamental Calibration Mode : % = confidence of hydrocarbon identification : (PFM) = Poor Fingerprint Match : (T) = Turbid : (P) = Particulate detected


B = Blank Drift : (SBS)/(LBS) = Site Specific or Library Background Subtraction applied to result : (BO) = Background Organics detected : (OCR) = Outside cal range : (M) = Modified Result.

% Ratios estimated aromatic carbon number proportions : HC = Hydrocarbon : PHC = Petroleum HC : FP = Fingerprint only. **Data generated by HC-1 Analyser**

QED Hydrocarbon Fingerprints

Project: G19011 U5797

Tuesday, April 16, 2019





PYRAMID GEOPHYSICAL SERVICES
(PROJECT 2019-091)

GEOPHYSICAL SURVEY

METALLIC UST INVESTIGATION: PARCEL 14 NCDOT PROJECT U-5797

2500-02 FAYETTEVILLE RD., LUMBERTON, NC

APRIL 22, 2019

Report prepared for: Christopher J. Burkhardt, PWS
Falcon Engineers
1210 Trinity Rd. #110
Raleigh, NC 27607

Prepared by: _____

A handwritten signature in black ink, appearing to read "E. Cross".

Eric C. Cross, P.G.
NC License #2181

Reviewed by: _____

A handwritten signature in black ink, appearing to read "Doug Canavella".

Douglas A. Canavella, P.G.
NC License #1066

503 INDUSTRIAL AVENUE, GREENSBORO, NC 27406

P: 336.335.3174 F: 336.691.0648

C257: GEOLOGY

C1251: ENGINEERING

GEOPHYSICAL INVESTIGATION REPORT
Parcel 14 - 2500-02 Fayetteville Rd.
Lumberton, Robeson County, North Carolina

Table of Contents

Executive Summary	1
Introduction.....	2
Field Methodology.....	2
Discussion of Results.....	3
<i>Discussion of EM Results</i>	3
<i>Discussion of GPR Results</i>	4
Summary & Conclusions	4
Limitations	5

Figures

- Figure 1 – Parcel 14 - Geophysical Survey Boundaries and Site Photographs
- Figure 2 – Parcel 14 - EM61 Results Contour Map
- Figure 3 – Parcel 14 - GPR Transect Locations and Images
- Figure 4 – Parcel 14 - Overlay of Metal Detection Results on NCDOT Engineering Plans

LIST OF ACRONYMS

CADD	Computer Assisted Drafting and Design
DF	Dual Frequency
EM.....	Electromagnetic
GPR.....	Ground Penetrating Radar
GPS	Global Positioning System
NCDOT.....	North Carolina Department of Transportation
ROW	Right-of-Way
UST	Underground Storage Tank

EXECUTIVE SUMMARY

Project Description: Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 14, located at 2500-02 Fayetteville Rd. in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-26, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

Geophysical Results: The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. A total of three EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. One EM anomaly was associated with interference from a car and was further investigated with GPR. The GPR transects did not record any evidence of buried structures, such as USTs. Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 14.

INTRODUCTION

Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 14, located at 2500-02 Fayetteville Rd. in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-26, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

The site included a commercial building surrounded by gravel, asphalt, and grass surfaces. An aerial photograph showing the survey area boundaries and ground-level photographs are shown in **Figure 1**.

FIELD METHODOLOGY

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is geo-referenced and can be overlain on aerial photographs and CADD drawings. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and assure complete coverage of the area.

According to the instrument specifications, the EM61 can detect a metal drum down to a maximum depth of approximately 8 feet. Smaller objects (1-foot or less in size) can be detected to a maximum depth of 4 to 5 feet. The EM61 data were digitally collected at approximately 0.8-foot intervals along north-south trending or east-west trending, generally parallel survey lines, spaced five feet apart. The data were downloaded to a

computer and reviewed in the field and office using the Geonics NAV61 and Surfer for Windows Version 15.0 software programs.

GPR data were acquired across select EM anomalies on March 26, 2019, using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Data were collected both in reconnaissance fashion as well as along formal transect lines across EM features. The GPR data were viewed in real-time using a vertical scan of 512 samples, at a rate of 48 scans per second. GPR data were viewed down to a maximum depth of approximately 6 feet, based on dielectric constants calculated by the DF unit in the field during the reconnaissance scans. GPR transects across specific anomalies were saved to the hard drive of the DF unit for post-processing and figure generation.

Pyramid's classifications of USTs for the purposes of this report are based directly on the geophysical UST ratings provided by the NCDOT. These ratings are as follows:

Geophysical Surveys for Underground Storage Tanks on NCDOT Projects			
High Confidence	Intermediate Confidence	Low Confidence	No Confidence
Known UST Active tank - spatial location, orientation, and approximate depth determined by geophysics.	Probable UST Sufficient geophysical data from both magnetic and radar surveys that is characteristic of a tank. Interpretation may be supported by physical evidence such as fill/vent pipe, metal cover plate, asphalt/concrete patch, etc.	Possible UST Sufficient geophysical data from either magnetic or radar surveys that is characteristic of a tank. Additional data is not sufficient enough to confirm or deny the presence of a UST.	Anomaly noted but not characteristic of a UST. Should be noted in the text and may be called out in the figures at the geophysicist's discretion.

DISCUSSION OF RESULTS

Discussion of EM Results

A contour plot of the EM61 results obtained across the survey area at the property is presented in **Figure 2**. Each EM anomaly is numbered for reference in the figure. The following table presents the list of EM anomalies and the cause of the metallic response, if known:

LIST OF METALLIC ANOMALIES IDENTIFIED BY EM SURVEY

Metallic Anomaly #	Cause of Anomaly	Investigated with GPR
1	Utilities	
2	Drop Inlet	
3	Car	☑

The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface, including utilities, a drop inlet, and a car. EM Anomaly 3 was associated with interference from a car and was further investigated with GPR to verify that the interference did not obscure buried structures such as USTs.

Discussion of GPR Results

Figure 3 presents the locations of the formal GPR transects performed at the property as well as the transect images. A total of two formal GPR transects were performed at the site. GPR Transects 1-2 were performed across EM Anomaly 3. These transects recorded no evidence of buried structures, such as USTs.

Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 14. **Figure 4** provides an overlay of the EM61 metal detection contour map onto the NCDOT MicroStation engineering plans for reference.

SUMMARY & CONCLUSIONS

Pyramid's evaluation of the EM61 and GPR data collected at Parcel 14 in Lumberton, North Carolina, provides the following summary and conclusions:

- The EM61 and GPR surveys provided reliable results for the detection of metallic USTs within the accessible portions of the geophysical survey area.
- The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface.
- One EM anomaly associated with interference from a car and was further

investigated with GPR. The GPR transects did not record any evidence of buried structures, such as USTs.

- Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 14.

LIMITATIONS

Geophysical surveys have been performed and this report was prepared for Falcon Engineers in accordance with generally accepted guidelines for EM61 and GPR surveys. It is generally recognized that the results of the EM61 and GPR surveys are non-unique and may not represent actual subsurface conditions. The EM61 and GPR results obtained for this project have not conclusively determined the definitive presence or absence of metallic USTs, but the evidence collected is sufficient to result in the conclusions made in this report. Additionally, it should be understood that areas containing extensive vegetation, reinforced concrete, or other restrictions to the accessibility of the geophysical instruments could not be fully investigated.

APPROXIMATE BOUNDARIES OF GEOPHYSICAL SURVEY AREA



View of Survey Area
(Facing Approximately North)



View of Survey Area
(Facing Approximately South)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology

PROJECT
PARCEL 14
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 14 - GEOPHYSICAL
SURVEY BOUNDARIES AND SITE PHOTOGRAPHS

DATE
3/26/2019
PYRAMID
PROJECT #:
2019-091

CLIENT
FALCON ENGINEERS
FIGURE 1


EM61 METAL DETECTION RESULTS



NO EVIDENCE OF METALLIC
USTs OBSERVED.

The contour plot shows the differential results of the EM61 instrument in millivolts (mV). The differential results focus on larger metallic objects such as USTs and drums. The EM data were collected on March 18, 2019, using a Geonics EM61-MK2 instrument. Verification GPR data were collected using a GSSI UtilityScan DF instrument with a dual frequency 300/800 MHz antenna on March 26, 2019.

EM61 Metal Detection Response
(millivolts)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology


PROJECT
PARCEL 14
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 14 -
EM61 METAL DETECTION CONTOUR MAP


DATE
3/26/2019
PYRAMID
PROJECT #: 2019-091

CLIENT
FALCON ENGINEERS
FIGURE 2

LOCATIONS OF GPR TRANSECTS



GPR TRANSECT 1 (T1)



GPR TRANSECT 2 (T2)




503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology

PROJECT
PARCEL 14
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 14 -
GPR TRANSECT LOCATIONS AND IMAGES

DATE
3/26/2019
PYRAMID
PROJECT #:
2019-091


CLIENT
FALCON ENGINEERS
FIGURE 3




LEGEND

- EXISTING ROW
- EXISTING PROPERTY BOUNDARY
- PROPOSED ROW LINE
- TEMPORARY CONSTRUCTION EASEMENT
- PUE - PROPOSED PERMANENT UTILITY EASEMENT
- PROPOSED SS CUT LINE
- PROPOSED SS FILL LINE

MILLIVOLTS (mV)



EM61 METAL DETECTION
CONTOURS (SEE FIGURE 2
FOR ANOMALY LABELS)

TITLE OVERLAY OF METAL DETECTION RESULTS ON NCDOT ENGINEERING PLANS	
PROJECT PARCEL 014 LUMBERTON, NORTH CAROLINA NCDOT PROJECT U-5797	
 <div>503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 336.335.3174 (p) 336.691.0648 (f) License # C1251 Eng. / #C257 Geology</div>	
DATE: 04-11-2019	REVISION NO. 0
PYRAMID PROJECT NO. 2019-091	FIGURE NO. 4

PRELIMINARY SITE ASSESSMENT

**SR 1997 (FAYETTEVILLE ROAD) WIDENING
TIP NO. U-5797, WBS NO. 44367.1.1**

**NCDOT PARCEL NO. 15
OWNER: FREEMAN INVESTMENTS INC
2504 FAYETTEVILLE ROAD
LUMBERTON, ROBESON COUNTY, NORTH CAROLINA**



PREPARED FOR:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
C/O STV ENGINEERS, INC.
1600 PERIMETER PARK DRIVE, SUITE 225
MORRISVILLE, NC 2756002

PREPARED BY:
FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
CARY, NC 27513

PROJECT NUMBER: G19011.00
JUNE 9, 2020





June 9, 2020

Mr. Patrick Livingston, PE
STV Engineers, Inc.
900 W. Trade St, Suite 715
Charlotte, NC 28202

Re: **Preliminary Site Assessment**
SR 1997 (Fayetteville Road) Widening
TIP No. U-5797, WBS No. 44367.1.1
Parcel No. 15
Owner: Freeman Investments Inc
2504 Fayetteville Road
Lumberton, Robeson County, North Carolina

Dear: Mr. Livingston:

Falcon is pleased to present the following Preliminary Site Assessment in support of the above-mentioned Project. Specifically, Falcon sampled soil in proximity to the project limits on this parcel in general accordance with the approved scope of work. Soils requiring remediation or special handling during construction were not identified.

Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

Please review this report and advise us if you have any questions or concerns. We appreciate this opportunity to provide services to you and look forward to partnering with you on future projects. If you have any questions, please give Falcon a call at (919) 871-0800.

Sincerely,

FALCON ENGINEERING, INC.

A handwritten signature in blue ink, reading "Christopher J. Burkhardt".

Christopher J. Burkhardt
Environmental Services Manager

A handwritten signature in blue ink, reading "Jeremy R. Hamm".

Jeremy R. Hamm, PE
Geotechnical Services Manager

TABLE OF CONTENTS

SECTION 1: INTRODUCTION	5
1.1 DESCRIPTION	5
1.2 SCOPE OF WORK.....	5
SECTION 2: HISTORY	6
2.1 PARCEL USAGE.....	6
2.2 FACILITY IDENTIFICATION NUMBER	6
2.3 GROUNDWATER INCIDENT NUMBER.....	6
SECTION 3: SITE OBSERVATIONS	7
3.1 GROUNDWATER MONITORING WELLS.....	7
3.2 ACTIVE USTS	7
3.3 FEATURES APPARENT BEYOND ROW/EASEMENT	7
SECTION 4: METHODOLOGY	8
4.1 GEOPHYSICS.....	8
4.2 BORINGS	8
4.3 SAMPLE PROTOCOL.....	8
SECTION 5: RESULTS.....	10
5.1 GEOPHYSICS	10
5.2 SAMPLE DATA	10
TABLE NO. 1 BORING COORDINATES.....	10
TABLE NO. 2 PID READINGS	10
TABLE NO. 3 SUMMARY OF UVF SOIL SAMPLING RESULTS	11
5.3 SAMPLE OBSERVATIONS	11
TABLE NO. 4 SOIL OBSERVATIONS.....	11
5.4 QUANTITIES CALCULATIONS	11
SECTION 6: CONCLUSIONS	12
6.1 INTERPRETATION OF RESULTS	12
6.2 GEOPHYSICS.....	12
6.3 SAMPLING	12
6.4 QUANTITIES	12
SECTION 7: RECOMMENDATIONS	13
7.1 ADDITIONAL SAMPLING	13
7.2 SPECIAL HANDLING OF IMPACTED SOIL.....	13

LIST OF FIGURES AND ATTACHMENTS

VICINITY MAP

USGS TOPOGRAPHIC MAP

PARCEL LOCATION MAP

BORING LOCATION MAP

SITE PHOTOGRAPHS

LABORATORY RESULTS

GEOPHYSICAL SURVEY



SECTION 1: INTRODUCTION

1.1 DESCRIPTION

Falcon Engineering, Inc. (Falcon) has completed a Preliminary Site Assessment of NCDOT TIP Project U-5797 Parcel No. 15. Parcel No. 15 is addressed as 2504 Fayetteville Road, Lumberton Robeson County, North Carolina. NCDOT is proposing to widen Fayetteville Road (SR 1997) from Farringdom Street to 22nd Street. The limits of the assessment are between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). Boring locations were placed in the vicinity of proposed excavations for drainage features, utilities, and roadway/ditch cuts to determine if soils requiring remediation or special handling were present where excavation was planned to take place.

1.2 SCOPE OF WORK

Falcon's scope of work included coordination of; public and private utility location near the proposed borings, geophysical surveys, collecting soil samples using direct push methods, and laboratory analysis. Samples were analyzed for petroleum hydrocarbons via UVF technology.



SECTION 2: HISTORY

2.1 PARCEL USAGE

Falcon performed a Phase I Environmental Site Assessment (ESA) for U-5797 under Project No. G17057 dated April 2018. The ESA identified this parcel as a Recognized Environmental Condition (REC) based on the history of the parcel and adjoining parcels. Falcon contacted Mr. Joe Oliver the County Fire Marshal during the ESA to inquire about known USTs along Fayetteville Road in the general area of Parcel No. 15. Mr. Oliver sent documents pertaining to USTs that had been installed and/or removed from Amerigas at 2502 Fayetteville Road. There are three buildings with separate addresses on this parcel. One building is addressed as 2502. The exact location of the UST is unknown. UST closure documentation including soil sampling results were not available for review.

2.2 FACILITY IDENTIFICATION NUMBER

A Facility Identification Number was not identified for this parcel.

2.3 GROUNDWATER INCIDENT NUMBER

A Groundwater Incident Number was not identified for this parcel.



SECTION 3: SITE OBSERVATIONS

3.1 GROUNDWATER MONITORING WELLS

Groundwater monitoring wells (MWs) were not observed on this parcel.

3.2 ACTIVE USTS

Active USTs were not observed within the project limits or registered at this parcel.

3.3 FEATURES APPARENT BEYOND ROW/EASEMENT

USTs, monitoring wells, remediation systems, or hydraulic lifts were not observed within the project limits. However, access to the buildings was not available. Philips Auto Body operates out of the large commercial building on this parcel; therefore, USTs and hydraulic lifts on this parcel cannot be ruled out.

SECTION 4: METHODOLOGY

4.1 GEOPHYSICS

Pyramid Geophysical Services (Pyramid) was subcontracted to perform a geophysical survey of the assessment area. The assessment area is between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). The survey was used to locate private utility lines, as well as possible indications of USTs, and/or their pits.

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is georeferenced and can be overlain on aerial photographs and CADD drawings.

GPR data was acquired across select EM anomalies (where identified), using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Pyramid marked their findings on the surface with paint. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and to obtain adequate coverage. A copy of the full Geophysical Report is included in the Attachments.

4.2 BORINGS

Regional Probing was subcontracted to advance soil borings using direct push technology. Regional Probing used a truck-mounted Geoprobe® 5410 unit mounted on an off-road modified Ford F350 Diesel 4x4. The unit has auger-capabilities and is equipped with a GH-42 soil-probing hammer, with 21,700 pounds of down force and 28,900 pounds of retraction force. The unit has an on-board tank for decontaminating the geoprobe rods before advancing the probe at each sample location.

4.3 SAMPLE PROTOCOL

Prior to initiating sample collection Falcon contacted NC One Call and requested public utility locations be marked around the proposed sample locations. Sampling was in general accordance with the NC Department of Environmental Quality (DEQ) Division of Waste Management's (DWM) "Guidelines for Site Checks, Tank Closure, and Initial Response and Abatement for UST Releases" (March 1, 2007 Version Change 9 – February 1, 2019) guidance document. Sampling strategy was derived based upon the project scope and objectives as outlined above. Red Lab, LLC was selected to perform the UVF laboratory analytical analysis. Appropriate sterile containers were received by Falcon from Red Lab prior to beginning the fieldwork. The containers were labeled appropriately.

A Minirae 3000 photoionization detector (PID) was used to field screen samples for volatile organics to determine if a release had occurred. The instrument was calibrated per manufacturer instructions prior to use. Falcon staff bagged composite soil samples of each boring in approximately two-foot sections. Representative samples were placed in a sealed plastic bag for approximately 10 minutes to allow soil hydrocarbons to reach equilibrium within the headspace prior to scanning with the PID. One sample per boring was collected from the depth of the proposed cut or from the section above the depth of cut with the highest PID reading.

To avoid cross contamination, a new unused pair of non-powdered nitrile gloves was worn while extracting each sample. Samples were placed in the appropriate laboratory provided containers. The labels on each container were then completed so that each provided the date and time of sampling, method of analysis, sample collector, preservative used and sampling location identification. Samples were placed in an ice filled cooler and transported to the lab. Appropriate chain-of-custody procedures, including the completion of necessary forms, were followed.

SECTION 5: RESULTS

5.1 GEOPHYSICS

The geophysical investigation was performed between March 18 and 26, 2019 to investigate for metallic underground storage tanks (USTs) beneath the survey area. A total of four EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. One EM anomaly was associated with interference from the building and cars and was further investigated with GPR to verify that the interference did not obscure buried structures such as USTs. These transects recorded no evidence of buried structures, such as USTs.

5.2 SAMPLE DATA

Falcon and our subcontractor advanced three borings (B-15, B-16, and B-17) to the proposed excavation depth of the drainage features, utilities, or roadway/ditch cut being assessed. Groundwater was not observed. Please see the Boring Location Plan in the attachments for a visual depiction of the sample locations. The coordinates (latitude and longitude) that correspond to the sample locations are shown below in Table No. 1 Boring Coordinates.

TABLE NO. 1 BORING COORDINATES

Boring	Latitude	Longitude
B-15	34.6367988	-79.0020563
B-16	34.6369054	-79.0020157
B-17	34.6372867	-79.001862

Borings were field screened with a PID in sections for evidence of volatile organics. The PID screening results are presented in Table No. 2 PID Readings. Falcon selected soil samples based on the field screening results and the needs of the project. Red Lab analyzed the selected samples and their full analytical report is attached. The results of the laboratory analysis are shown in Table No. 3 Summary of UVF Soil Sampling Results.

Petroleum hydrocarbons above State Action Levels were not detected in the samples.

TABLE NO. 2 PID READINGS

Boring	Depth BGS*	PID**
B-15	0-3	1.2
	3-6	1.0
B-16	0-3.0	1.2
	3.0-6.0	1.1
B-17	0-3.0	0.8
	3.0-6.0	1.0

*BGS = Depth below ground surface in feet

**PID readings are in parts per million

Samples shown in **bold** were selected for analysis

TABLE NO. 3 SUMMARY OF UVF SOIL SAMPLING RESULTS

Sample ID	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
								% light	% mid	% heavy	
B-15	<0.29	<0.29	0.29	0.29	0.15	<0.09	<0.012	0	75.5	24.5	V.Deg.PHC 96.2%,(FCM)
B-16	<0.28	<0.28	0.54	0.54	0.24	<0.09	<0.011	0	76.1	23.9	V.Deg.PHC 97%,(FCM)
B-17	<0.27	<0.27	6.5	6.5	3.1	0.16	<0.011	0	80.5	19.5	Deg.PHC 78.8%,(FCM)

Results reported in mg/kg (milligrams per kilogram)

5.3 SAMPLE OBSERVATIONS

Obvious visual indications of a release (stained soils, odors, or oily sheen) were not observed. Table No. 4 Soil Observations lists visual soil observations of color and texture.

TABLE NO. 4 SOIL OBSERVATIONS

Sample ID	Depth	Color	Soil Type
B-15	0-3	Red Brown	Sandy Clay (A-6)
	3-6	Gray Brown Red (mottled)	Sandy Clay (A-6)
B-16	0-3.0	Brown	Clayey Silty Sand (A-2-6)
	3.0-6.0	Brown Orange	Sandy Clay (A-6)
B-17	0-3.0	Brown Orange	Silty Sand (A-2-4)
	3.0-6.0	Brown Orange	Silty Clayey Sand (A-2-6)

Depth is in feet below ground surface

5.4 QUANTITIES CALCULATIONS

Soils requiring quantity calculations were not identified.

SECTION 6: CONCLUSIONS

6.1 INTERPRETATION OF RESULTS

This Preliminary Site Assessment was performed to evaluate the soils in proximity to the project limits on this parcel for the presence of petroleum hydrocarbons. The findings are as follows:

- Soil sampling completed on the parcel did not identify contaminants in the soil at levels requiring remediation.

6.2 GEOPHYSICS

The geophysical data did not record evidence of unknown metallic USTs within the geophysical survey area at Parcel No. 15. Falcon does not anticipate USTs will be encountered within the project limits on this parcel during construction.

6.3 SAMPLING

Sampling results did not identify contaminants in the soil which require remediation in the areas sampled. Based on past project experience, Falcon does not anticipate soil remediation or special handling and disposal will be required during construction on this parcel.

6.4 QUANTITIES

Soils requiring quantities calculations were not identified.

SECTION 7: RECOMMENDATIONS


7.1 ADDITIONAL SAMPLING

Contaminants above the Industrial / Commercial Soil Cleanup Levels were not identified; therefore, additional assessment is not warranted at this time. Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

7.2 SPECIAL HANDLING OF IMPACTED SOIL

Soils requiring special handling were not identified. If suspect contaminated soils are encountered during construction Falcon and the NCDOT GeoEnvironmental Group should be contacted for proper handling instructions.

NCDOT U-5797 (SR 1997 Widening) Parcel 15
Preliminary Site Assessment
Vicinity Map




Project No.: G19011.00
Date: September 2019
Source: Google Maps

NCDOT U-5797 (SR 1997 Widening) Parcel 15

Preliminary Site Assessment

USGS Topographic Maps



Project No.: G19011.00
Date: September 2019
Source: "NW, NE, SW, and SE Lumberton, NC" 2019

NCDOT U-5797 (SR 1997 Widening) Parcel 15


Preliminary Site Assessment

Parcel Location Map




September 5, 2019

-  County Line
-  City Limits
-  Streets
-  Parcels



Esri, HERE, Garmin, (c) OpenStreetMap contributors, and the GIS user community
Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Project No.: G19011.00
Date: September 2019
Source: Robeson County GIS



NOTES:

- BGS = BELOW GROUND SURFACE



FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
RALEIGH, NC 27607
PHONE: 919.871.0800
FAX: 919.871.0803

BORING LOCATION PLAN

NCDOT U-5797 (SR 1997 WIDENING)
PARCEL 15 - FREEMAN INVESTMENTS INC
ROBESON / LUMBERTON, NC
WBS NO.: 44367.1.1 & TIP NO.: U-5797
FALCON PROJECT NO. G19011.00

NCDOT U-5797 (SR 1997 Widening) Parcel 15
Preliminary Site Assessment
Site Photographs



Photograph No. 1: General view of Boring B-15.



Photograph No. 2: General view of Boring B-16.

NCDOT U-5797 (SR 1997 Widening) Parcel 15
Preliminary Site Assessment
Site Photographs



Photograph No. 3: General view of Boring B-17.






Data generated by HC-1 Analyser

QED Hydrocarbon Fingerprints

Project: G19011 U5797

Tuesday, April 16, 2019





PYRAMID GEOPHYSICAL SERVICES
(PROJECT 2019-091)

GEOPHYSICAL SURVEY

METALLIC UST INVESTIGATION: PARCEL 15 NCDOT PROJECT U-5797

2502-03 FAYETTEVILLE RD., LUMBERTON, NC

APRIL 22, 2019

Report prepared for: Christopher J. Burkhardt, PWS
Falcon Engineers
1210 Trinity Rd. #110
Raleigh, NC 27607

Prepared by: _____

A handwritten signature in black ink, appearing to read "E. Cross".

Eric C. Cross, P.G.
NC License #2181

Reviewed by: _____

A handwritten signature in black ink, appearing to read "Doug Canavella".

Douglas A. Canavella, P.G.
NC License #1066

503 INDUSTRIAL AVENUE, GREENSBORO, NC 27406

P: 336.335.3174 F: 336.691.0648

C257: GEOLOGY

C1251: ENGINEERING

GEOPHYSICAL INVESTIGATION REPORT
Parcel 15 - 2502-03 Fayetteville Rd.
Lumberton, Robeson County, North Carolina

Table of Contents

Executive Summary	1
Introduction.....	2
Field Methodology.....	2
Discussion of Results.....	3
<i>Discussion of EM Results</i>	3
<i>Discussion of GPR Results</i>	4
Summary & Conclusions	4
Limitations	5

Figures

- Figure 1 – Parcel 15 - Geophysical Survey Boundaries and Site Photographs
- Figure 2 – Parcel 15 - EM61 Results Contour Map
- Figure 3 – Parcel 15 - GPR Transect Locations and Images
- Figure 4 – Parcel 15 - Overlay of Metal Detection Results on NCDOT Engineering Plans

LIST OF ACRONYMS

CADD	Computer Assisted Drafting and Design
DF	Dual Frequency
EM.....	Electromagnetic
GPR.....	Ground Penetrating Radar
GPS	Global Positioning System
NCDOT.....	North Carolina Department of Transportation
ROW	Right-of-Way
UST	Underground Storage Tank

EXECUTIVE SUMMARY

Project Description: Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 15, located at 2502-03 Fayetteville Rd. in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-26, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

Geophysical Results: The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. A total of four EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. One EM anomaly was associated with interference from the building and cars and was further investigated with GPR to verify that the interference did not obscure buried structures such as USTs. These transects recorded no evidence of buried structures, such as USTs. Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 15.

INTRODUCTION

Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 15, located at 2502-03 Fayetteville Rd. in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-26, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

The site included a commercial building surrounded by gravel, asphalt, and grass surfaces. An aerial photograph showing the survey area boundaries and ground-level photographs are shown in **Figure 1**.

FIELD METHODOLOGY

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is geo-referenced and can be overlain on aerial photographs and CADD drawings. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and assure complete coverage of the area.

According to the instrument specifications, the EM61 can detect a metal drum down to a maximum depth of approximately 8 feet. Smaller objects (1-foot or less in size) can be detected to a maximum depth of 4 to 5 feet. The EM61 data were digitally collected at approximately 0.8-foot intervals along north-south trending or east-west trending, generally parallel survey lines, spaced five feet apart. The data were downloaded to a

computer and reviewed in the field and office using the Geonics NAV61 and Surfer for Windows Version 15.0 software programs.

GPR data were acquired across select EM anomalies on March 26, 2019, using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Data were collected both in reconnaissance fashion as well as along formal transect lines across EM features. The GPR data were viewed in real-time using a vertical scan of 512 samples, at a rate of 48 scans per second. GPR data were viewed down to a maximum depth of approximately 6 feet, based on dielectric constants calculated by the DF unit in the field during the reconnaissance scans. GPR transects across specific anomalies were saved to the hard drive of the DF unit for post-processing and figure generation.

Pyramid's classifications of USTs for the purposes of this report are based directly on the geophysical UST ratings provided by the NCDOT. These ratings are as follows:

Geophysical Surveys for Underground Storage Tanks on NCDOT Projects			
High Confidence	Intermediate Confidence	Low Confidence	No Confidence
Known UST Active tank - spatial location, orientation, and approximate depth determined by geophysics.	Probable UST Sufficient geophysical data from both magnetic and radar surveys that is characteristic of a tank. Interpretation may be supported by physical evidence such as fill/vent pipe, metal cover plate, asphalt/concrete patch, etc.	Possible UST Sufficient geophysical data from either magnetic or radar surveys that is characteristic of a tank. Additional data is not sufficient enough to confirm or deny the presence of a UST.	Anomaly noted but not characteristic of a UST. Should be noted in the text and may be called out in the figures at the geophysicist's discretion.

DISCUSSION OF RESULTS

Discussion of EM Results

A contour plot of the EM61 results obtained across the survey area at the property is presented in **Figure 2**. Each EM anomaly is numbered for reference in the figure. The following table presents the list of EM anomalies and the cause of the metallic response, if known:

LIST OF METALLIC ANOMALIES IDENTIFIED BY EM SURVEY

Metallic Anomaly #	Cause of Anomaly	Investigated with GPR
1	Utilities	
2	Rebar	
3	Cars/Building	✓
4	Utilities	

The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface, including utilities, rebar, cars, and the building. EM Anomaly 3 was associated with interference from the building and cars and was further investigated with GPR to verify that the interference did not obscure buried structures such as USTs.

Discussion of GPR Results

Figure 3 presents the locations of the formal GPR transects performed at the property as well as the transect images. A total of five formal GPR transects were performed at the site. GPR Transects 1-2 were performed across EM Anomaly 3, where cars were parked. These transects recorded no evidence of buried structures, such as USTs.

GPR Transects 3-5 were performed across EM Anomaly 3, along the northwest corner of the building. These transects recorded no evidence of buried structures, such as USTs.

Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 15. **Figure 4** provides an overlay of the EM61 metal detection contour map onto the NCDOT MicroStation engineering plans for reference.

SUMMARY & CONCLUSIONS

Pyramid's evaluation of the EM61 and GPR data collected at Parcel 15 in Lumberton, North Carolina, provides the following summary and conclusions:

- The EM61 and GPR surveys provided reliable results for the detection of metallic

USTs within the accessible portions of the geophysical survey area.

- The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface.
- One EM anomaly was associated with interference from the building and cars and was further investigated with GPR to verify that the interference did not obscure buried structures such as USTs. These transects recorded no evidence of buried structures, such as USTs.
- Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 15.

LIMITATIONS

Geophysical surveys have been performed and this report was prepared for Falcon Engineers in accordance with generally accepted guidelines for EM61 and GPR surveys. It is generally recognized that the results of the EM61 and GPR surveys are non-unique and may not represent actual subsurface conditions. The EM61 and GPR results obtained for this project have not conclusively determined the definitive presence or absence of metallic USTs, but the evidence collected is sufficient to result in the conclusions made in this report. Additionally, it should be understood that areas containing extensive vegetation, reinforced concrete, or other restrictions to the accessibility of the geophysical instruments could not be fully investigated.

APPROXIMATE BOUNDARIES OF GEOPHYSICAL SURVEY AREA



View of Survey Area
(Facing Approximately North)



View of Survey Area
(Facing Approximately South)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology

PROJECT
PARCEL 15
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 15 - GEOPHYSICAL
SURVEY BOUNDARIES AND SITE PHOTOGRAPHS

DATE
3/26/2019
PYRAMID
PROJECT #:
2019-091

CLIENT
FALCON ENGINEERS
FIGURE 1


EM61 METAL DETECTION RESULTS



NO EVIDENCE OF METALLIC
USTs OBSERVED.

The contour plot shows the differential results of the EM61 instrument in millivolts (mV). The differential results focus on larger metallic objects such as USTs and drums. The EM data were collected on March 18, 2019, using a Geonics EM61-MK2 instrument. Verification GPR data were collected using a GSSI UtilityScan DF instrument with a dual frequency 300/800 MHz antenna on March 26, 2019.

EM61 Metal Detection Response
(millivolts)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology


PROJECT
PARCEL 15
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 15 -
EM61 METAL DETECTION CONTOUR MAP


DATE
3/26/2019
PYRAMID
PROJECT #: 2019-091

CLIENT
FALCON ENGINEERS
FIGURE 2


LOCATIONS OF GPR TRANSECTS




GPR TRANSECT 1 (T1)




GPR TRANSECT 2 (T2)



GPR TRANSECT 3 (T3)



GPR TRANSECT 4 (T4)



GPR TRANSECT 5 (T5)




503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology

PROJECT
PARCEL 15
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 15 -
GPR TRANSECT LOCATIONS AND IMAGES

DATE
3/26/2019
PYRAMID
PROJECT #:
2019-091

CLIENT
FALCON ENGINEERS
FIGURE 3






**EM61 METAL DETECTION
CONTOURS (SEE FIGURE 2
FOR ANOMALY LABELS)**

LEGEND

- EXISTING ROW
- EXISTING PROPERTY BOUNDARY
- PROPOSED ROW LINE
- TEMPORARY CONSTRUCTION EASEMENT
- PUE - PROPOSED PERMANENT UTILITY EASEMENT
- PROPOSED SS CUT LINE
- PROPOSED SS FILL LINE

MILLIVOLTS (mV)



TITLE OVERLAY OF METAL DETECTION RESULTS ON NCDOT ENGINEERING PLANS	
PROJECT PARCEL 015 LUMBERTON, NORTH CAROLINA NCDOT PROJECT U-5797	
 503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 336.335.3174 (p) 336.691.0648 (f) License # C1251 Eng. / #C257 Geology	
DATE: 04-11-2019	REVISION NO. 0
PYRAMID PROJECT NO. 2019-091	FIGURE NO. 4

PRELIMINARY SITE ASSESSMENT

**SR 1997 (FAYETTEVILLE ROAD) WIDENING
TIP NO. U-5797, WBS NO. 44367.1.1**

**NCDOT PARCEL NO. 16
OWNER: BRYAN BUILDINGS LLC
2548-E FAYETTEVILLE ROAD
LUMBERTON, ROBESON COUNTY, NORTH CAROLINA**



PREPARED FOR:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
C/O STV ENGINEERS, INC.
1600 PERIMETER PARK DRIVE, SUITE 225
MORRISVILLE, NC 2756002

PREPARED BY:
FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
CARY, NC 27513

PROJECT NUMBER: G19011.00
JUNE 9, 2020





June 9, 2020

Mr. Patrick Livingston, PE
STV Engineers, Inc.
900 W. Trade St, Suite 715
Charlotte, NC 28202

Re: **Preliminary Site Assessment**
SR 1997 (Fayetteville Road) Widening
TIP No. U-5797, WBS No. 44367.1.1
Parcel No. 16
Owner: Bryan Buildings LLC
2548-E Fayetteville Road
Lumberton, Robeson County, North Carolina

Dear: Mr. Livingston:

Falcon is pleased to present the following Preliminary Site Assessment in support of the above-mentioned Project. Specifically, Falcon sampled soil in proximity to the project limits on this parcel in general accordance with the approved scope of work. Soils requiring remediation or special handling during construction were not identified.

Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

Please review this report and advise us if you have any questions or concerns. We appreciate this opportunity to provide services to you and look forward to partnering with you on future projects. If you have any questions, please give Falcon a call at (919) 871-0800.

Sincerely,

FALCON ENGINEERING, INC.

A handwritten signature in blue ink, reading "Christopher J. Burkhardt".

Christopher J. Burkhardt
Environmental Services Manager

A handwritten signature in blue ink, reading "Jeremy R. Hamm".

Jeremy R. Hamm, PE
Geotechnical Services Manager

TABLE OF CONTENTS

SECTION 1: INTRODUCTION	5
1.1 DESCRIPTION	5
1.2 SCOPE OF WORK.....	5
SECTION 2: HISTORY	6
2.1 PARCEL USAGE.....	6
2.2 FACILITY IDENTIFICATION NUMBER	6
2.3 GROUNDWATER INCIDENT NUMBER.....	6
SECTION 3: SITE OBSERVATIONS	7
3.1 GROUNDWATER MONITORING WELLS	7
3.2 ACTIVE USTS	7
3.3 FEATURES APPARENT BEYOND ROW/EASEMENT	7
SECTION 4: METHODOLOGY	8
4.1 GEOPHYSICS	8
4.2 BORINGS.....	8
4.3 SAMPLE PROTOCOL	8
SECTION 5: RESULTS.....	10
5.1 GEOPHYSICS	10
5.2 SAMPLE DATA.....	10
TABLE NO. 1 BORING COORDINATES.....	10
TABLE NO. 2 PID READINGS	10
5.3 SAMPLE OBSERVATIONS	10
TABLE NO. 3 SOIL OBSERVATIONS.....	11
5.4 QUANTITIES CALCULATIONS.....	11
SECTION 6: CONCLUSIONS	12
6.1 INTERPRETATION OF RESULTS.....	12
6.2 GEOPHYSICS	12
6.3 SAMPLING.....	12
6.4 QUANTITIES.....	12
SECTION 7: RECOMMENDATIONS	13
7.1 ADDITIONAL SAMPLING	13
7.2 SPECIAL HANDLING OF IMPACTED SOIL	13



LIST OF FIGURES AND ATTACHMENTS

VICINITY MAP

USGS TOPOGRAPHIC MAP

PARCEL LOCATION MAP

BORING LOCATION MAP

SITE PHOTOGRAPHS

LABORATORY RESULTS

GEOPHYSICAL SURVEY



SECTION 1: INTRODUCTION

1.1 DESCRIPTION

Falcon Engineering, Inc. (Falcon) has completed a Preliminary Site Assessment of NCDOT TIP Project U-5797 Parcel No. 16. Parcel 16 is addressed as 2548-E Fayetteville Road, Lumberton Robeson County, North Carolina. NCDOT is proposing to widen Fayetteville Road (SR 1997) from Farringdom Street to 22nd Street. The limits of the assessment are between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). Boring locations were placed in the vicinity of proposed excavations for drainage features, utilities, and roadway/ditch cuts to determine if soils requiring remediation or special handling were present where excavation was planned to take place.

1.2 SCOPE OF WORK

Falcon's scope of work included coordination of; public and private utility location near the proposed borings, geophysical surveys, collecting soil samples via direct push technology, and laboratory analysis. Samples were analyzed for volatile organic compounds (VOCs) via traditional methods.



SECTION 2: HISTORY

2.1 PARCEL USAGE

Falcon performed a Phase I Environmental Site Assessment (ESA) for U-5797 under Project No. G17057 dated April 2018. The ESA identified this parcel as a Recognized Environmental Condition (REC) based on the potential for an unreported or undiscovered release. Smith's Cleaners is an active dry-cleaning business at this parcel. Falcon spoke with the clerk behind the counter and learned the facility has been a drop off-only facility for about the last two years. Before then the facility performed dry-cleaning onsite since the 1940s.

2.2 FACILITY IDENTIFICATION NUMBER

Facility Identification No: 780002C corresponds to this parcel.

2.3 GROUNDWATER INCIDENT NUMBER

A Groundwater Incident Number was not identified for this parcel.

SECTION 3: SITE OBSERVATIONS

3.1 GROUNDWATER MONITORING WELLS

Groundwater monitoring wells (MWs) were not observed on this parcel.

3.2 ACTIVE USTS

Active USTs were not observed within the project limits or registered at this parcel.

3.3 FEATURES APPARENT BEYOND ROW/EASEMENT

USTs, monitoring wells, remediation systems, or hydraulic lifts were not observed within the project limits.

SECTION 4: METHODOLOGY

4.1 GEOPHYSICS

Pyramid Geophysical Services (Pyramid) was subcontracted to perform a geophysical survey of the assessment area. The assessment area is between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). The survey was used to locate private utility lines, as well as possible indications of USTs, and/or their pits.

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is georeferenced and can be overlain on aerial photographs and CADD drawings.

GPR data was acquired across select EM anomalies (where identified), using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Pyramid marked their findings on the surface with paint. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and to obtain adequate coverage. A copy of the full Geophysical Report is included in the Attachments.

4.2 BORINGS

Regional Probing was subcontracted to advance soil borings using direct push technology. Regional Probing used a truck-mounted Geoprobe® 5410 unit mounted on an off-road modified Ford F350 Diesel 4x4. The unit has auger-capabilities and is equipped with a GH-42 soil-probing hammer, with 21,700 pounds of down force and 28,900 pounds of retraction force. The unit has an on-board tank for decontaminating the geoprobe rods before advancing the probe at each sample location.

4.3 SAMPLE PROTOCOL

Prior to initiating sample collection Falcon contacted NC One Call and requested public utility locations be marked around the proposed sample locations. Sampling was in general accordance with the NC Department of Environmental Quality (DEQ) Division of Waste Management's (DWM) "Guidelines for Site Checks, Tank Closure, and Initial Response and Abatement for UST Releases" (March 1, 2007 Version Change 9 – February 1, 2019) guidance document. Sampling strategy was derived based upon the project scope and objectives as outlined above. Pace Analytical (North Carolina Field Services Certification #: 5342) was selected to provide traditional lab testing for VOCs. Appropriate sterile containers were received by Falcon from Red Lab prior to beginning the fieldwork. The containers were labeled appropriately.

A Minirae 3000 photoionization detector (PID) was used to field screen samples for volatile organics to determine if a release had occurred. The instrument was calibrated per manufacturer instructions prior to use. Falcon staff bagged composite soil samples of each boring in approximately two-foot sections. Representative samples were placed in a sealed plastic bag for approximately 10 minutes to allow soil hydrocarbons to reach equilibrium within the headspace prior to scanning with the PID. One sample per boring was collected from the depth of the proposed cut or from the section above the depth of cut with the highest PID reading.

To avoid cross contamination, a new unused pair of non-powdered nitrile gloves was worn while extracting each sample. Samples were placed in the appropriate laboratory provided containers. The labels on each container were then completed so that each provided the date and time of sampling, method of analysis, sample collector, preservative used and sampling location identification. Samples were placed in an ice filled cooler and transported to the lab. Appropriate chain-of-custody procedures, including the completion of necessary forms, were followed.

SECTION 5: RESULTS

5.1 GEOPHYSICS

The geophysical investigation was performed between March 18 and March 26, 2019 to investigate for metallic underground storage tanks (USTs) beneath the survey area. A total of nine EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. Several EM anomalies were associated with interference from a building, a car, and suspected reinforced concrete and were further investigated with GPR. GPR verified the presence of metal reinforcement in the concrete on the central and southern portions of the survey area. No evidence of any larger structures such as USTs was observed.

5.2 SAMPLE DATA

Falcon and our subcontractor advanced two borings (B-18 and B19) to the proposed excavation depth of the drainage features, utilities, or roadway/ditch cut being assessed. Groundwater was not observed. Please see Figure 3 in the attachments for a visual depiction of the sample locations. The coordinates (latitude and longitude) that correspond to the sample locations are shown below in Table No. 1 Boring Coordinates.

TABLE NO. 1 BORING COORDINATES

Boring	Latitude	Longitude
B-18	34.6379799	-79.0015504
B-19	34.6382736	-79.0014282

Borings were field screened with a PID in approximately three-foot sections for evidence of VOCs. The PID screening results are presented in Table No. 2 PID Readings. Falcon selected soil samples based on the field screening results and the needs of the project. Pace Analytical analyzed the selected samples and their full analytical report is attached. VOCs above State Action Levels were not detected in the samples.

TABLE NO. 2 PID READINGS

Boring	Depth BGS*	PID**
B-18	0-3.3	3.3
	3.3-6.7	2.6
B-19	0-3.3	2.2
	3.3-6.7	1.1

*BGS = Depth below ground surface in feet

**PID readings are in parts per million

Samples shown in **bold** were selected for analysis

5.3 SAMPLE OBSERVATIONS

Obvious indications of a release (stained soils, odors, or oily sheen) were not observed. Table No. 3 Soil Observations lists visual soil observations of color and texture.

TABLE NO. 3 SOIL OBSERVATIONS

Sample ID	Depth	Color	Soil Type
B-18	0-3.3	Gray	Silty Sand (A-2-4)
	3.3-6.7	Gray	Clayey Silty Sand (A-2-4)
B-19	0-3.3	Gray Brown	Silty Clayey Sand (A-2-6)
	3.3-6.7	Gray Brown	Clayey Silty Sand (A-2-4)

Depth is in feet below ground surface

5.4 QUANTITIES CALCULATIONS

Soils requiring quantity calculations were not identified.

SECTION 6: CONCLUSIONS

6.1 INTERPRETATION OF RESULTS

This Preliminary Site Assessment was performed to evaluate the soils in proximity to the project limits on this parcel for the presence of VOCs. The findings are as follows:

- Soil sampling completed on the parcel did not identify VOCs in the soil at levels requiring remediation.

6.2 GEOPHYSICS

Collectively, the geophysical data did not record evidence of unknown metallic USTs within the geophysical survey area at Parcel No. 16. Falcon does not anticipate USTs will be encountered within the project limits on this parcel during construction.

6.3 SAMPLING

Sampling results did not identify VOCs in the soil which require remediation in the areas sampled. Based on past project experience, Falcon does not anticipate soil remediation or special handling and disposal will be required during construction on this parcel.

6.4 QUANTITIES

Soils requiring quantities calculations were not identified.



SECTION 7: RECOMMENDATIONS


7.1 ADDITIONAL SAMPLING

VOCs above the Industrial / Commercial Soil Cleanup Levels were not identified; therefore, additional assessment is not warranted at this time. Falcon recommends if drums, USTs, above ground storage tanks (ASTs), monitoring wells, petroleum odors, or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

7.2 SPECIAL HANDLING OF IMPACTED SOIL

Soils requiring special handling were not identified. If suspect contaminated soils are encountered during construction Falcon and the NCDOT GeoEnvironmental Group should be contacted for proper handling instructions.

NCDOT U-5797 (SR 1997 Widening) Parcel 16
Preliminary Site Assessment
Vicinity Map




Project No.: G19011.00
Date: September 2019
Source: Google Maps

NCDOT U-5797 (SR 1997 Widening) Parcel 16

Preliminary Site Assessment

USGS Topographic Maps



Project No.: G19011.00
Date: September 2019
Source: "NW, NE, SW, and SE Lumberton, NC" 2019



NCDOT U-5797 (SR 1997 Widening) Parcel 16


Preliminary Site Assessment

Parcel Location Map



September 5, 2019

-  County Line
-  City Limits
-  Streets
-  Parcels



Esri, HERE, Garmin, (c) OpenStreetMap contributors, and the GIS user community
Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Project No.: G19011.00
Date: September 2019
Source: Robeson County GIS

NCDOT U-5797 (SR 1997 Widening) Parcel 16
Preliminary Site Assessment
Site Photographs



Photograph No. 1: General view of Boring B-18.



Photograph No. 2: General view of Boring B-19.

April 25, 2019

Christopher Burkhardt
Falcon Engineering
1210 Trinity Road
Suite 110
Cary, NC 27513


RE: Project: U5797
Pace Project No.: 92425908

Dear Christopher Burkhardt:

Enclosed are the analytical results for sample(s) received by the laboratory on April 12, 2019. The results relate only to the samples included in this report. Results reported herein conform to the most current, applicable TNI/NELAC standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Tyriek Hooks
tyriek.hooks@pacelabs.com
(704)875-9092
Project Manager

Enclosures

cc: Christopher Burkhardt, Falcon Engineering



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

CERTIFICATIONS

Project: U5797
Pace Project No.: 92425908

Charlotte Certification IDs

9800 Kincey Ave. Ste 100, Huntersville, NC 28078
Louisiana/NELAP Certification # LA170028
North Carolina Drinking Water Certification #: 37706
North Carolina Field Services Certification #: 5342
North Carolina Wastewater Certification #: 12

South Carolina Certification #: 99006001
Florida/NELAP Certification #: E87627
Kentucky UST Certification #: 84
Virginia/VELAP Certification #: 460221

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE ANALYTE COUNT

Project: U5797
Pace Project No.: 92425908

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92425908001	B3	EPA 8270E	PKS	74	PASI-C
		EPA 8260D	DLK	63	PASI-C
92425908002	B5.1	EPA 8270E	PKS	74	PASI-C
		EPA 8260D	DLK	63	PASI-C
92425908003	B18	EPA 8260D	CL	70	PASI-C
		ASTM D2974-87	KDF	1	PASI-C
92425908004	B19	EPA 8260D	CL	70	PASI-C
		ASTM D2974-87	KDF	1	PASI-C

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: U5797
Pace Project No.: 92425908

Sample: B18 **Lab ID: 92425908003** Collected: 04/10/19 14:41 Received: 04/12/19 14:45 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8260D/5035A Volatile Organics		Analytical Method: EPA 8260D Preparation Method: EPA 5035A						
Acetone	ND	ug/kg	84.1	1	04/19/19 13:00	04/19/19 22:11	67-64-1	
Benzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	71-43-2	
Bromobenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	108-86-1	
Bromochloromethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	74-97-5	
Bromodichloromethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	75-27-4	
Bromoform	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	75-25-2	
Bromomethane	ND	ug/kg	8.4	1	04/19/19 13:00	04/19/19 22:11	74-83-9	
2-Butanone (MEK)	ND	ug/kg	84.1	1	04/19/19 13:00	04/19/19 22:11	78-93-3	
n-Butylbenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	104-51-8	
sec-Butylbenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	135-98-8	
tert-Butylbenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	98-06-6	
Carbon tetrachloride	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	56-23-5	
Chlorobenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	108-90-7	
Chloroethane	ND	ug/kg	8.4	1	04/19/19 13:00	04/19/19 22:11	75-00-3	
Chloroform	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	67-66-3	
Chloromethane	ND	ug/kg	8.4	1	04/19/19 13:00	04/19/19 22:11	74-87-3	
2-Chlorotoluene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	95-49-8	
4-Chlorotoluene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	106-43-4	
1,2-Dibromo-3-chloropropane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	96-12-8	
Dibromochloromethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	124-48-1	
1,2-Dibromoethane (EDB)	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	106-93-4	
Dibromomethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	74-95-3	
1,2-Dichlorobenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	95-50-1	
1,3-Dichlorobenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	541-73-1	
1,4-Dichlorobenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	106-46-7	
Dichlorodifluoromethane	ND	ug/kg	8.4	1	04/19/19 13:00	04/19/19 22:11	75-71-8	
1,1-Dichloroethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	75-34-3	
1,2-Dichloroethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	107-06-2	
1,1-Dichloroethene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	75-35-4	
cis-1,2-Dichloroethene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	156-59-2	
trans-1,2-Dichloroethene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	156-60-5	
1,2-Dichloropropane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	78-87-5	
1,3-Dichloropropane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	142-28-9	
2,2-Dichloropropane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	594-20-7	
1,1-Dichloropropene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	563-58-6	
cis-1,3-Dichloropropene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	10061-01-5	
trans-1,3-Dichloropropene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	10061-02-6	
Diisopropyl ether	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	108-20-3	
Ethylbenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	100-41-4	
Hexachloro-1,3-butadiene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	87-68-3	
2-Hexanone	ND	ug/kg	42.0	1	04/19/19 13:00	04/19/19 22:11	591-78-6	
Isopropylbenzene (Cumene)	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	98-82-8	
p-Isopropyltoluene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	99-87-6	
Methylene Chloride	ND	ug/kg	16.8	1	04/19/19 13:00	04/19/19 22:11	75-09-2	
4-Methyl-2-pentanone (MIBK)	ND	ug/kg	42.0	1	04/19/19 13:00	04/19/19 22:11	108-10-1	
Methyl-tert-butyl ether	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	1634-04-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: U5797
Pace Project No.: 92425908

Sample: B18 Lab ID: 92425908003 Collected: 04/10/19 14:41 Received: 04/12/19 14:45 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8260D/5035A Volatile Organics Analytical Method: EPA 8260D Preparation Method: EPA 5035A								
Naphthalene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	91-20-3	
n-Propylbenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	103-65-1	
Styrene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	100-42-5	
1,1,1,2-Tetrachloroethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	630-20-6	
1,1,2,2-Tetrachloroethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	79-34-5	
Tetrachloroethene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	127-18-4	
Toluene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	108-88-3	
1,2,3-Trichlorobenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	87-61-6	
1,2,4-Trichlorobenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	120-82-1	
1,1,1-Trichloroethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	71-55-6	
1,1,2-Trichloroethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	79-00-5	
Trichloroethene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	79-01-6	
Trichlorofluoromethane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	75-69-4	
1,2,3-Trichloropropane	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	96-18-4	
1,2,4-Trimethylbenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	95-63-6	
1,3,5-Trimethylbenzene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	108-67-8	
Vinyl acetate	ND	ug/kg	42.0	1	04/19/19 13:00	04/19/19 22:11	108-05-4	
Vinyl chloride	ND	ug/kg	8.4	1	04/19/19 13:00	04/19/19 22:11	75-01-4	
Xylene (Total)	ND	ug/kg	8.4	1	04/19/19 13:00	04/19/19 22:11	1330-20-7	
m&p-Xylene	ND	ug/kg	8.4	1	04/19/19 13:00	04/19/19 22:11	179601-23-1	
o-Xylene	ND	ug/kg	4.2	1	04/19/19 13:00	04/19/19 22:11	95-47-6	
Surrogates								
Toluene-d8 (S)	98	%	70-130	1	04/19/19 13:00	04/19/19 22:11	2037-26-5	
4-Bromofluorobenzene (S)	96	%	70-130	1	04/19/19 13:00	04/19/19 22:11	460-00-4	
1,2-Dichloroethane-d4 (S)	101	%	70-132	1	04/19/19 13:00	04/19/19 22:11	17060-07-0	

Percent Moisture

Analytical Method: ASTM D2974-87

Percent Moisture	15.6	%	0.10	1	04/18/19 14:11
------------------	------	---	------	---	----------------

Sample: B19 Lab ID: 92425908004 Collected: 04/10/19 15:10 Received: 04/12/19 14:45 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8260D/5035A Volatile Organics Analytical Method: EPA 8260D Preparation Method: EPA 5035A								
Acetone	ND	ug/kg	91.6	1	04/19/19 13:00	04/19/19 22:36	67-64-1	
Benzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	71-43-2	
Bromobenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	108-86-1	
Bromochloromethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	74-97-5	
Bromodichloromethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	75-27-4	
Bromoform	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	75-25-2	
Bromomethane	ND	ug/kg	9.2	1	04/19/19 13:00	04/19/19 22:36	74-83-9	
2-Butanone (MEK)	ND	ug/kg	91.6	1	04/19/19 13:00	04/19/19 22:36	78-93-3	
n-Butylbenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	104-51-8	
sec-Butylbenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	135-98-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: U5797
Pace Project No.: 92425908

Sample: B19 **Lab ID: 92425908004** Collected: 04/10/19 15:10 Received: 04/12/19 14:45 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8260D/5035A Volatile Organics		Analytical Method: EPA 8260D Preparation Method: EPA 5035A						
tert-Butylbenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	98-06-6	
Carbon tetrachloride	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	56-23-5	
Chlorobenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	108-90-7	
Chloroethane	ND	ug/kg	9.2	1	04/19/19 13:00	04/19/19 22:36	75-00-3	
Chloroform	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	67-66-3	
Chloromethane	ND	ug/kg	9.2	1	04/19/19 13:00	04/19/19 22:36	74-87-3	
2-Chlorotoluene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	95-49-8	
4-Chlorotoluene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	106-43-4	
1,2-Dibromo-3-chloropropane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	96-12-8	
Dibromochloromethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	124-48-1	
1,2-Dibromoethane (EDB)	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	106-93-4	
Dibromomethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	74-95-3	
1,2-Dichlorobenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	95-50-1	
1,3-Dichlorobenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	541-73-1	
1,4-Dichlorobenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	106-46-7	
Dichlorodifluoromethane	ND	ug/kg	9.2	1	04/19/19 13:00	04/19/19 22:36	75-71-8	
1,1-Dichloroethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	75-34-3	
1,2-Dichloroethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	107-06-2	
1,1-Dichloroethene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	75-35-4	
cis-1,2-Dichloroethene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	156-59-2	
trans-1,2-Dichloroethene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	156-60-5	
1,2-Dichloropropane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	78-87-5	
1,3-Dichloropropane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	142-28-9	
2,2-Dichloropropane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	594-20-7	
1,1-Dichloropropene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	563-58-6	
cis-1,3-Dichloropropene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	10061-01-5	
trans-1,3-Dichloropropene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	10061-02-6	
Diisopropyl ether	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	108-20-3	
Ethylbenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	100-41-4	
Hexachloro-1,3-butadiene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	87-68-3	
2-Hexanone	ND	ug/kg	45.8	1	04/19/19 13:00	04/19/19 22:36	591-78-6	
Isopropylbenzene (Cumene)	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	98-82-8	
p-Isopropyltoluene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	99-87-6	
Methylene Chloride	ND	ug/kg	18.3	1	04/19/19 13:00	04/19/19 22:36	75-09-2	
4-Methyl-2-pentanone (MIBK)	ND	ug/kg	45.8	1	04/19/19 13:00	04/19/19 22:36	108-10-1	
Methyl-tert-butyl ether	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	1634-04-4	
Naphthalene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	91-20-3	
n-Propylbenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	103-65-1	
Styrene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	100-42-5	
1,1,1,2-Tetrachloroethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	630-20-6	
1,1,2,2-Tetrachloroethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	79-34-5	
Tetrachloroethene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	127-18-4	
Toluene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	108-88-3	
1,2,3-Trichlorobenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	87-61-6	
1,2,4-Trichlorobenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	120-82-1	
1,1,1-Trichloroethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	71-55-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: U5797
Pace Project No.: 92425908

Sample: B19 **Lab ID: 92425908004** Collected: 04/10/19 15:10 Received: 04/12/19 14:45 Matrix: Solid

Results reported on a "dry weight" basis and are adjusted for percent moisture, sample size and any dilutions.

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8260D/5035A Volatile Organics		Analytical Method: EPA 8260D Preparation Method: EPA 5035A						
1,1,2-Trichloroethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	79-00-5	
Trichloroethene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	79-01-6	
Trichlorofluoromethane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	75-69-4	
1,2,3-Trichloropropane	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	96-18-4	
1,2,4-Trimethylbenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	95-63-6	
1,3,5-Trimethylbenzene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	108-67-8	
Vinyl acetate	ND	ug/kg	45.8	1	04/19/19 13:00	04/19/19 22:36	108-05-4	
Vinyl chloride	ND	ug/kg	9.2	1	04/19/19 13:00	04/19/19 22:36	75-01-4	
Xylene (Total)	ND	ug/kg	9.2	1	04/19/19 13:00	04/19/19 22:36	1330-20-7	
m&p-Xylene	ND	ug/kg	9.2	1	04/19/19 13:00	04/19/19 22:36	179601-23-1	
o-Xylene	ND	ug/kg	4.6	1	04/19/19 13:00	04/19/19 22:36	95-47-6	
Surrogates								
Toluene-d8 (S)	99	%	70-130	1	04/19/19 13:00	04/19/19 22:36	2037-26-5	
4-Bromofluorobenzene (S)	99	%	70-130	1	04/19/19 13:00	04/19/19 22:36	460-00-4	
1,2-Dichloroethane-d4 (S)	101	%	70-132	1	04/19/19 13:00	04/19/19 22:36	17060-07-0	

Percent Moisture

Analytical Method: ASTM D2974-87

Percent Moisture	16.2	%	0.10	1		04/18/19 14:11
------------------	-------------	---	------	---	--	----------------

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

QC Batch:	470498	Analysis Method:	EPA 8260D
QC Batch Method:	EPA 5035A	Analysis Description:	8260D MSV 5035A Volatile Organics
Associated Lab Samples:	92425908003, 92425908004		

METHOD BLANK:	2554406	Matrix:	Solid
Associated Lab Samples:	92425908003, 92425908004		

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
1,1,1,2-Tetrachloroethane	ug/kg	ND	5.0	04/19/19 20:05	
1,1,1-Trichloroethane	ug/kg	ND	5.0	04/19/19 20:05	
1,1,2,2-Tetrachloroethane	ug/kg	ND	5.0	04/19/19 20:05	
1,1,2-Trichloroethane	ug/kg	ND	5.0	04/19/19 20:05	
1,1-Dichloroethane	ug/kg	ND	5.0	04/19/19 20:05	
1,1-Dichloroethene	ug/kg	ND	5.0	04/19/19 20:05	
1,1-Dichloropropene	ug/kg	ND	5.0	04/19/19 20:05	
1,2,3-Trichlorobenzene	ug/kg	ND	5.0	04/19/19 20:05	
1,2,3-Trichloropropane	ug/kg	ND	5.0	04/19/19 20:05	
1,2,4-Trichlorobenzene	ug/kg	ND	5.0	04/19/19 20:05	
1,2,4-Trimethylbenzene	ug/kg	ND	5.0	04/19/19 20:05	
1,2-Dibromo-3-chloropropane	ug/kg	ND	5.0	04/19/19 20:05	
1,2-Dibromoethane (EDB)	ug/kg	ND	5.0	04/19/19 20:05	
1,2-Dichlorobenzene	ug/kg	ND	5.0	04/19/19 20:05	
1,2-Dichloroethane	ug/kg	ND	5.0	04/19/19 20:05	
1,2-Dichloropropane	ug/kg	ND	5.0	04/19/19 20:05	
1,3,5-Trimethylbenzene	ug/kg	ND	5.0	04/19/19 20:05	
1,3-Dichlorobenzene	ug/kg	ND	5.0	04/19/19 20:05	
1,3-Dichloropropane	ug/kg	ND	5.0	04/19/19 20:05	
1,4-Dichlorobenzene	ug/kg	ND	5.0	04/19/19 20:05	
2,2-Dichloropropane	ug/kg	ND	5.0	04/19/19 20:05	
2-Butanone (MEK)	ug/kg	ND	100	04/19/19 20:05	
2-Chlorotoluene	ug/kg	ND	5.0	04/19/19 20:05	
2-Hexanone	ug/kg	ND	50.0	04/19/19 20:05	
4-Chlorotoluene	ug/kg	ND	5.0	04/19/19 20:05	
4-Methyl-2-pentanone (MIBK)	ug/kg	ND	50.0	04/19/19 20:05	
Acetone	ug/kg	ND	100	04/19/19 20:05	
Benzene	ug/kg	ND	5.0	04/19/19 20:05	
Bromobenzene	ug/kg	ND	5.0	04/19/19 20:05	
Bromochloromethane	ug/kg	ND	5.0	04/19/19 20:05	
Bromodichloromethane	ug/kg	ND	5.0	04/19/19 20:05	
Bromoform	ug/kg	ND	5.0	04/19/19 20:05	
Bromomethane	ug/kg	ND	10.0	04/19/19 20:05	
Carbon tetrachloride	ug/kg	ND	5.0	04/19/19 20:05	
Chlorobenzene	ug/kg	ND	5.0	04/19/19 20:05	
Chloroethane	ug/kg	ND	10.0	04/19/19 20:05	
Chloroform	ug/kg	ND	5.0	04/19/19 20:05	
Chloromethane	ug/kg	ND	10.0	04/19/19 20:05	
cis-1,2-Dichloroethene	ug/kg	ND	5.0	04/19/19 20:05	
cis-1,3-Dichloropropene	ug/kg	ND	5.0	04/19/19 20:05	
Dibromochloromethane	ug/kg	ND	5.0	04/19/19 20:05	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

METHOD BLANK: 2554406 Matrix: Solid

Associated Lab Samples: 92425908003, 92425908004

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Dibromomethane	ug/kg	ND	5.0	04/19/19 20:05	
Dichlorodifluoromethane	ug/kg	ND	10.0	04/19/19 20:05	
Diisopropyl ether	ug/kg	ND	5.0	04/19/19 20:05	
Ethylbenzene	ug/kg	ND	5.0	04/19/19 20:05	
Hexachloro-1,3-butadiene	ug/kg	ND	5.0	04/19/19 20:05	
Isopropylbenzene (Cumene)	ug/kg	ND	5.0	04/19/19 20:05	
m&p-Xylene	ug/kg	ND	10.0	04/19/19 20:05	
Methyl-tert-butyl ether	ug/kg	ND	5.0	04/19/19 20:05	
Methylene Chloride	ug/kg	ND	20.0	04/19/19 20:05	
n-Butylbenzene	ug/kg	ND	5.0	04/19/19 20:05	
n-Propylbenzene	ug/kg	ND	5.0	04/19/19 20:05	
Naphthalene	ug/kg	ND	5.0	04/19/19 20:05	
o-Xylene	ug/kg	ND	5.0	04/19/19 20:05	
p-Isopropyltoluene	ug/kg	ND	5.0	04/19/19 20:05	
sec-Butylbenzene	ug/kg	ND	5.0	04/19/19 20:05	
Styrene	ug/kg	ND	5.0	04/19/19 20:05	
tert-Butylbenzene	ug/kg	ND	5.0	04/19/19 20:05	
Tetrachloroethene	ug/kg	ND	5.0	04/19/19 20:05	
Toluene	ug/kg	ND	5.0	04/19/19 20:05	
trans-1,2-Dichloroethene	ug/kg	ND	5.0	04/19/19 20:05	
trans-1,3-Dichloropropene	ug/kg	ND	5.0	04/19/19 20:05	
Trichloroethene	ug/kg	ND	5.0	04/19/19 20:05	
Trichlorofluoromethane	ug/kg	ND	5.0	04/19/19 20:05	
Vinyl acetate	ug/kg	ND	50.0	04/19/19 20:05	
Vinyl chloride	ug/kg	ND	10.0	04/19/19 20:05	
Xylene (Total)	ug/kg	ND	10.0	04/19/19 20:05	
1,2-Dichloroethane-d4 (S)	%	103	70-132	04/19/19 20:05	
4-Bromofluorobenzene (S)	%	99	70-130	04/19/19 20:05	
Toluene-d8 (S)	%	99	70-130	04/19/19 20:05	

LABORATORY CONTROL SAMPLE: 2554407

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
1,1,1,2-Tetrachloroethane	ug/kg	50	49.9	100	70-130	
1,1,1-Trichloroethane	ug/kg	50	43.2	86	70-130	
1,1,2,2-Tetrachloroethane	ug/kg	50	48.2	96	55-130	
1,1,2-Trichloroethane	ug/kg	50	47.0	94	70-130	
1,1-Dichloroethane	ug/kg	50	42.4	85	68-130	
1,1-Dichloroethene	ug/kg	50	43.0	86	70-130	
1,1-Dichloropropene	ug/kg	50	42.8	86	70-130	
1,2,3-Trichlorobenzene	ug/kg	50	47.5	95	70-130	
1,2,3-Trichloropropane	ug/kg	50	51.4	103	70-130	
1,2,4-Trichlorobenzene	ug/kg	50	46.7	93	70-130	
1,2,4-Trimethylbenzene	ug/kg	50	44.0	88	69-130	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

LABORATORY CONTROL SAMPLE: 2554407

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
1,2-Dibromo-3-chloropropane	ug/kg	50	45.1	90	57-141	
1,2-Dibromoethane (EDB)	ug/kg	50	47.7	95	70-130	
1,2-Dichlorobenzene	ug/kg	50	44.9	90	70-130	
1,2-Dichloroethane	ug/kg	50	44.6	89	70-130	
1,2-Dichloropropane	ug/kg	50	46.5	93	70-130	
1,3,5-Trimethylbenzene	ug/kg	50	44.8	90	70-130	
1,3-Dichlorobenzene	ug/kg	50	44.2	88	70-130	
1,3-Dichloropropane	ug/kg	50	47.0	94	70-130	
1,4-Dichlorobenzene	ug/kg	50	44.2	88	70-130	
2,2-Dichloropropane	ug/kg	50	44.8	90	70-130	
2-Butanone (MEK)	ug/kg	100	101	101	60-130	
2-Chlorotoluene	ug/kg	50	44.8	90	70-130	
2-Hexanone	ug/kg	100	93.1	93	70-132	
4-Chlorotoluene	ug/kg	50	44.7	89	70-130	
4-Methyl-2-pentanone (MIBK)	ug/kg	100	93.1	93	69-130	
Acetone	ug/kg	100	102	102	49-148	
Benzene	ug/kg	50	45.6	91	70-130	
Bromobenzene	ug/kg	50	45.6	91	70-130	
Bromochloromethane	ug/kg	50	45.7	91	70-130	
Bromodichloromethane	ug/kg	50	46.8	94	70-130	
Bromoform	ug/kg	50	42.0	84	68-136	
Bromomethane	ug/kg	50	43.0	86	60-140	
Carbon tetrachloride	ug/kg	50	44.0	88	70-130	
Chlorobenzene	ug/kg	50	43.3	87	70-130	
Chloroethane	ug/kg	50	49.2	98	51-147	
Chloroform	ug/kg	50	43.8	88	70-130	
Chloromethane	ug/kg	50	42.4	85	48-130	
cis-1,2-Dichloroethene	ug/kg	50	43.8	88	70-130	
cis-1,3-Dichloropropene	ug/kg	50	47.8	96	70-130	
Dibromochloromethane	ug/kg	50	47.3	95	70-130	
Dibromomethane	ug/kg	50	47.3	95	70-130	
Dichlorodifluoromethane	ug/kg	50	43.1	86	49-130	
Diisopropyl ether	ug/kg	50	48.7	97	66-130	
Ethylbenzene	ug/kg	50	45.1	90	70-130	
Hexachloro-1,3-butadiene	ug/kg	50	45.1	90	70-130	
Isopropylbenzene (Cumene)	ug/kg	50	44.6	89	70-130	
m&p-Xylene	ug/kg	100	89.9	90	70-130	
Methyl-tert-butyl ether	ug/kg	50	48.2	96	70-130	
Methylene Chloride	ug/kg	50	38.3	77	50-137	
n-Butylbenzene	ug/kg	50	45.0	90	70-130	
n-Propylbenzene	ug/kg	50	45.0	90	70-130	
Naphthalene	ug/kg	50	47.1	94	70-131	
o-Xylene	ug/kg	50	44.2	88	70-130	
p-Isopropyltoluene	ug/kg	50	45.2	90	70-130	
sec-Butylbenzene	ug/kg	50	45.8	92	70-130	
Styrene	ug/kg	50	44.3	89	70-130	
tert-Butylbenzene	ug/kg	50	40.1	80	69-130	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

LABORATORY CONTROL SAMPLE: 2554407

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Tetrachloroethene	ug/kg	50	44.7	89	56-130	
Toluene	ug/kg	50	44.4	89	70-130	
trans-1,2-Dichloroethene	ug/kg	50	43.1	86	70-130	
trans-1,3-Dichloropropene	ug/kg	50	49.0	98	70-130	
Trichloroethene	ug/kg	50	43.9	88	70-141	
Trichlorofluoromethane	ug/kg	50	43.5	87	67-130	
Vinyl acetate	ug/kg	100	92.7	93	10-136	
Vinyl chloride	ug/kg	50	43.2	86	67-130	
Xylene (Total)	ug/kg	150	134	89	70-130	
1,2-Dichloroethane-d4 (S)	%			96	70-132	
4-Bromofluorobenzene (S)	%			99	70-130	
Toluene-d8 (S)	%			99	70-130	

MATRIX SPIKE SAMPLE: 2555712

Parameter	Units	92425764001 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
1,1,1,2-Tetrachloroethane	ug/kg	ND	437	469	107	52-133	
1,1,1-Trichloroethane	ug/kg	ND	437	426	98	49-137	
1,1,2,2-Tetrachloroethane	ug/kg	ND	437	320	73	39-150	
1,1,2-Trichloroethane	ug/kg	ND	437	377	86	48-140	
1,1-Dichloroethane	ug/kg	ND	437	424	97	46-135	
1,1-Dichloroethene	ug/kg	ND	437	530	121	38-149	
1,1-Dichloropropene	ug/kg	ND	437	420	96	41-140	
1,2,3-Trichlorobenzene	ug/kg	ND	437	427	98	10-158	
1,2,3-Trichloropropane	ug/kg	ND	437	322	74	33-157	
1,2,4-Trichlorobenzene	ug/kg	ND	437	451	103	10-155	
1,2,4-Trimethylbenzene	ug/kg	ND	437	499	114	24-154	
1,2-Dibromo-3-chloropropane	ug/kg	ND	437	237	54	33-158	
1,2-Dibromoethane (EDB)	ug/kg	ND	437	330	76	40-136	
1,2-Dichlorobenzene	ug/kg	ND	437	440	101	27-146	
1,2-Dichloroethane	ug/kg	ND	437	335	77	49-140	
1,2-Dichloropropane	ug/kg	ND	437	411	94	44-143	
1,3,5-Trimethylbenzene	ug/kg	ND	437	456	104	40-144	
1,3-Dichlorobenzene	ug/kg	ND	437	443	102	33-140	
1,3-Dichloropropane	ug/kg	ND	437	408	93	47-147	
1,4-Dichlorobenzene	ug/kg	ND	437	447	102	35-139	
2,2-Dichloropropane	ug/kg	ND	437	446	102	41-140	
2-Butanone (MEK)	ug/kg	ND	873	397J	45	10-181	
2-Chlorotoluene	ug/kg	ND	437	457	105	38-147	
2-Hexanone	ug/kg	ND	873	468J	54	18-169	
4-Chlorotoluene	ug/kg	ND	437	462	106	36-145	
4-Methyl-2-pentanone (MIBK)	ug/kg	ND	873	509J	58	16-175	
Acetone	ug/kg	ND	873	ND	22	10-200	
Benzene	ug/kg	ND	437	435	100	46-136	
Bromobenzene	ug/kg	ND	437	464	106	38-149	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

MATRIX SPIKE SAMPLE:		2555712	92425764001	Spike	MS	MS	% Rec	
Parameter	Units	Result	Conc.	Result	% Rec	Limits	Qualifiers	
Bromochloromethane	ug/kg	ND	437	335	77	44-142		
Bromodichloromethane	ug/kg	ND	437	369	85	41-140		
Bromoform	ug/kg	ND	437	331	76	34-145		
Bromomethane	ug/kg	ND	437	385	88	14-162		
Carbon tetrachloride	ug/kg	ND	437	442	101	44-141		
Chlorobenzene	ug/kg	ND	437	446	102	39-141		
Chloroethane	ug/kg	ND	437	215	49	10-182		
Chloroform	ug/kg	ND	437	387	89	45-140		
Chloromethane	ug/kg	ND	437	517	119	19-149		
cis-1,2-Dichloroethene	ug/kg	ND	437	401	92	38-150		
cis-1,3-Dichloropropene	ug/kg	ND	437	459	105	30-144		
Dibromochloromethane	ug/kg	ND	437	405	93	36-145		
Dibromomethane	ug/kg	ND	437	291	67	41-145		
Dichlorodifluoromethane	ug/kg	ND	437	241	55	16-146		
Diisopropyl ether	ug/kg	ND	437	445	102	41-143		
Ethylbenzene	ug/kg	ND	437	473	108	35-144		
Hexachloro-1,3-butadiene	ug/kg	ND	437	411	94	10-160		
Isopropylbenzene (Cumene)	ug/kg	ND	437	440	101	30-152		
m&p-Xylene	ug/kg	ND	873	1020	116	33-145		
Methyl-tert-butyl ether	ug/kg	ND	437	361	83	49-140		
Methylene Chloride	ug/kg	ND	437	489	112	10-174		
n-Butylbenzene	ug/kg	ND	437	428	98	10-160		
n-Propylbenzene	ug/kg	ND	437	468	107	24-159		
Naphthalene	ug/kg	ND	437	336	77	10-171		
o-Xylene	ug/kg	ND	437	507	116	31-150		
p-Isopropyltoluene	ug/kg	ND	437	445	102	21-154		
sec-Butylbenzene	ug/kg	ND	437	452	104	19-159		
Styrene	ug/kg	ND	437	442	101	15-152		
tert-Butylbenzene	ug/kg	ND	437	395	91	31-141		
Tetrachloroethene	ug/kg	ND	437	432	99	19-141		
Toluene	ug/kg	ND	437	517	118	31-146		
trans-1,2-Dichloroethene	ug/kg	ND	437	425	97	28-157		
trans-1,3-Dichloropropene	ug/kg	ND	437	376	86	25-146		
Trichloroethene	ug/kg	ND	437	442	101	34-149		
Trichlorofluoromethane	ug/kg	ND	437	427	98	10-167		
Vinyl acetate	ug/kg	ND	873	807J	92	10-200		
Vinyl chloride	ug/kg	ND	437	248	57	36-155		
Xylene (Total)	ug/kg	ND	1310	1520	116	29-148		
1,2-Dichloroethane-d4 (S)	%				72	70-132		
4-Bromofluorobenzene (S)	%				100	70-130		
Toluene-d8 (S)	%				102	70-130 P2		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

SAMPLE DUPLICATE: 2555711

Parameter	Units	92425574001 Result	Dup Result	RPD	Qualifiers
1,1,1,2-Tetrachloroethane	ug/kg	ND	ND		
1,1,1-Trichloroethane	ug/kg	ND	ND		
1,1,2,2-Tetrachloroethane	ug/kg	ND	ND		
1,1,2-Trichloroethane	ug/kg	ND	ND		
1,1-Dichloroethane	ug/kg	ND	ND		
1,1-Dichloroethene	ug/kg	ND	ND		
1,1-Dichloropropene	ug/kg	ND	ND		
1,2,3-Trichlorobenzene	ug/kg	ND	ND		
1,2,3-Trichloropropane	ug/kg	ND	ND		
1,2,4-Trichlorobenzene	ug/kg	ND	ND		
1,2,4-Trimethylbenzene	ug/kg	ND	ND		
1,2-Dibromo-3-chloropropane	ug/kg	ND	ND		
1,2-Dibromoethane (EDB)	ug/kg	ND	ND		
1,2-Dichlorobenzene	ug/kg	ND	ND		
1,2-Dichloroethane	ug/kg	ND	ND		
1,2-Dichloropropane	ug/kg	ND	ND		
1,3,5-Trimethylbenzene	ug/kg	ND	ND		
1,3-Dichlorobenzene	ug/kg	ND	ND		
1,3-Dichloropropane	ug/kg	ND	ND		
1,4-Dichlorobenzene	ug/kg	ND	ND		
2,2-Dichloropropane	ug/kg	ND	ND		
2-Butanone (MEK)	ug/kg	ND	ND		
2-Chlorotoluene	ug/kg	ND	ND		
2-Hexanone	ug/kg	ND	ND		
4-Chlorotoluene	ug/kg	ND	ND		
4-Methyl-2-pentanone (MIBK)	ug/kg	ND	ND		
Acetone	ug/kg	146	240	49	D6
Benzene	ug/kg	ND	ND		
Bromobenzene	ug/kg	ND	ND		
Bromochloromethane	ug/kg	ND	ND		
Bromodichloromethane	ug/kg	ND	ND		
Bromoform	ug/kg	ND	ND		
Bromomethane	ug/kg	ND	ND		
Carbon tetrachloride	ug/kg	ND	ND		
Chlorobenzene	ug/kg	ND	ND		
Chloroethane	ug/kg	ND	ND		
Chloroform	ug/kg	ND	ND		
Chloromethane	ug/kg	ND	ND		
cis-1,2-Dichloroethene	ug/kg	ND	ND		
cis-1,3-Dichloropropene	ug/kg	ND	ND		
Dibromochloromethane	ug/kg	ND	ND		
Dibromomethane	ug/kg	ND	ND		
Dichlorodifluoromethane	ug/kg	ND	ND		
Diisopropyl ether	ug/kg	ND	ND		
Ethylbenzene	ug/kg	ND	ND		
Hexachloro-1,3-butadiene	ug/kg	ND	ND		
Isopropylbenzene (Cumene)	ug/kg	ND	ND		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

SAMPLE DUPLICATE: 2555711

Parameter	Units	92425574001 Result	Dup Result	RPD	Qualifiers
m&p-Xylene	ug/kg	ND	ND		
Methyl-tert-butyl ether	ug/kg	ND	ND		
Methylene Chloride	ug/kg	ND	ND		
n-Butylbenzene	ug/kg	ND	ND		
n-Propylbenzene	ug/kg	ND	ND		
Naphthalene	ug/kg	ND	ND		
o-Xylene	ug/kg	ND	ND		
p-Isopropyltoluene	ug/kg	ND	ND		
sec-Butylbenzene	ug/kg	ND	ND		
Styrene	ug/kg	ND	ND		
tert-Butylbenzene	ug/kg	ND	ND		
Tetrachloroethene	ug/kg	ND	ND		
Toluene	ug/kg	ND	ND		
trans-1,2-Dichloroethene	ug/kg	ND	ND		
trans-1,3-Dichloropropene	ug/kg	ND	ND		
Trichloroethene	ug/kg	ND	ND		
Trichlorofluoromethane	ug/kg	ND	ND		
Vinyl acetate	ug/kg	ND	ND		
Vinyl chloride	ug/kg	ND	ND		
Xylene (Total)	ug/kg	ND	ND		
1,2-Dichloroethane-d4 (S)	%	100	92		
4-Bromofluorobenzene (S)	%	97	98		
Toluene-d8 (S)	%	99	102		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

QC Batch: 470847 Analysis Method: EPA 8260D
QC Batch Method: EPA 8260D Analysis Description: 8260D MSV Low Level
Associated Lab Samples: 92425908001, 92425908002

METHOD BLANK: 2555743 Matrix: Water
Associated Lab Samples: 92425908001, 92425908002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
1,1,1,2-Tetrachloroethane	ug/L	ND	1.0	04/22/19 23:47	
1,1,1-Trichloroethane	ug/L	ND	1.0	04/22/19 23:47	
1,1,2,2-Tetrachloroethane	ug/L	ND	1.0	04/22/19 23:47	
1,1,2-Trichloroethane	ug/L	ND	1.0	04/22/19 23:47	
1,1-Dichloroethane	ug/L	ND	1.0	04/22/19 23:47	
1,1-Dichloroethene	ug/L	ND	1.0	04/22/19 23:47	
1,1-Dichloropropene	ug/L	ND	1.0	04/22/19 23:47	
1,2,3-Trichlorobenzene	ug/L	ND	1.0	04/22/19 23:47	
1,2,3-Trichloropropane	ug/L	ND	1.0	04/22/19 23:47	
1,2,4-Trichlorobenzene	ug/L	ND	1.0	04/22/19 23:47	
1,2-Dibromo-3-chloropropane	ug/L	ND	5.0	04/22/19 23:47	
1,2-Dibromoethane (EDB)	ug/L	ND	1.0	04/22/19 23:47	
1,2-Dichlorobenzene	ug/L	ND	1.0	04/22/19 23:47	
1,2-Dichloroethane	ug/L	ND	1.0	04/22/19 23:47	
1,2-Dichloropropane	ug/L	ND	1.0	04/22/19 23:47	
1,3-Dichlorobenzene	ug/L	ND	1.0	04/22/19 23:47	
1,3-Dichloropropane	ug/L	ND	1.0	04/22/19 23:47	
1,4-Dichlorobenzene	ug/L	ND	1.0	04/22/19 23:47	
2,2-Dichloropropane	ug/L	ND	1.0	04/22/19 23:47	
2-Butanone (MEK)	ug/L	ND	5.0	04/22/19 23:47	
2-Chlorotoluene	ug/L	ND	1.0	04/22/19 23:47	
2-Hexanone	ug/L	ND	5.0	04/22/19 23:47	
4-Chlorotoluene	ug/L	ND	1.0	04/22/19 23:47	
4-Methyl-2-pentanone (MIBK)	ug/L	ND	5.0	04/22/19 23:47	
Acetone	ug/L	ND	25.0	04/22/19 23:47	
Benzene	ug/L	ND	1.0	04/22/19 23:47	
Bromobenzene	ug/L	ND	1.0	04/22/19 23:47	
Bromochloromethane	ug/L	ND	1.0	04/22/19 23:47	IK
Bromodichloromethane	ug/L	ND	1.0	04/22/19 23:47	
Bromoform	ug/L	ND	1.0	04/22/19 23:47	IK
Bromomethane	ug/L	ND	2.0	04/22/19 23:47	IK
Carbon tetrachloride	ug/L	ND	1.0	04/22/19 23:47	
Chlorobenzene	ug/L	ND	1.0	04/22/19 23:47	
Chloroethane	ug/L	ND	1.0	04/22/19 23:47	IK
Chloroform	ug/L	ND	5.0	04/22/19 23:47	
Chloromethane	ug/L	ND	1.0	04/22/19 23:47	
cis-1,2-Dichloroethene	ug/L	ND	1.0	04/22/19 23:47	
cis-1,3-Dichloropropene	ug/L	ND	1.0	04/22/19 23:47	
Dibromochloromethane	ug/L	ND	1.0	04/22/19 23:47	
Dibromomethane	ug/L	ND	1.0	04/22/19 23:47	
Dichlorodifluoromethane	ug/L	ND	1.0	04/22/19 23:47	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

METHOD BLANK: 2555743 Matrix: Water

Associated Lab Samples: 92425908001, 92425908002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Diisopropyl ether	ug/L	ND	1.0	04/22/19 23:47	
Ethylbenzene	ug/L	ND	1.0	04/22/19 23:47	
Hexachloro-1,3-butadiene	ug/L	ND	1.0	04/22/19 23:47	
m&p-Xylene	ug/L	ND	2.0	04/22/19 23:47	
Methyl-tert-butyl ether	ug/L	ND	1.0	04/22/19 23:47	
Methylene Chloride	ug/L	ND	5.0	04/22/19 23:47	
Naphthalene	ug/L	ND	1.0	04/22/19 23:47	
o-Xylene	ug/L	ND	1.0	04/22/19 23:47	
p-Isopropyltoluene	ug/L	ND	1.0	04/22/19 23:47	
Styrene	ug/L	ND	1.0	04/22/19 23:47	
Tetrachloroethene	ug/L	ND	1.0	04/22/19 23:47	
Toluene	ug/L	ND	1.0	04/22/19 23:47	
trans-1,2-Dichloroethene	ug/L	ND	1.0	04/22/19 23:47	
trans-1,3-Dichloropropene	ug/L	ND	1.0	04/22/19 23:47	
Trichloroethene	ug/L	ND	1.0	04/22/19 23:47	
Trichlorofluoromethane	ug/L	ND	1.0	04/22/19 23:47	
Vinyl acetate	ug/L	ND	2.0	04/22/19 23:47	
Vinyl chloride	ug/L	ND	1.0	04/22/19 23:47	
Xylene (Total)	ug/L	ND	1.0	04/22/19 23:47	
1,2-Dichloroethane-d4 (S)	%	103	70-130	04/22/19 23:47	
4-Bromofluorobenzene (S)	%	101	70-130	04/22/19 23:47	
Toluene-d8 (S)	%	109	70-130	04/22/19 23:47	

LABORATORY CONTROL SAMPLE: 2555744

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
1,1,1,2-Tetrachloroethane	ug/L	50	56.0	112	70-130	
1,1,1-Trichloroethane	ug/L	50	53.0	106	70-130	
1,1,2,2-Tetrachloroethane	ug/L	50	52.5	105	70-130	
1,1,2-Trichloroethane	ug/L	50	54.9	110	70-130	
1,1-Dichloroethane	ug/L	50	51.7	103	70-130	
1,1-Dichloroethene	ug/L	50	51.0	102	70-130	
1,1-Dichloropropene	ug/L	50	51.3	103	70-130	
1,2,3-Trichlorobenzene	ug/L	50	53.3	107	70-130	
1,2,3-Trichloropropane	ug/L	50	55.1	110	70-130	
1,2,4-Trichlorobenzene	ug/L	50	53.4	107	70-130	
1,2-Dibromo-3-chloropropane	ug/L	50	53.3	107	70-130	
1,2-Dibromoethane (EDB)	ug/L	50	54.5	109	70-130	
1,2-Dichlorobenzene	ug/L	50	51.0	102	70-130	
1,2-Dichloroethane	ug/L	50	48.8	98	70-130	
1,2-Dichloropropane	ug/L	50	52.8	106	70-130	
1,3-Dichlorobenzene	ug/L	50	50.4	101	70-130	
1,3-Dichloropropane	ug/L	50	53.2	106	70-131	
1,4-Dichlorobenzene	ug/L	50	51.1	102	70-130	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

LABORATORY CONTROL SAMPLE: 2555744

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
2,2-Dichloropropane	ug/L	50	54.4	109	69-130	
2-Butanone (MEK)	ug/L	100	113	113	64-135	
2-Chlorotoluene	ug/L	50	49.9	100	70-130	
2-Hexanone	ug/L	100	107	107	66-135	
4-Chlorotoluene	ug/L	50	49.6	99	70-130	
4-Methyl-2-pentanone (MIBK)	ug/L	100	104	104	70-130	
Acetone	ug/L	100	104	104	61-157	
Benzene	ug/L	50	51.8	104	70-130	
Bromobenzene	ug/L	50	51.9	104	70-130	
Bromochloromethane	ug/L	50	49.4	99	70-130	IK
Bromodichloromethane	ug/L	50	52.3	105	70-130	
Bromoform	ug/L	50	48.6	97	70-130	IK
Bromomethane	ug/L	50	50.9	102	38-130	IK
Carbon tetrachloride	ug/L	50	47.2	94	70-130	
Chlorobenzene	ug/L	50	49.8	100	70-130	
Chloroethane	ug/L	50	41.4	83	37-142	IK
Chloroform	ug/L	50	49.5	99	70-130	
Chloromethane	ug/L	50	50.1	100	48-130	
cis-1,2-Dichloroethene	ug/L	50	51.6	103	70-130	
cis-1,3-Dichloropropene	ug/L	50	57.6	115	70-130	
Dibromochloromethane	ug/L	50	54.9	110	70-130	
Dibromomethane	ug/L	50	51.4	103	70-130	
Dichlorodifluoromethane	ug/L	50	40.6	81	53-134	
Diisopropyl ether	ug/L	50	55.3	111	70-135	
Ethylbenzene	ug/L	50	50.2	100	70-130	
Hexachloro-1,3-butadiene	ug/L	50	50.6	101	68-132	
m&p-Xylene	ug/L	100	102	102	70-130	
Methyl-tert-butyl ether	ug/L	50	58.8	118	70-130	
Methylene Chloride	ug/L	50	47.3	95	67-132	
Naphthalene	ug/L	50	56.7	113	70-130	
o-Xylene	ug/L	50	51.8	104	70-131	
p-Isopropyltoluene	ug/L	50	53.6	107	70-130	
Styrene	ug/L	50	52.1	104	70-130	
Tetrachloroethene	ug/L	50	50.4	101	69-130	
Toluene	ug/L	50	49.4	99	70-130	
trans-1,2-Dichloroethene	ug/L	50	52.1	104	70-130	
trans-1,3-Dichloropropene	ug/L	50	51.2	102	70-130	
Trichloroethene	ug/L	50	51.6	103	70-130	
Trichlorofluoromethane	ug/L	50	44.0	88	63-130	
Vinyl acetate	ug/L	100	112	112	55-143	
Vinyl chloride	ug/L	50	52.1	104	70-131	
Xylene (Total)	ug/L	150	153	102	70-130	
1,2-Dichloroethane-d4 (S)	%			100	70-130	
4-Bromofluorobenzene (S)	%			98	70-130	
Toluene-d8 (S)	%			96	70-130	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

MATRIX SPIKE SAMPLE:		2555746	92425875006	Spike	MS	MS	% Rec	
Parameter	Units	Result	Conc.	Result	% Rec	Limits	Qualifiers	
1,1,1,2-Tetrachloroethane	ug/L	ND	20	22.8	114	73-134		
1,1,1-Trichloroethane	ug/L	ND	20	25.0	125	82-143		
1,1,2,2-Tetrachloroethane	ug/L	ND	20	21.2	106	70-136		
1,1,2-Trichloroethane	ug/L	ND	20	23.1	115	70-135		
1,1-Dichloroethane	ug/L	0.43J	20	24.2	119	70-139		
1,1-Dichloroethene	ug/L	ND	20	23.9	120	70-154		
1,1-Dichloropropene	ug/L	ND	20	23.8	119	70-149		
1,2,3-Trichlorobenzene	ug/L	ND	20	22.2	111	70-135		
1,2,3-Trichloropropane	ug/L	ND	20	22.7	113	71-137		
1,2,4-Trichlorobenzene	ug/L	ND	20	21.8	109	73-140		
1,2-Dibromo-3-chloropropane	ug/L	ND	20	19.7	98	65-134		
1,2-Dibromoethane (EDB)	ug/L	ND	20	21.6	108	70-137		
1,2-Dichlorobenzene	ug/L	ND	20	21.2	106	70-133		
1,2-Dichloroethane	ug/L	ND	20	22.4	112	70-137		
1,2-Dichloropropane	ug/L	ND	20	23.8	119	70-140		
1,3-Dichlorobenzene	ug/L	ND	20	21.0	105	70-135		
1,3-Dichloropropane	ug/L	ND	20	21.8	109	70-143		
1,4-Dichlorobenzene	ug/L	ND	20	21.1	105	70-133		
2,2-Dichloropropane	ug/L	ND	20	19.4	97	61-148		
2-Butanone (MEK)	ug/L	ND	40	49.5	124	60-139		
2-Chlorotoluene	ug/L	ND	20	21.0	105	70-144		
2-Hexanone	ug/L	ND	40	42.4	106	65-138		
4-Chlorotoluene	ug/L	ND	20	21.3	106	70-137		
4-Methyl-2-pentanone (MIBK)	ug/L	ND	40	42.5	106	65-135		
Acetone	ug/L	ND	40	55.4	139	60-148		
Benzene	ug/L	ND	20	23.6	118	70-151		
Bromobenzene	ug/L	ND	20	21.7	109	70-136		
Bromochloromethane	ug/L	ND	20	25.3	127	70-141 IK		
Bromodichloromethane	ug/L	ND	20	22.8	114	70-138		
Bromoform	ug/L	ND	20	19.5	97	63-130 IK		
Bromomethane	ug/L	ND	20	19.9	100	15-152 IK		
Carbon tetrachloride	ug/L	ND	20	22.6	113	70-143		
Chlorobenzene	ug/L	ND	20	21.6	108	70-138		
Chloroethane	ug/L	ND	20	22.6	113	52-163 IK		
Chloroform	ug/L	ND	20	23.7	116	70-139		
Chloromethane	ug/L	ND	20	19.9	99	41-139		
cis-1,2-Dichloroethene	ug/L	ND	20	23.9	119	70-141		
cis-1,3-Dichloropropene	ug/L	ND	20	22.1	110	70-137		
Dibromochloromethane	ug/L	ND	20	21.5	107	70-134		
Dibromomethane	ug/L	ND	20	22.9	114	70-138		
Dichlorodifluoromethane	ug/L	ND	20	19.2	96	47-155		
Diisopropyl ether	ug/L	ND	20	23.4	117	63-144		
Ethylbenzene	ug/L	ND	20	22.9	115	66-153		
Hexachloro-1,3-butadiene	ug/L	ND	20	20.2	101	65-149		
m&p-Xylene	ug/L	ND	40	46.2	116	69-152		
Methyl-tert-butyl ether	ug/L	ND	20	24.2	121	54-156		
Methylene Chloride	ug/L	ND	20	23.3	111	42-159		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

MATRIX SPIKE SAMPLE: 2555746		92425875006	Spike	MS	MS	% Rec	
Parameter	Units	Result	Conc.	Result	% Rec	Limits	Qualifiers
Naphthalene	ug/L	ND	20	23.2	116	61-148	
o-Xylene	ug/L	ND	20	23.1	116	70-148	
p-Isopropyltoluene	ug/L	ND	20	22.5	113	70-146	
Styrene	ug/L	ND	20	21.4	107	70-135	
Tetrachloroethene	ug/L	ND	20	22.0	110	59-143	
Toluene	ug/L	ND	20	22.8	114	59-148	
trans-1,2-Dichloroethene	ug/L	ND	20	24.3	122	70-146	
trans-1,3-Dichloropropene	ug/L	ND	20	20.2	101	70-135	
Trichloroethene	ug/L	ND	20	23.8	119	70-147	
Trichlorofluoromethane	ug/L	ND	20	24.5	122	70-148	
Vinyl acetate	ug/L	ND	40	35.2	88	49-151	
Vinyl chloride	ug/L	ND	20	23.4	117	70-156	
Xylene (Total)	ug/L	ND	60	69.3	116	63-158	
1,2-Dichloroethane-d4 (S)	%				104	70-130	
4-Bromofluorobenzene (S)	%				103	70-130	
Toluene-d8 (S)	%				100	70-130	

SAMPLE DUPLICATE: 2555745

Parameter	Units	92425875005	Dup	RPD	Qualifiers
		Result	Result		
1,1,1,2-Tetrachloroethane	ug/L	ND	ND		
1,1,1-Trichloroethane	ug/L	ND	ND		
1,1,2,2-Tetrachloroethane	ug/L	ND	ND		
1,1,2-Trichloroethane	ug/L	ND	ND		
1,1-Dichloroethane	ug/L	ND	ND		
1,1-Dichloroethene	ug/L	ND	ND		
1,1-Dichloropropene	ug/L	ND	ND		
1,2,3-Trichlorobenzene	ug/L	ND	ND		
1,2,3-Trichloropropane	ug/L	ND	ND		
1,2,4-Trichlorobenzene	ug/L	ND	ND		
1,2-Dibromo-3-chloropropane	ug/L	ND	ND		
1,2-Dibromoethane (EDB)	ug/L	ND	ND		
1,2-Dichlorobenzene	ug/L	ND	ND		
1,2-Dichloroethane	ug/L	ND	ND		
1,2-Dichloropropane	ug/L	ND	ND		
1,3-Dichlorobenzene	ug/L	ND	ND		
1,3-Dichloropropane	ug/L	ND	ND		
1,4-Dichlorobenzene	ug/L	ND	ND		
2,2-Dichloropropane	ug/L	ND	ND		
2-Butanone (MEK)	ug/L	ND	ND		
2-Chlorotoluene	ug/L	ND	ND		
2-Hexanone	ug/L	ND	ND		
4-Chlorotoluene	ug/L	ND	ND		
4-Methyl-2-pentanone (MIBK)	ug/L	ND	ND		
Acetone	ug/L	27.6	22.1J		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

SAMPLE DUPLICATE: 2555745

Parameter	Units	92425875005 Result	Dup Result	RPD	Qualifiers
Benzene	ug/L	ND	ND		
Bromobenzene	ug/L	ND	ND		
Bromochloromethane	ug/L	ND	ND		IK
Bromodichloromethane	ug/L	ND	ND		
Bromoform	ug/L	ND	ND		IK
Bromomethane	ug/L	ND	ND		IK
Carbon tetrachloride	ug/L	ND	ND		
Chlorobenzene	ug/L	ND	ND		
Chloroethane	ug/L	ND	ND		IK
Chloroform	ug/L	ND	ND		
Chloromethane	ug/L	ND	ND		
cis-1,2-Dichloroethene	ug/L	ND	ND		
cis-1,3-Dichloropropene	ug/L	ND	ND		
Dibromochloromethane	ug/L	ND	ND		
Dibromomethane	ug/L	ND	ND		
Dichlorodifluoromethane	ug/L	ND	ND		
Diisopropyl ether	ug/L	ND	ND		
Ethylbenzene	ug/L	ND	ND		
Hexachloro-1,3-butadiene	ug/L	ND	ND		
m&p-Xylene	ug/L	ND	ND		
Methyl-tert-butyl ether	ug/L	ND	ND		
Methylene Chloride	ug/L	ND	ND		
Naphthalene	ug/L	ND	ND		
o-Xylene	ug/L	ND	ND		
p-Isopropyltoluene	ug/L	ND	ND		
Styrene	ug/L	ND	ND		
Tetrachloroethene	ug/L	ND	ND		
Toluene	ug/L	ND	ND		
trans-1,2-Dichloroethene	ug/L	ND	ND		
trans-1,3-Dichloropropene	ug/L	ND	ND		
Trichloroethene	ug/L	ND	ND		
Trichlorofluoromethane	ug/L	ND	ND		
Vinyl acetate	ug/L	ND	ND		
Vinyl chloride	ug/L	ND	ND		
Xylene (Total)	ug/L	ND	ND		
1,2-Dichloroethane-d4 (S)	%	103	100		
4-Bromofluorobenzene (S)	%	102	100		
Toluene-d8 (S)	%	111	108		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

QC Batch:	470256	Analysis Method:	EPA 8270E
QC Batch Method:	EPA 3510C	Analysis Description:	8270E Water MSSV RVE
Associated Lab Samples: 92425908001, 92425908002			

METHOD BLANK:	2553172	Matrix:	Water
Associated Lab Samples: 92425908001, 92425908002			

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
1,2,4-Trichlorobenzene	ug/L	ND	10.0	04/19/19 16:02	
1,2-Dichlorobenzene	ug/L	ND	10.0	04/19/19 16:02	
1,3-Dichlorobenzene	ug/L	ND	10.0	04/19/19 16:02	
1,4-Dichlorobenzene	ug/L	ND	10.0	04/19/19 16:02	
1-Methylnaphthalene	ug/L	ND	10.0	04/19/19 16:02	
2,2'-Oxybis(1-chloropropane)	ug/L	ND	10.0	04/19/19 16:02	
2,4,5-Trichlorophenol	ug/L	ND	10.0	04/19/19 16:02	
2,4,6-Trichlorophenol	ug/L	ND	10.0	04/19/19 16:02	
2,4-Dichlorophenol	ug/L	ND	10.0	04/19/19 16:02	
2,4-Dimethylphenol	ug/L	ND	10.0	04/19/19 16:02	
2,4-Dinitrophenol	ug/L	ND	50.0	04/19/19 16:02	
2,4-Dinitrotoluene	ug/L	ND	10.0	04/19/19 16:02	
2,6-Dinitrotoluene	ug/L	ND	10.0	04/19/19 16:02	
2-Chloronaphthalene	ug/L	ND	10.0	04/19/19 16:02	
2-Chlorophenol	ug/L	ND	10.0	04/19/19 16:02	
2-Methylnaphthalene	ug/L	ND	10.0	04/19/19 16:02	
2-Methylphenol(o-Cresol)	ug/L	ND	10.0	04/19/19 16:02	
2-Nitroaniline	ug/L	ND	50.0	04/19/19 16:02	
2-Nitrophenol	ug/L	ND	10.0	04/19/19 16:02	
3&4-Methylphenol(m&p Cresol)	ug/L	ND	10.0	04/19/19 16:02	
3,3'-Dichlorobenzidine	ug/L	ND	20.0	04/19/19 16:02	
3-Nitroaniline	ug/L	ND	50.0	04/19/19 16:02	
4,6-Dinitro-2-methylphenol	ug/L	ND	20.0	04/19/19 16:02	
4-Bromophenylphenyl ether	ug/L	ND	10.0	04/19/19 16:02	
4-Chloro-3-methylphenol	ug/L	ND	20.0	04/19/19 16:02	
4-Chloroaniline	ug/L	ND	20.0	04/19/19 16:02	
4-Chlorophenylphenyl ether	ug/L	ND	10.0	04/19/19 16:02	
4-Nitroaniline	ug/L	ND	20.0	04/19/19 16:02	
4-Nitrophenol	ug/L	ND	50.0	04/19/19 16:02	
Acenaphthene	ug/L	ND	10.0	04/19/19 16:02	
Acenaphthylene	ug/L	ND	10.0	04/19/19 16:02	
Aniline	ug/L	ND	10.0	04/19/19 16:02	
Anthracene	ug/L	ND	10.0	04/19/19 16:02	
Benzo(a)anthracene	ug/L	ND	10.0	04/19/19 16:02	
Benzo(a)pyrene	ug/L	ND	10.0	04/19/19 16:02	
Benzo(b)fluoranthene	ug/L	ND	10.0	04/19/19 16:02	
Benzo(g,h,i)perylene	ug/L	ND	10.0	04/19/19 16:02	
Benzo(k)fluoranthene	ug/L	ND	10.0	04/19/19 16:02	
Benzoic Acid	ug/L	ND	50.0	04/19/19 16:02	
Benzyl alcohol	ug/L	ND	20.0	04/19/19 16:02	
bis(2-Chloroethoxy)methane	ug/L	ND	10.0	04/19/19 16:02	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

METHOD BLANK: 2553172 Matrix: Water

Associated Lab Samples: 92425908001, 92425908002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
bis(2-Chloroethyl) ether	ug/L	ND	10.0	04/19/19 16:02	
bis(2-Ethylhexyl)phthalate	ug/L	ND	6.0	04/19/19 16:02	
Butylbenzylphthalate	ug/L	ND	10.0	04/19/19 16:02	
Chrysene	ug/L	ND	10.0	04/19/19 16:02	
Di-n-butylphthalate	ug/L	ND	10.0	04/19/19 16:02	
Di-n-octylphthalate	ug/L	ND	10.0	04/19/19 16:02	
Dibenz(a,h)anthracene	ug/L	ND	10.0	04/19/19 16:02	
Dibenzofuran	ug/L	ND	10.0	04/19/19 16:02	
Diethylphthalate	ug/L	ND	10.0	04/19/19 16:02	
Dimethylphthalate	ug/L	ND	10.0	04/19/19 16:02	
Fluoranthene	ug/L	ND	10.0	04/19/19 16:02	
Fluorene	ug/L	ND	10.0	04/19/19 16:02	
Hexachloro-1,3-butadiene	ug/L	ND	10.0	04/19/19 16:02	
Hexachlorobenzene	ug/L	ND	10.0	04/19/19 16:02	
Hexachlorocyclopentadiene	ug/L	ND	10.0	04/19/19 16:02	
Hexachloroethane	ug/L	ND	10.0	04/19/19 16:02	
Indeno(1,2,3-cd)pyrene	ug/L	ND	10.0	04/19/19 16:02	
Isophorone	ug/L	ND	10.0	04/19/19 16:02	
N-Nitroso-di-n-propylamine	ug/L	ND	10.0	04/19/19 16:02	
N-Nitrosodimethylamine	ug/L	ND	10.0	04/19/19 16:02	
N-Nitrosodiphenylamine	ug/L	ND	10.0	04/19/19 16:02	
Naphthalene	ug/L	ND	10.0	04/19/19 16:02	
Nitrobenzene	ug/L	ND	10.0	04/19/19 16:02	
Pentachlorophenol	ug/L	ND	25.0	04/19/19 16:02	
Phenanthrene	ug/L	ND	10.0	04/19/19 16:02	
Phenol	ug/L	ND	10.0	04/19/19 16:02	
Pyrene	ug/L	ND	10.0	04/19/19 16:02	
2,4,6-Tribromophenol (S)	%	70	10-137	04/19/19 16:02	
2-Fluorobiphenyl (S)	%	54	13-130	04/19/19 16:02	
2-Fluorophenol (S)	%	45	10-130	04/19/19 16:02	
Nitrobenzene-d5 (S)	%	56	13-130	04/19/19 16:02	
Phenol-d6 (S)	%	33	10-130	04/19/19 16:02	
Terphenyl-d14 (S)	%	93	25-130	04/19/19 16:02	

LABORATORY CONTROL SAMPLE: 2553173

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
1,2,4-Trichlorobenzene	ug/L	50	27.1	54	30-130	
1,2-Dichlorobenzene	ug/L	50	29.3	59	30-130	
1,3-Dichlorobenzene	ug/L	50	28.2	56	20-130	
1,4-Dichlorobenzene	ug/L	50	29.6	59	30-130	
1-Methylnaphthalene	ug/L	50	35.7	71	30-130	
2,2'-Oxybis(1-chloropropane)	ug/L	50	32.7	65	20-130	
2,4,5-Trichlorophenol	ug/L	50	35.4	71	40-130	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

LABORATORY CONTROL SAMPLE: 2553173

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
2,4,6-Trichlorophenol	ug/L	50	34.4	69	40-130	
2,4-Dichlorophenol	ug/L	50	35.3	71	31-130	
2,4-Dimethylphenol	ug/L	50	37.4	75	30-130	
2,4-Dinitrophenol	ug/L	250	ND	5	30-130	L2
2,4-Dinitrotoluene	ug/L	50	41.3	83	49-130	
2,6-Dinitrotoluene	ug/L	50	38.1	76	50-130	
2-Chloronaphthalene	ug/L	50	30.1	60	30-130	
2-Chlorophenol	ug/L	50	36.5	73	30-130	
2-Methylnaphthalene	ug/L	50	34.4	69	30-130	
2-Methylphenol(o-Cresol)	ug/L	50	37.0	74	30-130	
2-Nitroaniline	ug/L	100	76.3	76	40-130	
2-Nitrophenol	ug/L	50	34.6	69	20-130	
3&4-Methylphenol(m&p Cresol)	ug/L	50	33.5	67	20-130	
3,3'-Dichlorobenzidine	ug/L	100	77.8	78	10-150	
3-Nitroaniline	ug/L	100	84.0	84	40-130	
4,6-Dinitro-2-methylphenol	ug/L	100	46.1	46	40-130	
4-Bromophenylphenyl ether	ug/L	50	35.3	71	30-130	
4-Chloro-3-methylphenol	ug/L	100	72.7	73	30-130	
4-Chloroaniline	ug/L	100	74.5	75	20-130	
4-Chlorophenylphenyl ether	ug/L	50	34.5	69	20-130	
4-Nitroaniline	ug/L	100	91.7	92	40-130	
4-Nitrophenol	ug/L	250	48.6J	19	10-130	
Acenaphthene	ug/L	50	37.0	74	30-130	
Acenaphthylene	ug/L	50	39.1	78	30-130	
Aniline	ug/L	50	34.1	68	20-130	
Anthracene	ug/L	50	43.9	88	50-130	
Benzo(a)anthracene	ug/L	50	45.3	91	50-130	
Benzo(a)pyrene	ug/L	50	45.2	90	50-130	
Benzo(b)fluoranthene	ug/L	50	45.4	91	50-130	
Benzo(g,h,i)perylene	ug/L	50	47.8	96	50-130	
Benzo(k)fluoranthene	ug/L	50	47.3	95	50-130	
Benzoic Acid	ug/L	250	ND	0	10-130	L2
Benzyl alcohol	ug/L	100	71.0	71	20-130	
bis(2-Chloroethoxy)methane	ug/L	50	35.9	72	30-130	
bis(2-Chloroethyl) ether	ug/L	50	36.8	74	30-130	
bis(2-Ethylhexyl)phthalate	ug/L	50	41.8	84	50-130	
Butylbenzylphthalate	ug/L	50	38.8	78	50-150	
Chrysene	ug/L	50	45.2	90	50-130	
Di-n-butylphthalate	ug/L	50	42.4	85	50-130	
Di-n-octylphthalate	ug/L	50	40.9	82	50-130	
Dibenz(a,h)anthracene	ug/L	50	49.4	99	40-130	
Dibenzofuran	ug/L	50	34.6	69	40-130	
Diethylphthalate	ug/L	50	41.7	83	40-130	
Dimethylphthalate	ug/L	50	39.7	79	40-130	
Fluoranthene	ug/L	50	47.6	95	30-130	
Fluorene	ug/L	50	39.4	79	20-130	
Hexachloro-1,3-butadiene	ug/L	50	25.8	52	10-130	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

LABORATORY CONTROL SAMPLE: 2553173

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Hexachlorobenzene	ug/L	50	37.4	75	30-130	
Hexachlorocyclopentadiene	ug/L	50	23.9	48	10-150	
Hexachloroethane	ug/L	50	27.0	54	10-130	
Indeno(1,2,3-cd)pyrene	ug/L	50	48.1	96	40-130	
Isophorone	ug/L	50	34.6	69	30-130	
N-Nitroso-di-n-propylamine	ug/L	50	35.7	71	30-130	
N-Nitrosodimethylamine	ug/L	50	31.8	64	10-130	
N-Nitrosodiphenylamine	ug/L	50	38.4	77	30-130	
Naphthalene	ug/L	50	35.1	70	20-130	
Nitrobenzene	ug/L	50	33.7	67	20-130	
Pentachlorophenol	ug/L	100	64.9	65	10-140	
Phenanthrene	ug/L	50	44.0	88	50-130	
Phenol	ug/L	50	22.6	45	10-130	
Pyrene	ug/L	50	42.4	85	50-130	
2,4,6-Tribromophenol (S)	%			89	10-137	
2-Fluorobiphenyl (S)	%			71	13-130	
2-Fluorophenol (S)	%			61	10-130	
Nitrobenzene-d5 (S)	%			76	13-130	
Phenol-d6 (S)	%			48	10-130	
Terphenyl-d14 (S)	%			83	25-130	

MATRIX SPIKE SAMPLE: 2553236

Parameter	Units	92425875001 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
1,2,4-Trichlorobenzene	ug/L	ND	50	12.3	25	30-130	M1
1,2-Dichlorobenzene	ug/L	ND	50	13.9	28	30-130	M1
1,3-Dichlorobenzene	ug/L	ND	50	13.2	26	20-130	
1,4-Dichlorobenzene	ug/L	ND	50	14.4	27	30-130	M1
1-Methylnaphthalene	ug/L	ND	50	16.8	34	30-130	
2,2'-Oxybis(1-chloropropane)	ug/L	ND	50	13.8	28	20-130	
2,4,5-Trichlorophenol	ug/L	ND	50	18.3	37	40-130	M1
2,4,6-Trichlorophenol	ug/L	ND	50	16.6	33	40-130	M1
2,4-Dichlorophenol	ug/L	ND	50	15.2	30	31-130	M1
2,4-Dimethylphenol	ug/L	ND	50	14.3	29	30-130	M1
2,4-Dinitrophenol	ug/L	ND	250	162	65	30-130	
2,4-Dinitrotoluene	ug/L	ND	50	30.4	61	49-130	
2,6-Dinitrotoluene	ug/L	ND	50	22.5	45	50-130	M1
2-Chloronaphthalene	ug/L	ND	50	13.9	28	30-130	M1
2-Chlorophenol	ug/L	ND	50	15.7	31	30-130	
2-Methylnaphthalene	ug/L	ND	50	16.3	33	30-130	
2-Methylphenol(o-Cresol)	ug/L	ND	50	16.0	32	30-130	
2-Nitroaniline	ug/L	ND	100	44.6J	45	40-130	
2-Nitrophenol	ug/L	ND	50	15.4	31	20-130	
3&4-Methylphenol(m&p Cresol)	ug/L	ND	50	14.2	28	20-130	
3,3'-Dichlorobenzidine	ug/L	ND	100	24.4	24	10-150	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

MATRIX SPIKE SAMPLE:		2553236	92425875001	Spike	MS	MS	% Rec	
Parameter	Units	Result	Conc.	Result	% Rec	Limits	Qualifiers	
3-Nitroaniline	ug/L	ND	100	53.9	54	40-130		
4,6-Dinitro-2-methylphenol	ug/L	ND	100	71.8	72	40-130		
4-Bromophenylphenyl ether	ug/L	ND	50	22.5	45	30-130		
4-Chloro-3-methylphenol	ug/L	ND	100	37.2	37	30-130		
4-Chloroaniline	ug/L	ND	100	25.0	25	20-130		
4-Chlorophenylphenyl ether	ug/L	ND	50	18.7	37	20-130		
4-Nitroaniline	ug/L	ND	100	66.6	67	40-130		
4-Nitrophenol	ug/L	ND	250	121	48	10-130		
Acenaphthene	ug/L	ND	50	19.0	38	30-130		
Acenaphthylene	ug/L	ND	50	19.4	39	30-130		
Aniline	ug/L	ND	50	3.2J	6	20-130	M1	
Anthracene	ug/L	ND	50	32.7	65	50-130		
Benzo(a)anthracene	ug/L	ND	50	36.1	72	50-130		
Benzo(a)pyrene	ug/L	ND	50	35.6	71	50-130		
Benzo(b)fluoranthene	ug/L	ND	50	36.1	72	50-130		
Benzo(g,h,i)perylene	ug/L	ND	50	36.4	73	50-130		
Benzo(k)fluoranthene	ug/L	ND	50	37.2	74	50-130		
Benzoic Acid	ug/L	ND	250	60.2	24	10-130		
Benzyl alcohol	ug/L	ND	100	30.0	30	20-130		
bis(2-Chloroethoxy)methane	ug/L	ND	50	15.2	30	30-130		
bis(2-Chloroethyl) ether	ug/L	ND	50	15.6	31	30-130		
bis(2-Ethylhexyl)phthalate	ug/L	ND	50	33.1	66	50-130		
Butylbenzylphthalate	ug/L	ND	50	32.1	64	50-150		
Chrysene	ug/L	ND	50	36.3	73	50-130		
Di-n-butylphthalate	ug/L	ND	50	35.2	70	50-130		
Di-n-octylphthalate	ug/L	ND	50	33.3	67	50-130		
Dibenz(a,h)anthracene	ug/L	ND	50	37.2	74	40-130		
Dibenzofuran	ug/L	ND	50	17.9	36	40-130	M1	
Diethylphthalate	ug/L	ND	50	30.3	61	40-130		
Dimethylphthalate	ug/L	ND	50	24.8	50	40-130		
Fluoranthene	ug/L	ND	50	39.9	80	30-130		
Fluorene	ug/L	ND	50	23.0	46	20-130		
Hexachloro-1,3-butadiene	ug/L	ND	50	11.1	22	10-130		
Hexachlorobenzene	ug/L	ND	50	22.3	45	30-130		
Hexachlorocyclopentadiene	ug/L	ND	50	10.7	21	10-150		
Hexachloroethane	ug/L	ND	50	12.3	25	10-130		
Indeno(1,2,3-cd)pyrene	ug/L	ND	50	36.6	73	40-130		
Isophorone	ug/L	ND	50	16.4	33	30-130		
N-Nitroso-di-n-propylamine	ug/L	ND	50	16.4	33	30-130		
N-Nitrosodimethylamine	ug/L	ND	50	14.4	29	10-130		
N-Nitrosodiphenylamine	ug/L	ND	50	8.5J	17	30-130	M1	
Naphthalene	ug/L	ND	50	17.4	35	20-130		
Nitrobenzene	ug/L	ND	50	15.2	30	20-130		
Pentachlorophenol	ug/L	ND	100	63.7	64	10-140		
Phenanthrene	ug/L	ND	50	33.9	68	50-130		
Phenol	ug/L	ND	50	10.5	21	10-130		
Pyrene	ug/L	ND	50	34.8	70	50-130		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

MATRIX SPIKE SAMPLE: 2553236		92425875001	Spike	MS	MS	% Rec	
Parameter	Units	Result	Conc.	Result	% Rec	Limits	Qualifiers
2,4,6-Tribromophenol (S)	%				58	10-137	
2-Fluorobiphenyl (S)	%				30	13-130	
2-Fluorophenol (S)	%				26	10-130	
Nitrobenzene-d5 (S)	%				33	13-130	
Phenol-d6 (S)	%				20	10-130	
Terphenyl-d14 (S)	%				61	25-130	

SAMPLE DUPLICATE: 2553237

Parameter	Units	92425875002	Dup	RPD	Qualifiers
		Result	Result		
1,2,4-Trichlorobenzene	ug/L	ND	ND		
1,2-Dichlorobenzene	ug/L	ND	ND		
1,3-Dichlorobenzene	ug/L	ND	ND		
1,4-Dichlorobenzene	ug/L	ND	ND		
1-Methylnaphthalene	ug/L	ND	2.1J		
2,2'-Oxybis(1-chloropropane)	ug/L	ND	ND		
2,4,5-Trichlorophenol	ug/L	ND	ND		
2,4,6-Trichlorophenol	ug/L	ND	ND		
2,4-Dichlorophenol	ug/L	ND	ND		
2,4-Dimethylphenol	ug/L	ND	ND		
2,4-Dinitrophenol	ug/L	ND	ND		
2,4-Dinitrotoluene	ug/L	ND	ND		
2,6-Dinitrotoluene	ug/L	ND	ND		
2-Chloronaphthalene	ug/L	ND	ND		
2-Chlorophenol	ug/L	ND	ND		
2-Methylnaphthalene	ug/L	3.1J	5.5J		
2-Methylphenol(o-Cresol)	ug/L	ND	ND		
2-Nitroaniline	ug/L	ND	ND		
2-Nitrophenol	ug/L	ND	ND		
3&4-Methylphenol(m&p Cresol)	ug/L	ND	ND		
3,3'-Dichlorobenzidine	ug/L	ND	ND		
3-Nitroaniline	ug/L	ND	ND		
4,6-Dinitro-2-methylphenol	ug/L	ND	ND		
4-Bromophenylphenyl ether	ug/L	ND	ND		
4-Chloro-3-methylphenol	ug/L	ND	ND		
4-Chloroaniline	ug/L	ND	ND		
4-Chlorophenylphenyl ether	ug/L	ND	ND		
4-Nitroaniline	ug/L	ND	ND		
4-Nitrophenol	ug/L	ND	ND		
Acenaphthene	ug/L	ND	ND		
Acenaphthylene	ug/L	ND	ND		
Aniline	ug/L	ND	ND		
Anthracene	ug/L	ND	ND		
Benzo(a)anthracene	ug/L	ND	ND		
Benzo(a)pyrene	ug/L	ND	ND		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

SAMPLE DUPLICATE: 2553237

Parameter	Units	92425875002 Result	Dup Result	RPD	Qualifiers
Benzo(b)fluoranthene	ug/L	ND	ND		
Benzo(g,h,i)perylene	ug/L	ND	ND		
Benzo(k)fluoranthene	ug/L	ND	ND		
Benzoic Acid	ug/L	ND	ND		
Benzyl alcohol	ug/L	ND	ND		
bis(2-Chloroethoxy)methane	ug/L	ND	ND		
bis(2-Chloroethyl) ether	ug/L	ND	ND		
bis(2-Ethylhexyl)phthalate	ug/L	ND	ND		
Butylbenzylphthalate	ug/L	ND	ND		
Chrysene	ug/L	ND	ND		
Di-n-butylphthalate	ug/L	ND	ND		
Di-n-octylphthalate	ug/L	ND	ND		
Dibenz(a,h)anthracene	ug/L	ND	ND		
Dibenzofuran	ug/L	ND	ND		
Diethylphthalate	ug/L	ND	ND		
Dimethylphthalate	ug/L	ND	ND		
Fluoranthene	ug/L	ND	ND		
Fluorene	ug/L	ND	ND		
Hexachloro-1,3-butadiene	ug/L	ND	ND		
Hexachlorobenzene	ug/L	ND	ND		
Hexachlorocyclopentadiene	ug/L	ND	ND		
Hexachloroethane	ug/L	ND	ND		
Indeno(1,2,3-cd)pyrene	ug/L	ND	ND		
Isophorone	ug/L	ND	ND		
N-Nitroso-di-n-propylamine	ug/L	ND	ND		
N-Nitrosodimethylamine	ug/L	ND	ND		
N-Nitrosodiphenylamine	ug/L	ND	ND		
Naphthalene	ug/L	7.8J	13.6		
Nitrobenzene	ug/L	ND	ND		
Pentachlorophenol	ug/L	ND	ND		
Phenanthrene	ug/L	ND	ND		
Phenol	ug/L	ND	2.7J		
Pyrene	ug/L	ND	ND		
2,4,6-Tribromophenol (S)	%	59	69		
2-Fluorobiphenyl (S)	%	51	57		
2-Fluorophenol (S)	%	46	48		
Nitrobenzene-d5 (S)	%	55	60		
Phenol-d6 (S)	%	36	37		
Terphenyl-d14 (S)	%	72	73		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: U5797
Pace Project No.: 92425908

QC Batch:	470258	Analysis Method:	ASTM D2974-87
QC Batch Method:	ASTM D2974-87	Analysis Description:	Dry Weight/Percent Moisture
Associated Lab Samples: 92425908003, 92425908004			

SAMPLE DUPLICATE: 2553186

Parameter	Units	92425748006 Result	Dup Result	RPD	Qualifiers
Percent Moisture	%	18.6	16.4	13	

SAMPLE DUPLICATE: 2553187

Parameter	Units	92425874002 Result	Dup Result	RPD	Qualifiers
Percent Moisture	%	4.5	5.2	14	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALIFIERS

Project: U5797
Pace Project No.: 92425908

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

Acid preservation may not be appropriate for 2 Chloroethylvinyl ether.

A separate vial preserved to a pH of 4-5 is recommended in SW846 Chapter 4 for the analysis of Acrolein and Acrylonitrile by EPA Method 8260.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

LABORATORIES

PASI-C Pace Analytical Services - Charlotte

ANALYTE QUALIFIERS

D6	The precision between the sample and sample duplicate exceeded laboratory control limits.
H2	Extraction or preparation conducted outside EPA method holding time.
IK	The recalculated concentration of the calibration standard(s) did not meet method acceptance criteria; this result should be considered an estimated value.
L2	Analyte recovery in the laboratory control sample (LCS) was below QC limits. Results for this analyte in associated samples may be biased low.
M1	Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
P2	Re-extraction or re-analysis could not be performed due to insufficient sample amount.
S0	Surrogate recovery outside laboratory control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: U5797
Pace Project No.: 92425908

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92425908001	B3	EPA 3510C	470256	EPA 8270E	470471
92425908002	B5.1	EPA 3510C	470256	EPA 8270E	470471
92425908003	B18	EPA 5035A	470498	EPA 8260D	470560
92425908004	B19	EPA 5035A	470498	EPA 8260D	470560
92425908001	B3	EPA 8260D	470847		
92425908002	B5.1	EPA 8260D	470847		
92425908003	B18	ASTM D2974-87	470258		
92425908004	B19	ASTM D2974-87	470258		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical

Document Name: Sample Condition Upon Receipt (SCUR) Document Revised: February 7, 2018
 Document No.: F-CAR-CS-033-Rev.06 Page 1 of 1
 Issuing Authority: Pace Carolinas Quality Office

Laboratory receiving samples:

Asheville ☐ Eden ☐ Greenwood ☐ Huntersville ☐ Raleigh ☒ Mechanicsville ☐

Sample Condition Upon Receipt

Client Name: Falcon Engineering Project

Courier: ☐ Commercial ☐ Fed Ex ☐ UPS ☐ USPS ☐ Other: ☒ Client

WO#: 92425908



Custody Seal Present? ☐ Yes ☒ No Seals Intact? ☐ Yes ☐ No

Packing Material: ☐ Bubble Wrap ☒ Bubble Bags ☐ None ☐ Other

Thermometer: 91TC005 Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temp (°C): 10.1 Correction Factor: Add/Subtract (°C) -0.1

Cooler Temp Corrected (°C): 10.0

Date/Initials Person Examining Contents: UBT 4/12/19

Biological Tissue Frozen? ☐ Yes ☐ No ☒ N/A

Temp should be above freezing to 6°C

☒ Samples out of temp criteria. Samples on ice, cooling process has begun

USDA Regulated Soil (☒ N/A, water sample)

Old samples originate in a quarantine zone within the United States: CA, NY, or SC (check maps)? ☐ Yes ☐ No

Old samples originate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☐ No

Chain of Custody Present?	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	1.
Samples Arrived within Hold Time?	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	2.
Short Hold Time Analysis (<72 hr.)?	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A <input type="checkbox"/>	3.
Rush Turn Around Time Requested?	Yes <input type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	4.
Sufficient Volume?	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	5.
Correct Containers Used?	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	6.
Pace Containers Used?	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	7.
Containers Intact?	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	8.
Dissolved analysis: Samples Field Filtered?	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A <input type="checkbox"/>	9.
Sample Labels Match COC?	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A <input type="checkbox"/>	10.
-Includes Date/Time/ID/Analysis Matrix <u>WT 5L</u>	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A <input type="checkbox"/>	11.
Head space in VOA Vials (>5-6mm)?	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A <input type="checkbox"/>	
Trip Blank Present?	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A <input type="checkbox"/>	
Trip Blank Custody Seals Present?	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A <input type="checkbox"/>	

COMMENTS/SAMPLE DISCREPANCY:

Field Data Requested? ☐ Yes ☐ No

CLIENT NOTIFICATION/RESOLUTION


Lot ID of split containers:

Person contacted:

Date/Time:

Project Manager SCUR Review:

Date:

	Document Name:	Document Revised: February 7, 2018
	Sample Condition Upon Receipt (SCUR)	Page 1 of 2
	Document No.: F-CAR-CS-033-Rev.06	Issuing Authority: Pace Carolinas Quality Office

*Check mark top half of box if pH and/or dechlorination is verified and within the acceptance range for preservation samples.

Exceptions: VOA, Coliform, TDC, Oil and Grease, DRO/2015 (water) DOC, L/Hg

**Bottom half of box is to list number of bottle

Project:

W0# : 92425908

PN: TIH

Due Date: 04/26/19

CLIENT: 92-FALCON

Item#	BP4U-125 mL Plastic Unpreserved (N/A) (C-)	BP3U-250 mL Plastic Unpreserved (N/A)	BP2U-500 mL Plastic Unpreserved (N/A)	BP1U-1 liter Plastic Unpreserved (N/A)	BP4S-125 mL Plastic H2SO4 (pH < 2) (C-)	BP3N-250 mL plastic HNO3 (pH < 2)	BP4Z-125 mL Plastic 2N Acetate & NaOH (pH > 9)	BP4C-125 mL Plastic NaOH (pH > 12) (C-)	WGFU-Wide-mouthed Glass Jar Unpreserved	AG1U-1 liter Amber Unpreserved (N/A) (C-)	AG1H-1 liter Amber HCl (pH < 2)	AG3U-250 mL Amber Unpreserved (N/A) (C-)	AG1S-1 liter Amber H2SO4 (pH < 2)	AG3S-250 mL Amber H2SO4 (pH < 2)	AG3A(pH3A)-250 mL Amber NH4Cl (N/A)(C-)	DG9H-40 mL VOA HCl (N/A)	V68T-40 mL VOA Na2S2O3 (N/A)	V68U-40 mL VOA Unp (N/A)	DG9P-40 mL VOA H3PO4 (N/A)	VOAK (6 vials per kit)-SDB5 kit (N/A)	V/OK (3 vials per kit)-VPH/Gas kit (N/A)	SP3T-125 mL Sterile Plastic (N/A -- lab)	SP2T-250 mL Sterile Plastic (N/A -- lab)	BP3A-250 mL Plastic (NH2)2SO4 (9.3-9.7)	AG0U-100 mL Amber Unpreserved vials (N/A)	VSGU-20 mL Scintillation Vials (N/A)	DG9U-40 mL Amber Unpreserved vials (N/A)	
1																												
2																												
3																												
4																												
5																												
6																												
7																												
8																												
9																												
10																												
11																												
12																												

pH Adjustment Log for Preserved Samples

Sample ID	Type of Preservative	pH upon receipt	Date preservation adjusted	Time preservation adjusted	Amount of Preservative added	Lot #

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e.

Chain-of-Custody / Analytical Request Document
The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

[illegible]



PYRAMID GEOPHYSICAL SERVICES
(PROJECT 2019-091)

GEOPHYSICAL SURVEY

METALLIC UST INVESTIGATION: PARCEL 16 NCDOT PROJECT U-5797

2548-E FAYETTEVILLE RD., LUMBERTON, NC

APRIL 22, 2019

Report prepared for: Christopher J. Burkhardt, PWS
Falcon Engineers
1210 Trinity Rd. #110
Raleigh, NC 27607

Prepared by: _____

A handwritten signature in black ink, appearing to read "E. Cross".

Eric C. Cross, P.G.
NC License #2181

Reviewed by: _____

A handwritten signature in black ink, appearing to read "Doug Canavella".

Douglas A. Canavella, P.G.
NC License #1066

503 INDUSTRIAL AVENUE, GREENSBORO, NC 27406

P: 336.335.3174 F: 336.691.0648

C257: GEOLOGY

C1251: ENGINEERING

GEOPHYSICAL INVESTIGATION REPORT
Parcel 16 - 2548-E Fayetteville Rd.
Lumberton, Robeson County, North Carolina

Table of Contents

Executive Summary	1
Introduction.....	2
Field Methodology.....	2
Discussion of Results.....	3
<i>Discussion of EM Results</i>	3
<i>Discussion of GPR Results</i>	4
Summary & Conclusions	5
Limitations	6

Figures

- Figure 1 – Parcel 16 - Geophysical Survey Boundaries and Site Photographs
- Figure 2 – Parcel 16 - EM61 Results Contour Map
- Figure 3 – Parcel 16 - GPR Transect Locations and Select Images
- Figure 4 – Parcel 16 - Overlay of Metal Detection Results on NCDOT Engineering Plans

Appendices

- Appendix A – GPR Transect Images

LIST OF ACRONYMS

CADD	Computer Assisted Drafting and Design
DF	Dual Frequency
EM.....	Electromagnetic
GPR.....	Ground Penetrating Radar
GPS	Global Positioning System
NCDOT.....	North Carolina Department of Transportation
ROW	Right-of-Way
UST	Underground Storage Tank

EXECUTIVE SUMMARY

Project Description: Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 16, located at 2548-E Fayetteville Rd. in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-26, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

Geophysical Results: The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. A total of nine EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. Several EM anomalies were associated with interference from a building, a car, and suspected reinforced concrete and were further investigated with GPR.

GPR verified the presence of metal reinforcement in the concrete on the central and southern portions of the survey area. No evidence of any larger structures such as USTs was observed. Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 16.

INTRODUCTION

Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 16, located at 2548-E Fayetteville Rd. in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-26, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

The site included commercial buildings surrounded by concrete, asphalt, and grass surfaces. An aerial photograph showing the survey area boundaries and ground-level photographs are shown in **Figure 1**.

FIELD METHODOLOGY

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is geo-referenced and can be overlain on aerial photographs and CADD drawings. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and assure complete coverage of the area.

According to the instrument specifications, the EM61 can detect a metal drum down to a maximum depth of approximately 8 feet. Smaller objects (1-foot or less in size) can be detected to a maximum depth of 4 to 5 feet. The EM61 data were digitally collected at approximately 0.8-foot intervals along north-south trending or east-west trending, generally parallel survey lines, spaced five feet apart. The data were downloaded to a

computer and reviewed in the field and office using the Geonics NAV61 and Surfer for Windows Version 15.0 software programs.

GPR data were acquired across select EM anomalies on March 26, 2019, using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Data were collected both in reconnaissance fashion as well as along formal transect lines across EM features. The GPR data were viewed in real-time using a vertical scan of 512 samples, at a rate of 48 scans per second. GPR data were viewed down to a maximum depth of approximately 6 feet, based on dielectric constants calculated by the DF unit in the field during the reconnaissance scans. GPR transects across specific anomalies were saved to the hard drive of the DF unit for post-processing and figure generation.

Pyramid's classifications of USTs for the purposes of this report are based directly on the geophysical UST ratings provided by the NCDOT. These ratings are as follows:

Geophysical Surveys for Underground Storage Tanks on NCDOT Projects			
High Confidence	Intermediate Confidence	Low Confidence	No Confidence
Known UST Active tank - spatial location, orientation, and approximate depth determined by geophysics.	Probable UST Sufficient geophysical data from both magnetic and radar surveys that is characteristic of a tank. Interpretation may be supported by physical evidence such as fill/vent pipe, metal cover plate, asphalt/concrete patch, etc.	Possible UST Sufficient geophysical data from either magnetic or radar surveys that is characteristic of a tank. Additional data is not sufficient enough to confirm or deny the presence of a UST.	Anomaly noted but not characteristic of a UST. Should be noted in the text and may be called out in the figures at the geophysicist's discretion.

DISCUSSION OF RESULTS

Discussion of EM Results

A contour plot of the EM61 results obtained across the survey area at the property is presented in **Figure 2**. Each EM anomaly is numbered for reference in the figure. The following table presents the list of EM anomalies and the cause of the metallic response, if known:

LIST OF METALLIC ANOMALIES IDENTIFIED BY EM SURVEY

Metallic Anomaly #	Cause of Anomaly	Investigated with GPR
1	Guard Rail	
2	Drop Inlet	
3	Drop Inlet	
4	Surface Metal	
5	Reinforced Concrete	✓
6	Drop Inlet	
7	Reinforced Concrete	✓
8	Car/Building	✓
9	Utilities	

The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface, including a guard rail, drop inlets, surface metal, a car, the buildings, and utilities. EM Anomalies 5 and 7 were associated with suspected reinforced concrete and were further investigated with GPR to confirm that there was reinforcement in the concrete slab and the reinforcement did not obscure any potential USTs.

EM Anomaly 8 was associated with interference from a building and a car and was further investigated with GPR to verify that the interference did not obscure buried structures such as USTs.

Discussion of GPR Results

Figure 3 presents the locations of the formal GPR transects performed at the property as well as select transect images. All of the transect images are included in **Appendix A**. A total of eleven formal GPR transects were performed at the site. GPR Transects 1-7 were performed in a grid-like fashion across EM Anomaly 5. These transects verified the presence of metal reinforcement in the concrete on the central portion of the survey area. No evidence of any larger structures such as USTs was observed.

GPR Transects 8-10 were performed across EM Anomaly 7. These transects verified the presence of metal reinforcement in the concrete on the southern portion of the survey area. No evidence of any larger structures such as USTs was observed.

GPR Transect 11 was performed across EM Anomaly 8. This transect did not record evidence of significant structures, such as USTs, and verified that the car and building were the cause for the EM interference.

Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 16. **Figure 4** provides an overlay of the EM61 metal detection contour map onto the NCDOT MicroStation engineering plans for reference.

SUMMARY & CONCLUSIONS

Pyramid's evaluation of the EM61 and GPR data collected at Parcel 16 in Lumberton, North Carolina, provides the following summary and conclusions:

- The EM61 and GPR surveys provided reliable results for the detection of metallic USTs within the accessible portions of the geophysical survey area.
- The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface.
- Several EM anomalies were associated with interference from a building, a car, and suspected reinforced concrete and were further investigated with GPR.
- GPR verified the presence of metal reinforcement in the concrete on the central and southern portions of the survey area. No evidence of any larger structures such as USTs was observed.
- Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 16.

LIMITATIONS

Geophysical surveys have been performed and this report was prepared for Falcon Engineers in accordance with generally accepted guidelines for EM61 and GPR surveys. It is generally recognized that the results of the EM61 and GPR surveys are non-unique and may not represent actual subsurface conditions. The EM61 and GPR results obtained for this project have not conclusively determined the definitive presence or absence of metallic USTs, but the evidence collected is sufficient to result in the conclusions made in this report. Additionally, it should be understood that areas containing extensive vegetation, reinforced concrete, or other restrictions to the accessibility of the geophysical instruments could not be fully investigated.

APPROXIMATE BOUNDARIES OF GEOPHYSICAL SURVEY AREA




View of Survey Area
(Facing Approximately North)



View of Survey Area
(Facing Approximately South)



 <div>503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 (336) 335-3174 (p) (336) 691-0648 (f) License # C1251 Eng. / License # C257 Geology</div>	PROJECT PARCEL 16 LUMBERTON, NORTH CAROLINA NCDOT PROJECT U-5797	TITLE PARCEL 16 - GEOPHYSICAL SURVEY BOUNDARIES AND SITE PHOTOGRAPHS	DATE 3/26/2019	CLIENT FALCON ENGINEERS
			PYRAMID PROJECT #: 2019-091	FIGURE 1


EM61 METAL DETECTION RESULTS



NO EVIDENCE OF METALLIC
USTs OBSERVED.

The contour plot shows the differential results of the EM61 instrument in millivolts (mV). The differential results focus on larger metallic objects such as USTs and drums. The EM data were collected on March 18, 2019, using a Geonics EM61-MK2 instrument. Verification GPR data were collected using a GSSI UtilityScan DF instrument with a dual frequency 300/800 MHz antenna on March 26, 2019.

EM61 Metal Detection Response
(millivolts)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology



PROJECT
PARCEL 16
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 16 -
EM61 METAL DETECTION CONTOUR MAP

DATE
3/26/2019
PYRAMID
PROJECT #: 2019-091


CLIENT
FALCON ENGINEERS
FIGURE 2

LOCATIONS OF GPR TRANSECTS




GPR TRANSECT 3 (T3)

GPR TRANSECT 4 (T4)




GPR TRANSECT 5 (T5)

GPR TRANSECT 6 (T6)



GPR TRANSECT 8 (T8)



GPR TRANSECT 11 (T11)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology

PROJECT
PARCEL 16
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 16 -
GPR TRANSECT LOCATIONS AND SELECT IMAGES

DATE
3/26/2019
PYRAMID
PROJECT #:
2019-091

CLIENT
FALCON ENGINEERS
FIGURE 3





EM61 METAL DETECTION
CONTOURS (SEE FIGURE 2
FOR ANOMALY LABELS)

LEGEND

- EXISTING ROW
- EXISTING PROPERTY BOUNDARY
- PROPOSED ROW LINE
- TEMPORARY CONSTRUCTION EASEMENT
- PROPOSED PERMANENT UTILITY EASEMENT
- PROPOSED SS CUT LINE
- PROPOSED SS FILL LINE


MILLIVOLTS (mV)




CULVERT #1 TWO BARRELS		ELEV.	
NORTH	EAST		
323409.54	1999548.25	118.99	
323415.20	1999550.13	119.00	
323415.73	1999550.28	118.99	
3412.30	1999552.23	119.00	
3412.76	1999549.39	127.06	
3415.26	1999550.56	128.74	
388.57	1999609.42	119.55	
94.21	1999611.37	119.55	
4.56	1999611.51	119.55	
.90	1999613.58	119.54	
83	1999612.09	127.61	
3	1999610.99	129.23	

TITLE OVERLAY OF METAL DETECTION RESULTS ON NCDOT ENGINEERING PLANS	
PROJECT PARCEL 016 LUMBERTON, NORTH CAROLINA NCDOT PROJECT U-5797	
503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 336.335.3174 (p) 336.691.0648 (f) License # C1251 Eng. / #C257 Geology	
DATE: 04-11-2019	REVISION NO. 0
PYRAMID PROJECT NO. 2019-091	FIGURE NO. 4


Appendix A – GPR Transect Images




GPR TRANSECT 1




GPR TRANSECT 2




GPR TRANSECT 5




GPR TRANSECT 3




GPR TRANSECT 6




GPR TRANSECT 4




GPR TRANSECT 7




GPR TRANSECT 8



GPR TRANSECT 11



GPR TRANSECT 9



GPR TRANSECT 10

PRELIMINARY SITE ASSESSMENT

**SR 1997 (FAYETTEVILLE ROAD) WIDENING
TIP NO. U-5797, WBS NO. 44367.1.1**

NCDOT PARCEL NO. 18

OWNER: FAYETTEVILLE ROAD INVESTORS II LLC

3001 FAYETTEVILLE ROAD

LUMBERTON, ROBESON COUNTY, NORTH CAROLINA



PREPARED FOR:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
C/O STV ENGINEERS, INC.
1600 PERIMETER PARK DRIVE, SUITE 225
MORRISVILLE, NC 2756002

PREPARED BY:
FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
CARY, NC 27513

PROJECT NUMBER: G19011.00
JUNE 9, 2020





June 9, 2020

Mr. Patrick Livingston, PE
STV Engineers, Inc.
900 W. Trade St, Suite 715
Charlotte, NC 28202

Re: **Preliminary Site Assessment**
SR 1997 (Fayetteville Road) Widening
TIP No. U-5797, WBS No. 44367.1.1
Parcel No. 18
Owner: Fayetteville Road Investors II LLC
3001 Fayetteville Road
Lumberton, Robeson County, North Carolina

Dear: Mr. Livingston:

Falcon is pleased to present the following Preliminary Site Assessment in support of the above-mentioned Project. Specifically, Falcon sampled soil in proximity to the project limits on this parcel in general accordance with the approved scope of work. Soils requiring remediation or special handling during construction were not identified.

Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

Please review this report and advise us if you have any questions or concerns. We appreciate this opportunity to provide services to you and look forward to partnering with you on future projects. If you have any questions, please give Falcon a call at (919) 871-0800.

Sincerely,

FALCON ENGINEERING, INC.

A handwritten signature in blue ink, reading "Christopher J. Burkhardt".

Christopher J. Burkhardt
Environmental Services Manager

A handwritten signature in blue ink, reading "Jeremy R. Hamm".

Jeremy R. Hamm, PE
Geotechnical Services Manager

TABLE OF CONTENTS

SECTION 1: INTRODUCTION	5
1.1 DESCRIPTION	5
1.2 SCOPE OF WORK.....	5
SECTION 2: HISTORY	6
2.1 PARCEL USAGE.....	6
2.2 FACILITY IDENTIFICATION NUMBER	6
2.3 GROUNDWATER INCIDENT NUMBER.....	6
SECTION 3: SITE OBSERVATIONS	7
3.1 GROUNDWATER MONITORING WELLS.....	7
3.2 ACTIVE USTS	7
3.3 FEATURES APPARENT BEYOND ROW/EASEMENT	7
SECTION 4: METHODOLOGY	8
4.1 GEOPHYSICS.....	8
4.2 BORINGS	8
4.3 SAMPLE PROTOCOL.....	8
SECTION 5: RESULTS.....	10
5.1 GEOPHYSICS	10
5.2 SAMPLE DATA	10
TABLE NO. 1 BORING COORDINATES.....	10
TABLE NO. 2 PID READINGS	11
TABLE NO. 3 SUMMARY OF UVF SOIL SAMPLING RESULTS	11
5.3 SAMPLE OBSERVATIONS	12
TABLE NO. 4 SOIL OBSERVATIONS.....	12
5.4 QUANTITIES CALCULATIONS	12
SECTION 6: CONCLUSIONS	13
6.1 INTERPRETATION OF RESULTS	13
6.2 GEOPHYSICS.....	13
6.3 SAMPLING	13
6.4 QUANTITIES	13
SECTION 7: RECOMMENDATIONS	14
7.1 ADDITIONAL SAMPLING	14
7.2 SPECIAL HANDLING OF IMPACTED SOIL.....	14



LIST OF FIGURES AND ATTACHMENTS

VICINITY MAP

USGS TOPOGRAPHIC MAP

PARCEL LOCATION MAP

BORING LOCATION MAP

AERIAL PHOTOGRAPHS

SITE PHOTOGRAPHS

UNDERGROUND STORAGE TANK DOCUMENTATION

LABORATORY RESULTS

GEOPHYSICAL SURVEY

SECTION 1: INTRODUCTION

1.1 DESCRIPTION

Falcon Engineering, Inc. (Falcon) has completed a Preliminary Site Assessment of NCDOT TIP Project U-5797 Parcel No. 18. Parcel No. 18 is addressed as 3001 Fayetteville Road, Lumberton Robeson County, North Carolina. NCDOT is proposing to widen Fayetteville Road (SR 1997) from Farringdom Street to 22nd Street. The limits of the assessment are between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). Boring locations were placed in the vicinity of proposed excavations for drainage features, utilities, and roadway/ditch cuts to determine if soils requiring remediation or special handling were present where excavation was planned to take place.

1.2 SCOPE OF WORK

Falcon's scope of work included coordination of; public and private utility location near the proposed borings, geophysical surveys, collecting soil samples using direct push technology, and laboratory analysis. Samples were analyzed for petroleum hydrocarbons via UVF technology.

SECTION 2: HISTORY

2.1 PARCEL USAGE

Falcon performed a Phase I Environmental Site Assessment (ESA) for U-5797 under Project No. G17057 dated April 2018. The ESA identified this parcel as a Recognized Environmental Condition (REC) based on the history of the parcel and adjoining parcels. Falcon contacted Mr. Joe Oliver the County Fire Marshal during the ESA to inquire about known USTs along Fayetteville Road in the general area of Parcel No. 18. Mr. Oliver sent documents pertaining to USTs that had been installed and/or removed from Baxley's addressed as Highway 211 East, and Taco Bell addressed as Fayetteville Road and Roberts Ave. The exact location of USTs associated with these facilities is not known. Historic air photographs dated 1976 through 2000 show Parcel No. 18 developed with a small commercial building, and a larger commercial building and parking lot adjoining Parcel No. 18 to the west and north. UST closure documentation including soil sampling results was not available for review.

2.2 FACILITY IDENTIFICATION NUMBER

A Facility Identification Number was not identified for this parcel.

2.3 GROUNDWATER INCIDENT NUMBER

A Groundwater Incident Number was not identified for this parcel.

SECTION 3: SITE OBSERVATIONS

3.1 GROUNDWATER MONITORING WELLS

Groundwater monitoring wells (MWs) were not observed on this parcel.

3.2 ACTIVE USTS

Active USTs were not observed within the project limits or registered at this parcel.

3.3 FEATURES APPARENT BEYOND ROW/EASEMENT

USTs, monitoring wells, remediation systems, or hydraulic lifts were not observed.

SECTION 4: METHODOLOGY

4.1 GEOPHYSICS

Pyramid Geophysical Services (Pyramid) was subcontracted to perform a geophysical survey of the assessment area. The assessment area is between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). The survey was used to locate private utility lines, as well as possible indications of USTs, and/or their pits.

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is georeferenced and can be overlain on aerial photographs and CADD drawings.

The GPR data was acquired across select EM anomalies (where identified), using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Pyramid marked their findings on the surface with paint. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and to obtain adequate coverage. A copy of the full Geophysical Report is included in the Attachments.

4.2 BORINGS

Regional Probing was subcontracted to advance soil borings using direct push technology. Regional Probing used a truck-mounted Geoprobe® 5410 unit mounted on an off-road modified Ford F350 Diesel 4x4. The unit has auger-capabilities and is equipped with a GH-42 soil-probing hammer, with 21,700 pounds of down force and 28,900 pounds of retraction force. The unit has an on-board tank for decontaminating the geoprobe rods before advancing the probe at each sample location.

4.3 SAMPLE PROTOCOL

Prior to initiating sample collection Falcon contacted NC One Call and requested public utility locations be marked around the proposed sample locations. Sampling was in general accordance with the NC Department of Environmental Quality (DEQ) Division of Waste Management's (DWM) "Guidelines for Site Checks, Tank Closure, and Initial Response and Abatement for UST Releases" (March 1, 2007 Version Change 9 – February 1, 2019) guidance document. Sampling strategy was derived based upon the project scope and objectives as outlined above. Red Lab, LLC was selected to perform the UVF laboratory analytical analysis. Appropriate sterile containers were received by Falcon from Red Lab prior to beginning the fieldwork. The containers were labeled appropriately.

A Minirae 3000 photoionization detector (PID) was used to field screen samples for volatile organics to determine if a release had occurred. The instrument was calibrated per manufacturer instructions prior to use. Falcon staff bagged composite soil samples of each boring in approximately two-foot sections. Representative samples were placed in a sealed plastic bag for approximately 10 minutes to allow soil hydrocarbons to reach equilibrium within the headspace prior to scanning with the PID. One sample per boring was collected from the depth of the proposed cut or from the section above the depth of cut with the highest PID reading.

To avoid cross contamination, a new unused pair of non-powdered nitrile gloves was worn while extracting each sample. Samples were placed in the appropriate laboratory provided containers. The labels on each container were then completed so that each provided the date and time of sampling, method of analysis, sample collector, preservative used and sampling location identification. Samples were placed in an ice filled cooler and transported to the lab. Appropriate chain-of-custody procedures, including the completion of necessary forms, were followed.

SECTION 5: RESULTS

5.1 GEOPHYSICS

The geophysical investigation was performed between March 18 and March 26, 2019 to investigate for metallic underground storage tanks (USTs) beneath the survey area. A total of eleven EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. Several EM anomalies were associated with suspected utilities and interference from vehicles and were further investigated with GPR.

GPR recorded small, low-amplitude anomalies, consistent with suspected utilities. GPR also recorded minor reflectors that were suggestive of possible buried metallic debris. No evidence of any larger structures such as USTs was observed.

5.2 SAMPLE DATA

Falcon and our subcontractor advanced five borings (B-20 through B-24) to the proposed excavation depth of the drainage features, utilities, or roadway/ditch cut being assessed. Groundwater was not observed. Please see the Boring Layout Plan in the attachments for a visual depiction of the sample locations. The coordinates (latitude and longitude) that correspond to the sample locations are shown below in Table No. 1 Boring Coordinates.

TABLE NO. 1 BORING COORDINATES

Boring	Latitude	Longitude
B-20	34.6395832	-79.0017437
B-21	34.6393869	-79.0013177
B-22	34.6395619	-79.0012098
B-23	34.6398805	-79.0010772
B-24	34.6400881	-79.0010401

Borings were field screened with a PID in sections for evidence of volatile organics. The PID screening results are presented in Table No. 2 PID Readings. Falcon selected soil samples based on the field screening results and the needs of the project. Red Lab analyzed the selected samples and their full analytical report is attached. The results of the laboratory analysis are shown in Table No. 3 Summary of UVF Soil Sampling Results.

Petroleum hydrocarbons above State Action Levels were not detected in the samples.

TABLE NO. 2 PID READINGS

Boring	Depth BGS*	PID**
B-20	0-2.5	0.6
B-21	0-2.5	0.4
	2.5-5.0	0.5
B-22	0-5.0	1.2
B-23	0-2.5	1.1
	2.5-5.0	1.1
B-24	0-2.5	0.9
	2.5-5.0	0.7

*BGS = Depth below ground surface in feet

**PID readings are in parts per million

Samples shown in **bold** were selected for analysis

TABLE NO. 3 SUMMARY OF UVF SOIL SAMPLING RESULTS

Sample ID	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
								% light	% mid	% heavy	
B-20	<0.57	<0.57	12.7	12.7	6.4	0.32	<0.023	0	76.5	23.5	V.Deg.PHC 96.9%,(FCM)
B-21	<0.27	<0.27	1.2	1.2	0.55	<0.09	<0.011	0	78.8	21.2	Deg.PHC 80.6%,(FCM)
B-22	<0.28	<0.28	<0.28	0.18	0.18	<0.09	<0.011	0	61.6	38.4	Residual HC,(BO)
B-23	<0.27	<0.27	<0.27	<0.27	<0.05	<0.09	<0.011	0	0	0	FCM)
B-24	<0.18	<0.18	<0.18	<0.18	<0.04	<0.06	<0.007	0	0	0	,(FCM),(BO)

Results reported in mg/kg (milligrams per kilogram)

5.3 SAMPLE OBSERVATIONS

Obvious indications of a release (stained soils, odors, or oily sheen) were not observed. Table No. 4 Soil Observations lists visual soil observations of color and texture.

TABLE NO. 4 SOIL OBSERVATIONS

Sample ID	Depth	Color	Soil Type
B-20	0-2.5	Brown Tan	Slightly Clayey Silty Sand (A-2-4)
B-21	0-2.5	Gray Brown	Silty Clayey Sand (A-2-6)
	2.5-5.0	Dark Brown & Tan	Silty Clayey Sand (A-2-6)
B-22	0-5.0 (Compressed)	Brown Orange	Silty Sandy Clay (A-6)
B-23	0-2.5	Brown	Sandy Clay (A-6)
	2.5-5.0	Orange Gray (mottled)	Sandy Clay (A-6)
B-24	0-2.5	Brown	Sandy Clay (A-6)
	2.5-5.0	Brown Tan	Sandy Clay (A-6)

Depth is in feet below ground surface

5.4 QUANTITIES CALCULATIONS

Soils requiring quantity calculations were not identified.

SECTION 6: CONCLUSIONS

6.1 INTERPRETATION OF RESULTS

This Preliminary Site Assessment was performed to evaluate the soils in proximity to the project limits on this parcel for the presence of petroleum hydrocarbons. The findings are as follows:

- Soil sampling completed on the parcel did not identify contaminants in the soil at levels requiring remediation.

6.2 GEOPHYSICS

Collectively, the geophysical data did not record evidence of unknown metallic USTs within the geophysical survey area at Parcel 18. Falcon does not anticipate USTs will be encountered within the project limits on this parcel during construction.

6.3 SAMPLING

Sampling results did not identify contaminants in the soil which require remediation in the areas sampled. Based on past project experience, Falcon does not anticipate soil remediation or special handling and disposal will be required during construction on this parcel.

6.4 QUANTITIES

Soils requiring quantities calculations were not identified.



SECTION 7: RECOMMENDATIONS


7.1 ADDITIONAL SAMPLING

Contaminants above the Industrial / Commercial Soil Cleanup Levels were not identified; therefore, additional assessment is not warranted at this time. Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

7.2 SPECIAL HANDLING OF IMPACTED SOIL

Soils requiring special handling were not identified. If suspect contaminated soils are encountered during construction Falcon and the NCDOT GeoEnvironmental Group should be contacted for proper handling instructions.

NCDOT U-5797 (SR 1997 Widening) Parcel 18
Preliminary Site Assessment
Vicinity Map




Project No.: G19011.00
Date: September 2019
Source: Google Maps

NCDOT U-5797 (SR 1997 Widening) Parcel 18

Preliminary Site Assessment

USGS Topographic Maps



Project No.: G19011.00
Date: September 2019
Source: "NW, NE, SW, and SE Lumberton, NC" 2019

NCDOT U-5797 (SR 1997 Widening) Parcel 18


Preliminary Site Assessment

Parcel Location Map



September 5, 2019


-  County Line
-  City Limits
-  Streets
-  Parcels



Esri, HERE, Garmin, (c) OpenStreetMap contributors, and the GIS user community
Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Project No.: G19011.00
Date: September 2019
Source: Robeson County GIS

NAD 83/ NRSRS 2007



NOTES:
• BGS = BELOW GROUND SURFACE



FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
RALEIGH, NC 27607
PHONE: 919.871.0800
FAX: 919.871.0803

BORING LOCATION PLAN


NCDOT U-5797 (SR 1997 WIDENING)
PARCEL 18 - FAYETTEVILLE RD INVESTORS II LLC
ROBESON / LUMBERTON, NC
WBS NO.: 44367.1.1 & TIP NO.: U-5797
FALCON PROJECT NO. G19011.00

NCDOT U-5797 (SR 1997 Widening) Parcel 18
Preliminary Site Assessment
1990 Aerial Photograph



Project No.: G19011.00
Date: September 2019
Source: NCDOT Historical Aerial Imagery Index

NCDOT U-5797 (SR 1997 Widening) Parcel 18
Preliminary Site Assessment
1986 Aerial Photograph



Project No.: G19011.00
Date: September 2019
Source: NCDOT Historical Aerial Imagery Index

NCDOT U-5797 (SR 1997 Widening) Parcel 18
Preliminary Site Assessment
1985 Aerial Photograph



Project No.: G19011.00
Date: September 2019
Source: NCDOT Historical Aerial Imagery Index

NCDOT U-5797 (SR 1997 Widening) Parcel 18
Preliminary Site Assessment
1976 Aerial Photograph



Project No.: G19011.00
Date: September 2019
Source: ERIS Aerial Photographs

NCDOT U-5797 (SR 1997 Widening) Parcel 18
Preliminary Site Assessment
Site Photographs



Photograph No. 1: General view of Boring B-20.



Photograph No. 2: General view of Boring B-21.

NCDOT U-5797 (SR 1997 Widening) Parcel 18
Preliminary Site Assessment
Site Photographs



Photograph No. 3: General view of Boring B-22.



Photograph No. 4: General view of Boring B-23.

NCDOT U-5797 (SR 1997 Widening) Parcel 18
Preliminary Site Assessment
Site Photographs



Photograph No. 5: General view of Boring B-24.

DIVISION OF ENVIRONMENTAL MANAGEMENT

June 26, 1991

Mr. Sam Everett
1203 East 11th Street
Lumberton, NC 28358

SUBJECT: Review of Lab Results
UST Soil Assessment
Oscar Baxley Grocery
Highway 211 - East
Lumberton, Robeson County

Dear Mr. Everett:

This is to acknowledge receipt of the above mentioned soil assessment dated June 14, 1991.

Based on review of the lab results, no additional soil excavation and removal is required. Should new information become available concerning this matter, we reserve the right to reverse this finding.

Should you have any questions or need clarification, please contact Mrs. Cindy Hegg of this office at (919) 486-1541.

Sincerely,

original signed by

[Signature]
M. J. Noland, P.E.
Regional Supervisor

C.H/
MJN/CH/gc

Site Investigation Report For Permanent Closure of U.S.T.

FOR TANKS IN NC	Return Completed Form To: The appropriate DEM Regional Office according to the county of the facility's location. [SEE MAP ON REVERSE SIDE OF OWNER'S COPY (BLUE) FOR REGIONAL OFFICE ADDRESS].	Sate Use Only I.D. Number _____ Date Received _____
--------------------------	--	---

INSTRUCTIONS

Please complete and return within (30) days following completion of site investigation.

I. Ownership of Tank(s)	II. Location of Tank(s)
Owner Name (Corporation, Individual, Public Agency, or Other Entity) <i>Pauline Barker Everett</i>	Facility Name or Company <i>Oscar Barker Grocery</i>
Street Address <i>1203 East 11th Street</i>	Facility ID # (if available) <i>None</i>
City <i>Robeson</i>	Street Address or State Road <i>1203 East</i>
County <i>Lumberton NC</i>	City <i>Robeson Lumberton</i>
Zip Code <i>28358</i>	Zip Code <i>28358</i>
Area Code <i>919</i>	Area Code <i>None</i>
Telephone Number <i>738-5863</i>	Telephone Number <i>None</i>

III. Contact Person

Name <i>Sam Everett</i>	Job Title <i>Husband of owner</i>	Telephone Number <i>(919) 738-5863</i>
Closure Contractor <i>Floyd Grading Co</i>	<i>PO Box 3107 Lumberton NC 28359</i>	
Lab <i>Oxford Laboratories Inc</i>	<i>1316 South 5th Street Wilmington, NC 28401</i>	

IV. U.S.T. Information				V. Excavation Condition				VI. Additional Information Required	
Tank No.	Size in Gallons	Tank Dimensions	Last Contents	Water In Excavation		Free Product		Notable Odor or Visible Soil Contamination	
				Yes	No	Yes	No	Yes	No
1	550	42" x 7'6"	GAS		✓		✓		✓
2	550	42" x 7'6"	GAS		✓		✓		✓

See reverse side of blue copy (owner's copy) for additional information required by N.C. - DEM in the written report and sketch.

VII. Check List

Check the activities completed.

- ☒ Contact local fire marshal
 - ☒ Notify DEM Regional Office before abandonment.
 - ☒ Drain & flush piping into tank.
 - ☒ Remove all product and residuals from tank
 - ☒ Excavate down to tank.
 - ☒ Clean and inspect tank.
 - ☒ Remove drop tube, fill pipe, gauge pipe, vapor recovery tank connections, submersible pumps and other tank fixtures.
 - ☒ Cap or plug all lines except the vent and fill lines.
 - ☒ Purge tank of all product & flammable vapors.
 - ☒ Cut one or more large holes in the tanks.
 - ☒ Backfill the area.
- Date Tank Permanently closed: *5/23/91*

- ABANDONMENT IN PLACE**
- ☐ Fill tank until material overflows tank opening;
 - ☐ Plug or cap all openings;
 - ☐ Disconnect and cap or remove vent line
 - ☐ Solid inert material used - please specify: _____

- REMOVAL**
- ☒ Create vent hole
 - ☒ Label tank
 - ☒ Dispose of tank in approved manner
 - Final tank destination: *Floyd Grading Co*

VIII. Certification (Read and Sign)

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete.

Print name and official title of owner or owner's authorized representative <i>Sam Everett</i>	Signature <i>Sam Everett</i>	Date Signed <i>5/23/91</i>
---	---------------------------------	-------------------------------

Notice of Intent: UST Permanent Closure or Change-In-Service

FOR
TANKS
IN
NC

Return Completed Form To:

The appropriate DEM Regional Office according to the county of the facility's location. [SEE REVERSE SIDE OF OWNER'S COPY (BLUE) FOR REGIONAL OFFICE ADDRESS].

State Use Only

I. D. Number _____

Date Received _____

INSTRUCTIONS

Complete and return thirty (30) days prior to closure or change-in-service.

I. OWNERSHIP OF TANK(S)

Tank Owner Name: Pauline Bentley Everett
(Corporation, Individual, Public Agency, or Other Entity)

Street Address: 1203 East 11th Street

County: Robeson

City: Lumberton State: NC Zip Code: 28358

Tele. No. (Area Code): 919-738-5863

II. LOCATION OF TANK(S)

Facility Name or Company: Oscar Bentley Grocery

Facility ID # (if available): None

Street Address or State Road: Highway 211 - East

County: Robeson City: Lumberton Zip Code: 28358

Tele. No. (Area Code): None

III. CONTACT PERSON

Name: Sam Everett Job Title: Husband Telephone Number: 919, 738-5863

IV. TANK REMOVAL, CLOSURE IN PLACE, CHANGE-IN-SERVICE

1. Contact Local Fire Marshall.
2. Plan the entire closure event.
3. Conduct Site Soil Assessments.
4. If Removing Tanks or Closing in Place refer to API Publications. 2015 "Cleaning Petroleum Storage Tanks" & 1604 "Removal & Disposal of Used Underground Petroleum Storage Tanks".

5. Provide a sketch locating piping, tanks and soil sampling locations.
6. Fill out form GW/UST-2 "Site Investigation Report for Permanent Closure" and return within 30 days following the site investigation.
7. Keep records for 3 years.

V. WORK TO BE PERFORMED BY:

(Contractor) Name: Floyd Grading Co.

Address: P.O. Box 3197 Lumberton State: N.C.

Zip Code: 28359

Contact: Calvin F. Floyd Phone: Office 671-1177

VI. TANK(S) SCHEDULED FOR CLOSURE OR CHANGE-IN-SERVICE

TANK ID#	TANK CAPACITY	LAST CONTENTS	PROPOSED ACTIVITY		
			CLOSURE		CHANGE-IN-SERVICE
			Removal	Abandonment In Place	New Contents Stored
1 1	550	GAS	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
2 2	550	GAS	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	

VII. OWNER OR OWNER'S AUTHORIZED REPRESENTATIVE

Print name and official title

Sam Everett - Owner

*Scheduled Removal Date: 5/23/91

Signature: Sam Everett

Date Submitted: 5/23/91

*If scheduled work date changes, notify your appropriate DEM Regional Office 48 hours prior to originally scheduled date.

APPLICATION TO USE, INSTALL, CONDUCT PROCESSES OR
CARRY ON OPERATIONS INVOLVING OR CREATING CONDI-
TIONS DEEMED HAZARDOUS TO LIFE OR PROPERTY

10-14-83
Date

To Chief of Fire Department, City of Lumberton, N. C.

Application is hereby made by the undersigned for a Permit to

Use
Install
Operate
Conduct

in or on the premises known as TACO-BELL / FAYETTEVILLE ROAD + ROBERTS ~~Street~~ or Avenue
the following materials, processes or operations.

(Describe briefly what is to be done and state what hazardous materials are to be used.)

FOR THE REMOVAL OF 4 - 4000 GALLON
UNDERGROUND GASOLINE STORAGE TANKS.

#12-83

Conditions, surroundings and arrangements to be in accordance with the Fire Prevention Ordinance.

This application ^{is} ~~is not~~ approved insofar
as Zoning and Building Ordinances are
concerned.

Inspector of Buildings

C. M. Lumberton Jr.
Name of Applicant

P.O. Box 1887
Lumberton N.C.
Address of Applicant

Complete plans and construction details must be filed on all major projects and when requested by the chief of the fire department.



Hydrocarbon Analysis Results

Client: FALCON
Address: 1210 TRINITY ROAD SUITE 116
CARY NC 28513

Samples taken Tuesday, April 9, 2019
Samples extracted Tuesday, April 9, 2019
Samples analysed Tuesday, April 16, 2019

Contact: CHRISTOPHER BURKHARDY

Operator DAVIS MARTINEC

Project: G19011 U5797

U00902

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	% Ratios			HC Fingerprint Match
										C5 - C10	C10 - C18	C18	
s	B20	22.6	<0.57	<0.57	12.7	12.7	6.4	0.32	<0.023	0	76.5	23.5	V.Deg.PHC 96.9%,(FCM)
s	B21	10.9	<0.27	<0.27	1.2	1.2	0.55	<0.09	<0.011	0	78.8	21.2	Deg.PHC 80.6%,(FCM)
s	B22	11.4	<0.28	<0.28	<0.28	0.18	0.18	<0.09	<0.011	0	61.6	38.4	Residual HC,(BO)
s	B23	10.9	<0.27	<0.27	<0.27	<0.27	<0.05	<0.09	<0.011	0	0	0	,(FCM)
s	B24	7.4	<0.18	<0.18	<0.18	<0.18	<0.04	<0.06	<0.007	0	0	0	,(FCM),(BO)

Initial Calibrator QC check

OK

Final FCM QC Check

OK





Concentration values in mg/kg for soil samples and mg/L for water samples. Soil values uncorrected for moisture or stone content. Fingerprints provide a tentative hydrocarbon identification.

Abbreviations :- FCM = Results calculated using Fundamental Calibration Mode : % = confidence of hydrocarbon identification : (PFM) = Poor Fingerprint Match : (T) = Turbid : (P) = Particulate detected

B = Blank Drift : (SBS)/(LBS) = Site Specific or Library Background Subtraction applied to result : (BO) = Background Organics detected : (OCR) = Outside cal range : (M) = Modified Result.

% Ratios estimated aromatic carbon number proportions : HC = Hydrocarbon : PHC = Petroleum HC : FP = Fingerprint only.

Data generated by HC-1 Analyser





PYRAMID GEOPHYSICAL SERVICES
(PROJECT 2019-091)

GEOPHYSICAL SURVEY

METALLIC UST INVESTIGATION: PARCEL 18 NCDOT PROJECT U-5797

HIGHWAY 211 EAST, LUMBERTON, NC

APRIL 22, 2019

Report prepared for: Christopher J. Burkhardt, PWS
Falcon Engineers
1210 Trinity Rd. #110
Raleigh, NC 27607

Prepared by: _____

A handwritten signature in black ink, appearing to read "E. Cross".

Eric C. Cross, P.G.
NC License #2181

Reviewed by: _____

A handwritten signature in black ink, appearing to read "Doug Canavella".

Douglas A. Canavella, P.G.
NC License #1066

503 INDUSTRIAL AVENUE, GREENSBORO, NC 27406

P: 336.335.3174 F: 336.691.0648

C257: GEOLOGY

C1251: ENGINEERING

GEOPHYSICAL INVESTIGATION REPORT
Parcel 18 - Highway 211 East
Lumberton, Robeson County, North Carolina

Table of Contents

Executive Summary	1
Introduction.....	2
Field Methodology.....	2
Discussion of Results.....	3
<i>Discussion of EM Results</i>	3
<i>Discussion of GPR Results</i>	4
Summary & Conclusions	5
Limitations	5

Figures

- Figure 1 – Parcel 18 - Geophysical Survey Boundaries and Site Photographs
- Figure 2 – Parcel 18 - EM61 Results Contour Map
- Figure 3 – Parcel 18 - GPR Transect Locations and Images
- Figure 4 – Parcel 18 - Overlay of Metal Detection Results on NCDOT Engineering Plans

LIST OF ACRONYMS

CADD	Computer Assisted Drafting and Design
DF	Dual Frequency
EM.....	Electromagnetic
GPR.....	Ground Penetrating Radar
GPS	Global Positioning System
NCDOT.....	North Carolina Department of Transportation
ROW	Right-of-Way
UST	Underground Storage Tank

EXECUTIVE SUMMARY

Project Description: Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 18, located on Highway 211 East in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-26, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

Geophysical Results: The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. A total of eleven EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. Several EM anomalies were associated with suspected utilities and interference from vehicles and were further investigated with GPR.

GPR recorded small, low-amplitude anomalies, consistent with suspected utilities. GPR also recorded minor reflectors that were suggestive of possible buried metallic debris. No evidence of any larger structures such as USTs was observed. Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 18.

INTRODUCTION

Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 18, located on Highway 211 East in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-26, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

The site included a commercial building surrounded by concrete, asphalt, and grass surfaces. An aerial photograph showing the survey area boundaries and ground-level photographs are shown in **Figure 1**.

FIELD METHODOLOGY

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is geo-referenced and can be overlain on aerial photographs and CADD drawings. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and assure complete coverage of the area.

According to the instrument specifications, the EM61 can detect a metal drum down to a maximum depth of approximately 8 feet. Smaller objects (1-foot or less in size) can be detected to a maximum depth of 4 to 5 feet. The EM61 data were digitally collected at approximately 0.8-foot intervals along north-south trending or east-west trending, generally parallel survey lines, spaced five feet apart. The data were downloaded to a

computer and reviewed in the field and office using the Geonics NAV61 and Surfer for Windows Version 15.0 software programs.

GPR data were acquired across select EM anomalies on March 26, 2019, using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Data were collected both in reconnaissance fashion as well as along formal transect lines across EM features. The GPR data were viewed in real-time using a vertical scan of 512 samples, at a rate of 48 scans per second. GPR data were viewed down to a maximum depth of approximately 6 feet, based on dielectric constants calculated by the DF unit in the field during the reconnaissance scans. GPR transects across specific anomalies were saved to the hard drive of the DF unit for post-processing and figure generation.

Pyramid's classifications of USTs for the purposes of this report are based directly on the geophysical UST ratings provided by the NCDOT. These ratings are as follows:

Geophysical Surveys for Underground Storage Tanks on NCDOT Projects			
High Confidence	Intermediate Confidence	Low Confidence	No Confidence
Known UST Active tank - spatial location, orientation, and approximate depth determined by geophysics.	Probable UST Sufficient geophysical data from both magnetic and radar surveys that is characteristic of a tank. Interpretation may be supported by physical evidence such as fill/vent pipe, metal cover plate, asphalt/concrete patch, etc.	Possible UST Sufficient geophysical data from either magnetic or radar surveys that is characteristic of a tank. Additional data is not sufficient enough to confirm or deny the presence of a UST.	Anomaly noted but not characteristic of a UST. Should be noted in the text and may be called out in the figures at the geophysicist's discretion.

DISCUSSION OF RESULTS

Discussion of EM Results

A contour plot of the EM61 results obtained across the survey area at the property is presented in **Figure 2**. Each EM anomaly is numbered for reference in the figure. The following table presents the list of EM anomalies and the cause of the metallic response, if known:

LIST OF METALLIC ANOMALIES IDENTIFIED BY EM SURVEY

Metallic Anomaly #	Cause of Anomaly	Investigated with GPR
1	Sign	
2	Light	
3	Utility	✓
4	Hydrant/Sign/Utilities	✓
5	Utilities	✓
6	Vehicles	✓
7	Guy Wires	
8	Sign	
9	Drop Inlets	
10	Sign/Guy Wires/Utilities	
11	Metal Plate	

The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface, including signs, a light, utilities, a hydrant, vehicles, guy wires, drop inlets, and a metal plate. EM Anomalies 3, 4, and 5 were associated with suspected utilities and were further investigated with GPR.

EM Anomaly 6 was associated with interference from vehicles and was further investigated with GPR to verify that the interference did not obscure buried structures such as USTs.

Discussion of GPR Results

Figure 3 presents the locations of the formal GPR transects performed at the property as well as the transect images. A total of six formal GPR transects were performed at the site. GPR Transects 1-3 were performed across the areas of interference from the vehicles (EM Anomaly 6). These transects recorded no evidence of buried structures, such as USTs.

GPR Transects 4-6 were performed across areas of suspected utilities (EM Anomalies 3, 4, and 5). GPR Transects 4 and 6 recorded small, low-amplitude anomalies, consistent with suspected utilities. GPR Transect 5 recorded minor reflectors that were suggestive of possible buried metallic debris. No evidence of any larger structures such as USTs was observed.

Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 18. **Figure 4** provides an overlay of the EM61 metal detection contour map onto the NCDOT MicroStation engineering plans for reference.

SUMMARY & CONCLUSIONS

Pyramid's evaluation of the EM61 and GPR data collected at Parcel 18 in Lumberton, North Carolina, provides the following summary and conclusions:

- The EM61 and GPR surveys provided reliable results for the detection of metallic USTs within the accessible portions of the geophysical survey area.
- The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface.
- Several EM anomalies were associated with suspected utilities and interference from vehicles and were further investigated with GPR.
- GPR recorded small, low-amplitude anomalies, consistent with suspected utilities. GPR also recorded minor reflectors that were suggestive of possible buried metallic debris. No evidence of any larger structures such as USTs was observed.
- Collectively, the geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 18.

LIMITATIONS

Geophysical surveys have been performed and this report was prepared for Falcon Engineers in accordance with generally accepted guidelines for EM61 and GPR surveys. It is generally recognized that the results of the EM61 and GPR surveys are non-unique and may not represent actual subsurface conditions. The EM61 and GPR results obtained for this project have not conclusively determined the definitive presence or absence of metallic USTs, but the evidence collected is sufficient to result in the conclusions made in this report. Additionally, it should be understood that areas containing extensive

vegetation, reinforced concrete, or other restrictions to the accessibility of the geophysical instruments could not be fully investigated.

APPROXIMATE BOUNDARIES OF GEOPHYSICAL SURVEY AREA



View of Survey Area
(Facing Approximately East)



View of Survey Area
(Facing Approximately South)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology

PROJECT
PARCEL 18
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 18 - GEOPHYSICAL
SURVEY BOUNDARIES AND SITE PHOTOGRAPHS

DATE
3/26/2019
PYRAMID
PROJECT #:
2019-091


CLIENT
FALCON ENGINEERS
FIGURE 1

EM61 METAL DETECTION RESULTS

NO EVIDENCE OF METALLIC
USTs OBSERVED.

The contour plot shows the differential results of the EM61 instrument in millivolts (mV). The differential results focus on larger metallic objects such as USTs and drums. The EM data were collected on March 18, 2019, using a Geonics EM61-MK2 instrument. Verification GPR data were collected using a GSSI UtilityScan DF instrument with a dual frequency 300/800 MHz antenna on March 26, 2019.

EM61 Metal Detection Response
(millivolts)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology


PROJECT
PARCEL 18
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 18 -
EM61 METAL DETECTION CONTOUR MAP


DATE
3/26/2019
PYRAMID
PROJECT #: 2019-091

CLIENT
FALCON ENGINEERS
FIGURE 2


LOCATIONS OF GPR TRANSECTS




GPR TRANSECT 1 (T1)




GPR TRANSECT 2 (T2)




GPR TRANSECT 3 (T3)



GPR TRANSECT 4 (T4)



GPR TRANSECT 5 (T5)



GPR TRANSECT 6 (T6)




503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology

PROJECT
PARCEL 18
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 18 -
GPR TRANSECT LOCATIONS AND IMAGES

DATE
3/26/2019
PYRAMID
PROJECT #:
2019-091

CLIENT
FALCON ENGINEERS
FIGURE 3






EM61 METAL DETECTION
CONTOURS (SEE FIGURE 2
FOR ANOMALY LABELS)

LEGEND

- EXISTING ROW
- EXISTING PROPERTY BOUNDARY
- PROPOSED ROW LINE
- TEMPORARY CONSTRUCTION EASEMENT
- PUE - PROPOSED PERMANENT UTILITY EASEMENT
- PROPOSED SS CUT LINE
- PROPOSED SS FILL LINE

MILLIVOLTS (mV)



TITLE OVERLAY OF METAL DETECTION RESULTS ON NCDOT ENGINEERING PLANS	
PROJECT PARCEL 018 LUMBERTON, NORTH CAROLINA NCDOT PROJECT U-5797	
 503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 336.335.3174 (p) 336.691.0648 (f) License # C1251 Eng. / #C257 Geology	
DATE: 04-11-2019	REVISION NO. 0
PYRAMID PROJECT NO. 2019-091	FIGURE NO. 4

PRELIMINARY SITE ASSESSMENT

**SR 1997 (FAYETTEVILLE ROAD) WIDENING
TIP NO. U-5797, WBS NO. 44367.1.1**

**NCDOT PARCEL NO. 19
OWNER LIDL US OPERATIONS LLC
2250 ROBERTS AVE
LUMBERTON, ROBESON COUNTY, NORTH CAROLINA**



PREPARED FOR:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
C/O STV ENGINEERS, INC.
1600 PERIMETER PARK DRIVE, SUITE 225
MORRISVILLE, NC 2756002

PREPARED BY:
FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
CARY, NC 27513

PROJECT NUMBER: G19011.00
JUNE 9, 2020





June 9, 2020

Mr. Patrick Livingston, PE
STV Engineers, Inc.
900 W. Trade St, Suite 715
Charlotte, NC 28202

Re: **Preliminary Site Assessment**
SR 1997 (Fayetteville Road) Widening
TIP No. U-5797, WBS No. 44367.1.1
Parcel No. 19
Owner: LIDL US Operations LLC
2250 Roberts Ave
Lumberton, Robeson County, North Carolina

Dear: Mr. Livingston:

Falcon is pleased to present the following Preliminary Site Assessment in support of the above-mentioned Project. Specifically, Falcon sampled soil in proximity to the project limits on this parcel in general accordance with the approved scope of work. Soils requiring remediation or special handling during construction were not identified.

Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

Please review this report and advise us if you have any questions or concerns. We appreciate this opportunity to provide services to you and look forward to partnering with you on future projects. If you have any questions, please give Falcon a call at (919) 871-0800.

Sincerely,

FALCON ENGINEERING, INC.

A handwritten signature in blue ink, reading "Christopher J. Burkhardt".

Christopher J. Burkhardt
Environmental Services Manager

A handwritten signature in blue ink, reading "Jeremy R. Hamm".

Jeremy R. Hamm, PE
Geotechnical Services Manager

TABLE OF CONTENTS

SECTION 1: INTRODUCTION	5
1.1 DESCRIPTION	5
1.2 SCOPE OF WORK.....	5
SECTION 2: HISTORY	6
2.1 PARCEL USAGE.....	6
2.2 FACILITY IDENTIFICATION NUMBER	6
2.3 GROUNDWATER INCIDENT NUMBER.....	6
SECTION 3: SITE OBSERVATIONS	7
3.1 GROUNDWATER MONITORING WELLS.....	7
3.2 ACTIVE USTS	7
3.3 FEATURES APPARENT BEYOND ROW/EASEMENT	7
SECTION 4: METHODOLOGY	8
4.1 GEOPHYSICS.....	8
4.2 BORINGS	8
4.3 SAMPLE PROTOCOL.....	8
SECTION 5: RESULTS.....	10
5.1 GEOPHYSICS	10
5.2 SAMPLE DATA	10
TABLE NO. 1 BORING COORDINATES.....	10
TABLE NO. 2 PID READINGS	10
TABLE NO. 3 SUMMARY OF UVF SOIL SAMPLING RESULTS	11
5.3 SAMPLE OBSERVATIONS.....	11
TABLE NO. 4 SOIL OBSERVATIONS.....	11
5.4 QUANTITIES CALCULATIONS	11
SECTION 6: CONCLUSIONS	12
6.1 INTERPRETATION OF RESULTS	12
6.2 GEOPHYSICS.....	12
6.3 SAMPLING	12
6.4 QUANTITIES	12
SECTION 7: RECOMMENDATIONS	13
7.1 ADDITIONAL SAMPLING	13
7.2 SPECIAL HANDLING OF IMPACTED SOIL.....	13



LIST OF FIGURES AND ATTACHMENTS

VICINITY MAP

USGS TOPOGRAPHIC MAP

PARCEL LOCATION MAP

BORING LOCATION MAP

AERIAL PHOTOGRAPHS

SITE PHOTOGRAPHS

UNDERGROUND STORAGE TANK DOCUMENTS

LABORATORY RESULTS

GEOPHYSICAL SURVEY



SECTION 1: INTRODUCTION

1.1 DESCRIPTION

Falcon Engineering, Inc. (Falcon) has completed a Preliminary Site Assessment of NCDOT TIP Project U-5797 Parcel No. 19. Parcel No. 19 is addressed as 2250 Roberts Ave, Lumberton, Robeson County, North Carolina. NCDOT is proposing to widen Fayetteville Road (SR 1997) from Farringdom Street to 22nd Street. The limits of the assessment are between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). Boring locations were placed in the vicinity of proposed excavations for drainage features, utilities, and roadway/ditch cuts to determine if soils requiring remediation or special handling were present where excavation was planned to take place.

1.2 SCOPE OF WORK

Falcon's scope of work included coordination of; public and private utility location near the proposed borings, geophysical surveys, collecting soil samples using direct push methods, and laboratory analysis. Samples were analyzed for petroleum hydrocarbons via UVF technology.



SECTION 2: HISTORY

2.1 PARCEL USAGE

Falcon performed a Phase I Environmental Site Assessment (ESA) for U-5797 under Project No. G17057 dated April 2018. The ESA identified this parcel as a Recognized Environmental Condition (REC) based on the history of the parcel and adjoining parcels. Falcon contacted Mr. Joe Oliver the County Fire Marshal during the ESA to inquire about known USTs along Fayetteville Road in the general area of Parcel No 19. Mr. Oliver sent documents pertaining to USTs that had been installed and/or removed from Baxley's addressed as Highway 211 East, and Taco Bell addressed as Fayetteville Road and Roberts Ave. The exact location of USTs associated with these facilities is not known. Historic air photographs dated 1976 through 2000 show Parcel No. 19 as mostly parking lot with a large commercial building. UST closure documentation including soil sampling results were not available for review.

2.2 FACILITY IDENTIFICATION NUMBER

A Facility Identification Number was not identified for this parcel.

2.3 GROUNDWATER INCIDENT NUMBER

A Groundwater Incident Number was not identified for this parcel.

SECTION 3: SITE OBSERVATIONS

3.1 GROUNDWATER MONITORING WELLS

Groundwater monitoring wells (MWs) were not observed on this parcel.

3.2 ACTIVE USTS

Active USTs were not observed within the project limits or registered at this parcel.

3.3 FEATURES APPARENT BEYOND ROW/EASEMENT

USTs, monitoring wells, remediation systems, or hydraulic lifts were not observed.

SECTION 4: METHODOLOGY

4.1 GEOPHYSICS

Pyramid Geophysical Services (Pyramid) was subcontracted to perform a geophysical survey of the assessment area. The assessment area is between the existing edge of NCDOT maintained pavement (within the existing NCDOT ROW) where accessible, and the proposed NCDOT ROW and/or easement (whichever boundary represents the largest area). The survey was used to locate private utility lines, as well as possible indications of USTs, and/or their pits.

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is georeferenced and can be overlain on aerial photographs and CADD drawings.

GPR data was acquired across select EM anomalies (where identified), using a Geophysical Survey Systems, Inc. (GSSI) UtilityScan DF unit equipped with a dual frequency 300/800 MHz antenna. Pyramid marked their findings on the surface with paint. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and to obtain adequate coverage. A copy of the full Geophysical Report is included in the Attachments.

4.2 BORINGS

Regional Probing was subcontracted to advance soil borings using direct push technology. Regional Probing used a truck-mounted Geoprobe® 5410 unit mounted on an off-road modified Ford F350 Diesel 4x4. The unit has auger-capabilities and is equipped with a GH-42 soil-probing hammer, with 21,700 pounds of down force and 28,900 pounds of retraction force. The unit has an on-board tank for decontaminating the geoprobe rods before advancing the probe at each sample location.

4.3 SAMPLE PROTOCOL

Prior to initiating sample collection Falcon contacted NC One Call and requested public utility locations be marked around the proposed sample locations. Sampling was in general accordance with the NC Department of Environmental Quality (DEQ) Division of Waste Management's (DWM) "Guidelines for Site Checks, Tank Closure, and Initial Response and Abatement for UST Releases" (March 1, 2007 Version Change 9 – February 1, 2019) guidance document. Sampling strategy was derived based upon the project scope and objectives as outlined above. Red Lab, LLC was selected to perform the UVF laboratory analytical analysis. Appropriate sterile containers were received by Falcon from Red Lab prior to beginning the fieldwork. The containers were labeled appropriately.

A Minirae 3000 photoionization detector (PID) was used to field screen samples for volatile organics to determine if a release had occurred. The instrument was calibrated per manufacturer instructions prior to use. Falcon staff bagged composite soil samples of each boring in approximately two-foot sections. Representative samples were placed in a sealed plastic bag for approximately 10 minutes to allow soil hydrocarbons to reach equilibrium within the headspace prior to scanning with the PID. One sample per boring was collected from the depth of the proposed cut or from the section above the depth of cut with the highest PID reading.

To avoid cross contamination, a new unused pair of non-powdered nitrile gloves was worn while extracting each sample. Samples were placed in the appropriate laboratory provided containers. The labels on each container were then completed so that each provided the date and time of sampling, method of analysis, sample collector, preservative used and sampling location identification. Samples were placed in an ice filled cooler and transported to the lab. Appropriate chain-of-custody procedures, including the completion of necessary forms, were followed.

SECTION 5: RESULTS

5.1 GEOPHYSICS

The geophysical investigation was performed between March 8 and 19, 2019 to investigate for metallic underground storage tanks (USTs) beneath the survey area. A total of six EM anomalies were identified. All of the EM anomalies were directly attributed to visible cultural features at the ground surface; therefore a GPR survey was not required. The geophysical data did not record any evidence of metallic USTs within the geophysical survey area at Parcel No. 19.

5.2 SAMPLE DATA

Falcon and our subcontractor advanced three borings (B-25, B-26, B-27) to the proposed excavation depth of the drainage features, utilities, or roadway/ditch cut being assessed. Groundwater was not observed. Please see the Boring Layout Plan in the attachments for a visual depiction of the sample locations. The coordinates (latitude and longitude) that correspond to the sample locations are shown below in Table No. 1 Boring Coordinates.

TABLE NO. 1 BORING COORDINATES

Boring	Latitude	Longitude
B-25	34.6399544	-79.0028739
B-26	34.6398230	-79.0025231
B-27	34.6396857	-79.0020726

Borings were field screened with a PID in sections for evidence of volatile organics. The PID screening results are presented in Table No. 2 PID Readings. Falcon selected soil samples based on the field screening results and the needs of the project. Red Lab analyzed the selected samples and their full analytical report is attached. The results of the laboratory analysis are shown in Table No. 3 Summary of UVF Soil Sampling Results.

Petroleum hydrocarbons above State Action Levels were not detected in the samples.

TABLE NO. 2 PID READINGS

Boring	Depth BGS*	PID**
B-25	0-2.0	0.5
	2.0-4.0	1.2
B-26	0-2.0	0.9
	2.0-4.0	1.1
B-27	0-2.0	0.8
	2.0-4.0	0.9

*BGS = Depth below ground surface in feet

**PID readings are in parts per million

Samples shown in **bold** were selected for analysis

TABLE NO. 3 SUMMARY OF UVF SOIL SAMPLING RESULTS

Sample ID	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios			HC Fingerprint Match
								% light	% mid	% heavy	
B-25	<0.28	<0.28	21.8	21.8	11.1	0.6	<0.011	0	88.6	11.4	Deg Fuel 77.1%,(FCM) (BO)
B-26	<0.26	<0.26	26.6	26.6	12.7	1.4	0.028	0	92.2	7.8	Road Tar 75.1%,(FCM) (BO)
B-27	<0.56	<0.56	7.6	7.6	6.2	0.34	<0.022	0	85.9	14.1	Deg Fuel 90.5%,(FCM)

Results reported in mg/kg (milligrams per kilogram)

5.3 SAMPLE OBSERVATIONS

Obvious visual indications of a release (stained soils, odors, or oily sheen) were not observed. Table No. 4 Soil Observations lists visual soil observations of color and texture.

TABLE NO. 4 SOIL OBSERVATIONS

Sample ID	Depth	Color	Soil Type
B-25	0-2.0	Gray	Silty Clayey Sand (A-2-6)
	2.0-4.0	Gray Brown	Silty Clayey Sand (A-2-6)
B-26	0-2.0	Gray Brown	Silty Sandy Clay (A-6)
	2.0-4.0	Brown Gray	Silty Sandy Clay (A-6)
B-27	0-2.0	Brown Orange	Silty Clayey Sand (A-2-6)
	2.0-4.0	Gray Brown	Silty Clayey Sand (A-2-6)

Depth is in feet below ground surface

5.4 QUANTITIES CALCULATIONS

Soils requiring quantity calculations were not identified.

SECTION 6: CONCLUSIONS

6.1 INTERPRETATION OF RESULTS

This Preliminary Site Assessment was performed to evaluate the soils in proximity to the project limits on this parcel for the presence of petroleum hydrocarbons. The findings are as follows:

- Soil sampling completed on the parcel did not identify contaminants in the soil at levels requiring remediation.

6.2 GEOPHYSICS

The Geophysics report did not identify probable or potential USTs within the project limits on this parcel. Falcon does not anticipate USTs will be encountered within the project limits on this parcel during construction.

6.3 SAMPLING

Sampling results did not identify contaminants in the soil which require remediation in the areas sampled. Based on past project experience, Falcon does not anticipate soil remediation or special handling and disposal will be required during construction on this parcel.

6.4 QUANTITIES

Soils requiring quantities calculations were not identified.



SECTION 7: RECOMMENDATIONS


7.1 ADDITIONAL SAMPLING

Contaminants above the Industrial / Commercial Soil Cleanup Levels were not identified; therefore, additional assessment is not warranted at this time. Falcon recommends if drums, USTs, above ground storage tanks (ASTs), petroleum odors or sheen are observed during any excavation associated with any property involved in the project that all work in the vicinity stop until further assessment takes place. Further assessment can include but is not limited to; sampling the soil and groundwater, excavation, and proper handling and disposal of contaminated soils and groundwater.

7.2 SPECIAL HANDLING OF IMPACTED SOIL

Soils requiring special handling were not identified. If suspect contaminated soils are encountered during construction Falcon and the NCDOT GeoEnvironmental Group should be contacted for proper handling instructions.

NCDOT U-5797 (SR 1997 Widening) Parcel 19
Preliminary Site Assessment
Vicinity Map




Project No.: G19011.00
Date: September 2019
Source: Google Maps

NCDOT U-5797 (SR 1997 Widening) Parcel 19

Preliminary Site Assessment

USGS Topographic Maps



Project No.: G19011.00
Date: September 2019
Source: "NW, NE, SW, and SE Lumberton, NC" 2019



NCDOT U-5797 (SR 1997 Widening) Parcel 19


Preliminary Site Assessment

Parcel Location Map



September 5, 2019

-  County Line
-  City Limits
-  Streets
-  Parcels



Esri, HERE, Garmin, (c) OpenStreetMap contributors, and the GIS user community
Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Project No.: G19011.00
Date: September 2019
Source: Robeson County GIS


NAD 83/ NSRS 2007

20

LIDL US OPERATIONS LLC

LIMITS AREA OF GEOPHYSICAL EXPLORATION

NS LLC



NOTES:


- BGS = BELOW GROUND SURFACE
- BORINGS B-25 & B-27 WERE DRILLED TO 4.0 BGS



FALCON ENGINEERING, INC.
1210 TRINITY ROAD, SUITE 110
RALEIGH, NC 27607
PHONE: 919.871.0800
FAX: 919.871.0803

BORING LOCATION PLAN

NCDOT U-5797 (SR 1997 WIDENING)
PARCEL 19 - LIDL US OPERATIONS LLC
ROBESON / LUMBERTON, NC
WBS NO.: 44367.1.1 & TIP NO.: U-5797
FALCON PROJECT NO. G19011.00



NCDOT U-5797 (SR 1997 Widening) Parcel 19
Preliminary Site Assessment
1990 Aerial Photograph



Project No.: G19011.00
Date: September 2019
Source: NCDOT Historical Aerial Imagery Index

NCDOT U-5797 (SR 1997 Widening) Parcel 19
Preliminary Site Assessment
1985 Aerial Photograph



Project No.: G19011.00
Date: September 2019
Source: NCDOT Historical Aerial Imagery Index

NCDOT U-5797 (SR 1997 Widening) Parcel 19
Preliminary Site Assessment
1976 Aerial Photograph



Project No.: G19011.00
Date: September 2019
Source: ERIS Aerial Photographs

NCDOT U-5797 (SR 1997 Widening) Parcel 19
Preliminary Site Assessment
Site Photographs



Photograph No. 1: General view of Boring B-25.



Photograph No. 2: General view of Boring B-26.

NCDOT U-5797 (SR 1997 Widening) Parcel 19
Preliminary Site Assessment
Site Photographs



Photograph No. 3: General view of Boring B-27.

DIVISION OF ENVIRONMENTAL MANAGEMENT

June 26, 1991

Mr. Sam Everett
1203 East 11th Street
Lumberton, NC 28358

SUBJECT: Review of Lab Results
UST Soil Assessment
Oscar Baxley Grocery
Highway 211 - East
Lumberton, Robeson County

Dear Mr. Everett:

This is to acknowledge receipt of the above mentioned soil assessment dated June 14, 1991.

Based on review of the lab results, no additional soil excavation and removal is required. Should new information become available concerning this matter, we reserve the right to reverse this finding.

Should you have any questions or need clarification, please contact Mrs. Cindy Hegg of this office at (919) 486-1541.

Sincerely,

original signed by

[Signature]
M. J. Noland, P.E.
Regional Supervisor

C.H/
MJN/CH/gc

Site Investigation Report For Permanent Closure of U.S.T.

FOR TANKS IN NC	Return Completed Form To: The appropriate DEM Regional Office according to the county of the facility's location. [SEE MAP ON REVERSE SIDE OF OWNER'S COPY (BLUE) FOR REGIONAL OFFICE ADDRESS].	Sate Use Only I.D. Number _____ Date Received _____
--------------------------	--	---

INSTRUCTIONS

Please complete and return within (30) days following completion of site investigation.

I. Ownership of Tank(s)	II. Location of Tank(s)
Owner Name (Corporation, Individual, Public Agency, or Other Entity) <i>Pauline Barker Everett</i>	Facility Name or Company <i>Oscar Barker Grocery</i>
Street Address <i>1203 East 11th Street</i>	Facility ID # (if available) <i>None</i>
City <i>Robeson</i>	Street Address or State Road <i>1203 East 11th Street</i>
County <i>Lumberton NC</i>	City <i>Robeson Lumberton</i>
Zip Code <i>28358</i>	Zip Code <i>28358</i>
Area Code <i>919</i>	Area Code <i>None</i>
Telephone Number <i>738-5863</i>	Telephone Number <i>None</i>

III. Contact Person

Name <i>Sam Everett</i>	Job Title <i>Husband of owner</i>	Telephone Number <i>(919) 738-5863</i>
Closure Contractor <i>Floyd Grading Co</i>	<i>PO Box 3107 Lumberton NC 28359</i>	
Lab <i>Oxford Laboratories Inc</i>	<i>1316 South 5th Street Wilmington, NC 28401</i>	

IV. U.S.T. Information				V. Excavation Condition				VI. Additional Information Required	
Tank No.	Size in Gallons	Tank Dimensions	Last Contents	Water In Excavation		Free Product		Notable Odor or Visible Soil Contamination	
				Yes	No	Yes	No	Yes	No
1	550	42" x 7'6"	GAS		✓		✓		✓
2	550	42" x 7'6"	GAS		✓		✓		✓

See reverse side of blue copy (owner's copy) for additional information required by N.C. - DEM in the written report and sketch.

VII. Check List

Check the activities completed.

- ☒ Contact local fire marshal
 - ☒ Notify DEM Regional Office before abandonment.
 - ☒ Drain & flush piping into tank.
 - ☒ Remove all product and residuals from tank
 - ☒ Excavate down to tank.
 - ☒ Clean and inspect tank.
 - ☒ Remove drop tube, fill pipe, gauge pipe, vapor recovery tank connections, submersible pumps and other tank fixtures.
 - ☒ Cap or plug all lines except the vent and fill lines.
 - ☒ Purge tank of all product & flammable vapors.
 - ☒ Cut one or more large holes in the tanks.
 - ☒ Backfill the area.
- Date Tank Permanently closed: *5/23/91*

- ABANDONMENT IN PLACE**
- ☐ Fill tank until material overflows tank opening;
 - ☐ Plug or cap all openings;
 - ☐ Disconnect and cap or remove vent line
 - ☐ Solid inert material used - please specify: _____

- REMOVAL**
- ☒ Create vent hole
 - ☒ Label tank
 - ☒ Dispose of tank in approved manner
 - Final tank destination: *Floyd Grading Co*

VIII. Certification (Read and Sign)

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete.

Print name and official title of owner or owner's authorized representative <i>Sam Everett</i>	Signature <i>Sam Everett</i>	Date Signed <i>5/23/91</i>
---	---------------------------------	-------------------------------

Notice of Intent: UST Permanent Closure or Change-in-Service

FOR
TANKS
IN
NC

Return Completed Form To:

The appropriate DEM Regional Office according to the county of the facility's location. [SEE REVERSE SIDE OF OWNER'S COPY (BLUE) FOR REGIONAL OFFICE ADDRESS].

State Use Only

I. D. Number _____

Date Received _____

INSTRUCTIONS

Complete and return thirty (30) days prior to closure or change-in-service.

I. OWNERSHIP OF TANK(S)

Tank Owner Name: Pauline Bunley Everett
(Corporation, Individual, Public Agency, or Other Entity)

Street Address: 1203 East 11th Street

County: Robeson

City: Lumberton State: NC Zip Code: 28358

Tele. No. (Area Code): 919-738-5863

II. LOCATION OF TANK(S)

Facility Name or Company: Oscar Bunley Grocery

Facility ID # (if available): None

Street Address or State Road: Highway 211 - East

County: Robeson City: Lumberton Zip Code: 28358

Tele. No. (Area Code): None

III. CONTACT PERSON

Name: Sam Everett Job Title: Husband Telephone Number: 919, 738-5863

IV. TANK REMOVAL, CLOSURE IN PLACE, CHANGE-IN-SERVICE

1. Contact Local Fire Marshall.
2. Plan the entire closure event.
3. Conduct Site Soil Assessments.
4. If Removing Tanks or Closing in Place refer to API Publications. 2015 "Cleaning Petroleum Storage Tanks" & 1604 "Removal & Disposal of Used Underground Petroleum Storage Tanks".

5. Provide a sketch locating piping, tanks and soil sampling locations.
6. Fill out form GW/UST-2 "Site Investigation Report for Permanent Closure" and return within 30 days following the site investigation.
7. Keep records for 3 years.

V. WORK TO BE PERFORMED BY:

(Contractor) Name: Floyd Grading Co.

Address: P.O. Box 3197 Lumberton State: N.C.

Zip Code: 28359

Contact: Calvin F. Floyd Phone: Office 671-1177

VI. TANK(S) SCHEDULED FOR CLOSURE OR CHANGE-IN-SERVICE

TANK ID#	TANK CAPACITY	LAST CONTENTS	PROPOSED ACTIVITY		
			CLOSURE		CHANGE-IN-SERVICE
			Removal	Abandonment In Place	New Contents Stored
<u>1</u>	<u>550</u>	<u>GAS</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<u>2</u>	<u>550</u>	<u>GAS</u>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	
			<input type="checkbox"/>	<input type="checkbox"/>	

VII. OWNER OR OWNER'S AUTHORIZED REPRESENTATIVE

Print name and official title

Sam Everett - Owner

*Scheduled Removal Date: 5/23/91

Signature: Sam Everett

Date Submitted: 5/23/91

*If scheduled work date changes, notify your appropriate DEM Regional Office 48 hours prior to originally scheduled date.

APPLICATION TO USE, INSTALL, CONDUCT PROCESSES OR
CARRY ON OPERATIONS INVOLVING OR CREATING CONDI-
TIONS DEEMED HAZARDOUS TO LIFE OR PROPERTY

10-14-83
Date

To Chief of Fire Department, City of Lumberton, N. C.

Application is hereby made by the undersigned for a Permit to

Use
Install
Operate
Conduct

in or on the premises known as TACO-BELL / FAYETTEVILLE ROAD + ROBERTS ~~Street~~ or Avenue
the following materials, processes or operations.

(Describe briefly what is to be done and state what hazardous materials are to be used.)

FOR THE REMOVAL OF 4 - 4000 GALLON

UNDERGROUND GASOLINE STORAGE TANKS.

#12-83

Conditions, surroundings and arrangements to be in accordance with the Fire Prevention Ordinance.

This application ^{is} ~~is not~~ approved insofar
as Zoning and Building Ordinances are
concerned.

Inspector of Buildings

C. M. Lumberton Jr.
Name of Applicant

P.O. Box 1887
Lumberton N.C.
Address of Applicant

Complete plans and construction details must be filed on all major projects and when requested by the chief of the fire department.



Hydrocarbon Analysis Results

Client: FALCON
Address: 1210 TRINITY ROAD SUITE 116
CARY NC 28513

Samples taken Tuesday, April 9, 2019
Samples extracted Tuesday, April 9, 2019
Samples analysed Tuesday, April 16, 2019




Contact: CHRISTOPHER BURKHARDY

Operator DAVIS MARTINEC

Project: G19011 U5797

													U00902
Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	% Ratios			HC Fingerprint Match
										C5 - C10	C10 - C18	C18	
s	B25	11.1	<0.28	<0.28	21.8	21.8	11.1	0.6	<0.011	0	88.6	11.4	Deg Fuel 77.1%,(FCM),(BO)
s	B26	10.4	<0.26	<0.26	26.6	26.6	12.7	1.4	0.028	0	92.2	7.8	Road Tar 75.1%,(FCM),(BO)
s	B27	22.4	<0.56	<0.56	7.6	7.6	6.2	0.34	<0.022	0	85.9	14.1	Deg Fuel 90.5%,(FCM)
Initial Calibrator QC check										OK			102.5 %

Concentration values in mg/kg for soil samples and mg/L for water samples. Soil values uncorrected for moisture or stone content. Fingerprints provide a tentative hydrocarbon identification.
Abbreviations :- FCM = Results calculated using Fundamental Calibration Mode : % = confidence of hydrocarbon identification : (PFM) = Poor Fingerprint Match : (T) = Turbid : (P) = Particulate detected
B = Blank Drift : (SBS)/(LBS) = Site Specific or Library Background Subtraction applied to result : (BO) = Background Organics detected : (OCR) = Outside cal range : (M) = Modified Result.
% Ratios estimated aromatic carbon number proportions : HC = Hydrocarbon : PHC = Petroleum HC : FP = Fingerprint only. **Data generated by HC-1 Analyser**





PYRAMID GEOPHYSICAL SERVICES
(PROJECT 2019-091)

GEOPHYSICAL SURVEY

METALLIC UST INVESTIGATION: PARCEL 19 NCDOT PROJECT U-5797

HIGHWAY 211 EAST, LUMBERTON, NC

APRIL 22, 2019

Report prepared for: Christopher J. Burkhardt, PWS
Falcon Engineers
1210 Trinity Rd. #110
Raleigh, NC 27607

Prepared by: _____

A handwritten signature in black ink, appearing to read "E. Cross".

Eric C. Cross, P.G.
NC License #2181

Reviewed by: _____

A handwritten signature in black ink, appearing to read "Doug Canavella".

Douglas A. Canavella, P.G.
NC License #1066

503 INDUSTRIAL AVENUE, GREENSBORO, NC 27406

P: 336.335.3174 F: 336.691.0648

C257: GEOLOGY

C1251: ENGINEERING

GEOPHYSICAL INVESTIGATION REPORT
Parcel 19 - Highway 211 East
Lumberton, Robeson County, North Carolina

Table of Contents

Executive Summary	1
Introduction.....	Error! Bookmark not defined.
Field Methodology.....	2
Discussion of Results.....	3
<i>Discussion of EM Results</i>	3
Summary & Conclusions	4
Limitations	5

Figures

- Figure 1 – Parcel 19 - Geophysical Survey Boundaries and Site Photographs
Figure 2 – Parcel 19 - EM61 Results Contour Map
Figure 3 – Parcel 19 - Overlay of Metal Detection Results on NCDOT Engineering Plans

LIST OF ACRONYMS

CADD	Computer Assisted Drafting and Design
DF	Dual Frequency
EM.....	Electromagnetic
GPR.....	Ground Penetrating Radar
GPS	Global Positioning System
NCDOT.....	North Carolina Department of Transportation
ROW	Right-of-Way
UST	Underground Storage Tank

EXECUTIVE SUMMARY

Project Description: Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 19, located on Highway 211 East in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-19, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

Geophysical Results: The geophysical investigation consisted of an electromagnetic (EM) induction-metal detection survey. A total of six EM anomalies were identified. All of the EM anomalies were directly attributed to visible cultural features at the ground surface; therefore, a GPR survey was not required. The geophysical data did not record any evidence of metallic USTs within the geophysical survey area at Parcel 19.

INTRODUCTION

Pyramid Environmental conducted a geophysical investigation for Falcon Engineers at Parcel 19, located on Highway 211 East in Lumberton, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project U-5797). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from March 18-19, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

The site included asphalt parking areas and grass medians near a commercial restaurant building. An aerial photograph showing the survey area boundaries and ground-level photographs are shown in **Figure 1**.

FIELD METHODOLOGY

The geophysical investigation consisted of an electromagnetic (EM) induction-metal detection survey. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is geo-referenced and can be overlain on aerial photographs and CADD drawings. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and assure complete coverage of the area.

According to the instrument specifications, the EM61 can detect a metal drum down to a maximum depth of approximately 8 feet. Smaller objects (1-foot or less in size) can be detected to a maximum depth of 4 to 5 feet. The EM61 data were digitally collected at approximately 0.8-foot intervals along north-south trending or east-west trending, generally parallel survey lines, spaced five feet apart. The data were downloaded to a

computer and reviewed in the field and office using the Geonics NAV61 and Surfer for Windows Version 15.0 software programs.

GPR data were not required due to all EM anomalies being directly attributed to visible cultural features at the ground surface (See *Discussion of Results* section below).

Pyramid's classifications of USTs for the purposes of this report are based directly on the geophysical UST ratings provided by the NCDOT. These ratings are as follows:

Geophysical Surveys for Underground Storage Tanks on NCDOT Projects			
High Confidence	Intermediate Confidence	Low Confidence	No Confidence
Known UST Active tank - spatial location, orientation, and approximate depth determined by geophysics.	Probable UST Sufficient geophysical data from both magnetic and radar surveys that is characteristic of a tank. Interpretation may be supported by physical evidence such as fill/vent pipe, metal cover plate, asphalt/concrete patch, etc.	Possible UST Sufficient geophysical data from either magnetic or radar surveys that is characteristic of a tank. Additional data is not sufficient enough to confirm or deny the presence of a UST.	Anomaly noted but not characteristic of a UST. Should be noted in the text and may be called out in the figures at the geophysicist's discretion.

DISCUSSION OF RESULTS

Discussion of EM Results

A contour plot of the EM61 results obtained across the survey area at the property is presented in **Figure 2**. Each EM anomaly is numbered for reference in the figure. The following table presents the list of EM anomalies and the cause of the metallic response, if known:

LIST OF METALLIC ANOMALIES IDENTIFIED BY EM SURVEY

Metallic Anomaly #	Cause of Anomaly	Investigated with GPR
1	Fence	
2	Sign	
3	Surface Metal	
4	Utility	
5	Utility	
6	Sign	

All of the EM anomalies were directly attributed to visible cultural features at the ground surface, including a fence, signs, surface metal, and utilities. Therefore, a GPR survey was not required.

The geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 19. **Figure 3** provides an overlay of the EM61 metal detection contour map onto the NCDOT MicroStation engineering plans for reference.

SUMMARY & CONCLUSIONS

Pyramid's evaluation of the EM61 data collected at Parcel 19 in Lumberton, North Carolina, provides the following summary and conclusions:

- The EM61 survey provided reliable results for the detection of metallic USTs within the accessible portions of the geophysical survey area.
- All of the EM anomalies were directly attributed to visible cultural features at the ground surface; therefore, a GPR survey was not required.
- The geophysical data did not record any evidence of unknown metallic USTs within the geophysical survey area at Parcel 19.

LIMITATIONS

Geophysical surveys have been performed and this report was prepared for Falcon Engineers in accordance with generally accepted guidelines for EM61 surveys. It is generally recognized that the results of the EM61 surveys are non-unique and may not represent actual subsurface conditions. The EM61 results obtained for this project have not conclusively determined the definitive presence or absence of metallic USTs, but the evidence collected is sufficient to result in the conclusions made in this report. Additionally, it should be understood that areas containing extensive vegetation, reinforced concrete, or other restrictions to the accessibility of the geophysical instruments could not be fully investigated.

APPROXIMATE BOUNDARIES OF GEOPHYSICAL SURVEY AREA



View of Survey Area
(Facing Approximately North)



View of Survey Area
(Facing Approximately West)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology

PROJECT
PARCEL 19
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 19 - GEOPHYSICAL
SURVEY BOUNDARIES AND SITE PHOTOGRAPHS

DATE
3/26/2019
PYRAMID
PROJECT #:
2019-091

CLIENT
FALCON ENGINEERS
FIGURE 1


EM61 METAL DETECTION RESULTS

NO EVIDENCE OF METALLIC
USTs OBSERVED.

The contour plot shows the differential results of the EM61 instrument in millivolts (mV). The differential results focus on larger metallic objects such as USTs and drums. The EM data were collected on March 18-19, 2019, using a Geonics EM61-MK2 instrument. All of the EM anomalies were associated with surface features and verification GPR was not necessary.



EM61 Metal Detection Response
(millivolts)



503 INDUSTRIAL AVENUE
GREENSBORO, NC 27406
(336) 335-3174 (p) (336) 691-0648 (f)
License # C1251 Eng. / License # C257 Geology


PROJECT
PARCEL 19
LUMBERTON, NORTH CAROLINA
NCDOT PROJECT U-5797

TITLE
PARCEL 19 -
EM61 METAL DETECTION CONTOUR MAP

DATE
3/26/2019
PYRAMID
PROJECT #: 2019-091




CLIENT
FALCON ENGINEERS
FIGURE 2

CUL1	323752.0	NORT
CUL2	323748.0	
CUL3	323747.8	
CUL4	323743.4	
CE1	323745.9	
HW1	323747.8	
CUL5	323871.6	
CUL6	323875.7	
CUL7	323876.0	
CUL8	323880.2	
CE2	323873.5	
HW2	323875.7	



LEGEND

- EXISTING ROW
- EXISTING PROPERTY BOUNDARY
- PROPOSED ROW LINE
- TEMPORARY CONSTRUCTION EASEMENT
- PROPOSED PERMANENT UTILITY EASEMENT
- PROPOSED SS CUT LINE
- PROPOSED SS FILL LINE



TITLE OVERLAY OF METAL DETECTION RESULTS ON NCDOT ENGINEERING PLANS	
PROJECT PARCEL 019 LUMBERTON, NORTH CAROLINA NCDOT PROJECT U-5797	
 503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 336.335.3174 (p) 336.691.0648 (f) License # C1251 Eng. / #C257 Geology	
DATE: 04-11-2019	REVISION NO. 0
PYRAMID PROJECT NO. 2019-091	FIGURE NO. 3