

7/21/2025
D:\AECOM\nc-pw-bentl\ey-com-AECOM\USA_North_Carol\nc\document\460598150-NCDDT-SMU_B-4838#00-CAD_015#910-CAD#70-NCDDT-TIP#Traffic#51.gns\B-4838_scp_dsh_1.dgn
T:\ndm

- 1

INSTALL COAX CABLE
- 2

INSTALL ETHERNET CABLE
- 3

EXISTING ETHERNET (OR COAX) CABLE
- 4

INSTALL SMFO CABLE
- 5

EXISTING SMFO CABLE
- 6

INSTALL FIBER OPTIC DROP CABLE
- 7

INSTALL TRACER WIRE
- 8

TRENCH
- 9

INSTALL PVC CONDUIT
- 10

INSTALL RIGID, GALVANIZED STEEL CONDUIT
- 11

INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
- 12

INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL
- 13

INSTALL OUTER-DUCT POLYETHYLENE CONDUIT
- 14

INSTALL POLYETHYLENE CONDUIT
- 15

DIRECTIONAL DRILL CONDUIT
- 16

BORE AND JACK CONDUIT
- 17

INSTALL CABLE(S) IN EXISTING CONDUIT
- 18

INSTALL CABLE(S) IN NEW CONDUIT
- 19

INSTALL CABLE(S) IN EXISTING RISER
- 20

INSTALL CABLE(S) IN NEW RISER
- 21

INSTALL CABLE(S) IN EXISTING CONDUIT STUB-OUTS
- 22

INSTALL NEW CONDUIT INTO EXISTING CABINET BASE
(USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 23

INSTALL NEW RISER INTO EXISTING CABINET BASE
(USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 24

INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET
- 25

INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET
- 26

INSTALL NEW ETHERNET EDGE SWITCH
- 27

INSTALL NEW FIBER OPTIC TRANSCEIVER
- 28

INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS
AND FUSION SPlice CABLE IN CABINET
- 29

INSTALL UNDERGROUND SPlice ENCLOSURE
- 30

INSTALL AERIAL SPlice ENCLOSURE
- 31

MODIFY EXISTING INTERCONNECT CENTER /SPlice ENCLOSURE
- 32

INSTALL POLE MOUNTED SPlice CABINET
- 33

INSTALL BASE MOUNTED SPlice CABINET

- 34

INSTALL CABINET FOUNDATION
- 35

INSTALL CCTV CAMERA POLE MOUNTED CABINET
- 36

INSTALL CCTV CAMERA ASSEMBLY
- 37

INSTALL CCTV CAMERA WOOD POLE
- 38

INSTALL CCTV CAMERA METAL POLE AND FOUNDATION
- 39

INSTALL JUNCTION BOX
- 40A

INSTALL OVERSIZED JUNCTION BOX(ES)
- 40B

INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" x 24" x 24")
- 41

REMOVE EXISTING JUNCTION BOX
- 42

INSTALL WOOD POLE
- 43

REMOVE EXISTING WOOD POLE
- 44

INSTALL AERIAL GUY ASSEMBLY
- 45

INSTALL STANDARD GUY ASSEMBLY
- 46

INSTALL SIDEWALK GUY ASSEMBLY
- 47

INSTALL MESSENGER CABLE
- 48A

REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE
- 48B

REMOVE EXISTING COMMUNICATIONS CABLE
- 49

BACK PULL EXISTING COMMUNICATIONS CABLE
- 50

INSTALL CELL MODEM AND ANTENNA
- 51

INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE
100 FEET OF CABLE
- 52A

INSTALL DELINEATOR MARKER
- 52B

INSTALL JUNCTION BOX MARKER
- 53A

STORE 20 FEET OF COMMUNICATIONS CABLE
- 53B

STORE 50 FEET OF EACH COMMUNICATIONS CABLE
- 54

LASH CABLE(S) TO EXISTING COMMUNICATIONS CABLE
- 55

LASH CABLE(S) TO EXISTING MESSENGER CABLE
- 56

LASH CABLE(S) TO NEW MESSENGER CABLE
- 57

MODIFY EXISTING ELECTRICAL SERVICE
- 58

INSTALL NEW ELECTRICAL SERVICE
- 59

INSTALL NEW EQUIPMENT CABINET DISCONNECT
- 60

BOND TRACER WIRE TO EQUIPMENT
GROUND BUS
DO NOT BOND TRACER WIRE TO
EQUIPMENT GROUND BUS
BOND RISER AND MESSENGER CABLE
TO POLE GROUND
- 61

DO NOT BOND TRACER WIRE TO
EQUIPMENT GROUND BUS
- 62

BOND RISER AND MESSENGER CABLE
TO POLE GROUND
- 63

BOND RISER TO POLE GROUND
- 64

BOND MESSENGER CABLE TO POLE GROUND
- 65

INSTALL HEAT SHRINK TUBING RETROFIT KIT
- 66

INSTALL MOLDABLE DUCT SEAL(S)
- 67

SLACK SPAN

ATTACHMENT POINT:

XX"SS
YYY

DISTANCE ABOVE (IN)/ATTACHMENT POINT
REFERENCE POINT

YYY
XX"SS

REFERENCE POINT
DISTANCE BELOW (IN)/ATTACHMENT POINT

"SS" REFERENCE LOCATION

FS = FRONT SIDE OF POLE
BS = BACK SIDE OF POLE

LEGEND	
	NEW FIBER OPTIC COMMUNICATIONS CABLE
	EXISTING COMMUNICATIONS CABLE
	EXISTING COMMUNICATIONS CABLE TO BE REMOVED
	NEW AERIAL GUY ASSEMBLY
	NEW CONDUIT
	EXISTING CONDUIT
	NEW DIRECTIONAL DRILLED CONDUIT

NEW		EXISTING
	CITY OF GOLDSBORO JUNCTION BOX	
	OVERSIZED JUNCTION BOX	
	WOOD POLE	
	CITY OF GOLDSBORO AERIAL SPlice ENCLOSURE	
	AERIAL SPlice ENCLOSURE	
	UNDERGROUND SPlice ENCLOSURE	
	METAL POLE	
	CCTV ASSEMBLY	
	STANDARD GUY ASSEMBLY	
	SIDEWALK GUY ASSEMBLY	
	CABLE STORAGE RACKS (SNOW SHOES)	
	SIGNAL/EQUIPMENT CABINET	
	SPlice CABINET	
	FLAT PANEL ANTENNA (SINGLE)	
	YAGI ANTENNA (DOUBLE) FOR REPEATER OPERATION	
	YAGI ANTENNA (SINGLE)	
	OMNI ANTENNA	
	SIGNAL POLE	
	SIGNAL INVENTORY NUMBER	

CONSTRUCTION NOTE SYMBOLOGY KEY

XX

INDICATES NUMBER OF CABLES, LOOPS, ETC.

XX

INDICATES NUMBER OF FIBERS PER CABLE,
TWISTED PAIRS PER CABLE, ETC.

XX

INDICATES NUMBER OF RISER(S)/CONDUIT(S)

XX

INDICATES DIAMETER OF RISER(S)/CONDUIT(S) (INCH)

NUMBER OF CABLE(S)

NUMBER OF FIBERS/TWISTED PAIRS

NEW/EXISTING CABLE

REMOVE/MODIFY CABLE

CONDUIT/RISER

NUMBER OF RISER(S)/CONDUIT(S)

DIAMETER OF RISER(S)/CONDUIT(S) (INCH)

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

AECOM

NC Firm License No.: F-0342
5438 Wade Park Boulevard
Suite 200 Raleigh, NC 27607
Phone: 919-461-1100

Prepared for the Offices of: 250 N. Greenfield Place, Garner, NC 27529		Construction Notes		SEAL DocuSigned by: 7/21/2025 CADD Filename:	
Division 4 Wayne County Goldsboro		PLAN DATE: May 2025 PREPARED BY: M. Tindal			
PREPARED BY: M.P. Cavanaugh		REVIEWED BY: C. Kalencik			
REVISIONS		INIT. DATE			