

ADA SUMMARY OF QUANTITIES - HUSKETH DR FROM SR 1814 TO DEAD END

Municipality:	Durham
WBS Number:	2026CPT.05.14.10321.1, etc.
County:	Durham

Sheet No.
41

Ramp ID	Inset Map Number	Route 1	Route 2	015600000-E (SY) Removal of Existing Asphalt Pavement	170400000-E (TON) Patching Existing Pavement	254900000-E (LF) 2'-6" Concrete Curb & Gutter	275200000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	275200000-E (LF) Remove 2'-6" Concrete Curb & Gutter	259100000-E (SY) 4" Concrete Sidewalk	273800000-E (SY) Remove And Replace 4" Concrete Sidewalk	273800000-E (SY) Remove 4" Concrete Sidewalk	283000000-N (EA) Adjustment of Manholes	284500000-N (EA) Adjustment of Meter Boxes or Valve Boxes	273800000-E (SY) Remove 5" Monolithic Concrete Islands (Keyed In)	261250000-N (EA) Remove and Replace Concrete Curb Ramps	275900000-N (EA) Remove Concrete Curb Ramps	Improvement Type
26419	1	SR-1814 (Stallings Rd)	SR-1877 (Husketh Dr)								9					1	Remove Ramp
26420	1	SR-1877 (Husketh Dr)	SR-1814 (Stallings Rd)												1		Type 1 Modified - 848.06
Sub-Total for Husketh Dr From SR 1814 To Dead End				0	0	0	0	0	0	0	9	0	0	0	1	1	

*Contingency line item amount provided for adjustments outside of curb ramp pay limits.

**While ramp is compliant upon initial inspection, it is to be improved in order to create a more resilient curb ramp.

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted.