

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

# STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

## CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+04.26	0	0	11+00.00	0	0
11+50.00	2204	0	11+50.00	73	2
12+00.00	2795	0	12+00.00	227	2
12+50.00	2576	0	12+50.00	389	0
13+00.00	1827	0	12+89.77	308	0
13+50.00	1287	0	<b>Station</b>	<b>Uncl. Exc.</b>	<b>Embt</b>
14+00.00	1149	0	<b>Y3 DET</b>	<b>(cu. yd.)</b>	<b>(cu. yd.)</b>
14+50.00	1097	0			
15+00.00	887	0	10+24.73	0	0
15+50.00	529	1	10+50.00	1	0
16+00.00	231	37	11+00.00	13	3
16+50.00	61	353	11+50.00	103	3
17+00.00	0	1049	12+00.00	337	0
17+50.00	0	1666	12+50.00	527	0
18+00.00	0	1804	12+72.15	246	0
18+50.00	0	1529	<b>Station</b>	<b>Uncl. Exc.</b>	<b>Embt</b>
19+00.00	0	1056	<b>Y3 DET</b>	<b>(cu. yd.)</b>	<b>(cu. yd.)</b>
19+50.00	0	616			
20+00.00	52	269	13+01.00	0	0
20+50.00	151	57	13+47.10	210	0
21+00.00	257	19	<b>Station</b>	<b>Uncl. Exc.</b>	<b>Embt</b>
21+50.00	288	38	<b>Y4</b>	<b>(cu. yd.)</b>	<b>(cu. yd.)</b>
22+00.00	218	62			
22+50.00	137	33	9+28.00	0	0
23+00.00	80	19	9+50.00	1	1
23+50.00	43	54	10+00.00	4	1
23+70.00	8	28	10+45.00	3	3
<b>Station</b>	<b>Uncl. Exc.</b>	<b>Embt</b>	10+50.00	0	0
<b>L</b>	<b>(cu. yd.)</b>	<b>(cu. yd.)</b>	11+00.00	3	38
			11+50.00	4	127
24+00.00	0	0	12+00.00	2	181
24+50.00	25	40	12+50.00	1	132
25+00.00	120	8	13+00.00	20	57
<b>Station</b>	<b>Uncl. Exc.</b>	<b>Embt</b>	13+20.35	16	12
<b>Y2</b>	<b>(cu. yd.)</b>	<b>(cu. yd.)</b>	<b>Station</b>	<b>Uncl. Exc.</b>	<b>Embt</b>
10+16.28	0	0	<b>SIDEPATH</b>	<b>(cu. yd.)</b>	<b>(cu. yd.)</b>
10+50.00	0	106	25+44.51	0	0
<b>Station</b>	<b>Uncl. Exc.</b>	<b>Embt</b>	25+50.00	0	0
<b>Y2</b>	<b>(cu. yd.)</b>	<b>(cu. yd.)</b>	26+00.00	1	28
			26+50.00	2	46
11+50.00	0	0	26+65.00	1	7
12+00.00	494	0			
12+50.00	628	0			
13+00.00	599	17			
13+50.00	344	19			
14+00.00	192	10			
14+50.00	118	29			
15+00.00	34	49			
15+30.00	3	38			

I:\2025\025\17-1112.013 - HL-0025 - Gr-ejlock\_Ridge\_Rd\_Ext\05-CAD\Gr-ejlock\_Ridge\_Ext\Roadway\XSC\Gr-ejlock\_Ridge\_Ext\X-1B.dgn