



1. FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM, CONTACT THE DIVISION 5 TRAFFIC ENGINEER AT (919) 536-4000 TO ARRANGE FOR THE TOWN TO PROGRAM THE NEW FIELD ETHERNET SWITCHES WITH THE NECESSARY NETWORK CONFIGURATION DATA, INCLUDING BUT NOT LIMITED TO: THE PROJECT IP ADDRESS, DEFAULT GATEWAY, SUBNET MASK AND VLAN ID INFORMATION. NOTIFY THE DIVISION 5 TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

2. ALL NCDOT ATTACHMENTS ARE 64" BELOW POWER, FRONT SIDE OF POLE, UNLESS OTHERWISE NOTED.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

	D05-17 Fuquay-Varina COMMUNICATIONS AND CABLE ROUTING PLANS		
	DIVISION 5 WAKE COUNTY FUQUAY VARINA PLAN DATE: AUGUST 2025 REVIEWED BY: GREGG GREEN PREPARED BY: M. DIAZ	REVISIONS: _____ INT: _____ DATE: _____	
750 N. Greenfield Pkwy., Garner, NC 27529 SCALE: 0 N/A	SIGNATURE: <i>Alex D. Stewart</i> DATE: 08/07/2025		