

- 1 INSTALL COAX CABLE
- 2 INSTALL ETHERNET CABLE
- 3 EXISTING ETHERNET (OR COAX) CABLE
- 4 INSTALL SMFO CABLE
- 5 EXISTING SMFO CABLE
- 6 INSTALL FIBER OPTIC DROP CABLE
- 7 INSTALL TRACER WIRE
- 8 TRENCH
- 9 INSTALL PVC CONDUIT
- 10 INSTALL RIGID, GALVANIZED STEEL CONDUIT
- 11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
- 12 INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL
- 13 INSTALL OUTER-DUCT POLYETHYLENE CONDUIT
- 14 INSTALL POLYETHYLENE CONDUIT
- 15 DIRECTIONAL DRILL CONDUIT
- 16 BORE AND JACK CONDUIT
- 17 INSTALL CABLE(S) IN EXISTING CONDUIT
- 18 INSTALL CABLE(S) IN NEW CONDUIT
- 19 INSTALL CABLE(S) IN EXISTING RISER
- 20 INSTALL CABLE(S) IN NEW RISER
- 21 INSTALL CABLE(S) IN EXISTING CONDUIT STUB-OUTS
- 22 INSTALL NEW CONDUIT INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 23 INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 24 INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET
- 25 INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET
- 26 INSTALL NEW ETHERNET EDGE SWITCH
- 27 INSTALL NEW FIBER OPTIC TRANSCEIVER
- 28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS AND FUSION SPlice CABLE IN CABINET
- 29 INSTALL UNDERGROUND SPlice ENCLOSURE
- 30 INSTALL AERIAL SPlice ENCLOSURE
- 31 MODIFY EXISTING INTERCONNECT CENTER /SPlice ENCLOSURE
- 32 INSTALL POLE MOUNTED SPlice CABINET
- 33 INSTALL BASE MOUNTED SPlice CABINET

- 34 INSTALL CABINET FOUNDATION
- 35 INSTALL CCTV CAMERA POLE MOUNTED CABINET
- 36 INSTALL CCTV CAMERA ASSEMBLY
- 37 INSTALL CCTV CAMERA WOOD POLE
- 38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION
- 39 INSTALL JUNCTION BOX
- 40A INSTALL OVERSIZED JUNCTION BOX
- 40B INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" x 24" x 24")
- 41 REMOVE EXISTING JUNCTION BOX
- 42 INSTALL WOOD POLE
- 43 REMOVE EXISTING WOOD POLE
- 44 INSTALL AERIAL GUY ASSEMBLY
- 45 INSTALL STANDARD GUY ASSEMBLY
- 46 INSTALL SIDEWALK GUY ASSEMBLY
- 47 INSTALL MESSENGER CABLE
- 48A REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE
- 48B REMOVE EXISTING COMMUNICATIONS CABLE
- 49 BACK PULL EXISTING COMMUNICATIONS CABLE
- 50 INSTALL CELL MODEM AND ANTENNA
- 51 INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE
- 52A INSTALL DELINEATOR MARKER
- 52B INSTALL JUNCTION BOX MARKER
- 53A STORE 20 FEET OF COMMUNICATIONS CABLE
- 53B STORE 50 FEET OF EACH COMMUNICATIONS CABLE
- 54 LASH CABLE(S) TO EXISTING COMMUNICATIONS CABLE
- 55 LASH CABLE(S) TO EXISTING MESSENGER CABLE
- 56 LASH CABLE(S) TO NEW MESSENGER CABLE
- 57 MODIFY EXISTING ELECTRICAL SERVICE
- 58 CCTV ELECTRICAL SERVICE
- 59 INSTALL NEW EQUIPMENT CABINET DISCONNECT
- 60 BOND TRACER WIRE TO EQUIPMENT GROUND BUS
- 61 DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS
- 62 BOND RISER AND MESSENGER CABLE TO POLE GROUND
- 63 BOND RISER TO POLE GROUND
- 64 BOND MESSENGER CABLE TO POLE GROUND
- 65 INSTALL HEAT SHRINK TUBING RETROFIT KIT
- 66 INSTALL MOLDABLE DUCT SEAL
- 67 SLACK SPAN

**LEGEND**

	NEW FIBER OPTIC COMMUNICATIONS CABLE
	EXISTING COMMUNICATIONS CABLE
	EXISTING COMMUNICATIONS CABLE TO BE REMOVED
	NEW AERIAL GUY ASSEMBLY
	NEW CONDUIT
	EXISTING CONDUIT
	NEW DIRECTIONAL DRILLED CONDUIT

**NEW**

	OVERSIZED JUNCTION BOX
	WOOD POLE
	AERIAL SPlice ENCLOSURE
	UNDERGROUND SPlice ENCLOSURE
	METAL POLE
	CCTV ASSEMBLY
	STANDARD GUY ASSEMBLY
	SIDEWALK GUY ASSEMBLY
	CABLE STORAGE RACKS (SNOW SHOES)
	SIGNAL/EQUIPMENT CABINET
	SPlice CABINET
	FLAT PANEL ANTENNA (SINGLE)
	YAGI ANTENNA (DOUBLE) FOR REPEATER OPERATION
	YAGI ANTENNA (SINGLE)
	OMNI ANTENNA
	SIGNAL POLE
	SIGNAL INVENTORY NUMBER

**EXISTING**

	OVERSIZED JUNCTION BOX
	WOOD POLE
	AERIAL SPlice ENCLOSURE
	UNDERGROUND SPlice ENCLOSURE
	METAL POLE
	CCTV ASSEMBLY
	STANDARD GUY ASSEMBLY
	SIDEWALK GUY ASSEMBLY
	CABLE STORAGE RACKS (SNOW SHOES)
	SIGNAL/EQUIPMENT CABINET
	SPlice CABINET
	FLAT PANEL ANTENNA (SINGLE)
	YAGI ANTENNA (DOUBLE) FOR REPEATER OPERATION
	YAGI ANTENNA (SINGLE)
	OMNI ANTENNA
	SIGNAL POLE
	SIGNAL INVENTORY NUMBER

**ATTACHMENT POINT:**

	XX"SS YYY	DISTANCE ABOVE (IN)/ATTACHMENT POINT REFERENCE POINT
	YYY XX"SS	REFERENCE POINT DISTANCE BELOW (IN)/ATTACHMENT POINT
<b>"SS" REFERENCE LOCATION</b>		
FS = FRONT SIDE OF POLE		
BS = BACK SIDE OF POLE		

**CONSTRUCTION NOTE SYMBOLOGY KEY**

	INDICATES NUMBER OF CABLES, LOOPS, ETC.
	INDICATES NUMBER OF FIBERS PER CABLE, TWISTED PAIRS PER CABLE, ETC.
	INDICATES NUMBER OF RISER(S)/CONDUIT(S)
	INDICATES DIAMETER OF RISER(S)/CONDUIT(S) (INCH)

NUMBER OF CABLE(S)      NUMBER OF FIBERS/TWISTED PAIRS

NEW/EXISTING CABLE

REMOVE/MODIFY CABLE

CONDUIT/RISER

NUMBER OF RISER(S)/CONDUIT(S)      DIAMETER OF RISER(S)/CONDUIT(S) (INCH)

9/20/2024 4:57:48 PM  
 \*\*\*vhabg:wpcl:qda:ei:gh:8536:23:W-5704:5601:Covered:105#echas:gnal:P:cm:W-5704E-SCP-1.dgn  
 sct11:lkka

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



Prepared for the Offices of:		<p align="center"><b>Construction Notes</b></p> <p>Division 4    Johnston County    Clayton</p> <p>PLAN DATE: February 2025    REVIEWED BY: J.M. Justine</p> <p>PREPARED BY: S.R. Chiluka    REVIEWED BY: M.L. Stygles</p>		
REVISIONS	INIT.	DATE	<p>DocuSigned by: S. R. Chiluka 0352ACB2A75E</p> <p>7/30/2025</p>	