

COMPUTED BY: S. Crockett DATE: 05/12/26
CHECKED BY: Hunsberger, W. S. DATE: 05/12/26

(9-17-24)

PROJECT NO.	SHEET NO.
I-6011A	3G-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
CONTINGENCY				SD	200
				TOTAL LF:	200

*UD = Underdrain
*BD = Blind Drain
*SD = Subsurface Drain

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	Station	Station	Aggregate Type* ASU(1/2)/ AST	Aggregate Thickness INCHES [8" for ASU(2)]	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Subgrade Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
CONTINGENCY			ASU(1)	12	100	200	300		
CONTINGENCY			AST	3					250
			TOTAL CY/TONS/SY:		100	200**	300**	0	250

*ASU(1/2) = Aggregate Subgrade (Type 1 or 2)
*AST = Aggregate Stabilization

**Total tons of "Class IV Subgrade Stabilization" and total square yards of "Geotextile for Subgrade Stabilization" are only the estimated quantities for ASU(1/2)/AST and may only represent a portion of the subgrade stabilization and geotextile quantities shown in the Item Sheets of the Proposal.

SUMMARY OF SETTLEMENT GAUGES

Gauge No.	LINE and Station	Offset	
		Distance FT	Direction LT/RT
SG-1	-L- 28+60	25	LT
SG-2	-L- 28+60	25	RT
SG-3	-L- 30+90	25	LT
SG-4	-L- 30+90	25	RT
TOTAL GAUGES (EACH):		4	

SUMMARY OF SURCHARGES
AND SURCHARGE WAITING PERIODS

LINE	Station	Station	Surcharge Height FT	MONTHS
-L-	27+00	28+82.80	3.0	2
-L-	30+70.50	32+50	5.0	2

SUMMARY OF BRIDGE WAITING PERIODS

Bridge Description	End Bent/ Bent No.	MONTHS
Bridge on -L- (SR 2225) over -Y1- (US 74)	1	2
Bridge on -L- (SR 2225) over -Y1- (US 74)	2	2