PROJ. REFERENCE NO.	SHEET NO.
U-5711	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+00.00	0	0
14+50.00	28	1
15+00.00	47	2
15+50.00	45	3
16+00.00	43	4
16+50.00	50	5
17+00.00	83	3
17+50.00	145	0
18+00.00	170	0
18+50.00	120	3
19+00.00	60	16
19+50.00	32	38
20+00.00	22	51
20+50.00	20	51
21+00.00	19	51
21+50.00	20	64
22+00.00	18	75
22+50.00	13	44
23+00.00	31	8
	966	419

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
23+00.00	0	0
23+50.00	83	1
24+00.00	149	0
24+45.98	165	0
	397	1

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
24+56.06	0	0
25+00.00	8	18
	8	18

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
25+00.00	0	0
25+50.00	13	11
26+00.00	14	7
26+50.00	26	6
27+00.00	20	19
27+50.00	2	19
28+00.00	16	32
28+50.00	44	49
29+00.00	52	27
29+50.00	44	21
30+00.00	31	29
30+50.00	23	32
31+00.00	29	30
31+50.00	28	22
32+00.00	22	18
32+50.00	16	47
33+00.00	14	148
33+50.00	7	162
34+00.00	0	96
34+50.00	19	56
35+00.00	46	19
35+50.00	46	19
36+00.00	28	37
36+50.00	19	38
37+00.00	18	38
37+50.00	47	31
38+00.00	99	6
38+50.00	131	0
39+00.00	128	4
39+50.00	106	15
40+00.00	68	27
40+50.00	67	27
41+00.00	56	19
41+50.00	8	14
42+00.00	7	12
42+50.00	34	37
43+00.00	33	70
43+50.00	9	69
43+88.00	6	45
	1376	1358

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
43+88.00	0	0
44+00.00	0	16
44+22.00	0	29
	0	45

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
44+22.00	0	0
44+50.00	0	17
45+00.00	13	30
45+50.00	28	35
46+00.00	96	25
46+50.00	146	8
47+00.00	120	15
47+50.00	89	25
48+00.00	53	36
48+50.00	49	51
49+00.00	40	30
49+50.00	20	18
50+00.00	27	27
50+50.00	33	21
51+00.00	34	21
51+50.00	71	17
52+00.00	115	13
52+50.00	122	10
53+00.00	135	4
53+50.00	135	5
54+00.00	115	22
54+50.00	92	55
55+00.00	86	51
55+50.00	85	14
55+81.06	46	0
	1750	550

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+50.00	0	0
12+00.00	20	17
12+31.64	26	21
	46	38

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+65.64	0	0
13+00.00	8	5
13+50.00	6	4
	14	9

Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+17.03	0	0
10+50.00	12	23
11+00.00	31	18
11+50.00	16	5
	59	46