


TIP PROJECT: U-5711

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS



RANDOLPH COUNTY

LOCATION: SR 1712 (PINEVIEW ROAD) FROM WEST OF
SYLVAN DRIVE TO US 220 BUSINESS IN ASHEBORO

TYPE OF WORK: TRAFFIC SIGNAL



VICINITY MAP (NOT TO SCALE)



LEGEND

XX-XXXX New or Existing Signal

Refer to "Roadway Standard Drawings
NCDOT" dated January 2024 and
"Standard Specifications for Roads
and Structures" dated January 2024.


Sheet #	Reference #	Index of Plans	Location/Description
Sig. 1.0	-----	Title Sheet	US 220 Bus (N Fayetteville St) at SR 1712 (Pineview Street)
Sig. 2.0-3.3	08-0580	Standard Drawings for Metal Poles	
Sig. M1A-M9	-----		

TRANSPORTATION SYSTEMS
MANAGEMENT & OPERATIONS UNIT


Contacts:

Rob Ziemba, PE - Central Region Signals Engineer
Ryan Hough, PE - Signal Equipment Design Engineer

DIVISION OF HIGHWAYS
TRANSPORTATION MOBILITY & SAFETY DIVISION



PHASING DIAGRAM




PHASING DIAGRAM DETECTION LEGEND

- DETECTED MOVEMENT
- UNDETECTED MOVEMENT (OVERLAP)
- UNSIGNALIZED MOVEMENT
- PEDESTRIAN MOVEMENT

SIGNAL FACE	PHASE			
	2 + 5	2 + 6	4	FLASH
21,22	G	G	R	R
41	R	R	—	R
42	R	R	—	R
51	—	Y	R	R
61,62	R	G	R	R

SIGNAL FACE I.D.

All Heads L.E.D.



MAXTIME DETECTOR INSTALLATION CHART

DETECTOR				PROGRAMMING							
LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	CALL PHASE	DELAY TIME	EXTEND TIME	EXTEND	ADDED INITIAL	CALL DURING GREEN	NEW CARD
2A	6X6	300	6	X	2	-	-	X	X	X	-
4A*	6X40	+5	*	*	4	5.0	-	X	-	X	-
5A	6X40	0	2-4-2	X	5	15.0	-	X	-	X	-
6A	6X6	330	6	X	6	-	-	X	X	X	-

* Video detection zone

3 Phase Fully Actuated Isolated

NOTES


- Refer to "Roadway Standard Drawings NCDOT" dated January 2024 and "Standard Specifications for Roads and Structures" dated January 2024.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 5 may be lagged.
- Set all detector units to presence mode.
- Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- This intersection uses video detection. Install according to the manufacturer's instructions to achieve the desired detection.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal sytem timing values supersede these values.

LEGEND


PROPOSED	EXISTING
	N/A
	N/A

MAXTIME TIMING CHART				
FEATURE	PHASE			
	2	4	5	6
Walk *	-	-	-	-
Ped Clear *	-	-	-	-
Min Green *	12	7	7	12
Passage *	6.0	2.0	2.0	6.0
Max I *	60	25	20	60
Yellow Change	4.6	3.2	3.0	4.6
Red Clear	1.0	2.1	1.4	1.0
Added Initial *	2.5	-	-	2.5
Maximum Initial *	34	-	-	37
Time Before Reduction *	15	-	-	15
Time To Reduce *	30	-	-	30
Minimum Gap	3.0	-	-	3.0
Advance Walk	-	-	-	-
Non Lock Detector	-	X	X	-
Vehicle Recall	MIN RECALL	-	-	MIN RECALL
Dual Entry	-	-	-	-

* These values may be field adjusted. Do not adjust Min Green and Passage times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.



MOTT MACDONALD
MOTT MACDONALD I & E, LLC
930 Main Campus Drive
Suite 200
RALEIGH, NC 27606
License No. F-0669



Signal Upgrade - Temporary Design

US 220 Bus (N Fayetteville St)
at
SR 1712 (Pineview Street)

Division 8 Randolph County Asheboro

PLAN DATE: November 2025 REVIEWED BY: R Mullinax

PREPARED BY: LD Stouchko REVIEWED BY:


REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



18 CHANNEL IP CONFLICT MONITOR
PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the signal plan.
- Program controller to start up in phase 2 Green No Walk and 6 Green No Walk.
- If this signal will be managed by an ATMS software, enable controller and detector logging for all detectors used at this location.

EQUIPMENT INFORMATION

Controller.....2070LX
Cabinet.....332 w/ Aux
Software.....Q-Free MAXTIME
Cabinet Mount.....Base
Output File Positions.....18 With Aux. Output File
Load Switches Used.....S2, S5, S7, S8, AUX S4
Phases Used.....2, 4, 5, 6
Overlap "1".....NOT USED
Overlap "2".....NOT USED
Overlap "3".....*
Overlap "4".....NOT USED

*See overlap programming detail on this sheet

PROJECT REFERENCE NO.	SHEET NO.
U-5711	Sig.2.1

SIGNAL HEAD HOOK-UP CHART


LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OL1	OL2	SPARE	OL3	OL4	SPARE
SIGNAL HEAD NO.	NU	21,22	NU	NU	41	42	NU	51★	61,62	NU	NU	NU	NU	NU	NU	51★	NU	NU
RED		128			101	101			134									
YELLOW		129					*		135									
GREEN		130							136									
RED ARROW																	A114	
YELLOW ARROW					102	102											A115	
FLASHING YELLOW ARROW																	A116	
GREEN ARROW					103	103		133										

NU = Not Used

* Denotes install load resistor. See load resistor installation detail this sheet.
*See pictorial of head wiring in detail this sheet.


FYA SIGNAL WIRING DETAIL

(wire signal heads as shown)



INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT POINT	DETECTOR NO.	CALL PHASE	DELAY TIME	EXTEND TIME	EXTEND	ADDED INITIAL	CALL	DELAY DURING GREEN
2A	TB2-5,6	I2U	39	1	2	2				X	X	
5A	TB3-1,2	J1U	55	17	15	5	15.0			X	X	
				.	31	2	3.0			X	X	X
6A	TB3-5,6	J2U	40	2	16	6				X	X	

INPUT FILE POSITION LEGEND: J2L




SPECIAL DETECTOR NOTE

Install a video detection system for zone 4A
Perform installation according to manufacturer's recommendations and NCDOT engineer-approved mounting location(s) to accomplish the detection schemes shown on the Signal Design Plans.

LOAD RESISTOR INSTALLATION DETAIL

(install resistors as shown)

ACCEPTABLE VALUES	
Value (ohms)	Wattage
1.5K - 1.9K	25W (min)
2.0K - 3.0K	10W (min)



OVERLAP PROGRAMMING

Front Panel
Main Menu >Controller >Overlap >Overlap Parameters/Overlap Timings

Web Interface
Home >Controller >Overlap Configuration >Overlaps

Overlap Plan 1

Overlap	1	2	3	4
Type	Off	Off	FYA 4 - Section	Off
Included Phases	-	-	6	-
Modifier Phases	-	-	5	-
Modifier Overlaps	-	-	-	-
Trail Green	0	0	0	0
Trail Yellow	0:0	0:0	0:0	0:0
Trail Red	0:0	0:0	0:0	0:0

M M

MOTT MACDONALD

MOTT MACDONALD I & E, LLC
930 Main Campus Drive
Suite 200
RALEIGH, NC 27606
License No. F-0669

Electrical Detail - Sheet 1 of 2 - Temporary Design

ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared for the Offices of:		US 220 Bus (N Fayetteville St) at SR 1712 (Pineview Street)		DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
Division 8 Randolph County Asheboro		Division 8 Randolph County Asheboro		SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 034437 LORI O. STOUCHKO	
PLAN DATE: November 2025		REVIEWED BY: R Mullinax		24-Nov-2025	
PREPARED BY: LD Stouchko		REVIEWED BY:		SIGNATURE DATE	
REVISIONS		INIT.		DATE	
750 N. Greenfield Pkwy, Corner, NC 27529				SIG. INVENTORY NO. 08-0580T	

OUTPUT CHANNEL CONFIGURATION

Front Panel
Main Menu >Controller >More>Channels>Channels Config

Web Interface
Home >Controller >Advanced IO>Channels>Channels Configuration

Channel Configuration

Channel	Control Type	Control Source	Flash Yellow	Flash Red	Flash Alt	MMU Channel
1	Phase Vehicle	1		X	X	1
2	Phase Vehicle	2		X		2
3	Phase Vehicle	3		X	X	3
4	Phase Vehicle	4		X		4
5	Phase Vehicle	5		X		5
6	Phase Vehicle	6		X	X	6
7	Phase Vehicle	7		X		7
8	Phase Vehicle	8		X	X	8
9	Overlap	1		X	X	9
10	Overlap	2		X	X	10
11	Overlap	3		X		11
12	Overlap	4		X		12
13	Phase Ped	2				13
14	Phase Ped	4				14
15	Phase Ped	6				15
16	Phase Ped	8				16
17	Overlap	5		X	X	17
18	Overlap	6		X		18

MAXTIME STARTUP AND SOFTWARE FLASH
PROGRAMMING DETAIL

Front Panel
Main Menu >Controller >Unit

Web Interface
Home >Controller >Unit

Modify parameters as shown below and save changes.

Startup Parameters	Unit Flash Parameters
Startup Clearance Hold	All Red Flash Exit Time
6	6

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 08-0580T
DESIGNED: November 2025
SEALED: 11/24/2025
REVISED:

M

MOTT
MACDONALD

MOTT MACDONALD I & E, LLC
930 Main Campus Drive
Suite 200
RALEIGH, NC 27606
License No. F-0669

ELECTRICAL AND PROGRAMMING
DETAILS FOR:

Prepared For the Offices of:



750 N. Greenfield Pkwy, Corner, NC 27529

US 220 Bus (N Fayetteville St)
at
SR 1712 (Pineview Street)

Division 8 Randolph County Asheboro


PLAN DATE: November 2025 REVIEWED BY: R Mullinax

PREPARED BY: LD Stouchko REVIEWED BY:

REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

SEAL




Lori O. Stouchko 24-Nov-2025

FF586C759DC645A

SIGNATURE DATE

SIG. INVENTORY NO. 08-0580T


PHASING DIAGRAM




SIGNAL FACE	PHASE			
	2 + 5	2 + 6	4	FLASH
21, 22	G	G	R	R
41, 43	←R	←R	←R	←R
42	←R	R	←R	R
51	←R	←R	←R	←R
61, 62, 63	R	G	R	R

SIGNAL FACE I.D.

All Heads L.E.D.



PHASING DIAGRAM DETECTION LEGEND



MAXTIME DETECTOR INSTALLATION CHART


DETECTOR					PROGRAMMING						
LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	CALL PHASE	DELAY TIME	EXTEND TIME	EXTEND	ADDED INITIAL	CALL	NEW CARD
2A	6X6	300	EXIST	-	2	-	-	X	X	X	-
4A	6X40	0	2-4-2	X	4	3.0	-	X	-	X	-
5A	6X40	0	2-4-2	-	5	15.0	-	X	-	X	-
5B	6X40	+5	2-4-2	X	5	15.0	-	X	-	X	-
6A	6X6	300	4	-	6	-	-	X	X	X	-

3 Phase
Fully Actuated
Isolated

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2024 and "Standard Specifications for Roads and Structures" dated January 2024.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Phase 5 may be lagged.
- Set all detector units to presence mode.
- Maximum times shown in timing charts are for free-run operation only. Coordinated signal system timing values supersede these values.

LEGEND




MAXTIME TIMING CHART

FEATURE	PHASE			
	2	4	5	6
Walk *	-	-	-	-
Ped Clear *	-	-	-	-
Min Green *	12	7	7	12
Passage *	6.0	2.0	2.0	6.0
Max I *	60	25	20	60
Yellow Change	4.6	3.2	3.0	4.6
Red Clear	1.5	2.6	1.6	1.5
Added Initial *	2.5	-	-	2.5
Maximum Initial *	34	-	-	34
Time Before Reduction *	15	-	-	15
Time To Reduce *	30	-	-	30
Minimum Gap	3.0	-	-	3.0
Advance Walk	-	-	-	-
Non Lock Detector	-	X	X	-
Vehicle Recall	MIN RECALL	-	-	MIN RECALL
Dual Entry	-	-	-	-

* These values may be field adjusted. Do not adjust Min Green and Passage times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

Signal Upgrade - Final Design

MOTT MACDONALD
750 N. Greenfield Pkwy, Garner, NC 27529
MOTT MACDONALD I & E, LLC
930 Main Campus Drive
Suite 200
RALEIGH, NC 27606
License No. F-9669



US 220 Bus (N Fayetteville St)
at
SR 1712 (Pineview Street)

Division 8 Randolph County Asheboro

PLAN DATE: November 2025 REVIEWED BY: R Mullinax

PREPARED BY: LD Stouchko REVIEWED BY:


REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

SEAL
NORTH CAROLINA
PROFESSIONAL
ENGINEER
Lori Stouchko
24-Nov-2025
SIGNATURE DATE
SIG. INVENTORY NO. 08-0580

18 CHANNEL IP CONFLICT MONITOR
PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that the Red Enable is active at all times during normal operation.
- Integrate monitor with Ethernet network in cabinet.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the signal plan.
- Program controller to start up in phase 2 Green No Walk and 6 Green No Walk.
- If this signal will be managed by an ATMS software, enable controller and detector logging for all detectors used at this location.

EQUIPMENT INFORMATION

Controller.....2070LX
Cabinet.....332 w/ Aux
Software.....Q-Free MAXTIME
Cabinet Mount.....Base
Output File Positions.....18 With Aux. Output File
Load Switches Used.....S2, S5, S7, S8, AUX S4, AUX S5
Phases Used.....2, 4, 5, 6
Overlap "1".....NOT USED
Overlap "2".....NOT USED
Overlap "3".....*
Overlap "4".....*

*See overlap programming detail on this sheet

PROJECT REFERENCE NO.	SHEET NO.
U-5711	Sig.3.1

SIGNAL HEAD HOOK-UP CHART


LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OL1	OL2	SPARE	OL3	OL4	SPARE
SIGNAL HEAD NO.	NU	21,22	NU	NU	41,43	NU	51	61,62 63	NU	NU	NU	NU	NU	NU	NU	51	42	NU
RED		128						134									A101	
YELLOW		129					*	135										
GREEN		130						136										
RED ARROW					101												A114	
YELLOW ARROW					102												A115	A102
FLASHING YELLOW ARROW																	A116	
GREEN ARROW					103		133										A103	

NU = Not Used

- * Denotes install load resistor. See load resistor installation detail this sheet.
- *See pictorial of head wiring in detail this sheet.

FYA SIGNAL WIRING DETAIL


(wire signal heads as shown)



51

INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT POINT	DETECTOR NO.	CALL PHASE	DELAY TIME	EXTEND TIME	EXTEND	ADDED INITIAL	CALL	DELAY DURING GREEN
2A	TB2-5,6	I2U	39	1	2	2			X	X	X	
4A	TB4-9,10	I6U	41	3	8	4	3.0		X		X	
5A	TB3-1,2	J1U	55	17	15	5	15.0		X		X	
5B	TB4-11,12	I6L	45	-	31	2	3.0		X		X	X
6A	TB3-5,6	J2U	40	2	16	6			X	X	X	


INPUT FILE POSITION LEGEND: J2L



LOAD RESISTOR INSTALLATION DETAIL

(install resistors as shown)

ACCEPTABLE VALUES	
Value (ohms)	Wattage
1.5K - 1.9K	25W (min)
2.0K - 3.0K	10W (min)



OVERLAP PROGRAMMING

Front Panel
Main Menu >Controller >Overlap >Overlap Parameters/Overlap Timings

Web Interface
Home >Controller >Overlap Configuration >Overlaps

Overlap Plan 1

Overlap	1	2	3	4
Type	Off	Off	FYA 4 - Section	Normal
Included Phases	-	-	6	4;5
Modifier Phases	-	-	5	-
Modifier Overlaps	-	-	-	-
Trail Green	0	0	0	0
Trail Yellow	0:0	0:0	0:0	0:0
Trail Red	0:0	0:0	0:0	0:0

M M

MOTT MACDONALD

MOTT MACDONALD I & E, LLC
930 Main Campus Drive
Suite 200
RALEIGH, NC 27606
License No. F-0669

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 08-0580
DESIGNED: November 2025
SEALED: 11/24/2025
REVISED:

Electrical Detail - Sheet 1 of 2 - Final Design

ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared for the Offices of: Seal of the State of North Carolina Department of Transportation Signal Management Section 750 N. Greenfield Pkwy, Corner, NC 27529		US 220 Bus (N Fayetteville St) at SR 1712 (Pineview Street) Division 8 Randolph County Asheboro PLAN DATE: November 2025 REVIEWED BY: R Mullinax PREPARED BY: LD Stouchko REVIEWED BY: REVISIONS INIT. DATE		DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 034437 Lori O. Stouchko 24-Nov-2025 SIGNATURE DATE SIG. INVENTORY NO. 08-0580
---	--	---	--	--

OUTPUT CHANNEL CONFIGURATION

Front Panel
Main Menu >Controller >More>Channels>Channels Config

Web Interface
Home >Controller >Advanced IO>Channels>Channels Configuration

Channel Configuration

Channel	Control Type	Control Source	Flash Yellow	Flash Red	Flash Alt	MMU Channel
1	Phase Vehicle	1		X	X	1
2	Phase Vehicle	2		X		2
3	Phase Vehicle	3		X	X	3
4	Phase Vehicle	4		X		4
5	Phase Vehicle	5		X		5
6	Phase Vehicle	6		X	X	6
7	Phase Vehicle	7		X		7
8	Phase Vehicle	8		X	X	8
9	Overlap	1		X	X	9
10	Overlap	2		X	X	10
11	Overlap	3		X		11
12	Overlap	4		X		12
13	Phase Ped	2				13
14	Phase Ped	4				14
15	Phase Ped	6				15
16	Phase Ped	8				16
17	Overlap	5		X	X	17
18	Overlap	6		X		18

FLASHER CIRCUIT MODIFICATION DETAIL

IN ORDER TO INSURE THAT SIGNALS FLASH CONCURRENTLY ON THE SAME APPROACH, MAKE THE FOLLOWING FLASHER CIRCUIT CHANGES:

1. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-4 AND TERMINATE ON T2-2.
2. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-5 AND TERMINATE ON T2-3.
3. REMOVE FLASHER UNIT 2.

THE CHANGES LISTED ABOVE TIES ALL PHASES AND OVERLAPS TO FLASHER UNIT 1.

MAXTIME STARTUP AND SOFTWARE FLASH PROGRAMMING DETAIL

Front Panel
Main Menu >Controller >Unit

Web Interface
Home >Controller >Unit

Modify parameters as shown below and save changes.

Startup Parameters	Unit Flash Parameters
Startup Clearance Hold	All Red Flash Exit Time
6	6

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 08-0580
DESIGNED: November 2025
SEALED: 11/24/2025
REVISED:

M

MOTT
MACDONALD

MOTT MACDONALD I & E, LLC
930 Main Campus Drive
Suite 200
RALEIGH, NC 27606
License No. F-0669

Electrical Detail - Sheet 2 of 2 - Final Design

ELECTRICAL AND PROGRAMMING
DETAILS FOR:
Prepared for the Offices of:



750 N. Greenfield Pkwy, Corner, NC 27529

US 220 Bus (N Fayetteville St)
at
SR 1712 (Pineview Street)

Division 8 Randolph County Asheboro

PLAN DATE: November 2025 REVIEWED BY: R Mullinax

PREPARED BY: LD Stouchko REVIEWED BY:

REVISIONS	INIT.	DATE

DocuSign
Lori Stouchko
EE586C759CCF6A5A

SIGNATURE DATE


SIG. INVENTORY NO. 08-0580

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

SEAL
NORTH CAROLINA
PROFESSIONAL
SEAL
034437
ENGINEER
LORI D. STOUCHKO

24-Nov-2025


Design Loading for METAL POLE NO. 1




Elevation View

SPECIAL NOTE
The contractor is responsible for verifying that the mast arm attachment height (H1) will provide the "Design Height" clearance from the roadway before submitting final shop drawings for approval. Verify elevation data below which was obtained by field measurement or from available project survey data.

Elevation Data for Mast Arm Attachment (H1)		
Elevation Differences for:	Pole 1	
Baseline reference point at C Foundation @ ground level	0.0 ft.	
Elevation difference at High point of roadway surface	+/-0.1 ft.	
Elevation difference at Edge of travelway or face of curb	NA	




POLE RADIAL ORIENTATION



8 BOLT BASE PLATE DETAIL

See Note 6



BASE PLATE TEMPLATE & ANCHOR BOLT
LOCK PLATE DETAIL
For 8 Bolt Base Plate

METAL POLE No. 1

PROJECT REFERENCE NO.	SHEET NO.
U-5711	Sig.3.3

MAST ARM LOADING SCHEDULE				
LOADING SYMBOL	DESCRIPTION	AREA	SIZE	WEIGHT
	RIGID MOUNTED SIGNAL HEAD 12"-4 SECTION-WITH BACKPLATE	11.5 S.F.	25.5" W X 66.0" L	74 LBS
	RIGID MOUNTED SIGNAL HEAD 8"-3 SECTION-WITH BACKPLATE	6.4 S.F.	22.0" W X 42.0" L	43 LBS
	SIGN RIGID MOUNTED	5.0 S.F.	24.0" W X 30.0" L	11 LBS

NOTES

DESIGN REFERENCE MATERIAL

- Design the traffic signal structure and foundation in accordance with:
 - The 6th Edition 2015 AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, including all of the latest interim revisions.
 - The 2024 NCDOT "Standard Specifications for Roads and Structures." The latest addenda to the specifications can be found in the traffic signal project special provisions.
 - The 2024 NCDOT Roadway Standard Drawings.
 - The traffic signal project plans and special provisions.
 - The NCDOT "Metal Pole Standards" located at the following NCDOT website:
<https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

DESIGN REQUIREMENTS

- Design the traffic signal structure using the loading conditions shown in the elevation views. These are anticipated worst case "design loads" and may not represent the actual loads that will be applied at the time of the installation. The contractor should refer to the traffic signal plans for the actual loads that will be applied at the time of the installation.
- Design all signal supports using stress ratios that do not exceed 0.9.
- The camber design for the mast arm deflection should provide an appearance of a low pitched arch where the tip or the free end of the mast arm does not deflect below horizontal when fully loaded.
- A clamp-type bolted mast arm-to-pole connection may be used instead of the welded ring stiffened box connection shown as long as the connection meets all of the design requirements. This requires staggering the connections. Use elevation data for each arm to determine appropriate arm connection points.
- Design base plate with 8 anchor bolt holes. Provide 2 inch x 60 inch anchor bolts.
- The mast arm attachment height (H1) shown is based on the following design assumptions:
 - Mast arm slope and deflection are not considered in determining the arm attachment height as they are assumed to offset each other.
 - Signal heads are rigidly mounted and vertically centered on the mast arm.
 - The roadway clearance height for design is as shown in the elevation views.
 - The top of the pole base plate is 0.75 feet above the ground elevation.
 - Refer to the Elevation Data Chart for the elevation differences between the proposed foundation ground level and the high point of the roadway.
- The pole manufacturer will determine the total height (H2) of each pole using the greater of the following:
 - Mast arm attachment height (H1) plus 2 feet, or
 - H1 plus 1/2 of the total height of the mast arm attachment assembly plus 1 foot.
- If pole location adjustments are required, the contractor must gain approval from the Engineer as this may affect the mast arm lengths and arm attachment heights. The contractor may contact the Signal Design Section Senior Structural Engineer for assistance at (919) 814-5000.
- The contractor is responsible for verifying that the mast arm length shown will allow proper positioning of the signal heads over the roadway.
- The contractor is responsible for providing soil penetration testing data (SPT) to the pole manufacturer so site specific foundations can be designed.

NCDOT (10-YR MRI) Service Wind Zone 3 (76 mph)
NCDOT (700-YR MRI) Wind Zone 5 (110 mph)

	US 220 Bus (N Fayetteville St) at SR 1712 (Pineview Street)			
	Division 8 Randolph County Asheboro			
	PLAN DATE: November 2025	REVIEWED BY: R Mullinax		
	PREPARED BY: LD Stouchko	REVIEWED BY:		
SCALE: 0 N/A		REVISIONS	INIT.	DATE
N/A				

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
SEAL	
SEAL	
24-Nov-2025	
SIGNATURE	
DATE	
SIG. INVENTORY NO. 08-0580	

03-01-2023 12:07 S:\ITS\SSM\115\Signal\Structures\Drawings\2024 Metal Pole Standards\2024 Sig. M1A Standard 411 Metal Pole (700-yr MRI).dgn kdurigon

NCDOT METAL POLE STANDARDS

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS


PROJECT I.D.NO.

SHEET NO.

U-5711


Sig.M1A

STANDARD DRAWINGS FOR ALL METAL POLES (LRFD)



<https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

Prepared in the Offices of:



750 N. Greenfield Pkwy.
Garner, NC 27529

Designed in conformance
with the latest
2020 Interim to the
1st Edition 2015

**AASHTO
LRFD**

Standard Specifications for
Highway Signs, Luminaires,
and Traffic Signals

DRAWING NUMBER

DRAWING NUMBER	DESCRIPTION
Sig. M 1A	Statewide Wind Zone Map (700-yr MRI)
Sig. M 1B	Statewide Wind Zone Map (10-yr MRI)
Sig. M 2	Typical Fabrication Details-All Metal Poles
Sig. M 3	Typical Fabrication Details-Strain Poles
Sig. M 4	Typical Fabrication Details-Mast Arm Poles
Sig. M 5	Typical Fabrication Details-Mast Arm Connection
Sig. M 6	Typical Fabrication Details-Strain Pole Attachments
Sig. M 7	Construction Details-Foundations
Sig. M 8	Standard Strain Pole Foundation-All Soil Conditions
Sig. M 9	Typical Fabrication Details-CCTV Camera Poles

INDEX OF PLANS DESCRIPTION


MOBILITY AND SAFETY DIVISION - TRANSPORTATION SYSTEMS MANAGEMENT AND OPERATIONS UNIT

D.Y. ISHAK - STATE SIGNALS ENGINEER

K. DURIGON, P.E. - ITS AND SIGNALS STRUCTURAL ENGINEER

B. WALKER, P.E. - ITS AND SIGNALS STRUCTURAL ENGINEER

SEAL



DocuSigned by:

Kevin Durigon
SIGNATURE
4B23DC79B3764DA

09/21/2023
DATE

03-001-2023 12/21
S:\ITS\ASU\ITS Signal Structures\Drawings\2024 Metal Pole (10-yr MRI).dgn
Koduri.gcn

NCDOT METAL POLE STANDARDS

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS


PROJECT I.D.NO.

SHEET NO.

U-5711

Sig.M1B

STANDARD DRAWINGS FOR ALL METAL POLES (LRFD)



(10-YR MRI)
SERVICE WIND ZONE LEGEND

SERVICE WIND ZONE 1 (90 mph)


SERVICE WIND ZONE 2 (80 mph)

SERVICE WIND ZONE 3 (76 mph)

SERVICE WIND ZONE 4 (85) SPECIAL REGION

<https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

Prepared In the Offices of:



750 N. Greenfield Pkwy.
Garner, NC 27529

Designed in conformance
with the latest
2020 Interim to the
1st Edition 2015

**AASHTO
LRFD**

Standard Specifications for
Highway Signs, Luminaires,
and Traffic Signals

DRAWING NUMBER

DRAWING NUMBER	DESCRIPTION
Sig. M 1A	Statewide Wind Zone Map (700-yr MRI)
Sig. M 1B	Statewide Wind Zone Map (10-yr MRI)
Sig. M 2	Typical Fabrication Details-All Metal Poles
Sig. M 3	Typical Fabrication Details-Strain Poles
Sig. M 4	Typical Fabrication Details-Mast Arm Poles
Sig. M 5	Typical Fabrication Details-Mast Arm Connection
Sig. M 6	Typical Fabrication Details-Strain Pole Attachments
Sig. M 7	Construction Details-Foundations
Sig. M 8	Standard Strain Pole Foundation-All Soil Conditions
Sig. M 9	Typical Fabrication Details-CCTV Camera Poles

INDEX OF PLANS DESCRIPTION


NCDOT CONTACTS: MOBILITY AND SAFETY DIVISION - TRANSPORTATION SYSTEMS MANAGEMENT AND OPERATIONS UNIT

D.Y. ISHAK - STATE SIGNALS ENGINEER

K. DURIGON, P.E. - ITS AND SIGNALS STRUCTURAL ENGINEER

B. WALKER, P.E. - ITS AND SIGNALS STRUCTURAL ENGINEER

SEAL




DocuSigned by:

Kevin Durigon

4B23DC79B3784DA

09/21/2023

DATE





MFG _____ MFG. DATE: MM/YY SHAFT D/T/L/Y _____ ARM-A D/T/L/Y _____ ARM-B D/T/L/Y _____ A.B. DIA./B.C./L/Y _____ NCDOT SIG. INV. NO. _____ NCDOT POLE NO. _____	MFG _____ MFG. DATE: MM/YY SECTION D/T/L/Y _____ NCDOT SIG. INV. NO. _____ NCDOT POLE NO. _____ ARM I.D. TAG (PROVIDE ON EACH SECTION OF A MULTI-SECTION MAST ARM)
---	---



SHAFT I.D. TAG
(PROVIDE ON SHAFT OF STRAIN POLES
AND MAST ARM POLE SHAFT)

NOTES:

- D = DIAMETER, T = THICKNESS, L = LENGTH, Y = YIELD STRENGTH
- A.B. = ANCHOR BOLT
- B.C. = BOLT CIRCLE OF ANCHOR BOLTS
- IF STANDARD DESIGN, INCLUDE CASE NUMBER IN ADDITION TO POLE NUMBER ON "NCDOT POLE NO." LINE.
- SIGNAL INV. NUMBER AND POLE I.D. NUMBER.
SEE DRAWING M3 AND M4 FOR MOUNTING POSITIONS OF I.D. TAGS.


IDENTIFICATION TAG DETAILS




Prepared In the Offices of:  750 N. Greenfield Pkwy, Garner, NC 27529	Typical Fabrication Details For All Metal Poles PLAN DATE: SEPTEMBER 2023 DESIGNED BY: C.F. ANDREWS PREPARED BY: K.C. DURIGON REVIEWED BY: D.C. SARKAR REVISIONS <table><tr><th>INIT.</th><th>DATE</th></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr></table>	INIT.	DATE							SEAL  DocuSigned by: Kevin Durigon 4B23DC79B3784DA 09/21/2023 DATE
INIT.	DATE									

NOTE:

1. OPENING IN POLE BASE PLATE SHALL BE EQUAL TO POLE BASE INSIDE DIAMETER MINUS $3\frac{1}{2}$ " BUT SHALL NOT BE LESS THAN $8\frac{1}{2}$ ".




CABLE ENTRANCES AT TOP OF POLE




SECTION B-B

POLE BASE PLATE DETAILS
(8 AND 12 BOLT PATTERN)



SECTION A-A

RADIAL ORIENTATION OF FACTORY INSTALLED
ACCESSORIES AT TOP OF POLE




SECTION C-C

(POLE ATTACHMENT TO BASE PLATE)

FULL-PENETRATION
GROOVE WELD DETAIL



2 CABLE CLAMPS DESIGNED FOR
VARIABLE ATTACHMENT HEIGHTS
FROM 1'-6" TO 6'-6" BELOW
THE TOP OF THE POLE



MONOTUBE STRAIN POLE

	Typical Fabrication Details For Strain Poles		
	PLAN DATE: SEPTEMBER 2023 DESIGNED BY: K.C. DURIGON PREPARED BY: K.C. DURIGON REVIEWED BY: D.C. SARKAR	DESIGNED BY: K.C. DURIGON REVIEWED BY: D.C. SARKAR INIT. DATE	
SCALE 0 NA NONE			09/21/2023 DATE

1. OPENING IN POLE BASE PLATE SHALL BE EQUAL TO POLE BASE INSIDE DIAMETER MINUS 3½" BUT SHALL NOT BE LESS THAN 8½".




WELDED RING STIFFENED MAST ARM CONNECTION

PROJECT I.D. NO.


SHEET NO.

U-5711


Sig.M5




SECTION B-B
FULL-PENETRATION GROOVE WELD DETAIL




PLAN VIEW




FRONT ELEVATION VIEW




SIDE ELEVATION VIEW



BACK ELEVATION VIEW





SECTION A-A
MAST ARM ATTACHMENT PLATE




BOTTOM VIEW

NOTES:


1. PROVIDE A PERMANENT MEANS OF IDENTIFICATION ABOVE THE MAST ARM TO INDICATE PROPER ATTACHMENT ORIENTATION OF THE MAST ARM.
2. DESIGNER WILL DETERMINE THE SIZE OF ALL STRUCTURAL COMPONENTS, PLATES, FASTENERS, AND WELDS SHOWN UNLESS THEY ARE ALREADY SPECIFIED.
3. FABRICATOR IS RESPONSIBLE FOR PROVIDING APPROPRIATE HOLES AT DRAINAGE POINTS TO DRAIN GALVANIZING MATERIALS.
4. FOR MINIMUM EDGE DISTANCE AND NOMINAL BOLT HOLE SIZE, FOLLOW THE LATEST AISC STEEL CONSTRUCTION MANUAL.
5. PROVIDE UPPER HANDHOLE AS NECESSARY WHEN SHAFT EXTENSIONS ARE REQUIRED FOR LUMINAIRE ARMS OR CAMERA. FOR POLES WITHOUT LUMINAIRES/CAMERA, WIRING CAN BE DONE THROUGH THE TOP OF POLE.
6. ALLOWABLE RANGE OF FLANGE TILT ANGLE WILL VARY FROM 0° TO AS REQUIRED.

Prepared In the Offices of:  750 N. Greenfield Pkwy, Garner, NC 27529		Typical Fabrication Details For Mast Arm Connection To Pole		SEAL 	
PLAN DATE: SEPTEMBER 2023 DESIGNED BY: C.F. ANDREWS		PREPARED BY: K.C. DURIGON REVIEWED BY: D.C. SARKAR		DocuSigned by: 	
SCALE 0 NA NONE		REVISIONS		INIT. DATE	
				09/21/2023 DATE	




STRAIN POLE ATTACHMENTS


- NOTES:
- 1. STRAP ALL SIGNAL CABLES TO THE SIDE OF THE POLE WITH 3/4" STAINLESS STEEL STRAPS WHEN THE DISTANCE BETWEEN SPAN WIRE ATTACHMENT CLAMP AND WEATHERHEADS EXCEEDS 3'-0".
 - 2. PROVIDE MINIMUM TWO SPAN WIRE POLE CLAMPS PER POLE.
 - 3. IT IS PROHIBITED TO ATTACH TWO SPAN WIRES AT ONE POLE CLAMP.
 - 4. FOR GENERAL REQUIREMENTS, REFER TO NCDOT STANDARD SPECIFICATIONS FOR ROADWAY AND STRUCTURES, JANUARY 2024.




ATTACHMENT OF CABLE TO INTERMEDIATE METAL POLE



METAL POLE GROUNDING DETAIL FOR STRAIN POLE AND MAST ARM



750 N.Greenfield Pkwy,Garner,NC 27529



Typical Fabrication Details
For
Strain Pole Attachments

PLAN DATE: SEPTEMBER 2023 DESIGNED BY: C.F. ANDREWS
PREPARED BY: K.C. DURIGON REVIEWED BY: D.C. SARKAR


REVISIONS	INIT.	DATE

DocuSigned by:
Kevin Durigon
4B23DC79B3784DA...


SEAL
NORTH CAROLINA
PROFESSIONAL ENGINEER
SEAL
036626
KEYVIN C. DURIGON

09/21/2023
DATE


09-gdt-2023-10-41
S:\175551415 Signal\Signal Design Section\Structures\Drawings\2024 Metal Pole Strd Drawings for LRF\02024 Sig.M6 Strd Fabrication Details-Strain Poles.dgn
Kedurigon




CONCRETE SHAFT ELEVATION



SECTION A-A



TYPICAL "C" BAR DETAIL




TYPICAL FOUNDATION CONDUIT DETAILS

GENERAL NOTES:

- IF ACTUAL SUBSURFACE CONDITIONS DIFFER SIGNIFICANTLY FROM BORING DATA, CONTACT THE ENGINEER BEFORE EXCAVATING OR PLACING CONCRETE.
- CIRCULAR TIE REINFORCING RINGS MAY BE VERTICALLY ADJUSTED BY +/-3" AT A DEPTH BETWEEN 2'-0" AND 3'-0" TO FACILITATE THE INSTALLATION OF ELECTRICAL CONDUIT ENTERING IN THE CAGE.
- FOR STANDARD FOUNDATIONS, SEE SHEET SIG. M8 FOR DETAILS. VERTICAL REINFORCING BARS (V1) MAY BE HORIZONTALLY ADJUSTED BY +/-3" TO FACILITATE THE INSTALLATION OF ELECTRICAL CONDUIT ENTERING INTO THE CAGE.
- PROVIDE 2" TO 5" FOUNDATION PROJECTION ABOVE GROUND LEVEL, DEPENDING ON THE GROUND SLOPE.
- UNLESS OTHERWISE SHOWN, FOUNDATION DESIGNS ARE BASED ON NON-SLOPING LEVEL GROUND SURFACES WITH SLOPE RATIOS OF 8:1 (H:V) OR FLATTER. IF ACTUAL GROUND LINE SLOPES ARE STEEPER, CONTACT THE ENGINEER BEFORE EXCAVATING OR PLACING CONCRETE.
- CONSTRUCT FOUNDATIONS IN ACCORDANCE WITH NCDOT STANDARD PROVISIONS SP09 R005- FOUNDATIONS AND ANCHOR ROD ASSEMBLIES FOR METAL POLES. ALL APPLICABLE 2024 NCDOT STANDARD SPECIFICATIONS ARE REFERENCED IN THIS PROVISION. REFER TO THE NCDOT RESOURCES/SPECIFICATIONS PAGE LOCATED ON THE CONNECT NCDOT WEBSITE.
[https://connect.ncdot.gov/resources/Specifications and Special Provisions.aspx](https://connect.ncdot.gov/resources/Specifications%20and%20Special%20Provisions.aspx)
- USE AIR ENTRAINED AA CONCRETE MIX WITH A COMPRESSION STRENGTH OF f'c=4500 psi (MIN) AFTER 28 DAYS.
- USE ASTM A615 GRADE 60 DEFORMED BARS FOR ALL REINFORCING STEEL. MAINTAIN AT LEAST 3" COVER ON ALL REINFORCEMENT.
- LOCATE IDENTIFICATION TAG ON TOP OF THE FOUNDATION, DIRECTLY ABOVE THE CONDUIT'S ENTRY POINT.
- PROVIDE TWO LAYERS OF 4 MESH GALVANIZED WELDED 23 GAUGE (0.025) 6" WIDE AROUND PIPES UNDER THE BASE PLATE AND SECURE IT WITH TIES IF NECESSARY.
- PREFERRED LOCATION FOR THE I.D. TAG IS AS SHOWN IN DETAIL-A: DIRECTLY ABOVE THE CONDUIT ENTERING THE FOUNDATION.

REINFORCING STEEL TABLE FOR STANDARD DRILL PIER SHAFT (4'-0" DIAMETER)						
"D" SHAFT DIAMETER	CONCRETE VOLUME (CU. YDS)	BAR NAME	MIN. SIZE	TYPE	LENGTH	
4'-0"	.465 X L	V1	-	#8 STR.	**	
		C	*	#4 CIR.	12'-6"	


* SEE NOTE 2
** SEE NOTE 3



DETAIL-A

D = DIAMETER
L = LENGTH / DEPTH
mm = MONTH
yy = YEAR

TYPICAL FOUNDATION ANCHOR BOLT DETAILS
(REINFORCING CAGE NOT SHOWN FOR CLARITY)



Prepared In the Offices of: 750 N.Greenfield Pkwy,Garner,NC 27529 SCALE 0 NA NONE	Construction Details For Foundations PLAN DATE: SEPTEMBER 2023 DESIGNED BY: K.C. DURIGON PREPARED BY: K.C. DURIGON REVIEWED BY: D.C. SARKAR <table><tr><th>REVISIONS</th><th>INIT.</th><th>DATE</th></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr></table>	REVISIONS	INIT.	DATE										SEAL DocuSigned by: 4B23DC79B3784DA 09/23/2023 DATE
	REVISIONS	INIT.	DATE											

SOIL CONDITION

STANDARD STRAIN POLES						STANDARD FOUNDATIONS 48" Diameter Drilled Pier Length (L) – Feet							Reinforcement			
Case No.	Pole Height (Ft.)	Base Plate BC (In.)	Reactions at the Pole Base			Clay				Sand			Longitudinal		Stirrups	
			Axial (kip)	Shear (kip)	Moment (ft–kip)	Medium N–Value 4–8	Stiff N–Value 9–15	Very Stiff N–Value 16–30	Hard N–Value > 30	Loose N–Value 4–10	Medium N–Value 11–30	Dense N–Value > 30	Bar Size (#)	Quantity (ea.)	Bar Size (#)	Spacing (in.)
S26L1	26	22	2	9	210	19.5	12.5	9	6.5	15.5	14.5	13	8	12	4	12
S26L2	26	23	2	10	240	19.5	12	9	6.5	15.5	14.5	13	8	12	4	12
S26L3	26	25	2	11	260	20.5	12	10	8	16	15	13	8	12	4	12
S30L1	30	22	2	9	230	19	11	9	7	15.5	14	12.5	8	12	4	12
S30L2	30	23	2	10	270	20	12	10	8	16	14.5	13	8	12	4	12
S30L3	30	25	2	11	290	21	12	10	8	17	15	13.5	8	12	4	12
S30H1	30	25	3	13	355	23	13	11	9	18	16.5	14.5	8	12	4	12
S30H2	30	29	3	15	405	25	14	11	9	19	17.5	15.5	8	14	4	12
S30H3	30	29	3	16	430	26	15	12	9	20	18	16	8	14	4	6
S35L1	35	22	3	8	260	19.5	12	10	8	15.5	14.5	13	8	12	4	12
S35L2	35	23	3	10	300	21	12	10	8	16.5	15	13.5	8	12	4	12
S35L3	35	25	3	10	320	21.5	13	10	8	17	15.5	14	8	12	4	12
S35H1	35	25	3	12	390	23.5	14	11	9	18	17	15	8	14	4	12
S35H2	35	29	4	14	460	26	15	12	9	20	18	16	8	14	4	6
S35H3	35	29	4	16	495	28.5	15	13.5	10	21.5	19	17	8	14	4	6

48" DIAMETER FOUNDATION CONCRETE VOLUME (CUBIC YARDS) = (0.465) x DRILLED PIER LENGTH

PROJECT I.D. NO.	SHEET NO.
U-5711	Sig.M8

GENERAL NOTES:


1. VALUES SHOWN IN THE "REACTIONS AT THE POLE BASE" COLUMN REPRESENT THE MINIMUM ACCEPTABLE CAPACITY ALLOWED FOR DESIGN USING A COMBINED FORCE RATIO (CFR) OF 1.00.
2. USE CHAIRS AND SPACERS TO MAINTAIN PROPER CLEARANCE.
3. FOR FOUNDATION, ALWAYS USE AIR-ENTRAINED CONCRETE MIX.

FOUNDATION SELECTION:

1. PERFORM A STANDARD PENETRATION TEST AT EACH PROPOSED FOUNDATION SITE TO DETERMINE "N" VALUE.
2. SELECT THE APPROPRIATE WIND ZONE FROM M1 DRAWING.
3. SELECT THE SOIL TYPE (CLAY OR SAND) THAT BEST DESCRIBES THE SOIL CHARACTERISTICS.
4. GET THE APPROPRIATE STANDARD POLE CASE NUMBER FROM THE PLANS OR FROM THE ENGINEER.
5. SELECT THE APPROPRIATE COLUMN UNDER "STANDARD FOUNDATIONS" BASED ON SOIL TYPE AND "N" VALUE. SELECT THE APPROPRIATE ROW BASED ON THE POLE LOAD CASE.
6. THE FOUNDATION DEPTH IS THE VALUE SHOWN IN THE "STANDARD FOUNDATIONS" CATEGORY WHERE THE COLUMN AND THE ROW INTERSECT.
7. USE CONSTRUCTION PROCEDURES AND DESIGN METHODS PRESCRIBED BY FHWA-NHI-10-016 MANUAL FOR DRILLED SHAFTS.

09-001-2023 19x48
S:\1\SSM1\15 Signal\Signal Design Section\Structures\Drawings\2024 Metal Pole Str Drawing for LBF02024 Sig.M8 Str. Strain Pole Found.-Saturated Soil Condition.dgn
Kedur.fgn

Prepared In the Offices of:



750 N.Greenfield Pkwy,Garner,NC 27529

SCALE

0 1"=10' NA

NONE

Standard Strain Pole Foundation for All Soil Conditions

PLAN DATE: SEPTEMBER 2023

DESIGNED BY: K.C. DURIGON

PREPARED BY: K.C. DURIGON


REVIEWED BY: D.C. SARKAR

REVISIONS

INIT.

DATE

SEAL




DocuSigned by:

4B23DC79B3784DA


09/21/2023

DATE

Standard Strain Pole Foundation – All Soil Conditions



BASE PLATE DETAILS



SECTION D-D
(POLE ATTACHMENT TO BASE PLATE)
FULL - PENETRATION
GROOVE WELD DETAIL

CCTV CAMERA POLE
(NOT TO SCALE)

- NOTES:
1. THIS DRAWING PROVIDES BASIC DETAILS FOR CCTV POLES. PROJECT REQUIREMENTS MAY REQUIRE SPECIAL FACTORY PREPS THAT ARE NOT SHOWN ON THESE DETAILS.
 2. DETAILS FOR INTERNAL CAMERA LOWERING SYSTEMS ARE NOT SHOWN.
 3. POLE MOUNTED CABINETS MAY REQUIRE MODIFICATIONS TO THE LOWER HANDHOLE OPENING TO MOUNT CABINETS. 4" X 8" REINFORCED HANDHOLES ARE ACCEPTABLE OPTIONS, AND MAY BE PREFERRED.
 4. OPENING IN POLE BASE SHALL BE EQUAL TO POLE BASE INSIDE DIAMETER MINUS 3 1/2" BUT SHALL NOT BE LESS THAN 8 1/2".
 5. USE COMPACT SECTION CRITERIA D/T RATIO PER AASHTO LTS-LRFD 1ST EDITION SECTION 5.7.2.

	Typical Fabrication Details For CCTV Poles		
	PLAN DATE: SEPTEMBER 2023	DESIGNED BY: K.C. DURIGON	
	PREPARED BY: K.C. DURIGON	REVIEWED BY: C.F. ANDREWS	
SCALE: 0 = NA	REVISIONS	INIT.	DATE
NONE			

DocuSigned by:

4B23DC79B3784DA...

SEAL

09/21/2023

DATE