PROJECT NO.	SHEET NO.	TOTAL NO.
PT.07.07.10791, 2027CPT.07.07	15	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	BEGIN MP	END MP	0106000000-E BORROW EXCAVATION	1220000000-E INCIDENTAL STONE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E MILLING ASPHALT PAVEMENT, DEPTH (1 1/2")	1297000000-E MILLING ASPHALT PAVEMENT, DEPTH (1-1/4")	1330000000-E INCIDENTAL MILLING	1491000000-E ASPHALT CONC BASE COURSE, TYPE B25.0C	1519000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1523000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775000000-E ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	2830000000-N ADJUSTMENT OF MANHOLES	2845000000-N ADJUSTMENT OF METER BOXES OR VALVE BOXES	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEEDING & MULCHING	7990000000-E INDUCTIVE LOOP SAW CUT (DEEP CUT)
							MI	FT			CY	TONS	SMI	TON	SY	SY	SY	TON	TONS	TONS	TON	TON	SY	GAL	EA	EA	LF	LF	AC	LF
2027CPT.07.07.10791	Rockingham	1	NC-704	FROM US 220 TO NC 65	1	2	8.14	25	6.84	14.98	643		16.08	1,823	138,425		11,770	8,603		13,878	1,207	16					3,216	322	2.34	
TOTAL FOR MAP NO. 1							**8.14**				**643**		**16.08**	**1,823**	**138,425**		**11,770**	**8,603**		**13,878**	**1,207**	**16**					**3,216**	**322**	**2.34**	
2027CPT.07.07.10791	Rockingham	2	NC-14	FROM NEW PVMT JOINT 750' SE OF SR 2543 - ADAMS ROAD TO SR 1985 - WILSON ROAD	2	5	2.93	71	0.32	3.25		15			125,938		9,359			12,501	738	16								4,506
TOTAL FOR MAP NO. 2							**2.93**					**15**			**125,938**		**9,359**			**12,501**	**738**	**16**								**4,506**
2027CPT.07.07.10791	Rockingham	3	US-158 W	FROM SR 2670 - S SCALES STREET TO SR 2686 - RICHARDSON DRIVE	2	2	1.69	36	11.91	13.60		15			43,291		6,946			4,642	275	16			11	9				2,302
TOTAL FOR MAP NO. 3							**1.69**					**15**			**43,291**		**6,946**			**4,642**	**275**	**16**			**11**	**9**				**2,302**
2027CPT.07.07.10791	Rockingham	4	US-158 E	FROM SR 2670 - S SCALES STREET TO SR 2686 - RICHARDSON DRIVE	2	2	1.69	36	11.91	13.60		15			43,552		3,873			4,382	259	16			11					2,592
TOTAL FOR MAP NO. 4							**1.69**					**15**			**43,552**		**3,873**			**4,382**	**259**	**16**			**11**					**2,592**
TOTAL FOR PROJ NO. 2027CPT.07.07.10791							**14.45**				**643**	**45**	**16.08**	**1,823**	**351,206**		**31,948**	**8,603**		**35,403**	**2,479**	**64**			**22**	**9**	**3,216**	**322**	**2.34**	**9,400**
2027CPT.07.07.20791	Rockingham	5	SR-1709 / N HAMILTON ST	FROM SR 1708 - BRYANT STREET TO SR 1605 - S OAKLAND AVE	3	2	0.61	20	0.00	0.61		51				6,981	334		553		36	3			4	3				
TOTAL FOR MAP NO. 5							**0.61**					**51**				**6,981**	**334**		**553**		**36**	**3**			**4**	**3**				
2027CPT.07.07.20791	Rockingham	6	SR-2740 / ARROWHEAD RD	FROM CUL-DE-SAC TO SR 1914 - OREGON HILL ROAD	4	2	0.35	19	0.00	0.35	7	48	0.69	20			208		386		26	14	4,253	1,403			138	14	0.03	
TOTAL FOR MAP NO. 6							**0.35**				**7**	**48**	**0.69**	**20**			**208**		**386**		**26**	**14**	**4,253**	**1,403**			**138**	**14**	**0.03**	
2027CPT.07.07.20791	Rockingham	7	SR-2422 / MONROETON RD	FROM SR 2406 - IRON WORKS RD TO US 158	4	2	1.59	22.5	0.00	1.59	31	60	3.15	89			392		1,975		129	16	21,212	7,000			630	63	0.11	702
TOTAL FOR MAP NO. 7							**1.59**				**31**	**60**	**3.15**	**89**			**392**		**1,975**		**129**	**16**	**21,212**	**7,000**			**630**	**63**	**0.11**	**702**
2027CPT.07.07.20791	Rockingham	8	SR-2992 / STREAMSIDE CT	FROM CUL-DE-SAC TO CUL-DE-SAC	4	2	0.11	21	0.00	0.11	2		0.23	6					194		13	9	2,069	683			45	5	0.01	
TOTAL FOR MAP NO. 8							**0.11**				**2**		**0.23**	**6**					**194**		**13**	**9**	**2,069**	**683**			**45**	**5**	**0.01**	
2027CPT.07.07.20791	Rockingham	9	SR-2989 / OAK LEAF DR	FROM SR 2992 - STREAMSIDE CT TO US 158	4	2	0.20	19.5	0.00	0.20	4	3	0.38	11			404		213		14	2	2,346	774			76	8	0.01	
TOTAL FOR MAP NO. 9							**0.20**				**4**	**3**	**0.38**	**11**			**404**		**213**		**14**	**2**	**2,346**	**774**			**76**	**8**	**0.01**	
2027CPT.07.07.20791	Rockingham	10	SR-1239 / ANGIELINE DR	FROM END OF MAINTENANCE TO SR 1110 - ELLISBORO ROAD	4	2	0.40	20.5	0.00	0.40	8	45	0.80	23			175		486		32	8	5,116	1,688			161	16	0.03	
TOTAL FOR MAP NO. 10							**0.40**				**8**	**45**	**0.80**	**23**			**175**		**486**		**32**	**8**	**5,116**	**1,688**			**161**	**16**	**0.03**	
TOTAL FOR PROJ NO. 2027CPT.07.07.20791							**3.26**				**52**	**207**	**5.25**	**149**		**6,981**	**1,513**		**3,807**		**250**	**52**	**34,996**	**11,548**	**4**	**3**	**1,050**	**106**	**0.19**	**702**
GRAND TOTAL							**17.71**				**695**	**252**	**21.33**	**1,972**	**351,206**	**6,981**	**33,461**	**8,603**	**3,807**	**35,403**	**2,729**	**116**	**34,996**	**11,548**	**26**	**12**	**4,266**	**428**	**2.53**	**10,102**