

ADA SUMMARY OF QUANTITIES - US 64 BUS FROM MORNING FLYER WAY TO 70 FT EAST OF OLD HOME PLACE CIR.

Municipality:	Unincorporated Wake Co
WBS Number:	2027CPT.05.02.10921 , ETC.
County:	Wake

Sheet No.
25

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	2655000000-E (SY) 5" Monolithic Concrete Island (Keyed In)	2738000000-E (SY) Remove 5" Monolithic Concrete Islands (Keyed In)	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2605000000-N (EA) Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps	Improvement Type
26823	1	US-64 BUS (Wendell Blvd)	Sheetz (505 Wendell Blvd)												1			Type 1 Modified - 848.06
26656	2	US-64 BUS (Wendell Blvd)	State Employees' Credit Union (605 Wendell Blvd)												1			Type 1 Modified - 848.06
26659	2	US-64 BUS (Wendell Blvd)	State Employees' Credit Union (605 Wendell Blvd)												1			Type 1 Modified - 848.06
26657	3	US-64 BUS (Wendell Blvd)	Mobility Ln												1			Type 2A - 848.06
26660	4	US-64 BUS (Wendell Blvd)	SPC Mechanical (1500 Wendell Blvd) North Entrance								4				1			Type 1C - 848.06
26661	4	US-64 BUS (Wendell Blvd)	SPC Mechanical (1500 Wendell Blvd) North Entrance												1			Type 7 - 848.06
26662	4	US-64 BUS (Wendell Blvd)	SPC Mechanical (1500 Wendell Blvd) North Entrance												1			Type 7 - 848.06
12326	5	US-64-BUS (Wendell Blvd)	Hephzibah Baptist Church (1794 Wendell Blvd) West Entrance												1			Type 1C - 848.06
12328	6	US-64-BUS (Wendell Blvd)	Hephzibah Baptist Church (1794 Wendell Blvd) East Entrance												1			Type 1C - 848.06
12329	6	US-64-BUS (Wendell Blvd)	Hephzibah Baptist Church (1794 Wendell Blvd) East Entrance												1			Type 1C - 848.06
26824	7	US-64-BUS (Wendell Blvd)	SR-2473 (Old Oak Tree Rd)												1			Type 1C - 848.06
-	-	-	-	-	3*	-	44*	-	-	6*	-	-	-	-	-	-	-	
Sub-Total for US 64 Bus From Morning Flyer Way To 70 ft East of Old Home Place Cir.				0	3	0	44	0	0	6	4	0	0	0	11	0	0	

*Contingency line item amount provided for additional adjustments outside of curb ramp pay limits, as needed.

**While ramp is compliant upon initial inspection, it is to be improved in order to create a more resilient curb ramp.

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted. (3) In accordance with PROWAG Sections R304.2.1 and R304.3.1, curb ramp running slope is to be constructed to a maximum of 8.33%. Where the curb ramp length must exceed 15 feet to achieve an 8.33% running slope, the curb ramp length shall extend at least 15 feet and may have a running slope greater than 8.33%.