PROJECT REFERENCE NO.	SHEET NO.
I-2513AC	EC-3B

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	15+00	14+45	RT	70 TYPE 2
4	-L-	17+60	20+00	RT	245 TYPE 2
6	-Y2A-	12+45	29+00	RT	650 TYPE 3
6	-Y2B-	16+00	15+00	RT	110 TYPE 2
6	-DET2-	19+64	15+00	RT	490 TYPE 1
7	-L-	70+75	70+00	LT	50 TYPE 1
8	-L-	101+07	101+53	RT	75 TYPE 4
6	-DET2-	19+64	18+00	LT	175 TYPE 1
		SUBTOTAL TYPE 1			715
		SUBTOTAL TYPE 2			425
		SUBTOTAL TYPE 3			650
		SUBTOTAL TYPE 4			20
		ADDITIONAL PSRM TO BE INSTALLED			0
				TOTAL	1810

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)