



KEY-IN RIP RAP
TRANSITION PAD
65 TONS CL II RIP-RAP
130 SY GEOTEXTILE

-L- PC Sta. 26+55.42
Y2RCP - POT Sta. 10+00.00
-L- PT Sta. 26+88.21 53.50

7' LATERAL BASE DITCH
SEE DETAIL 23
EST. 202 TONS CL II RIP RAP
EST. 358 SY GEOTEXTILE

N

NOTE:	PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
NOTE:	ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING RW OR EASEMENT.
NOTE:	PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
NOTE:	CONTRACTOR SHALL PROVIDE GROUND COVER ON EXPOSED SLOPES IN ACCORDANCE WITH THE "SOIL STABILIZATION TIMEFRAMES," SEE EC-3C.
NOTE:	PRIOR TO INSTALLATION OF EROSION CONTROL DEVICES, CONTRACTOR SHALL VERIFY BOUNDARIES OF JURISDICTIONAL AREAS AND DELINEATE WITH SAFETY FENCE OR FLAGGING

6/19/2026 R:\Environmental\Design\AC.PSH\1-25\3AC.EC.PSH_04.dgn David Becker	8/17/95
--	---------