

SUMMARY 3: PHASE I, STEP 4A

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will use methods including but not limited to recross-sectioning, truck measurements, and aerial surveys to compute final quantities which the contractor will be paid.

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
32+00.00	0	0
32+50.00	20	15
33+00.00	19	15
33+50.00	18	15
34+00.00	15	23
34+50.00	12	34
35+00.00	10	43
35+50.00	7	52
36+00.00	5	35
36+50.00	3	16
37+00.00	2	33
37+50.00	2	56
38+00.00	2	50
38+50.00	2	44
39+00.00	2	62
39+50.00	2	86
40+00.00	2	114