SUMMARY 11: PHASE III, STEP 2B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
I-2513AC	X-1K

Quantities are approximate only. The Resident Engineer will use methods including but not limited to recross-sectioning, truck measurements, and aerial surveys to compute final quantities which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
110+50.00	0	0
111+00.00	7	22
111+50.00	18	4
112+00.00	37	0
112+50.00	50	0
113+00.00	55	0
113+50.00	56	0
114+00.00	58	0
114+50.00	60	0
115+00.00	62	0
115+50.00	64	0
116+00.00	68	0
116+50.00	67	0
117+00.00	66	0
117+50.00	71	0
118+00.00	71	0
118+50.00	71	0
119+00.00	70	0
119+50.00	67	0
120+00.00	63	0
120+50.00	58	0
121+00.00	49	0