Docusign Envelope ID: 83617E26-EBF2-8BCC-8248-7916CADECCD9

5/28/99

-Y10-

HNTB NORTH CAROLINA, P.C.
4000 Center at North Hills St
Suite 500
Raleigh, North Carolina 27609
NC License No: C-1554

PROJECT REFERENCE NO.	SHEET NO.
R-5759	36

ROADWAY DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 36786 ENGINEER
Douglas Edward Slaten
A878936E9B4F4A1...
10/12/2026

HYDRAULICS ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 40801 ENGINEER
Paul Richard McAmaro
157E2E7A2...
10/12/2026

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DITCH LEGEND	
LEFT DITCH	----------·----------
RIGHT DITCH	----------

PIPE HYDRAULIC DATA
-Y10- Sta.16+00 (STR #1134)

DRAINAGE AREA	= 0.52	AC
DESIGN FREQUENCY	= 25	YRS
DESIGN DISCHARGE	= 1.6	CFS
DESIGN HW ELEVATION	= 1164.70	FT
100 YEAR DISCHARGE	= 1.9	CFS
100 YEAR HW ELEVATION	= 1164.76	FT
OVERTOPPING FREQUENCY	= >500	YRS
OVERTOPPING DISCHARGE	= 12	CFS
OVERTOPPING ELEVATION	= 1166.38	FT

PI = 14+00.00
EL = 1,172.36'
K = 22
VC = 150'
V = 30 MPH

PI = 15+50.00
EL = 1,167.25'
K = 37
VC = 150'
V = 30 MPH

PROPOSED GRADE

(+)3.3000%
(-)3.4054%
(+) 2.5061%
(-) 5.4140%
(-)3.4054%
(-) 1.6958%
(+)0.7000%

BEGIN GRADE
-Y10- STA 10+25.00
ELEV. = 1159.99'

EXISTING GROUND

BEGIN DITCH
PI = 12+25.00 (LT)
EI = 1164.36

PI = 14+25.00 (LT)
EI = 1169.37'

PI = 14+75.00 (LT)
EI = 1166.66

18" RCP-IV

END DITCH
PI = 16+25.00 (LT)
EI = 1164.12

END GRADE
-Y10- STA 17+00.00
ELEV. = 1168.30'

10+00 11+00 12+00 13+00 14+00 15+00 16+00 17+00
1200 1190 1180 1170 1160 1150 1140 1130 1120 1110

FOR -Y10- PLAN, SEE SHEET 11

-Y11-

DITCH LEGEND	
LEFT DITCH	----------·----------
RIGHT DITCH	----------

CENTERLINE INTERSECTION
-C4- STA. 12+39.23 =
-Y11- STA 10+00.00

PI = 10+75.00
EL = 1,167.26'
K = 27
VC = 110'
V = 30 MPH

PI = 13+00.00
EL = 1,155.87'
K = 111
VC = 300'
V = 50 MPH

EXISTING GROUND

PROPOSED GRADE

(-)1.0000%
(-)5.0620%
(-)6.9513%
(-)5.0620%
(-)12.3600%
(-) 4.9914%
(+) 0.8000%

BEGIN GRADE
-Y11- STA 10+00.00
ELEV. = 1168.01'

BEGIN DITCH
PI = 11+25.00 (RT)
EI = 1163.95

BEGIN DITCH
PI = 11+25.00 (LT)
EI = 1161.78

END DITCH
PI = 12+50.00 (RT)
EI = 1155.26

18" RCP-IV

PI =14+25.00 (LT)
EI = 1146.80

END DITCH
PI = 15+50.00 (LT)
EI = 1147.80

END GRADE
-Y11- STA 15+50.00
ELEV. = 1149.97'

PIPE HYDRAULIC DATA
-Y11- Sta.14+25 (STR #1801)

DRAINAGE AREA	= 2.02	AC
DESIGN FREQUENCY	= 25	YRS
DESIGN DISCHARGE	= 5.4	CFS
DESIGN HW ELEVATION	= 1148.10	FT
100 YEAR DISCHARGE	= 6.3	CFS
100 YEAR HW ELEVATION	= 1148.25	FT
OVERTOPPING FREQUENCY	= >500	YRS
OVERTOPPING DISCHARGE	= 22	CFS
OVERTOPPING ELEVATION	= 1152.71	FT

10+00 11+00 12+00 13+00 14+00 15+00 16+00
1200 1190 1180 1170 1160 1150 1140 1130 1120 1110

FOR -Y11- PLAN, SEE SHEETS 11 & 18

07-AUG-2026 09:40
C:\Projects\R-5759_RDY_PFL_PSH36.dgn
HNTB