

REVISIONS

RIGHT OF WAY CONTROL SHEET

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y1	10+65.00	29.56	875572.9986	1378693.9307
Y1	10+65.00	35.00	875572.0976	1378699.2999
Y1	10+95.00	37.00	875597.7727	1378706.0730
Y1	10+95.00	30.95	875599.3394	1378700.2315

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y3	12+12.00	84.50	876519.5264	1378567.4178
Y3	12+28.00	84.50	876500.7908	1378584.5324
Y3	12+28.00	42.00	876531.1528	1378614.2712

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y4	10+25.00	-119.00	877695.2966	1378926.2521
Y4	10+73.00	-50.00	877618.0100	1378972.5864
Y4	10+78.00	-76.50	877642.5269	1378984.1915
Y4	11+00.00	-82.00	877641.0452	1379011.0735
Y4	11+11.00	-64.00	877619.9930	1379018.1393
Y4	11+57.12	86.55	877463.7103	1379005.0231
Y4	11+88.00	42.72	877490.5398	1379052.6905
Y4	11+88.00	78.20	877457.8957	1379038.7940
Y4	14+03.00	30.00	877436.3989	1379268.2144
Y4	14+03.00	47.75	877419.0132	1379264.6223
Y4	14+16.50	-30.00	877492.5822	1379293.2252

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y5	10+95.00	30.00	878378.3451	1378290.6094

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y6REV	15+90.23	-15.00	878986.3077	1377405.9494
Y6REV	16+23.21	-19.88	879017.8866	1377401.0363

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y7	11+10.26	44.04	880010.7491	1377104.1566
Y7	11+63.00	47.00	880017.1691	1377154.3936
Y7	11+63.00	31.70	880032.2738	1377151.9424
Y7	11+91.00	32.80	880035.1865	1377178.9634
Y7	11+91.00	47.00	880021.1111	1377180.8711
Y7	13+26.75	-30.00	880108.1849	1377307.7482
Y7	13+26.75	-43.75	880121.9015	1377306.7899

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y9	12+16.02	31.32	881398.9907	1375634.6004
Y9	12+50.00	31.00	881422.6468	1375664.0756
Y9	12+88.50	-15.00	881483.0170	1375658.7723
Y9	12+88.50	-69.50	881518.1914	1375617.1429
Y9	12+90.50	36.00	881451.8339	1375699.1814
Y9	13+10.00	36.00	881467.3160	1375711.7745
Y9	13+10.00	-69.50	881533.7847	1375629.8467
Y9	13+10.00	-15.49	881499.7575	1375671.7879
Y9	13+39.50	-18.43	881524.5182	1375688.0912
Y9	13+50.75	24.75	881506.0490	1375728.7121
Y9	13+50.75	15.00	881512.1918	1375721.1405
Y9	13+53.75	-50.00	881555.4738	1375672.5538
Y9	13+73.00	-24.37	881554.2731	1375704.5876
Y9	14+00.00	30.00	881540.9872	1375763.8183
Y9	14+35.89	-39.14	881612.4196	1375732.7367

PROJECT REFERENCE NO.
R-5759

SHEET NO.
RW03E-10

Location and Surveys

DEWBERRY ENGINEERS INC.
2610 WYCLIFF ROAD
SUITE 410
RALEIGH, NC 27607

PROJECT SURVEYOR


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

I, Adam C. Hales, certify that the right of way and permanent easement monumentation for this project shown herein was completed under my direct and responsible charge from an actual survey made under my supervision; that all horizontal closures had a minimum ratio of precision of 1:10,000 (Class A). Field work was performed from 8/30/2022 to 8/26/2026, and all coordinates are based on NAD83/2011. That this survey was performed to meet the requirements of 21NCAC 56.1600 as applicable.

This 4th day of September, 2026.

DocuSigned by:

ES1DD8C1163E43D...
Professional Land Surveyor L-4980

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y10	11+09.96	-29.72	882265.1797	1374587.6895
Y10	11+09.96	-46.75	882281.6873	1374591.8758
Y10	12+03.00	30.00	882179.5774	1374657.4094
Y10	12+15.50	39.00	882166.7032	1374664.8879
Y10	12+22.50	30.00	882172.3105	1374674.5665
Y10	12+41.50	-42.78	882230.5014	1374722.2892
Y10	12+73.99	-50.37	882221.6340	1374756.7073
Y10	12+84.96	-53.35	882218.5931	1374768.5102
Y10	12+86.77	-69.53	882231.7579	1374778.1170
Y10	12+92.31	-65.20	882224.9864	1374781.2909
Y10	13+12.00	106.00	882067.8583	1374710.7401
Y10	13+25.00	127.00	882044.3478	1374708.7621
Y10	13+25.00	78.25	882085.4708	1374734.9435
Y10	13+89.00	45.55	882078.6621	1374801.2524
Y10	14+33.00	62.00	882035.6830	1374830.9207
Y10	14+33.00	56.00	882040.7432	1374834.1448
Y10	14+40.00	62.00	882030.8663	1374838.7885
Y10	14+40.00	50.00	882041.2114	1374844.8694
Y10	16+45.00	134.50	881966.4594	1375132.7090
Y10	16+57.00	137.50	881974.5604	1375151.6336

ROW MARKER PERMANENT EASEMENT				
ALIGN	STATION	OFFSET	NORTH	EAST
Y11	12+32.00	106.80	882404.0866	1375411.3943
Y11	12+88.00	50.00	882475.0696	1375366.0265
Y11	13+04.51	50.00	882492.6361	1375368.1218

NOTES:

- IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
- PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
- RIGHT OF WAY MONUMENTATION ESTABLISHED 8/30/2022 TO 8/26/2026 .