

North Carolina Department of Transportation

Highway Stormwater Program STORMWATER MANAGEMENT PLAN



Version 3.02: Released April 23, 2024)

FOR NCDOT PROJECTS WBS Element: 34598.2.2 TIP/Proj No: R-4045/BR-0012 County(ies): Cleveland Page **General Project Information** WBS Element: 34598.2.2 TIP Number: R-4045/BR-0012 Project Type: Roadway Widening 6/3/2024 Date: NCDOT Contact: Andy Hussey Contractor / Designer: Brandon Johnson, PE Address: 1020 Birch Ridge Drive Address: 3301 Benson Dr Room #16 Suite 400 Raleigh, NC 27610 Raleigh, NC 27609 Phone: (919) 707-6641 Phone: (919) 322-0115 Email: brandon.iohnson@summitde.com Email: lahussev@ncdot.gov City/Town: Mooresboro County(ies): Cleveland River Basin(s): Broad CAMA County? Nο Wetlands within Project Limits? Yes **Project Description** Rural Area with Residential and Agricultural Land Use Project Length (lin. miles or feet): 1.59 Surrounding Land Use: **Existing Site Proposed Project** Project Built-Upon Area (ac.) 19.2 15.6 Typical Cross Section Description: 2 12' lane divided highway with 12' total shoulder (10' payed) 2 12' lane divided highway with 4' payed shoulder Annual Avg Daily Traffic (veh/hr/day): Design/Future: 30300 Year: 2043 Existing: 22600 Year: 2023 General Project Narrative: State Project involves an upgrade of US 74 at SR 1168 insterection to an interchange and replacement of NCDOT Bridge 220048 and 220049 over Sandy Run Creek on US 74 in (Description of Minimization of Water Cleveland County. An addition of 2 ramps that will fill over two jurisdictional streams, and one of the ramps will be a new crossing over UT to Sandy Run Creek. An addition of 1 Quality Impacts) ramp, 1 loop and a major collector that will be new crossings over UT to Sandy Run Creek. Minimization measures such as utilizing 1.5:1 fill slopes are used near wetlands and streams to reduce permanent stream impact. Grass lined ditches are used to help promote infiltration in proposed ditches and ditches with rip rap are used to reduce erosions. Bank stabilization and rip rap at embankment are utilized to reduce erosion at streams.

Stream SA is outside the project limits, so there are no surface water impacts to this stream.

Stream SB is crossed by four alignments (-Y1RPA-, -Y1LPA-, -Y1LPA-, -Y1-, and -Y2-). The proposed -Y1RPA- crossing is a single span bridge. Proposed fill slopes of 2:1 and 1.5:1 ensure all fill is at least 10 feet outside top of bank. The existing topography around the stream is very steep, so ditches are lined with rip rap to reduce velocity and rip rap at embankment is used at the ties to the stream. The proposed -Y1LPA- crossing is an 8' x 7' box culvert. The culvert is aligned with the upstream and downstream channels to the greatest extent possible with minimal channel work. The culvert is embedded 1.0' and rip rap channels/protection at the inlet and outlet are embedded to align with the stream. 1.5:1 fill slopes are utilized to minimize culvert length, minimize impacts to Wetland WF, and ensure the fill slope does not impact the stream south of the culvert. Streambank stabilization is proposed to protect the banks during and after culvert phasing. The proposed -Y1- crossing is a 78" pipe. The pipe is aligned the upstream and downstream channels to the greatest extent possible with minimal channel work. The pipe is embedded 1.0' and rip rap channels/protection at the inlet and outlet are embedded to align with the stream. 1.5:1 fill slopes are utilized to minimize pipe length and minimize impacts to Wetland WE. Additionally, the alignment of -Y1- is shifted west of the existing which reduces the impact to Wetland WE with the grade increase required for the -Y1- bridge. The ditch tie in is located at the proposed rip rap channel at the pipe inlet. The proposed -Y2- crossing is a 60" pipe. The pipe is aligned the upstream and downstream channels to the greatest extent possible with minimal channel work. The pipe is embedded 1.0' and rip rap channels/protection at the inlet and outlet are embedded to align with the stream. 1.5:1 fill slopes is utilized to minimize pipe length. The drainage areas of the ditches in the northwest and southeast quadrants are large, so the ditches are lined with rip rap and the last ditch section has a slope of 0.005 ft/ft to reduce the velocity at the tie to the stream. Similarly, the ditch in the southwest quadrant utilizes rip rap to reduce velocity, and all ditches tie to the pipe inlet/outlet stabilization. With the large ditch in the southeast quadrant tying to Stream SB, adding additional drainage area to Stream SD is minimized.

Stream SE has a temporary impact due to a clean water diversion being used to divert clean water around the construction site tying to the stream.

Stream SC is crossed by alignment -SR1-. A proposed 60" pipe buried 1.0' will be used as the crossing. Fill slopes are 2:1 on both sides of the alignment near the stream to minimize stream impacts. Outlet channel stabilization will be used to reduce erosion at the downstream end. Rip rap will be extended downstream to include the outlet of a closed drainage system that discharges into the stream. Due to the steepness of the existing topography, the storm drain system will also utilize elbows to reduce the velocity of the discharge going into the stream. Wetland WB and WC are directly downstream of the crossing. WB will not be impacted. The impacts to WC will be minimized with the use of 2:1 fill slopes. Existing topography near the stream is steep and stream bank stabilization will be installed at the inlet to reduce runoff velocity from the proposed ditches and minimize erosion.



Version 3.02; Released April 23, 2024)

WBS Element: 34598.2.2

North Carolina Department of Transportation

Highway Stormwater Program STORMWATER MANAGEMENT PLAN



FOR NCDOT PROJECTS

R-4045/BR-0012

TIP No.:



Page

2

General Project Narrative: (Description of Minimization of Water Quality Impacts)

County(ies): Cleveland Additional General Project Information

Per the CE document, a new 54" pipe will be placed parallel to the existing 48" pipe on Stream SC under US 74, ensuring a more stable stream with less susceptibility to stream blockages, minimizing impacts to dwarf-flowered heartleaf plants located upstream from the existing inlet. The -L- alignment has been shifted north to avoid any impacts to the upstream stream section and the dwarf flowered heartleaf boundary. NCDOT Hydraulics design guidelines were followed to minimize impacts to aquatic passage. A jurisdictional stream rip rap protection pad is proposed at the outlet of retain existing 48" RCP extension. The proposed new 54" steel pipe will be trenchless installation parallel to the existing 48" RCP with sufficient clearance to avoid and minimize impacts to stream SC. During installation, temporary dikes will be utilized to separate pushing and receiving pits from stream SC. Due to the requirement to construct parallel to existing 48" RCP upstream and downstream, 54" pipe ends will not align with stream SC. A bench excavation upstream within the existing roadway slope limits is proposed as an overflow in accordance with RFP requirements. Downstream will require a proposed channel lined with rip rap from the 54" pipe to the existing stream SC tie in where pipe outlet channel stabilization is proposed. 1.5:1 roadway fill slopes will be utilized to minimize pipe length and stream impacts.

A new 60" pipe buried 1.0' will cross alignment -RPD-. Channel stabilization will be placed at outlet to reduce velocity and prevent erosion. Stream SG will be realigned downstream of the 60" -RPD- pipe and upstream of a new 66" pipe as a 47 ft long, 8 ft wide riprap-lined tail ditch with 2:1 side slopes. A proposed 66" pipe buried 1.0' will replace the existing 48" RCP under US 74. The proposed 66" steel pipe will be trenchless installation with sufficient clearance to minimize impacts to stream SG. The proposed 66" pipe will discharge to the same outlet as the existing 48" RCP with pipe outlet stabilization. During installation, temporary dikes will be utilized to separate pushing and receiving pits from stream SG. A temporary diversion channel will be utilized downstream of the 66" pipe in order to stabilize the existing channel before restoring flow to the existing condition. 1.5:1 roadway fill slopes will be utilized to minimize pipe length and stream impacts.

Alignment -SR1- does not cross stream SG but discharges directly downstream to SG. Pipe outlet channel stabilization will be installed at the cross pipe upstream of SG to reduce velocity and prevent erosion.

Streams SD and SF south of -L- interchange Quadrant C are fully impacted by the preliminary and final proposed design/construction, so Stream SD and SF flows will be directed into a single 60" steel trenchless installed pipe. The outlet will be aligned with an existing ditch outside of stream SD north of -L- and pipe outlet channel is proposed to connect the outfall ditch with Stream SD. During trenchless installation, a temporary dike will be utilized to separate receiving pit from existing stream SD at the pipe outlet, and a temporary diversion channel will also be utilized. The proposed drainage will direct existing stream SD drainage north and south of -L- directly to Stream SB to minimize the effects of adding the existing SF drainage to SD.

Sandy Run Creek is crossed by one alignment (-L-/US 74). The proposed crossing are two-span dual bridges that are taller and longer than the existing bridges. Proposed spill through abutment slopes of 1.5:1 will ensure all fill is at least 10 feet outside top of bank. The single interior drill shaft bents are outside the stream. The proposed bents are located to avoid conflicts with the existing bents. A stormdrain system is proposed right of -L- near the eastbound lane to outfall the proposed 10-ft base ditch minimizing erosion to Sandy Run Creek. Extending the ditch to Sandy Run Creek will require a steep grade that would create undesired erosive velocity.



North Carolina Department of Transportation



Highway Stormwater Program STORMWATER MANAGEMENT PLAN

FOR NCDOT PROJECTS Version 3.02; Released April 23, 2024) TIP/Proj No.: R-4045/BR-0012 WBS Element: 34598.2.2 County(ies): Cleveland Page of **General Project Information** Waterbody Information Surface Water Body (1): Sandy Run Creek NCDWR Stream Index No.: 9-46-(3.5) Primary Classification: Water Supply IV (WS-IV) NCDWR Surface Water Classification for Water Body Supplemental Classification: None Other Stream Classification: None Impairments: None Aquatic T&E Species? Comments: No NRTR Stream ID: Sandy Run Creek Buffer Rules in Effect: N/A Project Includes Bridge Spanning Water Body? Yes Deck Drains Discharge Over Buffer? N/A N/A Dissipator Pads Provided in Buffer? (If yes, provide justification in the General Project Narrative) (If yes, describe in the General Project Narrative; if no, justify in the Deck Drains Discharge Over Water Body? No General Project Narrative) (If yes, provide justification in the General Project Narrative) Surface Water Body (2): UT to Sandy Run Creek NCDWR Stream Index No.: 9-46-(3.5) Primary Classification: Water Supply IV (WS-IV) NCDWR Surface Water Classification for Water Body Supplemental Classification: None Other Stream Classification: None Impairments: None Aquatic T&E Species? No Comments: NRTR Stream ID: Buffer Rules in Effect: N/A N/A Project Includes Bridge Spanning Water Body? No Deck Drains Discharge Over Buffer? N/A Dissipator Pads Provided in Buffer? (If yes, describe in the General Project Narrative; if no, justify in the N/A (If yes, provide justification in the General Project Narrative) Deck Drains Discharge Over Water Body? General Project Narrative) (If yes, provide justification in the General Project Narrative) UT to Sandy Run Creek NCDWR Stream Index No.: Surface Water Body (3): 9-46-(3.5) Primary Classification: Water Supply IV (WS-IV) NCDWR Surface Water Classification for Water Body Supplemental Classification: None Other Stream Classification: None Impairments: None Aquatic T&E Species? No Comments: NRTR Stream ID: **Buffer Rules in Effect:** N/A N/A Project Includes Bridge Spanning Water Body? Deck Drains Discharge Over Buffer? Dissipator Pads Provided in Buffer? Yes (If yes, provide justification in the General Project Narrative) (If yes, describe in the General Project Narrative; if no, justify in the No Deck Drains Discharge Over Water Body? General Project Narrative) (If yes, provide justification in the General Project Narrative)



North Carolina Department of Transportation


Highway Stormwater Program STORMWATER MANAGEMENT PLAN





(Version 3.02; Released April 23, 2024)

FOR NCDOT PROJECTS

(Version 3.02; Released April 23, 2024)			FOR NCDOT I	PROJECTS						
WBS Element: 34598.2.2	TIP No.:	R-4045/BR-00	12 County(ies):	Cleveland			Page	4	of	5
			Additional Waterbo	dy Information						
Surface Water Body (4):		UT to Sand	y Run Creek	NCDWR Stream I	ndex No.:		9-46-(3.5)			
NCDWR Surface Water Classification for Water Body		Primary Classification:	Water Supply IV (WS-IV)							
		Supplemental Classification:	None	e						
Other Stream Classification:	er Stream Classification:									
Impairments:	None									
Aquatic T&E Species?	Yes	Comments	Dwarf Flowered Heartleaf	•			•		•	
NRTR Stream ID:	SC	•				Buffer Rules in Effect:			N/A	
			Deck Drains Discharge Over Bu	uffer?	N/A	Dissipator Pads Provided	N/A			
Deck Drains Discharge Over Water Body? N/A		(If yes, provide justification in the General Project Narrative)			(If yes, describe in the General Project Narrative; if n				n the	
(If yes, provide justification in the	•	Narrative)				Gene	eral Project Narra	tive)		
Surface Water Body (5):		UT to Sand	y Run Creek	NCDWR Stream I	ndex No.:		9-46-(3.5)			
		Primary Classification:	Water Supply IV (WS-IV)			(2.2)				
INCOWR Surface water Classification fo	NCDWR Surface Water Classification for Water Body		Supplemental Classification:	None						
Other Stream Classification:	No	one								
Impairments:		one								
Aquatic T&E Species?	No	Comments								
NRTR Stream ID:	SD		-1			Buffer Rules in Effect:			N/A	
Project Includes Bridge Spanning Water	r Body?	No	Deck Drains Discharge Over Bu	uffer?	Dissipator Pads Provided	in Buffer?		N/A		
Deck Drains Discharge Over Water Bod		N/A	(If yes, provide justification in		(If yes, describe in the Ge		rrative; if r	no, justify in	n the	
(If yes, provide justification in the	•		1			Gene	eral Project Narra	tive)		
Surface Water Body (6):		UT to Sand	y Run Creek	NCDWR Stream I	ndex No.:		9-46-(3.5)			
			Primary Classification:	Water Supply						
NCDWR Surface Water Classification to	NCDWR Surface Water Classification for Water Body			None	e					
			Supplemental Classification:							
Other Stream Classification:	None									
Impairments:		one								
Aquatic T&E Species?	No	Comments								
NRTR Stream ID:	SE					Buffer Rules in Effect:			N/A	
Project Includes Bridge Spanning Water			Deck Drains Discharge Over Buffer? N/A			Dissipator Pads Provided in Buffer?			N/A	
eck Drains Discharge Over Water Body? N/A		(If yes, provide justification in the General Project Narrative)			(If yes, describe in the General Project Narrative; if no, justify in the					
(If yes, provide justification in the			1	·	•	Gene	eral Project Narra	tive)		
, , , , , , , , , , , , , , , , , , , ,	,		•							
Surface Water Body (7):		UT to Sand	y Run Creek	NCDWR Stream I	ndex No.:		9-46-(3.5)			
NCDWR Surface Water Classification for Water Body		Primary Classification:	Water Supply IV (WS-IV)			(0.0)				
		Supplemental Classification:	None							
				11011						
Other Stream Classification:	No	one								
mpairments: None										
Aquatic T&E Species?	No	Comments								
NRTR Stream ID:	SF	Comments.				Buffer Rules in Effect:			N/A	
Project Includes Bridge Spanning Water Body?			Deck Drains Discharge Over Buffer?			Dissipator Pads Provided in Buffer? N/A				
Deck Drains Discharge Over Water Body? N/A			(If yes, provide justification in	(If yes, describe in the General Project Narrative; if no, justify in the						
										-
(If yes, provide justification in the			(ii yes, provide justineation iii	the General Froject	r rananvo _j		eral Project Narra		,,	







SHEET 2 OF 30





Type of Liner = 7 TONS,CL | Rip-Rap, Keyed-In

STA. 48 + 08 -L- LT



FROM STA. 36+50 TO STA. 37+50 -L- CL FROM STA. 49+50 TO STA. 50+50 -L- CL


SEE DITCH PROFILE SHEET






FROM STA. 11+00 TO STA. 11+45.18 -RAB- RT

DETAIL 54 SPECIAL BASE DITCH (Not to Scale)















DETAIL 68 TAIL DITCH (Not to Scale)

Geotextile — Min. D= 1.5 Ft.

Type of Liner= CL II Rip-Rap, Keyed-In d= 1.0 Ft.

FROM STA. 17+39 TO STA. 17+80 -Y3- LT 46 FT @ 0.087 FT/FT



Type of Liner= CL B Rip-Rap, Keyed-In B= 3 Ft.

FROM STA. 48+05 TO STA. 48+08 -L- LT
27 FT @0.019 FLFT

DETAIL 69
TAIL DITCH
(Not to Scale)



PROJECT REFERENCE NO.

R-4045/BR-0012

INCOMPLETE PLANS
DO NOT USE FOR R/W ACQUISITION

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

1 SUMMIT

WRA

ROADWAY DESIGN ENGINEER

SHEET NO.


PAVEMENT DESIGN ENGINEER


120 Edwards Mill Road Suite 320, Raleigh, NC 27606 (919) 859-0808





NGLISH


PERMIT DRAWING SHEET 3 OF 30










































































	WETLAND AND SURFACE WATER IMPACTS SUMMARY											
			WETLAND IMPACTS				(SURFACE	WATER IM	PACTS		
							Hand			Existing	Existing	
			Permanent	Temp.	Excavation	Mechanized	Clearing	Permanent	Temp.	Channel	Channel	Natural
Site	Station	Structure	Fill In	Fill In	in	Clearing	in	SW	SW	Impacts	Impacts	Stream
No.	(From/To)	Size / Type	Wetlands	Wetlands	Wetlands	in Wetlands	Wetlands	impacts	impacts	Permanent	Temp.	Design
			(ac)	(ac)	(ac)	(ac)	(ac)	(ac)	(ac)	(ft)	(ft)	(ft)
1a	26+70 to 30+41 -L- RT	Roadway Fill Slope/Rip Rap Channel						0.03		378		
1b	26+70 to 30+41 -L- LT	Proposed 60" Pipe Outlet						< 0.01	< 0.01	30	63	
1c	26+70 to 30+41 -L- LT	Bank Stabilization						< 0.01		33		
2a	20+65 to 21+32 Y2	60" Pipe						< 0.01	< 0.01	122	27	
2b	20+65 to 21+32 Y2	Pipe Outlet						< 0.01		22		
2c	20+65 to 21+32 Y2	Bank Stabalization						< 0.01		47		
3	25+95 to 26+35 Y1	Roadway Fill Slope						< 0.01		110		
4	27+32 to 28+56 Y1	Roadway Fill Slope	0.01			0.02						
5	26+72 to 26+79 Y1	78" Pipe and Channel						0.01	< 0.01	130	23	
6a	-L- 40+05 LT	66" Pipe Outlet						< 0.01		32		
6b	-L- 40+05 LT	Bank Stabilization						< 0.01		31		
6c	19+76 to 20+28 Y1RPD RT	60" Pipe / Stream Re-alignment						0.04		320		
7	11+44 to 11+96 Y1LPA	Roadway Fill Slope				< 0.01						
8a	14+08 to 14+20 Y1LPA	8' x 7' RCBC						0.03	< 0.01	184	25	
8b	14+08 to 14+20 Y1LPA	Culvert Outlet						< 0.01		24		
8c	14+08 to 14+20 Y1LPA	Bank Stabalization						0.03		161		
9a	19+65 to 19+82 Y1RPA	Rip Rap at Embankment						< 0.01	< 0.01	17	19	
9b	-L- 48+00 LT	Bank Stabilization						< 0.01	< 0.01	13	20	
9с	17+49 to 17+61 Y1RPA	Rip Rap at Embankment						< 0.01	< 0.01	21	33	
10	16+92 to 17+11 Y1RPA	Rip Rap at Embankment						< 0.01		34		
11	-L- 55+09 LT	Extend EX 48" Pipe						0.01	< 0.01	132	10	
12	-L- 81+20 RT	Bank Stabilization						< 0.01	< 0.01	19	20	
13a	26+25 to 26+55 SR1	60" Pipe						< 0.01	< 0.01	147	23	
13b	26+25 to 26+55 SR1	60" Pipe Outlet						< 0.01	< 0.01	26	27	
13c	26+56 to 26+88 SR1 LT	Roadway Fill Slope	< 0.01			< 0.01						
		-										
TOTAL	S*:		0.02			0.03		0.23	0.04	2033	290	0

^{*}Rounded totals are sum of actual impacts

NOTES:

NC DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS 6/3/2024 CLEVELAND COUNTY R-4045/BR-0012

NG AND BRIDGE REPLACEMENT ON US-74 OVER S SHEET

30

Revised 2018 Feb