



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

February 20, 2004

U. S. Army Corps of Engineers
6508 Falls of the Neuse Road, Suite 120
Raleigh, North Carolina 27615

ATTN: Mr. Eric Alsemeyer
NCDOT Coordinator

Dear Sir:

Subject: **Application for Section 404 and 401 Permits for Improvements to I-85 from North of SR 2120 in Rowan County to North of I-85 Business in Davidson County**, Federal Aid No. NHF-85-3(164)80, State Project No. 8.1631403, TIP Nos. I-2304AA and I-2304AB, \$475.00 Debit work order 8.1631403, WBS Element 34156.1.1

The North Carolina Department of Transportation (NCDOT) proposes to make improvements to I-85 from north of SR 2120 (Long Ferry Road, Exit 81) in Rowan County to north of NC 150 in Davidson County (Section AA) and from north of NC 150 to just north of US 29-52-70/I-85 Business (Exit 87) in Davidson County (Section AB). Proposed improvements involve widening of the existing highway to eight lanes with a 46-foot median. This project lies in the Piedmont Physiographic Province in Rowan and Davidson Counties in the Yadkin-PeeDee River Basin (Hydrologic Catalog Unit 03040103). Work is scheduled to commence on Sections I-2304AA and I-2304AB of I-85 in July 2004. The application consists of this cover letter, an ENG Form 4345, 8.5- x 11-inch permit drawings, 11- x 17-inch half-size plan sheets, interagency meeting minutes, and on-site riverine wetland mitigation plan.

Purpose and Need: The purpose of this project is to provide an acceptable level of service along the subject section of I-85 through the design year of 2025. It is also the intent of the project to improve traffic flow while providing adequate access and connectivity for area residents and businesses. Improvements to this section of I-85 are needed to effectively accommodate increased traffic demand along I-85 on a regional level as well as to establish congruency among the regional system. It is also the purpose of the project to address the structural deficiencies of the bridges, pipes, and culverts along the project while maintaining traffic along I-85.

The need for the project is based on a combination of factors including reducing congestion and improving traffic flow along this section of I-85 by constructing additional travel lanes within the subject project area. Safety will also be improved with the removal and reconstruction of interchanges and service roads.

Several alternatives for I-2304AA and I-2304AB were investigated by NCDOT which are discussed in detail on pages 15 through 18 of the Environmental Assessment (EA).

Summary of Impacts: Impacts to areas that are jurisdictional under the Federal Clean Water Act due to the proposed project footprint include the following for I-2304 Section AA.

- 0.02 acre of permanent impacts to riverine wetlands (excavation and mechanized clearing)
- 1.08 acres of permanent impacts to non-riverine wetlands (fill and mechanized clearing)
- 2644 linear feet of stream
- No temporary wetland impacts
- No permanent impacts to ponds (filling or draining)

Impacts to areas that are jurisdictional under the Federal Clean Water Act due to the proposed project footprint include the following for Section I-2304AB.

- 1.03 acres of permanent impacts to riverine wetlands (fill, excavation, and mechanized clearing)
- 0.16 acre of permanent impacts to non-riverine wetlands (fill and mechanized clearing)
- 1811 linear feet of stream
- No temporary wetland impacts
- 0.003 acre of permanent impacts to ponds (filling or draining)

Summary of Mitigation: The project has been designed to avoid and minimize impacts to jurisdictional areas to the maximum extent practicable throughout the NEPA and design processes. Detailed descriptions of these actions are presented elsewhere in this application. Compensatory mitigation for the remaining impacts in I-2304 Section AA consists of the following.

- 0.02 acre of on-site riverine wetland restoration within I-2304 Section AA
- 2644 linear feet of stream will be mitigated through the use of the North Carolina Department of Environment and Natural Resources Ecosystem Enhancement Program (EEP)
- 1.08 acre of impacts to non-riverine wetlands will be mitigated through the use of EEP

Compensatory mitigation for the remaining impacts in I-2304 Section AB consists of the following.

- 1.03 acre of on-site riverine wetland restoration within I-2304 Section AA
- 1811 linear feet of stream will be mitigated through the use of EEP
- 0.16 acre of impacts to non-riverine wetlands will be mitigated through the use of EEP

NEPA DOCUMENT STATUS

The EA for this project was approved on November 11, 2000 and the Finding of no Significant Impact (FONSI) September 30, 2003. Subsequently, the approved documents were circulated to federal, state, and local agencies. Additional copies will be provided upon request.

INDEPENDENT UTILITY

The project is in compliance with 23 CFR Part 771.111(f) which lists the Federal Highway Administration (FHWA) characteristics of independent utility of a project including the following.

1. The project connects logical termini and is of sufficient length to address environmental matters on a broad scope.
2. The project is usable and a reasonable expenditure even if no additional transportation improvements are made in the area.
3. The project does not restrict consideration of alternatives for other reasonably foreseeable transportation improvements.

The proposed project is needed to connect projects along I-85 that are recently completed or to be completed in the near future. The southwestern terminus will tie into TIP Project I-2511CB near the town of Spencer north of SR 2120 (Exit 81 of I-85), and the northeastern terminus will tie into TIP Project I-4033 to US 29-52-70/I-85 Business (Exit 87 of I-85). The locations of the proposed project's termini have been coordinated with other programmed TIP projects in the area. The locations of the termini do not preclude the development and assessment of multiple alternates for other programmed TIP projects in the area. In this regard, the proposed project demonstrates logical termini and independent utility.

This project can stand alone as a functioning project and is designed to be compatible with other TIP projects in the area. The environmental impacts of the other projects will be fully evaluated in separate environmental documents. NCDOT has determined this project meets the criteria set forth in 23 CFR 771.111(f).

RESOURCE STATUS

Delineations: Delineations of jurisdictional wetlands and streams were completed by NCDOT biologists in November and December 1999. Guidance provided in the 1987 Corps of Engineers Wetland Delineation Manual (Environmental Laboratory, 1987) was used for determining wetland boundaries. Wetland and stream delineations were verified on September 19, 2000 by Eric Alsmeyer of the U.S. Army Corps of Engineers (USACE).

SECTION AA

As previously mentioned, jurisdictional impacts for Section AA include 0.02 acre of permanent impacts to riverine wetlands, 1.08 acres of permanent impacts to non-riverine wetlands, 2644 linear feet of stream, no temporary wetland impacts, and no permanent impacts to ponds. The following table summarizes this information. This table refers to the impact summary table on Sheet 21 of the permit drawings for I-2304 Section AA.

Table 1. Jurisdictional Impacts for I-2304AA

Site	Permanent Wetland Impacts (acres)*		Stream Impacts (linear feet)	Stream Impacts Requiring Mitigation (linear feet)	Natural Channel Design (linear feet)
	Riverine	Non-Riverine			
1	0	0	262	262	0
2	0	0	0	0	0
3	0	0	485	485	0
4	0	0	190	190	0
5	0	1.079	619	619	0
6	0	0	863	863	0
7	0	0.003	0	0	0
8	0	0	97	97	0
9	0.017	0	128	128	0
10	0	0	0	0	0
11	0	0.	0	0	0
Total	0.02	1.08	2644	2644	0

* -- Includes fill, excavation, and mechanized clearing.

Section AA Wetlands: Impacts to jurisdictional wetlands occur at three sites within the project area in the Yadkin-Pee Dee River Basin (Hydrologic Catalog Unit 03040103, Subbasin 03-07-04). Table 2 summarizes information for each of the wetland impact sites associated with I-2304AA. A description of each site is as follows.

Table 2. Jurisdictional Wetland Information for I-2304AA

Site	Cowardin Classification*	DEM Rating	Community Name	Impact Type **	Total Impact (acres)
5	PFO	36	Bottomland Hardwood Forest	F, M	1.079
7	PFO	36	Bottomland Hardwood Forest	F, M	0.003
9	PEM	34	Emergent Wetland	E, M	0.017
Total					1.10

*--P = palustrine; FO = forested; EM = emergent

**--F = fill; E = excavation; M = mechanized clearing (method III)

Palustrine Forested Wetlands (Sites 5 and 7): These wetland sites are located southeast of I-85 on the Clark Road interchange. The wetlands support a predominance of woody vegetation including basswood (*Tilia americana*), tag alder (*Alnus serrulata*), sweet-gum (*Liquidambar styraciflua*), black willow (*Salix nigra*), red maple (*Acer rubrum*), tulip tree (*Liriodendron tulipifera*), American elm (*Ulmus americana*), green ash (*Fraxinus pennsylvanica*), silky dogwood (*Cornus amomum*), sycamore (*Platanus occidentalis*), elderberry (*Sambucus canadensis*), water oak (*Quercus nigra*), Chinese privet (*Ligustrum sinense*), American holly (*Ilex americana*), muscadine (*Vitis rotundifolia*), poison ivy (*Toxicodendron radicans*), and greenbrier (*Smilax rotundifolia*). Herbaceous species such as rushes (*Juncus* spp.), sedges (*Carex* spp.), microstegium (*Microstegium vimineum*), swamp rose mallow (*Hibiscus moscheutos*), field garlic (*Allium vineale*), St-John's wort (*Hypericum* sp.), trumpet creeper

(*Campsis radicans*), climbing hempweed (*Mikania scandens*), and Japanese honeysuckle (*Lonicera japonica*) are frequently present, although they are not dominant.

Palustrine Emergent Wetland (Site 9): This wetland site is located southeast of the Clark Road interchange on Clark Road. Vegetation within this wetland consists primarily of herbaceous species including rushes, sedges, wool grass (*Scirpus cyperinus*), panic grasses (*Panicum* spp.), tearthumb (*Polygonum sagittatum*), smartweeds (*Polygonum* spp.), bushy seedbox (*Ludwigia alternifolia*), goldenrods (*Solidago* spp.), broad-leaved cattail (*Typha latifolia*), microstegium, asters (*Aster* spp.), milkweeds (*Ascepias* spp.), water horehound (*Lycopus virginicus*), jewelweed (*Impatiens capensis*), yellow jessamine (*Gelsemium sempervirens*), Japanese honeysuckle, and giant cane (*Arundinaria gigantea*). Other vegetation includes woody species such as black willow, sweet-gum, sycamore, basswood, swamp rose (*Rosa palustris*), red maple, tag alder, and blackberries (*Rubus* spp.). Standing water was present within this area at the time of the site visit.

Section AA Streams: Impacts to seven jurisdictional stream sites occur on tributaries to the Yadkin River within the Yadkin-Pee Dee River Basin (Hydrologic Catalog Unit 03040103, Subbasin 03-07-04). Table 3 summarizes the information for each of the stream impact sites associated with I-2304AA.

Table 3. Jurisdictional Stream Information for I-2304AA

Site	Station No.	Structure	Stream	DWQ Index No./Classification	Impact (linear feet)	Mitigation Required (linear feet)
1	812+00 -L-	8' x 7' RCBC	UT to Yadkin River	12-(108.5) WS-V	262	262
3	900+00 -L-	36" RCP	UT to Yadkin River	12-(108.5) WS-V	485	485
4	910+00 -L-	8" PVC	UT to Yadkin River	12-(108.5) WS-V	190	190
5	9+00 -LOOP C-	48" RCP	UT to Yadkin River	12-(108.5) WS-V	619	619
6	952+60 -L-	72"	UT to Yadkin River	12-(108.5) WS-V	863	863
8	963+00 -L-	None	UT to Yadkin River	12-(108.5) WS-V	97	97
9	50+50 -Y1-	42" RCP	UT to Yadkin River	12-(108.5) WS-V	128	128
Total					2644	2644

Unnamed Tributaries the Yadkin River: The unnamed tributaries to the Yadkin River to be impacted include perennial (Sites 1, 5, 6, 8, and 9) and intermittent streams (Sites 3, 4, and 9). The perennial streams range from 2.0 to 6.0 feet in width and 0.5 to 1.0 foot in depth with sand or sand/gravel substrates and little to good flow. The banks of the perennial streams are well-developed and very steep, and the channels are well-developed and meandering. The intermittent streams average 2.0 feet in width and 0.5 foot in depth with sandy substrates and little flow. The intermittent stream channels are distinct and meandering.

Water Quality Information: The tributaries to the Yadkin River within the project have been assigned NC Division of Water Quality (DWQ) Index No. 12-(108.5) and a best usage classification of WS-V. The WS-V classification describes waters that are protected as water supplies, generally upstream and draining to Class WS-IV waters or waters used by industry to supply their employees with drinking water or as waters formerly used as water supply. These waters are also protected for Class C uses. WS-V has no categorical restrictions on watershed development or wastewater discharges unlike other WS classifications and local governments are not required to adopt watershed protection ordinances.

The Yadkin River and its tributaries are not listed in any section of the North Carolina 2002 Section 303(d) list.

SECTION AB

As previously mentioned, jurisdictional impacts for Section AB include 1.03 acres of permanent impacts to riverine wetlands, 0.16 acre of permanent impacts to non-riverine wetlands, 1811 linear feet of stream, no temporary wetland impacts, and 0.003 acre of permanent impacts to ponds. The following tables summarize this information. This table refers to the impact summary table on Sheet 19 of the permit drawings for I-2304 Section AB.

Table 4. Jurisdictional Impacts for I-2304AB

Site	Permanent Wetland Impacts (acres)*		Stream Impacts (linear feet)	Stream Impacts Requiring Mitigation (linear feet)	Natural Channel Design (linear feet)
	Riverine	Non-Riverine			
1	0	0.052	0	0	0
2	0	0	219	219	0
3	0.171	0	216	216	0
4	0	0.107	0	0	0
5	0	0	270	270	0
6	0.063	0	0	0	0
7	0	0	272	272	0
8	0.277	0	380	380	0
9	0.039	0	395	395	0
10	0	0	59	59	0
Total	1.03	0.16	1811	1811	0

* -- Includes fill, excavation, and mechanized clearing.

Section AB Wetlands: Impacts to jurisdictional wetlands occur at six sites within the project area in the Yadkin-Pee Dee River Basin (Hydrologic Catalog Unit 03040103, Subbasin 03-07-04). Table 5 summarizes information for each of the wetland impact sites associated with I-2304AB. A description of each site is as follows.

Table 5. Jurisdictional Wetland Information for I-2304AB

Site	Cowardin Classification*	DEM Rating	Community Name	Impact Type **	Total Impact (acres)
1	PFO	36	Bottomland Hardwood Forest	F, M	0.052
3	PFO & PEM	47/39	Bottomland Hardwood Forest/Emergent Wetland	F, E, M	0.650
4	PEM	38	Emergent Wetland	F, M	0.107
6	PEM	37	Emergent Wetland	F, M	0.063
8	PFO	36	Bottomland Hardwood Forest	F, M	0.277
9	PFO	47	Bottomland Hardwood Forest	F	0.039
Total					1.19

*--P = palustrine; FO = forested; EM = emergent

**--F = fill; E = excavation; M = mechanized clearing (method III)

Palustrine Forested Wetlands (Sites 1, 3, 8, and 9): These wetland sites are just southwest of the southwesternmost interchange (Site 1) and on the Belmont Road interchange (Sites 3, 8, and 9). The wetlands support a predominance of woody vegetation, including tag alder, sweet-gum, black willow, red maple, tulip tree, American elm, green ash, silky dogwood, sycamore, elderberry, water oak, Chinese privet, American holly, muscadine, poison ivy, and greenbrier. Herbaceous species such as rushes, sedges, microstegium, swamp rose mallow, field garlic, St-John's wort, trumpet creeper, climbing hempweed, and Japanese honeysuckle are frequently present, although they are not dominant.

Palustrine Emergent Wetlands (Site 3, 4, and 6): These wetland sites are located on the Belmont Road interchange (Sites 3 and 4) and on I-85 near Sharp Road (Site 6). Vegetation within this wetland consists primarily of herbaceous species including rushes, sedges, wool grass, panic grass, tearthumb, smartweed, bushy seedbox, goldenrod, broad-leaved cattail, microstegium, aster, milkweed, water horehound, jewelweed, yellow jessamine, Japanese honeysuckle, and giant cane. Other vegetation includes woody species such as black willow, sweet-gum, swamp rose, red maple, tag alder, and blackberries. Standing water was present within this area at the time of the site visit.

Section AB Streams: Impacts to seven jurisdictional stream sites occur on tributaries to the Yadkin River within the Yadkin-Pee Dee River Basin (Hydrologic Catalog Unit 03040103, Subbasin 03-07-04). Table 6 summarizes the information for each of the stream impact sites associated with I-2304AB.

Table 6. Jurisdictional Stream Information for I-2304AB

Site	Station No.	Structure	Stream	DWQ Index No./ Classification	Impact (linear feet)	Mitigation Required (linear feet)
2	-L-1006+08R/ -L-1007+00L	42" RCP	UT to South Potts Creek	12-111 C	219	219
3	-L-1036+00/ -L-1042+70R	4@11' x 11' RCBC w/ 2@72"	South Potts Creek	12-111 C	216	216
5	-L-1075+70R/ -L-1078+70R	66" RCP	UT to South Potts Creek	12-111 C	270	270
7	-L-1021+15L/ -L-1124+05R	66" RCP	UT to North Potts Creek	12-112 C	272	272
8	-Y3REV-6+80R/ -Y3REV-6+92L and -Y3REV-7+80R/ -Y3REV-9+70R	54" RCP and 42" RCP	UT to South Potts Creek	12-111 C	380	380
9	-Y3REV-28+65L/ -Y3REV-29+35R	2@7' x 7' RCBC w/ 2' conc. sill	UT to South Potts Creek	12-111 C	395	395
10	-SRD-12+26R/ -SRD12+78 L	2@7' x 6' RCBC w/ 2' conc. sill	UT to South Potts Creek	12-111 C	59	59
Total					1811	1811

South Potts Creek and Unnamed Tributaries: South Potts Creek and its tributaries will be impacted at six sites including Sites 2, 3, 5, 8, 9, and 10. Each of these stream sections are considered perennial and range from 1.0 to 3.0 feet in width and average 0.5 foot in depth. The substrate of these stream reaches varies from sand to sand/gravel to clay/gravel. Flow within these reaches is low and some erosion is present. The stream banks are well-developed and very steep, and the channels are well-developed and meandering.

Unnamed Tributary to North Potts Creek: Impacts to an unnamed tributary to North Potts Creek will occur at Site 7. This portion of the stream is considered perennial and averages 3.0 feet in

width and 0.5 foot in depth. The substrate is a mixture of sand and gravel. Some flow is present within this stream reach and a section of this reach has been impounded.

Water Quality Information: The portion of South Potts Creek and its tributaries within the project have been assigned a DWQ Index No. of 12-111 and a best usage classification of C. The portions of tributaries to North Potts Creek within the project have been assigned a DWQ Index No. of 12-112 and a best usage classification of C. The designation C refers to waters protected for secondary recreation, fishing, wildlife, fish and aquatic life propagation and survival, and agriculture. Secondary recreation includes wading, boating, and other uses involving human body contact with water where such activities take place in an infrequent, unorganized, or incidental manner. There are no restrictions on watershed development or types of discharges.

South Potts Creek and its tributaries, and tributaries to North Potts Creek are not listed in any section of the North Carolina 2002 Section 303(d) list.

PROTECTED SPECIES

Plants and animals with federal classification of Endangered (E) or Threatened (T) are protected under provisions of Section 7 and Section 9 of the Endangered Species Act of 1973, as amended. As of February 25, 2003, the U.S. Fish and Wildlife Service (FWS) lists two federally protected species for Rowan County, and as of February 11, 2003, the FWS lists three federally protected species for Davidson County (Table 7).

Table 7. Federally Protected Species for Davidson and Rowan Counties

Scientific Name	Common Name	Status	County
<i>Haliaeetus leucocephalus</i>	bald eagle	Threatened *	Davidson & Rowan
<i>Clemmys muhlenbergii</i>	bog turtle	Threatened S/A	Davidson
<i>Helianthus schweinitzii</i>	Schweinitz's sunflower	Endangered	Davidson & Rowan

Endangered -- a species that is in danger of extinction throughout all or a significant portion of its range.

Threatened -- a species likely to become Endangered within the foreseeable future throughout all or a significant portion of its range.

* -- denotes a species proposed for delisting.

S/A -- denotes a species listed due to similarity of appearance

Bald eagle: Bald eagles typically nest in tall, living trees in conspicuous locations near open water. Suitable habitat for bald eagle does occur within the project study area at the I-85 bridge over upper High Rock Lake; therefore, surveys were conducted along the Yadkin River, including High Rock Lake, by the Center for Conservation Biology (College of William and Mary) and Alcoa Power Company. The area was flown on April 23, 2002 in a high-wing Cessna 172 aircraft at approximately 328 feet of altitude to survey for nesting eagles. No bald eagles or nests were observed within 1.0 mile of the bridge. As of August 7, 2003, no known nests are documented by the N.C. Natural Heritage Program (NHP) to occur within 1.0 mile of the bridge. Based on surveys for the bald eagle, an NHP records search, and professional judgment this project may affect, but is not likely to adversely affect bald eagle. FWS concurred with this biological conclusion in a letter dated September 12, 2003.

Bog turtle: Bog turtles are typically found in grassed fields, bogs, and marshes. Potential habitat for the bog turtle occurs within the project study area in several of the wetland areas. The bog

turtle is listed as Threatened due to its similarity of appearance [T(S/A)] to another rare species listed for protection. T (S/A) species are not subject to Section 7 consultation; therefore, a biological conclusion for this species is not required.

Schweinitz's sunflower: Schweinitz's sunflower is typically found in full sunlight or light shade in clearings and along the edges of open stands of upland woods. Habitat in the form of disturbed woodland edges with sandy clay soil is present within the boundaries of the project study area. Plant-by-plant surveys were conducted in areas of suitable habitat by NCDOT biologists on October 6, 2003 and no Schweinitz's sunflower plants were found. Based on surveys for Schweinitz's sunflower, an NHP records search, and professional judgment, this project may affect, but is not likely to adversely affect Schweinitz's sunflower.

CULTURAL RESOURCES

Archaeology: The State Historic Preservation Office (SHPO) reviewed the proposed project regarding the identification of archaeological sites. The SHPO stated in a letter that "Fort York was determined to be potentially eligible for the National Register of Historic Places under Criteria A (association with events that have made a significant contribution to the broad patterns of history) and D (likely to yield information important in prehistory or history). Further work at Fort York, which will not be adversely impacted by the proposed project, should consist of the production of a detailed map of the surface features. It is recommended that as much mapping of the site as possible be done during the survey for the final roadway design."

Historic: The project is subject to compliance with Section 106 of the National Historic Preservation Act of 1966, as amended, implemented by the Advisory Council on Historic Preservation's Regulations for compliance with Section 106, codified at 36 CFR Part 800. Section 106 requires that if a federally funded, licensed, or permitted project has an effect on a property listed on or eligible for the National Register of Historic Places, the Advisory Council on Historic Preservation will be given an opportunity to comment.

To comply with Section 106, the area of potential effect of the project was surveyed by NCDOT and reviewed with SHPO. The site was surveyed in November and December of 1998 by NCDOT staff architectural historians, and determined one structure eligible for the National Register of Historic Places. The eligible structure is Bridge Number 46, the "Wil Cox Bridge", located on US 29/70, which spans the Yadkin River at the Davidson/Rowan County line.

Due to the proposed improvement, the "Wil Cox Bridge," Bridge Number 46, which accommodates two lanes in the southbound direction, will remain in place, but will be closed to vehicular traffic. The bridge will remain in place to serve pedestrian and bicycle traffic. Since this bridge will be preserved in place, it has been determined that there will be no adverse effect.

Section 4(f) Resources: Section 4(f) of the United States Department of Transportation Act of 1966 specifies that publicly owned land from a park, recreation area, or wildlife or waterfowl refuge or land from historic resources of national, state, or local significance may be used for federal-aid projects only if there is no feasible and prudent alternative to the use of such land, or such highway program or project includes all possible planning to minimize harm to 4(f) lands resulting from such use.

The “Wil Cox Bridge,” Bridge Number 46, and the Fort York property are considered 4(f) properties in the vicinity of the project. Because the “Wil Cox Bridge” will remain in place to serve pedestrian and bicycle traffic, it will not be affected by the project. Since the proposed roadway will be moved farther away from the Fort York Archaeological Site, the project will have neither direct nor indirect effects on the site.

UTILITY IMPACTS

In addition to impacts from the construction of the road, impacts often result from the need to move existing utilities. These impacts to jurisdictional areas result from activities that “but for” the construction of the road would not have occurred. The following paragraphs describe and quantify the “but for” impacts. Occasionally a utility company will decide to upgrade a line or construct a new line near the proposed highway right-of-way. The impacts from these activities would have occurred whether or not the road project was constructed. Therefore, they do not fall under the “but for” scenario. In those cases, the utility company is responsible for obtaining any permits, and the impacts are not addressed in the highway project application. However, if the information is available to us, we will attempt to identify these non-“but for” actions so that you are kept informed about the actions that may occur near our right-of-way.

According to the NCDOT, no utility relocations will result in additional impacts to wetlands and/or buffer zones.

FEMA COMPLIANCE

According to the NCDOT hydraulics engineers, no Federal Emergency Management Agency involvement is required for this project.

ICE INFORMATION

An Indirect and Cumulative Effects (ICE) study is not proposed for this project due to the low probability of indirect and cumulative effects.

WILD AND SCENIC RIVERS

The project will not impact any Designated Wild and Scenic Rivers or any rivers included in the list of study rivers (Public Law 90-542, as amended).

ESSENTIAL FISH HABITAT

The project will not impact any Essential Fish Habitat (EFH) afforded protection under the Magnuson-Stevens Act of 1996 (16 U.S.C. 1801 *et seq.*).

MITIGATION OPTIONS

The USACE has adopted, through the Council on Environmental Quality (CEQ), a wetland mitigation policy that embraces the concept of “no net loss of wetlands” and sequencing. The purpose of this policy is to restore and maintain the chemical, biological, and physical integrity of the waters of the United States. Mitigation of wetland and surface water impacts has been defined by the CEQ to include: avoiding impacts, minimizing impacts, rectifying impacts,

reducing impacts over time and compensating for impacts (40 CFR 1508.20). Executive Order 11990 (Protection of Wetlands) and Department of Transportation Order 5660.1A (Preservation of the Nations Wetlands), emphasize protection of the functions and values provided by wetlands. These directives require that new construction in wetlands be avoided as much as possible and that all practicable measures are taken to minimize or mitigate impacts to wetlands.

The NCDOT is committed to incorporating all reasonable and practicable design features to avoid and minimize wetland impacts, and to provide full compensatory mitigation of all remaining wetland impacts. Avoidance measures were taken during the planning and minimization measures were incorporated as part of the project design.

AVOIDANCE: All wetland areas not affected by the project will be protected from unnecessary encroachment.

1. No staging of construction equipment or storage of construction supplies will be allowed in wetlands or near surface waters.
2. Aquatic Life Movement: The project was designed to avoid disturbance to aquatic life movements.
3. I-2304AA, Sites 2 and 10: The Yadkin River will be spanned by a bridge constructed from high ground to high ground; therefore, avoiding impacts to the river and wetlands associated with the river floodplain.

MINIMIZATION: Minimization includes the examination of appropriate and practicable steps to reduce the adverse impacts. Minimization techniques implemented include the following.

1. High Quality Waters BMP: NCDOT has committed that “construction related impacts associated with the proposed action will be minimized through the use of High Quality Waters erosion and sediment control measures. All practical measures have been taken to minimize environmental harm.”
2. Protection of Surface Waters BMP: In order to minimize potential impacts to water resources in the project area, NCDOT BMPs for the Protection of Surface Waters will be strictly enforced during the construction phase of the project.
3. Slopes: Fill slopes in wetlands are at a 2:1 ratio.
4. Ditching: It is the policy of the NCDOT to eliminate lateral ditching in wetlands as much as possible, thus preserving the hydrology of adjacent wetlands.
5. Median Width: The project was designed using a 46-foot median width.
6. I-2304AA, Site 1: The channel relocation right of station 809+60 to 809+90, as noted on the permit drawings (Sheet 5), is to be permitted under I-2511CB. The 24-inch reinforced concrete pipe has been redesigned to eliminate a 90-degree turn in flow.
7. I-2304AB, Site 3: A preformed scour hole was eliminated at this location, and the flow will be redirected through the 72-inch overflow pipe (Sheet 5).

COMPENSATION: The primary emphasis of the compensatory mitigation is to reestablish a condition similar to what would have existed if the project was not built. As previously stated, mitigation is limited to reasonable expenditures and practicable considerations related to highway operation. Mitigation is generally accomplished through a combination of methods designed to replace wetland functions and values lost as a result of construction of the project. These methods consist of creation of new wetlands from uplands, borrow pits, and other non-wetland areas; restoration of wetlands; and enhancement of existing wetlands. Where such

options may not be available, or when existing wetlands and wetland-surface water complexes are considered to be important resources worthy of preservation, consideration is given to preservation as at least one component of a compensatory mitigation proposal.

FHWA Step-Down Compliance: All compensatory mitigation must be in compliance with 23 CFR Part 777.9, "Mitigation of Impacts," that describes the actions that should be followed to qualify for federal-aid highway funding. This process known as the FHWA "Step Down" procedures includes the following.

1. Consideration must be given to mitigation within the right-of-way and should include the enhancement of existing wetlands and the creation of new wetlands in the highway median, borrow pit areas, interchange areas, and along the roadside.
2. Where mitigation within the right-of-way does not fully offset wetland losses, compensatory mitigation may be conducted outside the right-of-way including enhancement, creation, and preservation.

Based upon the agreements stipulated in the "Memorandum of Agreement Among the North Carolina Department of Environment and Natural Resources, the North Carolina Department of Transportation, and the United States Army Corps of Engineers, Wilmington District" (MOA), it is understood that EEP will assume responsibility for satisfying the federal Clean Water Act compensatory mitigation requirements for NCDOT projects that are listed in Exhibit 1 of the subject MOA during the EEP transition period which ends on June 30, 2005.

Although the subject project is not listed in Exhibit 1, the necessary compensatory mitigation to offset unavoidable impacts to waters that are jurisdictional under the federal Clean Water Act are anticipated to be provided by the EEP. The offsetting mitigation will derive from an inventory of assets already in existence within the same 8-digit cataloguing unit. NCDOT has avoided and minimized impacts to jurisdictional resources to the greatest extent possible as described above. The remaining, unavoidable impacts to 1.24 acres of non-riverine wetlands and 4455 linear feet of jurisdictional streams will be offset by compensatory mitigation provided by the EEP program.

Wetland Mitigation: Wetland impacts total 1.05 acres of riverine wetland impacts and 1.24 acres of non-riverine wetland impacts. The following combination of compensatory mitigation is proposed.

1. 1.05 acres of riverine wetland restoration within Site 2 of I-2304AA.
2. 1.24 acres of non-riverine wetland will be mitigated through the use of EEP.

Stream Mitigation: Stream impacts total 4455 linear feet of intermittent and perennial streams. Compensatory mitigation will be provided through the use of EEP for 4455 linear feet of stream impacts.

REGULATORY APPROVALS

Application is hereby made for a USACE Individual 404 Permit and a 401 Water Quality Certification from DWQ as required for the activities described above. In compliance with Section 143-215.3D(e) of the NCAC, we will provide \$475.00 to act as payment for processing the Section 401 Water Quality Certification previously noted in this application (see Subject line). Seven copies of this application are provided to the DWQ for review.

If you have any questions or need additional information please call Matt Haney at (919) 715-1428.

Sincerely,

A handwritten signature in black ink, appearing to read "Gregory J. Thorpe". The signature is stylized with a large "G" and "T".

Gregory J. Thorpe, Ph.D.
Environmental Management Director, PDEA

cc: Mr. David Franklin, USACE, Wilmington
Mr. John Dorney, NCDWQ (7 copies)
Ms. Marla Chambers, NCWRC
Ms. Becky Fox, USEPA
Ms. Marella Buncick, USFWS
Mr. John F. Sullivan III, FHWA
Mr. Jay Bennett, P.E., Roadway Design
Mr. Omar Sultan, Programming and TIP
Mr. Art McMillan, P.E., Highway Design
Mr. David Chang, P.E., Hydraulics
Mr. Greg Perfetti, P.E., Structure Design
Mr. Mark Staley, Roadside Environmental
Mr. S.P. Ivey, P.E. (Div. 9), Division Engineer
Ms. Diane Hampton, P.E. (Div. 9), Division Environmental Officer

APPLICATION FOR DEPARTMENT OF THE ARMY PERMIT
(33 CFR 325)

OMB APPROVAL NO. 071-0003
Expires December 31, 2004

The public reporting burden for this collection of information is estimated to average 10 hours per response, although the majority of applications should require 5 hours or less. This includes time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to Department of Defense, Washington Headquarters Service Directorate of Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302; and to the Office of Management and Budget, Paperwork Reduction Project (0710-0003), Washington, DC 20503. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to either of those addresses. Completed applications must be submitted to the District Engineer having jurisdiction over the location of the proposed activity.

PRIVACY ACT STATEMENT

Authorities: Rivers and Harbors Act, Section 10, 33 USC 403; Clean Water Act, Section 404, 33 USC 1344; Marine Protection, Research, and Sanctuaries Act, Section 103, 33 USC 1413. Principal Purpose: Information provided on this form will be used in evaluating the application for a permit. Routine Uses: This information may be shared with the Department of Justice and other federal, state, and local government agencies. Submission of requested information is voluntary, however, if information is not provided, the permit application cannot be processed nor can a permit be issued.

One set of original drawings or good reproducible copies which show the location and character of the proposed activity must be attached to this application (see sample drawings and instructions) and be submitted to the District Engineer having jurisdiction over the location of the proposed activity. An application that is not completed in full will be returned.

(ITEMS 1 THRU 4 TO BE FILLED BY THE CORPS)

1. APPLICATION NO.	2. FIELD OFFICE CODE	3. DATE RECEIVED	4. DATE APPLICATION COMPLETED
--------------------	----------------------	------------------	-------------------------------

(ITEMS BELOW TO BE FILLED BY APPLICANT)

5. APPLICANT=S NAME Gregory J. Thorpe, Ph.D., Environmental Management Director Project Development and Environmental Analysis North Carolina Department of Transportation	8. AUTHORIZED AGENT=S NAME AND TITLE (an agent is not required) Not applicable
---	---

6. APPLICANT=S ADDRESS 1548 Mail Service Center Raleigh, North Carolina 27699-1548	9. AGENT=S ADDRESS
--	--------------------

7. APPLICANT=S PHONE NOS. WITH AREA CODE a. Residence b. Business (919) 733-3141	10. AGENTS PHONE NOS. WITH AREA CODE a. Residence b. Business
--	---

11. STATEMENT OF AUTHORIZATION

I hereby authorize, _____ to act in my behalf as my agent in the processing of this application and to furnish, upon request, supplemental information in support of this permit application.

APPLICANT=S SIGNATURE

DATE

NAME, LOCATION, AND DESCRIPTION OF PROJECT OR ACTIVITY

12. PROJECT NAME OR TITLE (see instructions)
Improvements to I-85 from north of SR 2120 (Long Ferry Road, Exit 81) in Rowan County to north of NC 150 in Davidson County (Section AA) and from north of NC 150 to just north of US 29-52-70/I-85 Business (Exit 87) in Davidson County (Section AB). Proposed improvements involve widening of the existing highway to eight lane with a 46-foot median. Federal Aid No. NHF-85-3(164)80, State Project No. 8.1631403, TIP Nos. I-2403AA and I-2403AB

13. NAME OF WATERBODY, IF KNOWN (if applicable) South Potts Creek and it's tributaries, tributaries to North Potts Creek, and tributaries to the Yadkin River	14. PROJECT STREET ADDRESS (if applicable) NA
--	--

LOCATION OF PROJECT

Rowan and Davidson
COUNTIES

NC
STATE

16. OTHER LOCATION DESCRIPTIONS, IF KNOWN (see instructions)
See the November 1990 Environmental Assessment (EA) and September 2003 Finding of No Significant Impact (FONSI).

17. DIRECTIONS TO THE SITE
See the attached permit drawings and half size plan sheets.

18. Nature of Activity (*Description of project, include all features*)

The North Carolina Department of Transportation proposes to improve and widen I-85 from north of SR 2120 (Long Ferry Road, Exit 81) in Rowan County to north of NC 150 in Davidson County (Section AA) and from north of NC 150 to just north of US 29-52-70/I-85 Business (Exit 87) in Davidson County (Section AB). Improvement involve the widening of the existing I-85 to an 8-lane facility, 4 lanes in each direction separated by a 46-foot median.

19. Project Purpose (*Describe the reason or purpose of the project, see instructions*)

To make improvements to I-85, a public highway facility, for public safety and transportation. The purpose and need are briefly explained in the permit application cover letter and are explained in detail in the November 1990 Environmental Assessment (EA) and the September 2003 Finding of no Significant Impact (FONSI).

USE BLOCKS 20-22 IF DREDGED AND/OR FILL MATERIAL IS TO BE DISCHARGED

20. Reason(s) for Discharge

Proposed improvements and widening of I-85 from north of SR 2120 (Long Ferry Road, Exit 81) in Rowan County to north of NC 150 in Davidson County (Section AA) and from north of NC 150 to just north of US 29-52-70/I-85 Business (Exit 87) in Davidson County (Section AB). Improvements involve the widening of the existing I-85 to an 8-lane facility, 4 lanes in each direction separated by a 46-foot median.

21. Type(s) of Material Being Discharged and the Amount of Each Type in Cubic Yards

See the attached permit drawings.

22. Surface Area in Acres of Wetlands or Other Waters Filled (*see instructions*)

See sheet 21 of the attached permit drawings for Section AA and sheet 19 of the attached permit drawings for Section AB.

23. Is Any Portion of the Work Already Complete? YES ☐ NO ☒ IF YES, DESCRIBE THE COMPLETED WORK

24. Addresses of Adjoining Property Owners, Lessees, Etc., Whose Property Adjoins the Waterbody (If more than can be entered here, please attach a supplemental list).

See sheets 20 of the attached permit drawings for Section AA and sheets 20 and 21 of the attached permit drawings for Section AB.


25. List of Other Certifications or Approvals/Denials Received from other Federal, State, or Local Agencies for Work Described in This Application.

Agency	Type approval*	Identification number	Date applied	Date approved	Date Denied
Not Applicable					

*Would include but is not restricted to zoning, building, and flood plain permits.

26. Application is hereby made for a permit or permits to authorize the work described in this application. I certify that the information in this application is complete and accurate. I further certify that I possess the authority to undertake the work described herein or am acting as the duly authorized agent of the applicant.





SIGNATURE OF APPLICANT

DATE



SIGNATURE OF AGENT

DATE

The application must be signed by the person who desires to undertake the proposed activity (applicant) or it may be signed by a duly authorized agent if the statement in block 11 has been filled out and signed.

18 U.S.C. Section 1001 provides that: Whoever, in any manor within the jurisdiction of any department or agency of the United States knowingly and willfully falsifies, conceals, or covers up any trick, scheme, or disguises a material fact or makes any false, fictitious, or fraudulent statements or representations or makes or uses any false writing or document knowing same to contain any false, fictitious, or fraudulent statements of entry, shall be fines not more than \$10,000 or imprisoned not more than five years or both.

NORTH CAROLINA



VICINITY MAPS

NCDOT

DIVISION OF HIGHWAYS
DAVIDSON/ROWAN

PROJECT: 8.1631403 (I-2304AA)

I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

SHEET OF 2

5/7/05



DIVISION OF HIGHWAYS DAVIDSON/ROWAN

PROJECT: 8.1631403 (I-2304AA)




I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

SHEET 2 OF 2

WETLAND

LEGEND

—WLB— WETLAND BOUNDARY




→ FLOW DIRECTION

TB TOP OF BANK

WE EDGE OF WATER

C PROP. LIMIT OF CUT

F PROP. LIMIT OF FILL



NG NATURAL GROUND

PL PROPERTY LINE


TDE TEMP. DRAINAGE EASEMENT

PDE PERMANENT DRAINAGE EASEMENT






EAB EXIST. ENDANGERED ANIMAL BOUNDARY

EPB EXIST. ENDANGERED PLANT BOUNDARY

WATER SURFACE



CORE FIBER ROLLS



NCDOT

DIVISION OF HIGHWAYS
DAVIDSON/ROWAN COUNTY

PROJECT: 8.1631403 (I-2304AA)


I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

SHEET

4

OF 21

5/7/05



DIVISION OF HIGHWAYS DAVIDSON / ROWAN


PROJECT: 8.1631403 (I-2304AA)

I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

SCALE 1''=100'

SHEET OF

6/25/03



PLAN VIEW
STREAM
IMPACTS
SITE 2

SCALE 1" = 100'


NCDOT

DIVISION OF HIGHWAYS

DAVIDSON/ROWAN

PROJECT: 81631403 (I-2304.AA)

I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY



PLAN VIEW
STREAM
IMPACTS
SITE 2

SCALE 1" = 100'


NCDOT

DIVISION OF HIGHWAYS

DAVIDSON/ROWAN

PROJECT: 81631403 (I-2304AA)

I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY




NCDOT
 DIVISION OF HIGHWAYS
 DAVIDSON/ROWAN
 PROJECT: 8.1631403 (I-250-4.A.A)
 I-85 FROM NORTH OF SR 2120 IN
 ROWAN COUNTY TO NORTH OF
 NC 150 IN DAVIDSON COUNTY

PLAN VIEW
 STREAM
 IMPACTS
 SITE 2

SCALE 1" = 100'

SHEET 8 OF 21
 8/30/02



NCDOT

DIVISION OF HIGHWAYS

DAVIDSON/ROWAN

PROJECT: 8.1631403 (I-2304.A.A)


I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

SHEET 9 OF 21

5/7/03

PROFILE VIEW
SITE 2

SCALE 1" = 200' HORIZONTAL
1" = 20' VERTICAL




PROFILE VIEW SITE 2

SCALE 1" = 200' HORIZONTAL
 1" = 20' VERTICAL

NCDOT
 DIVISION OF HIGHWAYS
 DAVIDSON/ROWAN


PROJECT: 8.1631403 (I-2504.A.A)

I-85 FROM NORTH OF SR 2120 IN
 ROWAN COUNTY TO NORTH OF
 NC 150 IN DAVIDSON COUNTY




PLAN VIEW
 STREAM
 IMPACTS
 SITE 3
 SCALE 1" = 50'

NCDOT
 DIVISION OF HIGHWAYS
 DAVIDSON/ROWAN
 PROJECT: 8.1631403 (I-2304AA)
 I-85 FROM NORTH OF SR 2120 IN
 ROWAN COUNTY TO NORTH OF
 NC 150 IN DAVIDSON COUNTY
 SHEET 11 OF 31
 6/25/05




PLAN VIEW
 SITE 4
 STREAM
 IMPACTS
 SCALE 1"=50'

NCDOT
 DIVISION OF HIGHWAYS
 DAVIDSON/ROWAN COUNTY
 PROJECT: 8.1631403 (I-2304AA)
 I-85 FROM NORTH OF SR 2120 IN
 ROWAN COUNTY TO NORTH OF
 NC 150 IN DAVIDSON COUNTY
 SHEET 10 OF 10
 10/3/03



PLAN VIEW
STREAM
IMPACTS
SITE 5
SCALE 1"=100'

NCDOT
DIVISION OF HIGHWAYS
DAVIDSON/ROWAN COUNTY
PROJECT: 8.1631403 (I-2304AA)
I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY
SHEET 12 OF 13
10/3/03




PLAN VIEW
WETLAND
IMPACTS
SITE 5
SCALE 1" = 100'

NCDOT
DIVISION OF HIGHWAYS
DAVIDSON/ROWAN COUNTY
PROJECT: 8.1631403 (I-2304AA)

I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

SHEET 14 OF 24


5/7/03



PLAN VIEW
 STREAM
 IMPACTS
 SITE 6


SCALE
 1" = 100'

NCDOT
 DIVISION OF HIGHWAYS
 DAVIDSON/ROWAN COUNTY
 PROJECT: 8.1631403 (I-2304AA)
 I-85 FROM NORTH OF SR 2120 IN
 ROWAN COUNTY TO NORTH OF
 NC 150 IN DAVIDSON COUNTY
 SHEET 15 OF 21
 5/7/03



PLAN VIEW
WETLAND
IMPACTS
SITE 7
SCALE 1" = 50'

NCDOT
DIVISION OF HIGHWAYS
DAVIDSON/ROWAN COUNTY
PROJECT: 8.1631403 (I-2504AA)
I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY
SHEET 12 OF 24
5/7/03



PLAN VIEW
 STREAM & WETLAND
 IMPACTS
 SITE 9
 SCALE 1" = 50'

NCDOT
 DIVISION OF HIGHWAYS
 DAVIDSON / ROWAN
 PROJECT: 8.1631405 (I-2304AA)
 I-85 FROM NORTH OF SR 2120 IN
 ROWAN COUNTY TO NORTH OF
 NC 150 IN DAVIDSON COUNTY
 SHEET 1 OF 21
 6/25/05

YADKIN RIVER

-SRB- 35+00

-SRB- 40+00

8

YADKIN INCORPORATED

BRIDGE #46

SSP

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE

BRIDGE


CONC. WALL

STEEL

TEMPORARY WORK BRIDGE

3

PLAN VIEW
STREAM
IMPACTS
SITE 10



SCALE 1" = 100'

NCDOT

DIVISION OF HIGHWAYS


DAVIDSON/ROWAN

PROJECT: 81631403 (I-2304-AA)

I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

SHEET 13 OF 21

5/7/03



NCDOT
 DIVISION OF HIGHWAYS
 DAVIDSON/ROWAN
 PROJECT: 81631403 (I-2304AA)
 I-85 FROM NORTH OF SR 2120 IN
 ROWAN COUNTY TO NORTH OF
 NC 150 IN DAVIDSON COUNTY
 SHEET 19 OF 27 5/7/03

PROFILE VIEW
 SITE 10

SCALE 1" = 100' HORIZONTAL
 1" = 20' VERTICAL

PROPERTY OWNERS

NAMES AND ADDRESSES

PARCEL NO.	NAMES	ADDRESSES
1	HINKLE, PAUL P.	455 HINKLE LANE SALISBURY, NC 28144-8555
2	HINKLE, JR., HOLLIS L.	655 HACKETT ST. SALISBURY, NC 28144-7769
3	SOUTHERN RAIL CO.	8 NORTH JEFFERSON ST. ROANOKE, VA 24042
4	GRUBB, ROBERT L.	P.O. BOX 388 HIGH POINT, NC 27260
5	DUKE POWER COMPANY	P.O. BOX 1090 CHARLOTTE, NC 28201-1090
6	FALCON DEVELOPMENT GROUP INC.	1329 SOUTH MAIN ST. SALISBURY, NC 28144
7	ALUMINUM COMPANY OF AMERICA	P.O. BOX 688 BADIN, NC 28009
8	YADKIN INCORPORATED	P.O. BOX 688 BADIN, NC 28009

NCDOT

DIVISION OF HIGHWAYS
DAVIDSON/ROWAN COUNTY
PROJECT: 8.1631403 (I-2304AA)

I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

WETLANDS IMPACT PERMIT SUMMARY

Site No.	Station (From/To)	Structure Size / Type	Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation In Wetlands (ac)	Mechanized Clearing (Method III) (ac)	Fill In SW (Natural) (ac)	Fill In SW (Pond) (ac)	Temp ¹ Fill In SW (ac)	Existing Channel Impacted (ft)	Natural Stream Design Depth (ft)
1	812+00 -L-	8' X 7' RCBC					0.1129			262	
2	868+60 TO 897+27 -L-	BRIDGE									
3	900+00 -L-	36" RCP					0.0378			485	
4	910+00 -L-	8" PVC					0.0138			190	
5	9+00 -LOOP C-	48" RCP					0.0705			619	
5	9+00 -LOOP C-		1.0385			0.0404					
6	952+60 -L-	72"					0.1343			863	
7	27+00 -SRD-		0.000086			0.0027					
8	963+00 -L-						0.0075			97	
9	50+50 -Y1-	42" RCP			0.0077	0.0088	0.0146			128	
10	31+07 TO 39+79 -SRB-	BRIDGE									
11	1+00 -RAMP C-										
TOTALS:			1.04	0.00	0.01	0.05	0.39	0.00	0.00	2644	0.00




NCDOT

DIVISION OF HIGHWAYS
DAVIDSON/ ROWAN COUNTY
PROJECT 8.1631403 (I-2304AA)
I-85 FROM NORTH OF SR 2120 IN
ROWAN COUNTY TO NORTH OF
NC 150 IN DAVIDSON COUNTY

Form Revised 3/22/01

SHEET 5 OF 5

10/3/2003



N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS



DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 1 OF 2 02 / 24 / 03

LEGEND

---WLB--- WETLAND BOUNDARY



— BZ — RIPARIAN BUFFER ZONE

← ← FLOW DIRECTION

— TB — TOP OF BANK

— WE — EDGE OF WATER

— C — PROP. LIMIT OF CUT

— F — PROP. LIMIT OF FILL

— ▲ — PROP. RIGHT OF WAY

— NG — NATURAL GROUND

— PL — PROPERTY LINE

— TDE — TEMP. DRAINAGE EASEMENT

— PDE — PERMANENT DRAINAGE EASEMENT

— EAB — EXIST. ENDANGERED ANIMAL BOUNDARY


— EPB — EXIST. ENDANGERED PLANT BOUNDARY

— ▽ — WATER SURFACE


X X X LIVE STAKES

~ BOULDER

— — COIR FIBER ROLLS



PROPOSED BRIDGE



PROPOSED BOX CULVERT




PROPOSED PIPE CULVERT

(DASHED LINES DENOTE EXISTING STRUCTURES)




SINGLE TREE



WOODS LINE



DRAINAGE INLET




ROOTWAD



RIP RAP



ADJACENT PROPERTY OWNER OR PARCEL NUMBER IF AVAILABLE



RIP RAP ENERGY DISSIPATOR BASIN


N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORHT
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 2 OF 2


2/24/03




PLAN VIEW SITE 1



DENOTES MECHANIZED
CLEARING



DENOTES FILL IN
WETLANDS




N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 3 OF 21

2/24/03



PLAN VIEW SITE 3


- DENOTES MECHANIZED CLEARING
- DENOTES EXCAVATION IN WETLAND
- DENOTES FILL IN WETLANDS
- DENOTES FILL IN SURFACE WATERS

NOTE: HAND CLEAR IN WETLANDS TO INSTALL CONTROLLED ACCESS FENCING.




N.C. DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS

 DAVIDSON COUNTY
 PROJECT: 81631403 (I-2504AB)
 I-85 WIDENING FROM JUST NORTH
 OF NC 150 TO JUST NORTH
 OF I-85 BUSINESS
 SHEET 5 OF 2 2/11/03



PROFILE SITE 3



N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS



DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS


SHEET 6 OF 21

2/24/03


1039 + 00 -L-



SITE 3 SECTION A-A




DENOTES FILL IN
WETLANDS



N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 81631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS





PLAN VIEW SITE 4



DENOTES MECHANIZED
CLEARING

DENOTES FILL IN
WETLANDS




N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 1 OF 2


2 / 24 / 03



PLAN VIEW SITE 5



DENOTES FILL IN
SURFACE WATERS




N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 1 OF 21

2/24/03



PLAN VIEW SITE 6




NOTE: HAND CLEAR IN WETLANDS
TO INSTALL CONTROLLED
ACCESS FENCING.



•••••
DENOTES MECHANIZED
CLEARING

F F
DENOTES FILL IN
WETLANDS

P P
DENOTES FILL IN
SURFACES WATERS
(POND)




N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 10 OF 21

2/24/03




PROFILE SITE 8



DENOTES FILL IN
SURFACE WATERS

DENOTES FILL IN
WETLANDS



N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS



DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS


SHEET 16 OF 21

2/24/03

9 + 00 -Y3REV-




SITE 8
SECTION A-A



DENOTES FILL IN SURFACE WATERS
 DENOTES FILL IN WETLANDS

N.C. DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 DAVIDSON COUNTY
 PROJECT: 8.1631403 (I-2304AB)
 I-85 WIDENING FROM JUST NORTH
 OF NC 150 TO JUST NORTH
 OF I-85 BUSINESS
 SHEET 14 OF 21

2/24/03





PLAN VIEW SITE 9



DENOTES FILL IN
WETLANDS

DENOTES FILL IN
SURFACE WATERS



N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 15 OF 24

2 / 24 / 03

-Y3REV- PROFILE GRADE LINE

(-)-2.9360%

NATURAL GROUND LINE
@ US FACE

2 @ 7' x 7' RCBC

2' -0" CONC. SILL

EXISTING STREAM BED

PROPOSED STREAM BED

PROFILE SITE 9



N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS


DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)

I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 16 OF 21


2/24/03



PLAN VIEW SITE 10



DENOTES FILL IN
SURFACE WATERS




N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 17 OF 21

2 / 24 / 03



PROFILE SITE 10



N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 81631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 12 OF 21

2/24/03

WETLAND PERMIT IMPACT SUMMARY

Site No.	Station (From / To)	Structure / Type Size	WETLAND IMPACTS			SURFACE WATER IMPACTS						
			Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation In Wetlands (ac)	Mechanized Clearing (Method III) (ac)	Fill In SW (Natural) (ac)	Fill In SW (Pond) (ac)	Temp. Fill In SW (ac)	Existing Channel Impacted (ft)	Natural Stream Design (ft)	
1	-L- 988+45R / -L- 989+70R	-	0.033	-	-	0.019	-	-	-	-	-	-
2	-L- 1006+08R / -L- 1007+00L	1 @ 42" RCP	-	-	-	-	0.021	-	-	219	-	-
3	-L- 1036+00 / -L- 1042+70R	4 @ 11" x 11" RCBC w/ 2 @ 72"	0.463	-	0.016	0.171	0.062	-	-	216	-	-
4	-SRA- 13+50L / -SRA- 16+70R	1 @ 30" RCP	0.071	-	-	0.036	-	-	-	-	-	-
5	-L- 1075+70R / -L- 1078+70R	1 @ 66" RCP	-	-	-	-	0.034	-	-	270	-	-
6	-L- 1102+75L / -L- 1106+10R	1 @ 42" RCP	0.037	-	-	0.026	-	0.003	-	-	-	-
7	-L- 1121+15L / -L- 1124+05R	1 @ 66" RCP	-	-	-	-	0.030	-	-	272	-	-
8	-Y3REV- 6+50R / -Y3REV- 6+92L -Y3REV- 7+80R / -Y3REV- 9+70R	1 @ 54" RCP 1 @ 42" RCP	- 0.263	-	-	0.005 0.003	0.009 0.014	-	-	179 201	-	-
9	-Y3REV- 28+65L / -Y3REV- 29+35R	2 @ 7' x 7' RCBC w/ 2' CONC. SILL	0.039	-	-	-	0.042	-	-	395	-	-
10	-SRD- 12+26R / -SRD- 12+78L	2 @ 7' x 6' RCBC w/ 2' CONC. SILL	-	-	-	-	0.006	-	-	59	-	-
TOTALS:			0.906	0.000	0.016	0.266	0.218	0.003	0.000	1811	0	0

N.C. DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORTH
OF NC 150 TO JUST NORTH OF
I-85 BUSINESS

Project No. 8.1631403 (I-2304AB)

Property Owner List

Site NO.	Parcel NO.	Name DB and Pg	Address
1	(1)	Robert L. Grubb Trustee of June C. Little DB 698 Pg 336	P.O. BOX 388 High Point, NC 27260
2	(1)	Robert L. Grubb Trustee of June C. Little DB 698 Pg 336	P.O. BOX 388 High Point, NC 27260
	(2)	Franklin Haywood Graves And Wife, Margaret L Graves DB 635 Pg 17 DB 915 Pg 965 DB 401 Pg 338	8291 Old Salisbury Road Linwood, NC 27299-9708
	(3)	Everhart Used Cars, Inc. DB 635 Pg 161	1517 Greensboro Road Lexington NC 27292-1919
3	(1)	Robert L. Grubb Trustee of June C. Little DB 699 Pg 336	P.O. BOX 388 High Point, NC 27260
	(4)	Earl L Blanton And Wife, Kathy L Blanton DB 705 Pg 514	7847 Old Salisbury Road Linwood, NC 27299
4	(1)	Robert L. Grubb Trustee of June C. Little DB 699 Pg 336	P.O. BOX 388 High Point, NC 27260
	(5)	Walser Enterprises DB 112 Pg 110	Snider-Kines Road Linwood, NC 27299
5	(6)	C. C. Fitzgerald Heirs DB 57 Pg 205	194 Redwine Road Linwood, NC 27299
	(7)	Randall G Lomax And Wife, Tammy P Lomax DB 875 Pg 936	310 Lake Shore Drive Lexington, NC 27292-8117

N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORHT
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 20 OF 24

2 / 24 / 03

Project No. 8.1631403 (I-2304AB)

Property Owner List

Site NO.	Parcel NO.	Name DB and Pg	Address
6	(8)	Mobile Development Corp. DB 1051 Pg 1588	23 West Second Street Lexington, NC 27292
	(9)	Robert A. Gusman DB 634 Pg 656 DB 613 Pg 959	P.O. Box 992 Lexington, NC 27293-0992
7	(10)	George W Gobble And Wife, Betty E Gobble DB 596 Pg 757	984 Wayane Gobble Road Linwood, NC 27299-9706
	(11)	Margaret N. Clark DB 832 Pg 814	1089 Clyde Fitzgerald Road Linwood, NC 27299
8	(1)	Robert L. Grubb Trustee of June C. Little DB 699 Pg 336	P.O. BOX 388 High Point, NC 27260
9	(12)	Beallmont Farms Inc. DB 931 Pg 628	P.O. Box 835 Linwood, NC 27299
	(13)	Henderson Hargrave Heirs DB 102 Pg 288	561 Belmont Road Linwood, NC 27299-9201
10	(2)	Walter McDowell, SR DB 550 Pg 769	796 Belmont Road Linwood, NC 27299-9201
	(14)	Henderson Hargrave Heirs DB 102 Pg 288	561 Belmont Road Linwood, NC 27299-9201

N.C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

PROJECT: 8.1631403 (I-2304AB)
I-85 WIDENING FROM JUST NORHT
OF NC 150 TO JUST NORTH
OF I-85 BUSINESS

SHEET 21 OF 2

2 / 24 / 03

November 22, 2002

Subject: Draft Minutes Interagency Hydraulic Design 4B Review Meeting on November 21, 2002, for I2304AA and AB, Davidson and Rowan Counties.

Team Members:

Eric Alsmeyer – USACE (Present)
Cynthia Van Der Wiele – NCDWQ (Present)
Marla Chambers – NCWRC (Present)
Marella Buncick – USFWS (Present)
Chris Militscher – EPA (Present)
Matt Haney – NCDOT PDEA (Present)

Participants:

David Chang – NCDOT Hydraulics
Jenny Fleming – Barbara H. Mulkey Engineering
Jamie Byrd – Transite Engineering
Cathy Houser – NCDOT Design Services
Robert Stroup – NCDOT Design Services
Scott Pridgen – NCDOT Design Services
Jackie Obediente – NCDOT PDEA
Marshall Clawson – NCDOT Hydraulics
Anne Gamber – NCDOT Hydraulics

This project consists of the widening of I-85 in Rowan and Davidson Counties.

1. Stream and Wetlands Locations: Eric Alsmeyer had concerns about the location of streams and wetlands. Matt Haney will provide complete wetlands delineation and jurisdiction stream identification on the plans for both projects.
2. Outfall at Wetlands “G” at Station 845+60: Wetlands “G” was not shown on the plans. Installing level spreaders and/or dry detention pond in this area will be investigated to ensure proper velocity controls.
3. Removal of existing bridge far left of Station 870+00: Marella Buncick noted that to support the machinery and to restrain debris during the removal of the existing bridge, a causeway might be advantageous. David Chang suggested that in the future 4C meeting the construction personnel be invited for more discussion.
4. Hazardous Spill Basin at Bridge Station 868+60 to Station 897+50: To span the lake and its adjoining wetlands, the existing 883 foot bridge would be replaced with dual 2,890 foot bridges. The existing and proposed bridge decks are 59 and 170 feet, respectively. The bridge is located 14 miles upstream from a water supply intake. Cynthia Van Der Wiele requested DOT engineers design a closed system that collect the stormwater runoff from the bridge deck and discharge it onto hazardous spill basins outside the wetlands areas. After more thorough review to the DOT Guidelines and the bridge crossing, David Henderson and David Chang have directed the design engineers to comply with Cynthia’s request. As a Design/Build project, a preliminary bridge survey report was presented to the agencies. It depicts the layout of the proposed bridge assuming the worst case scenario: maximum superstructure depth and minimum span length.
5. Erosion Control: Eric Alsmeyer requested that the Roadside Environmental Unit be made aware of the standing water wetlands on the project at Station 1040+00.

The meeting was adjourned at 4:45.

Comments:

Cynthia Van Der Wiele: ... *the distance of the intake from the bridge... is not 14 miles.* (Distance along the river is 14 miles) **DWQ's request was for a closed system for stormwater (no deck drains) and that stormwater be directed off the bridge and pre-treated by whatever means was feasible ...**

May 23, 2003

Subject: Minutes Interagency 4C Permit Review Meeting on May 22, 2003, for I2304AA and AB, Davidson and Rowan Counties.

Team Members:

Eric Alsmeyer – USACE (Present)
Cynthia Van Der Wiele – NCDWQ (Present)
Marla Chambers – NCWRC (Present)
Marella Buncick – USFWS (Present)
Chris Militscher – EPA (Present)
Matt Haney – NCDOT PDEA (Present)

Participants:

Robert Stroup – NCDOT Design Services
John Frye – NCDOT Structures
Ricky Keith – NCDOT Structures
Steve Rackley – NCDOT Structures
Jackie Obediente – NCDOT PDEA
Marshall Clawson – NCDOT Hydraulics
Anne Gamber – NCDOT Hydraulics

Marshall Clawson began the meeting at 1:30 pm with the description of the project. This project consists of the widening of I-85 in Rowan and Davidson Counties.

1. Site 1 I2304AA: The channel relocation right of station 809+60 to 809+90, as noted on the permit drawings, is to be permitted under I-2511CB. The 24" pipe right of station 809+60 is to be angled to avoid a 90° turn in flow.

ACTION TAKEN: The 24" RCP has been skewed to eliminate the 90° turn in flow. The permit drawings and plan sheet have been revised.

2. Site 2 I2304AA: John Frye agreed to provide the quantity of impacts due to the piers for the proposed bridge to Matt Haney and Jackie Obediente for the permits. The environmental impact statement need to reflect the fact that the bridge was located within the critical area of a water supply intake. The wetlands boundary near the pond needs to be clarified in the drawings.

ACTION TAKEN: Wetlands symbols have been removed in the pond area.

3. The temporary work bridge piles at Site 2 I2304AA: Marella Buncick questioned if a platform may be used in this area instead of a work bridge to eliminate impacts due to the use and removal of the temporary piles. Eric Alsmeyer commented that as long as fill would not be required the piles would be okay. Marella Buncick suggested that this might be a good site to use for monitoring the effects of the temporary work bridge impacts.

No Action Required.

4. Site 3 I2304AA: Clarify the inlet of the culvert under the railroad.

ACTION TAKEN: The existing culvert under the railroad has been clearly denoted on the permit drawings.

5. Site 6 I2304AA: Determine why we are impacting existing stream.

The existing 66" pipe under I-85 has an invert approximately 4.5' lower than the stream bed. To maintain positive drainage the entire stream between the Interstate and the Ramp needed to be regraded. To ease construction, a new channel is proposed in lieu of cleaning the existing channel. This site was recommended to PDEA as potential in-site mitigation which would create the positive drainage required for safety and eliminate the significant impacts to this site. However, no on-site mitigation is proposed.

6. Site 9 I2304AA: Check alignment of cross pipe on Plan Sheet 22.

ACTION TAKEN: Cross pipe alignment has been revised on the permit drawings and plan sheet.

7. Site 3 I2304AB: Eliminate northwest preformed scour hole. Investigate redirecting flow through 72" pipe.

ACTION TAKEN: The flow was redirected through the 72" overflow pipe.

8. Site 5 I2304AB: Label permanent soil reinforcement matting on permit drawing.

ACTION TAKEN: Label added.

9. Site 8 I2304AB: Eric Alsmeyer noted that for credit to be given for the channel in the area of pipe removal the stream characteristics must be given.

No Action Required.

10. Site 9 I2304AB: Label slope protection on permit.

ACTION TAKEN: Label added.

The meeting was adjourned at 2:45.


Email from John Frye:

As this project has progressed, an early concurrence point discussed the use of "dual bridges" to cross the Yadkin River at the Counties' line. The "dual bridges" has been carried forth to Concurrence Point #3 which we all know is the LEDPA. That concurrence point was signed in December 2001. In reviewing the Draft FONSI, I commented that a single bridge or a set of dual bridges should never be called out in the LEDPA unless there is a very compelling, very necessary argument by the Department or by the agencies. I do not know of an argument for committing to "dual bridges" for this project.

In the 4C meeting on May 22, I brought this concern to the agencies for discussion. From the discussion that took place, the agencies stated that it was DOT that requested the dual bridges, that they did not have a concern for whether it was one bridge or two, and indicated that they would have no concerns if a single bridge were constructed. For reference, Eric Alsmeyer, Cynthia Van Der Wiele, Marla Chambers, Marella Buncick, and Chris Militscher attended the 4C meeting. In further discussions and e-mails with Marshall and Jackie, and then I met with Debbie

Barbour, it has been decided that it is best if we get agreement from the agencies to ignore the reference to "dual bridges."

This is where you come into this discussion. In my discussion with Debbie Barbour, she determined that the retraction of the "dual bridges" is best handled in the permit applications for this project. Hopefully, in writing the permit application, you could add a single paragraph explaining the Department's oversight, and the Department's request to design either a single wide bridge or dual bridges. As in all the design build projects, we would keep the commitment that the contractor cannot increase the environmental impacts from those called out in the approved permit.



DESIGN DATA

ADT 2005 =	69,400
ADT 2025 =	112,400
DHV =	10 %
D =	60 %
T =	24 % *
V =	70 MPH
* TTST 18 %	DUAL 6 %

PROJECT LENGTH

LENGTH ROADWAY F.A. PROJECT NHF-85-3(164)80 = 3.584 MILES
LENGTH STRUCTURES F.A. PROJECT NHF-85-3(164)80 = 0.009 MILES
TOTAL LENGTH STATE PROJECT 8.1631403 = 3.593 MILES

TRANSMITE CONSULTING Engineers, Incorporated 1300 Paddock Drive, Suite G-10 Raleigh, N.C. 27609	PROJECT ENGINEER DOUGLAS B. SAUNDERS, P.E.	PROJECT DESIGN ENGINEER RICHARD L. BOLLINGER, P.E.	NC DOT CONTACT: MAY 16, 2003 (PRODUCTION) MARCH 16, 2004 (PRODUCTION)	CATHY S. HOUSER, P.E. DESIGN SERVICES - PROJECT ENGINEER
---	--	--	--	--

HYDRAULICS ENGINEER

P.E.



ROADWAY DESIGN ENGINEER

P.E.

SIGNATURE: _____

SIGNATURE: _____

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA	
F.E.	
STATE DESIGN ENGINEER	
DEPARTMENT OF TRANSPORTATION	
FEDERAL HIGHWAY ADMINISTRATION	
APPROVED	DIVISION ADMINISTRATOR
DATE	



See Sheet 1-A For Index of Sheets
See Sheet 1-B For Conventional Symbols

LOCATION: I-85 WIDENING FROM JUST NORTH OF NC 150
TO JUST NORTH OF I-85 BUSINESS
TYPE OF WORK: GRADING, DRAINAGE, PAVING, WIDENING, RESURFACING,
STRUCTURES, CULVERTS, TRAFFIC SIGNALS, & SIGNING, AND

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

DAVIDSON COUNTY

STATE	N.C.	1-2304AB	SHEET NO.	1	42
STATE PROJECT REFERENCE NO.			SHEET TOTAL		
STATE PROJ NO.	8.1631403	NHF-85-3(164)80	DESCRIPTION	P.E.	


PAVEMENT SCHEDULE			
A1	13" PORTLAND CEMENT CONCRETE PAVEMENT	E5	PROP. VARIABLE DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YARD PER 1" DEPTH, TO BE PLACED IN LAYERS NOT GREATER THAN 5.5" IN DEPTH OR LESS THAN 3" IN DEPTH.
A2	VARIABLE DEPTH PORTLAND CEMENT CONCRETE PAVEMENT	J	PROP. 6" AGGREGATE BASE COURSE
C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5A, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YARD.	L	BASE TO BE STABILIZED WITH 200 TO 400 LBS. PER SQ. YARD OF STABILIZER AGGREGATE MIXED WITH THE TOP 3" OF SUB-GRADE SOIL AT LOCATIONS DIRECTED BY THE ENGINEER.
C2	PROP. APPROX. 2.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 140 LBS. PER SQ. YARD IN EACH OF TWO LAYERS.	R1	2'-6" CONCRETE CURB AND GUTTER
C3	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YARD.	R2	4'-0" CONCRETE EXPRESSWAY GUTTER
D1	PROP. APPROX. 2.5" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YARD.	R3	5" MONOLITHIC CONCRETE ISLAND (KEYED IN)
D2	PROP. APPROX. 3.5" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 399 LBS. PER SQ. YARD.	T	EARTH MATERIAL
D3	PROP. APPROX. 4.5" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 256.5 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	U	EXISTING PAVEMENT
E1	PROP. APPROX. 3" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YARD.	X1	PROP. APPROX. 3" PERMEABLE ASPHALT DRAINAGE COURSE TYPE PADL
E2	PROP. APPROX. 3.5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 399 LBS. PER SQ. YARD.	X2	PROP. VARIABLE DEPTH PERMEABLE ASPHALT DRAINAGE COURSE TYPE PADL
E3	PROP. APPROX. 5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 570 LBS. PER SQ. YARD.		
E4	PROP. APPROX. 6" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YARD IN EACH OF TWO LAYERS		

NOTES:
* SHOULDER WIDTH INCREASED 3' WHERE GUARDRAIL IS USED
** FILL SLOPES WITHIN THE INTERCHANGES WILL BE 4:1 OR FLATTER.
*** SEE CROSS SECTIONS FOR VARIABLE SLOPES
**** BITUMINOUS CONCRETE PAVEMENT EDGE SLOPES ARE 1:1
UNLESS SHOWN OTHERWISE

USE TYPICAL SECTION NO. 1A AT THE FOLLOWING STATIONS
-L- Sta. 1015+60.00 TO 1016+30.00 Lt.

-L- 1-85

TYPICAL SECTION NO. 1A




***** GRADE POINTS VARY 11'-0" TO 23'-0" AND MEDIAN LANES VARY FROM 12'-0" TO 0'-0" FROM

-L- Sta. 1144+00.00 TO 1169+68.50 Lt.
-L- Sta. 1144+00.00 TO 1169+68.50 Lt.

NOTE: USE TYPICAL SECTION NO. 3 CURB AND GUTTER TYPICAL AT THE FOLLOWING STATIONS
-L- Sta. 1055+45.96 TO 1056+44.12 Lt.
-L- Sta. 1055+49.06 TO 1056+44.12 Rt.
SEE SHEET 2A TYPICAL SECTION NO. 3

USE TYPICAL SECTION NO. 1 AT THE FOLLOWING STATIONS
-L- Sta. 980+00.00 TO 1015+60.00 Lt. & Rt.
-L- Sta. 1016+30.00 TO 1064+00.00 Lt. & Rt.
-L- Sta. 1064+00.00 Rt. TO 1097+00.00 Rt.
-L- Sta. 1011+50.00 Rt. TO 1144+00.00 Rt.
-L- Sta. 1095+00.00 Lt. TO 1125+00.00 Lt.
-L- Sta. 1130+00.00 Lt. TO 1144+00.00 Lt.




TRANITE CONSULTING
1300 Piedmont Drive, Suite 2100
Atlanta, GA 30329
(404) 525-1100

PROJECT REFERENCE NO.
1-2304AB


ROADWAY DESIGN ENGINEER
ENGINEER
SHEET NO. 2

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION


X2	VARIABLE PADL
X1	3" PADL
T	EARTH MATERIAL
R2	4' EXPRESSWAY GUTTER
R1	2'-6" CURB & GUTTER
L	STABILIZER AGGREGATE
E4	6" ACBC TYPE B25.0B
E2	3.5" ACBC TYPE B25.0B
D3	4.5" ACIC TYPE I19.0B
D2	3.5" ACIC TYPE I19.0B
C2	2.5" ACSC TYPE S9.5B
C1	1.5" ACSC TYPE S9.5A
A1	13" CONCRETE




DETAIL NO. 1A
SEE SHEET 2



TYPICAL SECTION NO. 1B



TYPICAL SECTION NO. 2
RAMPS -Y3REV- INTERCHANGE



TYPICAL SECTION NO. 3
LOOPS -Y3REV- INTERCHANGE


USE TYPICAL SECTION NO. 3 AT THE FOLLOWING STATIONS
-LPB33- Sta. 0+00.00 TO 11+74.87
-LPC33- Sta. 0+00.00 TO 11+72.55

USE TYPICAL SECTION NO. 2 AT THE FOLLOWING STATIONS
-RPB33- Sta. 0+00.00 TO 19+30.90
-RPC33- Sta. 0+00.00 TO 19+21.36

USE TYPICAL SECTION NO. 1B AT THE FOLLOWING STATIONS
-L- Sta. 988+00.00 Rt. TO 993+58.00 Rt.
-L- Sta. 988+50.00 Lt. TO 990+50.00 Lt.
-L- Sta. 1003+00.00 Rt. TO 1007+50.00 Rt.
-L- Sta. 1034+10.00 Rt. TO -RPC33- 5+50.00 Rt.
-L- Sta. 1034+85.00 Lt. TO 1042+95.00 Lt.
-L- Sta. 1064+00.00 Lt. TO 1095+00.00 Lt.
-L- Sta. 1071+00.00 Rt. TO 1080+50.00 Rt.
-L- Sta. 1086+00.00 Rt. TO 1088+75.00 Rt.
-L- Sta. 1097+00.00 Rt. TO 1101+50.00 Rt.
-L- Sta. 1104+10.00 Rt. TO 1107+10.00 Rt.
-L- Sta. 1104+86.00 Lt. TO 1107+10.00 Lt.
-L- Sta. 1116+00.00 Rt. TO 1127+50.00 Rt.
-L- Sta. 1120+50.00 Lt. TO 1130+00.00 Lt.

NOTES:
* SHOULDER WIDTH INCREASED 3' WHERE GUARDRAIL IS USED
** FILL SLOPES WITHIN THE INTERCHANGES WILL BE 4:1 OR FLATTER.
*** SEE CROSS SECTIONS FOR VARIABLE SLOPES
**** PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE


C2	2.5" BCSC S9.5B
D2	3.5" BCIC 119.0B
E3	5" BCBC B25.0B
R3	5" MONO. CONC. ISLAND (KEYED IN)
T	EARTH MATERIAL



TYPICAL SECTION NO. 4B
BELMONT BLVD. -Y3REV-
INSIDE INTERCHANGE


USE TYPICAL SECTION NO. 4B AT THE FOLLOWING STATIONS
-Y3REV- Sta. 22 + 30.23 TO 25 + 50.00

NOTES:
* SHOULDER WIDTH INCREASED 3' WHERE GUARDRAIL IS USED
** FILL SLOPES WITHIN THE INTERCHANGES WILL BE 4:1 OR FLATTER.
*** SEE CROSS SECTIONS FOR VARIABLE SLOPES
**** PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE



TYPICAL SECTION NO. 4A
BELMONT BLVD. -Y3REV-
INSIDE / WEST OF INTERCHANGE

USE TYPICAL SECTION NO. 4A AT THE FOLLOWING STATIONS
-Y3REV- Sta. 5 + 12.52 TO 20 + 50.00



TYPICAL SECTION NO. 4
BELMONT BLVD. -Y3REV-
EAST OF INTERCHANGE

USE TYPICAL SECTION NO. 4 AT THE FOLLOWING STATIONS
-Y3REV- Sta. 26 + 50.00 TO 47 + 62.68

TRAN SITE CONSULTING ENGINEERS, INCORPORATED 1800 Redbank Drive, Suite 210 Raleigh, N.C. 27608	PROJECT REFERENCE NO. I-2304AB	SHEET NO. 2-B
ROADWAY DESIGN ENGINEER	PAVEMENT DESIGN ENGINEER	DO NOT USE FOR CONSTRUCTION


C3	1.5" BCSC S9.5B
J	PROP. 6.0" ABC
T	EARTH MATERIAL
U	EXISTING PAVEMENT

-Y7- Sta. 16+17.39
 -Y3REV- Sta. 47+62.68
 -SR3- Sta. 10+90.05
 -SR3- Sta. 36+90.00
 -SR3- Sta. 51+38.75
 -RP85B- Sta. 21+15.08
 -RP85C- Sta. 12+03.85


USE DETAIL E-1 AT THE FOLLOWING STATIONS

EXISTING TIE IN MILLING DETAIL E-1

VARIABLE - - AS ESTABLISHED BY ENGINEER



TYPICAL SECTION NO. 11 D3 (DRIVEWAY)




USE TYPICAL SECTION NO. 11 AT THE FOLLOWING STATIONS

-D3- Sta. 10+00.00 TO Sta. 11+23.18

NOTES:

PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE

TYPICAL SECTION NO. 10 D1, D2 (DRIVEWAYS)



USE TYPICAL SECTION NO. 10 AT THE FOLLOWING STATIONS

-D1- Sta. 10+12.00 TO Sta. 11+07.00

-D2- Sta. 10+12.00 TO Sta. 11+32.00

TRAN SITE CONSULTING ENGINEERS, INCORPORATED 1000 Parkway Drive, Suite 200 Raleigh, N. C. 27605		ROADWAY DESIGN ENGINEER		DO NOT USE FOR CONSTRUCTION	
PROJECT REFERENCE NO.		1-2304AB		PRELIMINARY PLANS	
SHEET NO.		2-E		PAVEMENT DESIGN ENGINEER	

REVISIONS


TEAM SITE CONSULTING
1700 RIVERSIDE DRIVE, SUITE 210
RICHMOND, N.C. 27609

PROJECT REFERENCE NO. 1-2304AB
SHEET NO. 2-F


ROADWAY DESIGN ENGINEER
HYDRAULICS ENGINEER

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

DETOUR (-SRD2-)



SEE SHEET 36 & 37 FOR -SRD2- PROFILE
SEE SHEET 45 FOR -DETSRD2- PROFILE



-L-/-Y3REV- SHEAR POINT DIAGRAM

PROJECT REFERENCE NO.		SHEET NO.	
1-2304AB		2-6	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS			
DO NOT USE FOR CONSTRUCTION			

TRAN SITE CONSULTING
1000 RIVERSIDE DRIVE, SUITE 210
Raleigh, NC 27609

REVISIONS

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK
IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
SUMMARY #1					
-L- (LT) STA. 980 + 00.00 to 998 + 00.00	50,350		2,218	0	48,132
-L- (MED) STA. 980 + 00.00 to 998 + 00.00	3,491		347	0	3,144
-L- (RT) STA. 980 + 00.00 to 998 + 00.00	9,308		12,709	3,402	0
-SRD1- STA. 55 + 97.51 to 68 + 00.00	37,868		16,375	0	21,494
#1 TOTAL	101,018		31,649	3,402	72,770
SUMMARY #2					
-L- (LT) STA. 998 + 00.00 to 1036 + 00.00	69,521		18,833	0	50,688
-L- (MED) STA. 998 + 00.00 to 1036 + 00.00	8,179		2,522	0	5,656
-L- (RT) STA. 998 + 00.00 to 1036 + 00.00	16,691		32,260	15,569	0
-SRD1- STA. 68 + 00.00 to 100 + 28.15	60,829		27,308	0	33,521
#2 TOTAL	155,220		80,923	15,569	89,866
SUMMARY #3					
-L- (LT) STA. 1036 + 00.00 to 1058 + 00.00	18,297		38,648	20,351	0
-L- (MED) STA. 1036 + 00.00 to 1058 + 00.00	2,624		5,906	3,282	0
-L- (RT) STA. 1036 + 00.00 to 1058 + 00.00	15,625		38,274	22,648	0
-Y3REV- STA. 5 + 12.52 to 47 + 62.58	132,594		481,002	348,408	0
-RPB3- STA. 7 + 00.00 to 14 + 50.00	21,814		4,861	0	16,952
-LPB3- STA. 2 + 50.00 to 11 + 00.00	27,580		6,145	0	21,435
-RPC3- STA. 7 + 00.00 to 15 + 00.00	20,699		55,700	35,000	0
-LPC3- STA. 2 + 50.00 to 11 + 00.00	7,420		220,665	213,245	0
-SRD- STA. 21 + 45.00 to 28 + 50.00	573		4,364	3,791	0
-Y7- STA. 10 + 50.00 to 16 + 17.39	251		9,104	8,853	0
#3 TOTAL	247,477		864,669	655,578	38,388
SUMMARY #4					
-L- (LT) STA. 1058 + 00.00 to 1098 + 00.00	22,492		3,147	0	19,345
-L- (MED) STA. 1058 + 00.00 to 1098 + 00.00	8,139		699	0	7,441
-L- (RT) STA. 1058 + 00.00 to 1098 + 00.00	54,619		46,115	0	8,503
-SRA- STA. 11 + 00.00 to 51 + 38.75	66,003		36,691	0	29,312
-SRD2- STA. 11 + 00.00 to 19 + 61.43	14,893		119,401	104,508	0
-SR4- STA. 10 + 12.17 to 18 + 03.09	9,854		74	0	9,780
-DETSRD2- STA. 13 + 68.00 to 15 + 87.00	0		2863	3436	0
DETOUR REMOVAL					
-DETSRD2- STA. 13 + 68.00 to 15 + 87.00	3436		0	0	3436
#4 TOTAL	179,436		208,990	107,944	77,817
SUMMARY #5					
-L- (LT) STA. 1098 + 00.00 to 1147 + 50.00	31,658		32,235	419	0
-L- (MED) STA. 1098 + 00.00 to 1147 + 50.00	8,818		1,361	0	7,477
-L- (RT) STA. 1098 + 00.00 to 1147 + 50.00	17,094		28,514	11,420	0
-SR3- STA. 10 + 90.05 to 36 + 90.00	6,982		12,111	5,130	0
-RP85B- STA. 11 + 13.49 to 21 + 15.08	4,635		1,153	0	3,482
-RP85C- STA. 7 + 68.22 to 11 + 43.48	3,193		0	0	3,193
#5 TOTAL	72,380		75,374	16,968	14,152
SUMMARY #6					
-L- (LT) STA. 1147 + 50.00 to 1169 + 68.50	12,802		33	0	3,465
-L- (MED) STA. 1147 + 50.00 to 1169 + 68.50	8,469		847	0	5,699
-L- (RT) STA. 1147 + 50.00 to 1169 + 68.50	5,942		190	0	5,752
#6 TOTAL	27,213		1,070	0	14,916
SUMMARIES #1-6 TOTAL	782,744		1,262,675	799,461	304,472
EST. 5% TO REPLACE SOIL IN BORROW PIT				39,973	
WASTE IN LIEU OF BORROW				-304,472	-304,472
GRAND TOTALS	782,744		1,262,675	534,962	3436
SAY	783,000		1,263,000	535,000	3450

RIGHT OF WAY AREA DATA SHEET

COMPUTED BY: PER	DATE: 1-06-03
CHECKED BY: CUM	DATE: 4-25-03

PROD. REFERENCE NO.	1-2304AB
SHEET NO.	3-B

PARCEL NO.	PROPERTY OWNERS NAME	TOTAL AREA	AREA TAKEN	AREA REMAINING	AREA REMAINING	CONSTR. EASEMENT	PERMANENT DRAINAGE EASEMENT	TEMPORARY DRAINAGE EASEMENT
1	LOUISE C. SIGMON ESTATE	45,302 SF	11,265 SF	34,037 SF				
2	MOBILE HOME CITY, INC.	3,59 AC	13,398 SF	3,28 AC				
3	MOBILE HOME CITY, INC.	6,53 AC	2,041 SF	6,48 AC				
4	ROBERT L. GRUBB	UNKNOWN	28326 SF	UNKNOWN	3,435 SF	3,774 SF		
5	EVERHART USED CARS, INC.	5,60 AC	1,25 AC	4,35 AC	1,251 SF			
6	FRANKLIN HAYWOOD GRAVES & WIFE, MARAGARET L. GRAVES	4,00 AC	18,380 SF	3,58 AC				
7	FRANKLIN HAYWOOD GRAVES & WIFE, MARAGARET L. GRAVES	5,02 AC	21,863 SF	4,52 AC				
8	TRUSTEES OF GREYS CHAPEL UNITED METHODIST CHURCH	6,17 AC	21,649 SF	5,67 AC				
9	MICHAEL EDWARD TURNER & WIFE, MARIE OVERLA TURNER	5,84 AC	28,842 SF	5,18 AC				
10	FRANK J. BONDATTI & WIFE, JACQUELINE D. BONDATTI	9,07 AC	3,89 AC	5,18 AC				
11	RANDOLPH NATHAN MARTIN & WIFE, CATHY R. MARTIN	5,33 AC	14,830 SF	4,99 AC				
12	THOMAS E. MARTIN & BELINDA E. LEMONS	7,35 AC	24,937 SF	6,78 AC				
13	EARL L. BLANTON & WIFE, KATHY L. BLANTON	12,36 AC	35,540 SF	11,54 AC				
14	ROBERT L. GRUBB, TRUSTEE OF JUNE C. LITTLE	UNKNOWN	2,66 AC	UNKNOWN				
15	ROBERT L. GRUBB, TRUSTEE OF JUNE C. LITTLE	UNKNOWN	2,39 AC	UNKNOWN	1,125 SF	2,027 SF		
16	WALTER MCDOWELL, SR	3,00 AC	3,00 AC		571 SF	2,030 SF		
17	HENDERSON HARGRAVE HEIRS	34,90 AC	14,00 AC	20,90 AC	479 SF	900 SF		
18	RANDALL G. LOMAX & WIFE, TAMMY P. LOMAX	7,01 AC	17,631 SF	6,61 AC	1,832 SF			
19	DAVID G. VARNER & WIFE, TRACEY S. VARNER	12,14 AC	9,57 AC		2,57 AC			
20	ROBERT L. GRUBB, TRUSTEE OF JUNE C. LITTLE	UNKNOWN	2,53 AC	UNKNOWN				
21	WALSER ENTERPRISES	9,80 AC	1,95 AC	7,85 AC				6,261 SF
22	ROBERT L. GRUBB, TRUSTEE OF JUNE C. LITTLE	UNKNOWN	1,16 AC	UNKNOWN				21,723 SF
23	WHITEHAT NIGHT CLUB, INC.	39,706 SF	38,744 SF					852 SF
24	BILL'S TRUCK STOP, INC.	1 AC	2,04 AC		479 SF			
25	C.C. FITZGERALD HEIRS	UNKNOWN	1,87 AC	UNKNOWN				
26	C.C. FITZGERALD HEIRS	UNKNOWN	3,14 AC	UNKNOWN				
27	DELMONT C. GRIM & WIFE, ELSIE L. GRIM	3,20 AC	17,907 SF	2,79 AC				
28	BRIGHT I. SINK & WIFE, ANNIE LEE FITZGERALD SINK	3,08 AC	12,855 SF	2,79 AC				3,582 SF
29	JOHN H. FERGUSON & WIFE, BETTY G. FERGUSON	3,94 AC	12,103 SF	3,66 AC				3,492 SF
30	ROBERT A. GUSMAN	4,33 AC	29,132 SF	3,66 AC				
31	LESTER C. KINES & WIFE, TROY KINES	16,553 SF	16,453 SF					8,388 SF
32	LESTER C. KINES & WIFE, TROY KINES	1,30 AC	24,308 SF	32,320 SF				3,233 SF
33	WILLIAM RODGER FOSTER & WIFE, SYLVIA L. FOSTER	1,31 AC		1,31 AC				6,871 SF
34	MOBILE DEVELOPMENT CORPORATION	10,06 AC	1,36 AC	8,70 AC				
35	CHARLES E. SEARS & WIFE, MARY JANE SEARS	2,77 AC	20,866 SF	2,29 AC				
36	DEBORAH L. BUFFKIN & HUSBAND, ZACHARY A. BUFFKIN	1,39 AC	10,588 SF	1,15 AC				
37	FOY M. MCMAHAN & WIFE, DOROTHY D. MCMAHAN	1,39 AC	10,686 SF	1,14 AC				
38	ANDREW W. LEONARD & WIFE, JEAN E. LEONARD	7,01 AC	25,978 SF	6,41 AC				1,700 SF
39	LARRY L. GOBBLE & WIFE, KATHY L. GOBBLE	1,30 AC	5,437 SF	1,17 AC				
40	GEORGE W. GOBBLE & WIFE, BETTY E. GOBBLE	16,54 AC	17,465 SF	16,14 AC				317 SF

03-001-001/005N/45W/4-0W-00105N04T.SUM Rev. date: 04-25-03

RIGHT OF WAY PARCEL INDEX

PARCEL NUMBER	SHEET NUMBER	PROPERTY OWNER NAME
1	4	LOUISE C. SIGMON ESTATE
2	4	MOBILE HOME CITY, INC.
3	4,5	MOBILE HOME CITY, INC.
4	4,5,6,7	ROBERT L. GRUBB
5	5,6	EVERHART USED CARS, INC.
6	5,6	FRANKLIN HAYWOOD GRAVES & WIFE, MARAGARET L. GRAVES
7	6	FRANKLIN HAYWOOD GRAVES & WIFE, MARAGARET L. GRAVES
8	6,7	TRUSTEES OF GREERS CHAPEL UNITED METHODIST CHURCH
9	7	MICHAEL EDWARD TURNER & WIFE, MARIE OVERLA TURNER
10	7	FRANK J. BONDATTI & WIFE, JACQUELINE D. BONDATTI
11	7	RANDOLPH NATHAN MARTIN & WIFE, CATHY R. MARTIN
12	7	THOMAS E. MARTIN & BELINDA E. LEMONS
13	7,8	EARL L. BLANTON & WIFE, KATHY L. BLANTON
14	7,8,9	ROBERT L. GRUBB, TRUSTEE OF JUNE C. LITTLE
15	8,9	ROBERT L. GRUBB, TRUSTEE OF JUNE C. LITTLE
16	9,18	WALTER MCDOWELL, SR
17	9,18,19	HENDERSON HARGRAVE HEIRS
18	9,10	RANDALL G. LOMAX & WIFE, TAMMY P. LOMAX
19	9,18	DAVID G. VARNER & WIFE, TRACEY S. VARNER
20	18	ROBERT L. GRUBB, TRUSTEE OF JUNE C. LITTLE
21	9	WALSER ENTERPRISES
22	9,18	ROBERT L. GRUBB, TRUSTEE OF JUNE C. LITTLE
23	9,10	WHITEHAT NIGHTCLUB, INC.
24	9,10	BILL'S TRUCK STOP, INC.
25	9,10,11,12	C.C. FITZGERALD HEIRS
26	9,10,11	C.C. FITZGERALD HEIRS
27	10,11	DELMONT C. GRIM & WIFE, ELSIE L. GRIM
28	11	BRIGHT I. SINK & WIFE, ANNIE LEE FITZGERALD SINK

[illegible]

DATUM DESCRIPTION

IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCOT FOR MONUMENT "POINTS"

WITH NAD 83 STATE PLANE GRID COORDINATES OF NORTHING: 726960.143911 EASTING: 1593494.155511

THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.999876970

THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "POINTS" TO L-1 STATION 980+00.00 IS S 69° 19' 06.31" E 1098.494111

5 69° 19' 06.31" E 1098.494111

ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES

VERTICAL DATUM USED IS NGVD 29

50 (-SRDI-)

55 (-SRDI-)

60 (-SRDI-)

65 (-SRDI-)

70 (-SRDI-)

75 (-SRDI-)

80 (-SRDI-)

85 (-SRDI-)

90 (-SRDI-)

95 (-SRDI-)

100 (-SRDI-)

105 (-SRDI-)

110 (-SRDI-)

115 (-SRDI-)

120 (-SRDI-)

125 (-SRDI-)

130 (-SRDI-)

135 (-SRDI-)

140 (-SRDI-)

145 (-SRDI-)

150 (-SRDI-)

155 (-SRDI-)

160 (-SRDI-)

165 (-SRDI-)

170 (-SRDI-)

175 (-SRDI-)

180 (-SRDI-)

185 (-SRDI-)

190 (-SRDI-)

195 (-SRDI-)

200 (-SRDI-)

205 (-SRDI-)

210 (-SRDI-)

215 (-SRDI-)

220 (-SRDI-)

225 (-SRDI-)

230 (-SRDI-)

235 (-SRDI-)

240 (-SRDI-)

245 (-SRDI-)

250 (-SRDI-)

255 (-SRDI-)

260 (-SRDI-)

265 (-SRDI-)

270 (-SRDI-)

275 (-SRDI-)

280 (-SRDI-)

285 (-SRDI-)

290 (-SRDI-)

295 (-SRDI-)

300 (-SRDI-)

305 (-SRDI-)

310 (-SRDI-)

315 (-SRDI-)

320 (-SRDI-)

325 (-SRDI-)

330 (-SRDI-)

335 (-SRDI-)

340 (-SRDI-)

345 (-SRDI-)

350 (-SRDI-)

355 (-SRDI-)

360 (-SRDI-)

365 (-SRDI-)

370 (-SRDI-)

375 (-SRDI-)

380 (-SRDI-)

385 (-SRDI-)

390 (-SRDI-)

395 (-SRDI-)

400 (-SRDI-)

405 (-SRDI-)

410 (-SRDI-)

415 (-SRDI-)

420 (-SRDI-)

425 (-SRDI-)

430 (-SRDI-)

435 (-SRDI-)

440 (-SRDI-)

445 (-SRDI-)

450 (-SRDI-)

455 (-SRDI-)

460 (-SRDI-)

465 (-SRDI-)

470 (-SRDI-)

475 (-SRDI-)

480 (-SRDI-)

485 (-SRDI-)

490 (-SRDI-)

495 (-SRDI-)

500 (-SRDI-)

505 (-SRDI-)

510 (-SRDI-)

515 (-SRDI-)

520 (-SRDI-)

525 (-SRDI-)

530 (-SRDI-)

535 (-SRDI-)

540 (-SRDI-)

545 (-SRDI-)

550 (-SRDI-)

555 (-SRDI-)

560 (-SRDI-)

565 (-SRDI-)

570 (-SRDI-)

575 (-SRDI-)

580 (-SRDI-)

585 (-SRDI-)

590 (-SRDI-)

595 (-SRDI-)

600 (-SRDI-)

605 (-SRDI-)

610 (-SRDI-)

615 (-SRDI-)

620 (-SRDI-)

625 (-SRDI-)

630 (-SRDI-)

635 (-SRDI-)

640 (-SRDI-)

645 (-SRDI-)

650 (-SRDI-)

655 (-SRDI-)

660 (-SRDI-)

665 (-SRDI-)

670 (-SRDI-)

675 (-SRDI-)

680 (-SRDI-)

685 (-SRDI-)

690 (-SRDI-)

695 (-SRDI-)

700 (-SRDI-)

705 (-SRDI-)

710 (-SRDI-)

715 (-SRDI-)

720 (-SRDI-)

725 (-SRDI-)

730 (-SRDI-)

735 (-SRDI-)

740 (-SRDI-)

745 (-SRDI-)

750 (-SRDI-)

755 (-SRDI-)

760 (-SRDI-)

765 (-SRDI-)

770 (-SRDI-)

775 (-SRDI-)

780 (-SRDI-)

785 (-SRDI-)

790 (-SRDI-)

795 (-SRDI-)

800 (-SRDI-)

805 (-SRDI-)

810 (-SRDI-)

815 (-SRDI-)

820 (-SRDI-)

825 (-SRDI-)

830 (-SRDI-)

835 (-SRDI-)

840 (-SRDI-)

845 (-SRDI-)

850 (-SRDI-)

855 (-SRDI-)

860 (-SRDI-)

865 (-SRDI-)

870 (-SRDI-)

875 (-SRDI-)

880 (-SRDI-)

885 (-SRDI-)

890 (-SRDI-)

895 (-SRDI-)

900 (-SRDI-)

905 (-SRDI-)

910 (-SRDI-)

915 (-SRDI-)

920 (-SRDI-)

925 (-SRDI-)

930 (-SRDI-)

935 (-SRDI-)

940 (-SRDI-)

945 (-SRDI-)

950 (-SRDI-)

955 (-SRDI-)

960 (-SRDI-)

965 (-SRDI-)

970 (-SRDI-)

975 (-SRDI-)

980 (-SRDI-)

985 (-SRDI-)

990 (-SRDI-)

995 (-SRDI-)

1000 (-SRDI-)

1005 (-SRDI-)

1010 (-SRDI-)

1015 (-SRDI-)

1020 (-SRDI-)

1025 (-SRDI-)

1030 (-SRDI-)

1035 (-SRDI-)

1040 (-SRDI-)

1045 (-SRDI-)

1050 (-SRDI-)

1055 (-SRDI-)

1060 (-SRDI-)

1065 (-SRDI-)

1070 (-SRDI-)

1075 (-SRDI-)

1080 (-SRDI-)

1085 (-SRDI-)

1090 (-SRDI-)

1095 (-SRDI-)

1100 (-SRDI-)

1105 (-SRDI-)

1110 (-SRDI-)

1115 (-SRDI-)

1120 (-SRDI-)

1125 (-SRDI-)

1130 (-SRDI-)

1135 (-SRDI-)

1140 (-SRDI-)

1145 (-SRDI-)

1150 (-SRDI-)

1155 (-SRDI-)

1160 (-SRDI-)

1165 (-SRDI-)

1170 (-SRDI-)

1175 (-SRDI-)

1180 (-SRDI-)

1185 (-SRDI-)

1190 (-SRDI-)

1195 (-SRDI-)

1200 (-SRDI-)

1205 (-SRDI-)

1210 (-SRDI-)

1215 (-SRDI-)

1220 (-SRDI-)

1225 (-SRDI-)

1230 (-SRDI-)

1235 (-SRDI-)

1240 (-SRDI-)

1245 (-SRDI-)

1250 (-SRDI-)

1255 (-SRDI-)

1260 (-SRDI-)

1265 (-SRDI-)

1270 (-SRDI-)

1275 (-SRDI-)

1280 (-SRDI-)

1285 (-SRDI-)

1290 (-SRDI-)

1295 (-SRDI-)

1300 (-SRDI-)

1305 (-SRDI-)

1310 (-SRDI-)

1315 (-SRDI-)

1320 (-SRDI-)

1325 (-SRDI-)

1330 (-SRDI-)

1335 (-SRDI-)

1340 (-SRDI-)

1345 (-SRDI-)

1350 (-SRDI-)

1355 (-SRDI-)

1360 (-SRDI-)

1365 (-SRDI-)

1370 (-SRDI-)

1375 (-SRDI-)

1380 (-SRDI-)

1385 (-SRDI-)

1390 (-SRDI-)

1395 (-SRDI-)

1400 (-SRDI-)

1405 (-SRDI-)

1410 (-SRDI-)

1415 (-SRDI-)




1420 (-SRDI-)

1425 (-SRDI-)

1430 (-SRDI-)


1435 (-SRDI-)

1440 (-SRDI-)




PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

REVISIONS



PROJECT REFERENCE NO. 1-2304AB		RW SHEET NO. 6	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION			



REVISIONS	
-----------	--








NC GRID + NAD 83

TRAN SITE CONSULTING ENGINEERS, INCORPORATED 1100 Piedmont Drive, Suite 410-10 Raleigh, N.C. 27609		ROADWAY DESIGN ENGINEER HYDRAULICS ENGINEER		DO NOT USE FOR CONSTRUCTION PRELIMINARY PLANS	
PROJECT REFERENCE NO.		RMW SHEET NO.		1-2304AB	
SHEET NO.		8			


101.001.001/dgn/12304dbs01.dgn rev. date: 03-03-03

MATCH LINE STA. 1070+00 SEE SHEET 9

MATCH LINE STA. 1083+00 SEE SHEET 11



SEE SHEET 24 FOR L- PROFILE
SEE SHEET 36 & 37 FOR SRA- PROFILE



REVISIONS	

P Sta 25+83.38
Δ = 57.53' 54.0" (LT)
D = 12' 19' 18.0"
L = 469.89'
T = 257.21'
R = 465.00'
e = 0.080
RO = 168'
DS = 40 MPH

NC GRID NAD 83

TRAN SITE CONSULTING
1300 Piedmont Drive, Suite 210
Raleigh, N.C. 27609





PROJECT REFERENCE NO.
1-2304AB

RW SHEET NO.
10

ROADWAY DESIGN
ENGINEER

HYDRAULICS
ENGINEER

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION



REMOVE

EX.R/W





















































































































+38.75 -SRA



















1.5

1.5

TRANSLIFE CONSULTING ENGINEERS, INCORPORATED
1300 Paddock Drive, Suite G-10
Raleigh, N.C. 27609

PROJECT REFERENCE NO.		1-2304AB	
SHEET NO.		11	
ROADWAY DESIGN		HYDRAULICS	
ENGINEER		ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION			





REVISIONS

0+31.33
ANGLE
IRON

DS = 65 MPH
e = 0.070
R = 2035.00'
T = 365.78'
L = 723.83'
D = 2' 48" 55.9"
LS = 2' 57" 22.7"
Δ = 20' 22" 46.5" (RT)
PI Sta 5+75.78
P1 Sta 1+40.02

-RP85C-

[illegible]

Δ = 41.48 33.0° (LT) Δ = 2.59 14.6° (LT) Δ = 18.18 15.8° (LT)
 D = 13.35 26.15° D = 27.27 40.0° D = 27.09 40.5°
 L = 31.33° L = 121.38° L = 41.62°
 T = 16.40° T = 60.71° T = 20.88°
 R = 42.94° R = 2.3280.3° R = 210.95°
 e = 0.020 e = 0.020 e = 0.020
 RO = 0.00° RO = 0.00° RO = 0.00°
 DS = 25 MPH DS = 25 MPH DS = 25 MPH

NC GRID NAD 83


TRANSITE CONSULTING
ENGINEERS, INCORPORATED
1300 Raddock Drive, Suite G-10
Raleigh, N.C. 27609

PROJECT REFERENCE NO.	1-2304AB
SHEET NO.	14


ROADWAY DESIGN	HYDRAULICS
ENGINEER	ENGINEER

PRELIMINARY PLANS	DO NOT USE FOR CONSTRUCTION
-------------------	-----------------------------

MATCH LINE STA. 1135+00 SEE SHEET 15

[illegible]

PRELIMINARY PLANS	DO NOT USE FOR CONSTRUCTION
-------------------	-----------------------------





REVISIONS	

TRAN SITE CONSULTING ENGINEERS, INCORPORATED 1300 REDWOOD CHASE, SUITE 210 BIRMINGHAM, AL 35209		GRID NAD 83
PROJECT REFERENCE NO. _____ SHEET NO. _____		
ROADWAY DESIGN ENGINEER		
HYDRAULICS ENGINEER		
RM SHEET NO. _____		
1/-2304B		16
PROJECT REFERENCE NO. _____ SHEET NO. _____		

SEE SHEET 27 & 28 FOR -L- PROFILE
SEE SHEET 44 FOR -RP85B- PROFILE

MATCH LINE STA. 1160 + 00 SEE SHEET 16




REVISIONS

TRAN SITE CONSULTING
1000 P.O. Box 1000
Raleigh, N.C. 27609

PROJECT REFERENCE NO. 1-2304AB
SHEET NO. 17
RW SHEET NO. 17
ROADWAY DESIGN
HYDRAULICS
ENGINEER
DO NOT USE FOR CONSTRUCTION
PRELIMINARY PLANS

PROJECT: 8.1631403

I-2304AA



DESIGN DATA

ADT 2001 =	60,800
ADT 2025 =	112,400
DHV =	10 %
D =	60 %
T =	24 %
V =	70 MPH
* TTST =	18 %
DUAL =	6 %

PROJECT LENGTH

LENGTH ROADWAY F.A. PROJECT NHF-85-3(164)80 =	2.70 MI.
LENGTH STRUCTURES F.A. PROJECT NHF-85-3(164)80 =	0.58 MI.
TOTAL LENGTH STATE PROJECT 8.1631403 =	3.28 MI.

Barbara H. Mulkey Engineering Inc.

FOR THE N.C. DEPT. OF TRANSPORTATION

2002 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE: 12/20/02 (PROD.)

LETTING DATE: 11/20/07

NCDOT CONTACT:

PROJECT ENGINEER - DESIGN SERVICES	CATHY S. HOUSER, P.E.
PROJECT DESIGN ENGINEER	TIM JORDAN, P.E.
PROJECT ENGINEER	TIM S. HAYES, P.E.

HYDRAULICS ENGINEER

ROADWAY DESIGN ENGINEER

STATE DESIGN ENGINEER

APPROVED

DIVISION ADMINISTRATOR

DATE

DIVISION OF HIGHWAYS

STATE OF NORTH CAROLINA

FEDERAL HIGHWAY ADMINISTRATION

DEPARTMENT OF TRANSPORTATION

INCOMPLETE PLANS

DO NOT USE FOR R/W ACQUISITION

PRELIMINARY PLANS

DO NOT USE FOR CONSTRUCTION

Barbara H. Mulkey Engineering, Inc.

P.O. Box 3302


RAVENNA, NC 27856-3021

(919) 851-9188 (FAX)

THIS IS A CONTROLLED-ACCESS PROJECT WITH ACCESS BEING LIMITED TO INTERCHANGES.

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

THIS PROJECT IS NOT WITHIN ANY MUNICIPAL BOUNDARIES.



*S.U.E = SUBSURFACE UTILITY ENGINEER

CONVENTIONAL SYMBOLS

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

BARBARA H. MILKREY ENGINEERING, INC.

P.O. BOX 3327
RALEIGH, N.C. 27605-3327
(919) 851-9192
(919) 851-1918 (FAX)

PROJECT REFERENCE NO.

1-2304AA

SHEET NO.

1-B

PRELIMINARY PLANS

DO NOT USE FOR CONSTRUCTION

ROADS & RELATED ITEMS

Edge of Pavement	---
Curb	---
Prop. Slope Stakes Cut	- - - C
Prop. Slope Stakes Fill	- - - F
Prop. Woven Wire Fence	---○---○---
Prop. Chain Link Fence	---□---□---
Prop. Barbed Wire Fence	---◇---◇---
Prop. Wheelchair Ramp	---(WCR)---
Exist. Guardrail	---+---+---
Prop. Guardrail	---+---+---
Equality Symbol	⊕
Pavement Removal	▒

RIGHT OF WAY

Baseline Control Point	◆
Existing Right of Way Marker	▽
Exist. Right of Way Line w/Marker	▽
Prop. Right of Way Line with Proposed RW Marker (Iron Pin & Cap)	▼
Prop. Right of Way Line with Proposed (Concrete or Granite) RW Marker	⦿
Exist. Control of Access Line	⦿
Prop. Control of Access Line	⦿
Exist. Easement Line	⦿
Prop. Temp. Construction Easement Line	---
Prop. Temp. Drainage Easement Line	---
Prop. Perm. Drainage Easement Line	---

HYDROLOGY

Stream or Body of Water	---
Flow Arrow	→
Disappearing Stream	---
Spring	---
Swamp Marsh	---
Shoreline	---
Falls, Rapids	---
Prop Lateral, Tail, Head Ditches	---

STRUCTURES

MAJOR	---
Bridge, Tunnel, or Box Culvert	---
Bridge Wing Wall, Head Wall and End Wall	---

UTILITIES

MINOR	---
Head & End Wall	---
Pipe Culvert	---
Footbridge	---
Drainage Boxes	---
Paved Ditch Gutter	---
Exist. Pole	•
Exist. Power Pole	•
Prop. Power Pole	•
Exist. Telephone Pole	•
Prop. Telephone Pole	•
Exist. Joint Use Pole	•
Prop. Joint Use Pole	•
Telephone Pedestal	⦿
Cable TV Pedestal	⦿
Hydrant	⦿
Satellite Dish	⦿
Exist. Water Valve	⦿
Sewer Clean Out	⦿
Power Manhole	⦿
Telephone Booth	⦿
Water Manhole	⦿
Light Pole	⦿
H-Frame Pole	⦿
Power Line Tower	⦿
Pole with Base	⦿
Gas Valve	⦿
Gas Meter	⦿
Telephone Manhole	⦿
Power Transformer	⦿
Sanitary Sewer Manhole	⦿
Storm Sewer Manhole	⦿
Tank, Water, Gas, Oil	⦿
Water Tank With Legs	⦿
Traffic Signal Junction Box	⦿
Fiber Optic Splice Box	⦿
Television or Radio Tower	⦿
Utility Power Line Connects to Traffic Signal Lines Cut Into the Pavement	---

BOUNDARIES & PROPERTIES

Recorded Water Line	---
Designated Water Line (S.U.E.*)	---
Sanitary Sewer	---
Recorded Sanitary Sewer Force Main	---
Designated Sanitary Sewer Force Main(S.U.E.*)	---
Recorded Gas Line	---
Designated Gas Line (S.U.E.*)	---
Storm Sewer	---
Recorded Power Line	---
Designated Power Line (S.U.E.*)	---
Recorded Telephone Cable	---
Designated Telephone Cable (S.U.E.*)	---
Recorded UG Telephone Conduit	---
Designated UG Telephone Conduit(S.U.E.*)	---
Unknown Utility (S.U.E.*)	---
Recorded Television Cable	---
Designated Television Cable (S.U.E.*)	---
Recorded Fiber Optics Cable	---
Designated Fiber Optics Cable (S.U.E.*)	---
Exist. Water Meter	---
UG Test Hole (S.U.E.*)	---
Abandoned According to UG Record	---
End of Information	---
State Line	---
County Line	---
Township Line	---
City Line	---
Reservation Line	---
Property Line	---
Property Line Symbol	---
Exist. Iron Pin	---
Property Corner	---
Property Monument	---
Parcel Number	---
Fence Line	---
Existing Wetland Boundaries	---
Proposed Wetland Boundaries	---
Existing Endangered Animal Boundaries	---
Existing Endangered Plant Boundaries	---

TOPOGRAPHY

Swimming Pool	---
Small Mine	---
Well	---
Sign	---
Dam	---
Cemetery	---
Park	---
School	---
Church	---
Gas Pump Vent or UG Tank Cap	---
Gate	---
Area Outline	---
Foundations	---
Buildings	---




VEGETATION

Light House	---
Single Tree	---
Single Shrub	---
Hedge	---
Woods Line	---
Orchard	---
Vineyard	---

RAILROADS


Standard Gauge	---
RR Signal Milepost	---
Switch	---

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION




13" CONCRETE	A1
1 1/2" S-95A	CI
STABILIZER	L
EXP. GUTTER	R2
EARTH	T
3" PADL	X

BARBARA H. MULKER ENGINEERING, INC.			
P.O. Box 33127 Raleigh, N.C. 27636-3272		(919) 851-9122 (919) 851-9126 (FAX)	
PROJECT REFERENCE NO.	1-23044A	R/W	SHEET NO.
SHEET NO.	2-B		




-RAMP A- STA.7+26.50 TO 21+68.96 ±
-RAMP C- STA.4+30.72 TO 16+40.57 ±

7007S






-L00P A- STA.2+17.65 TO 7+58.48 ±
-L00P C- STA.2+17.65 TO 7+84.89 ±


		BARNHART H. MULLEN ENGINEERING, INC. P. O. Box 3317 Raleigh, N.C. 27656-0317 (919) 561-0102 (919) 561-7916 (FAX)	
PROJECT REFERENCE NO.		1-230474	
SHEET NO.		2-D	
RM. SHEET NO.		1-230474	




C3	1 1/2" S-95B
DI	2 1/2" I-190B
EI	3" B-250B
T	EARTH
U	EXIST. PAVE



BARBARA H. WILKEY ENGINEERING, INC.			
PROJECT REFERENCE NO.		P.O. Box 33127 Richmond, VA 23268-3127 (819) 854-2021 (519) 851-1910 (FAX)	
SHEET NO.		RW SHEET NO.	
1-23044A		2-F	




* WHEN THESE DISTANCES INDICATE SLOPES OUTSIDE THE LIMITS OF 6:1 TO 2:1, THE DISTANCE BECOMES VARIABLE AND THE MAXIMUM OR MINIMUM SLOPE MAINTAINED.



TYPICAL SECTION NO. 15
USE TYPICAL SECTION NO. 15 AS FOLLOWS:
-SRB- STA. 18+00.00 TO 31+07.19 (BEGIN BRIDGE)

* WHEN THESE DISTANCES INDICATE SLOPES OUTSIDE THE LIMITS OF 6:1 TO 2:1, THE DISTANCE BECOMES VARIABLE AND THE MAXIMUM OR MINIMUM SLOPE MAINTAINED.



TYPICAL SECTION NO. 14
USE TYPICAL SECTION NO. 14 AS FOLLOWS:
-SRB- STA. 15+44.34 TO 18+00.00

U	EXIST. PAVE
T	EARTH
EI	3" B-25.0B
D3	3 1/2" 1-19.0B
C4	2 1/2" S-9.5B


PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

Blume
BARBARA H. WILKEY ENGINEERING, INC.
P.O. BOX 33827
RICHMOND, VA 23263-2827
(804) 851-1902
(919) 851-1908 (FAX)


PROJECT REFERENCE NO. 1-2304AA
SHEET NO. 2-6

T	2 1/2" S-95A
C2	2 1/2" S-95B
C4	2 1/2" S-95B
D1	2 1/2" S-95B
D3	2 1/2" S-95B
E1	3" B-25.0B
T	EARTH

TRANSITION FROM T.S. NO. 17 TO EXISTING
 -SRD- STA. 60+17.34 TO 60+67.34
 -SRD- STA. 11+16.00 ± TO 60+17.34
 USE TYPICAL SECTION NO. 17 AS FOLLOWS:
 TYPICAL SECTION NO. 17



USE TYPICAL SECTION NO. 16 AS FOLLOWS:
 -SRB- STA. 48+72.00 ± TO 95+45.00 ±
 TYPICAL SECTION NO. 16



* WHEN THESE DISTANCES INDICATE SLOPES
 DISTANCE BECOMES VARIABLE AND THE
 MAXIMUM OR MINIMUM SLOPE MAINTAINED.


PRELIMINARY PLANS
 DO NOT USE FOR CONSTRUCTION

GRAPHIC SCALE
50 25 0
100
FOOT
1:2304AA
COUNTY: DAVIDSON
SHEET NO.: 2.1
PROJECT REVISION NO.: 1-2304AA
DESIGNER: D.B.E.
CHECKED BY: W.S.H.
DATE: 12/03/01

INTERCHANGE AT
L- (I-85) AND -Y1- (NC 150)

PLANS
50 25 0
100
FOOT
1:2304AA
COUNTY: DAVIDSON
SHEET NO.: 2.1
PROJECT REVISION NO.: 1-2304AA
DESIGNER: D.B.E.
CHECKED BY: W.S.H.
DATE: 12/03/01

INTERCHANGE AT
L- (I-85) AND -Y1- (NC 150)



REVISIONS

SUMMARY OF EARTHWORK
IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
AREA 1 : PHASE I					
-SR1- 31+47.82 TO 42+00.00	4,055		9,464	5,409	
-SR1- 42+00.00 TO 47+12.00	5,590				5,590
-SR2- 36+49.32 TO 72+45.00	31,686		52,444	20,758	
SUBTOTAL	41,331		61,908	26,167	5,590
-L- 820+00.00 TO 838+97.00	5,339		112,021	106,682	
SUBTOTAL	5,339		112,021	106,682	
AREA 1 : PHASE I SUBTOTAL					
	46,670		173,929	132,849	5,590
AREA 1 : PHASE II					
-L- MED. 807+00.00 TO 826+00.00	1,598		2,932	1,334	
SUBTOTAL	1,598		2,932	1,334	
-L- SBL 807+00 TO 838+00.00	6,146		14,489	8,343	
SUBTOTAL	6,146		14,489	8,343	
AREA 1 : PHASE II SUBTOTAL					
	7,744		17,421	9,677	
AREA 2 : PHASE I					
-L- 843+00.00 TO 869+35.00	193,065		168,964		24,101
SUBTOTAL	193,065		168,964		24,101
-L- 839+89.00 TO 843+00.00			77,489	77,489	
SUBTOTAL			77,489	77,489	
AREA 2 : PHASE I SUBTOTAL					
	193,065		246,453	77,489	24,101
AREA 3 : PHASE I					
-SRD- 11+00.00 TO 32+50.00	11,112		35,317	24,205	
-Y1- 36+00.00 TO 60+00.00	12,438		176,600	164,162	
-L- 896+65.00 TO 980+00.00	8,770		324,061	315,291	
-RAMP A- 10+00.00 TO 23+00.00	32,839		8,483		24,356
-LOOP A- 2+50.00 TO 7+50.00	17,521				17,521
-RAMP C- 12+00.00 TO 18+00.00	198		50,249	50,051	
-LOOP C- 4+50.00 TO 7+00.00	138		8,790	8,652	
-Y1- 24+00.00 TO 32+50.00	1,511		33,223	31,712	
-SRB- 95+45.00 TO 96+50.00	113		762	649	
SUBTOTAL	84,640		637,485	594,722	41,877
-SRD- 33+00.00 TO 60+67.00	13,943		6,457		7,486
-Y7- 10+50.00 TO 12+62.00	941		7		934
SUBTOTAL	14,884		6,464		8,420
-Y5- 18+42.00 TO 22+00.00	424		605	181	
-Y1- 60+00.00 TO 64+50.00	1,649		1,114		535
SUBTOTAL	2,073		1,719	181	535
-L- NBL 916+00.00 TO 980+00.00	25,994		96,348	70,354	
-Y5- 10+50.00 TO 18+42.00	602		6		596
-RAMP C- 5+00.00 TO 12+00.00	22,914		4,080		18,834
-LOOP C- 2+50.00 TO 4+50.00	2,398		2,342		56
-Y1- 35+06.18 TO 36+00.00	1		17,878	17,877	
-SRB- 84+50.00 TO 95+45.00	7,314		3,928		3,386
SUBTOTAL	59,223		124,582	88,231	22,872
AREA 3 : PHASE I SUBTOTAL					
	160,820		770,250	683,134	73,704
AREA 3 : PHASE II					
-L- MED 923+00.00 TO 980+00.00	8,565		784		7,781
SUBTOTAL	8,565		784		7,781
-L- SBL 908+00.00 TO 939+00.00	37,196		570		36,626
-L- SBL 939+00.00 TO 980+00.00	7,568				7,568
-SRB- 15+46.00 TO 31+09.00	215		2,658	2,443	
-SRB- 39+80.00 TO 95+00.00	17,254		19,124	1,870	
-Y2- 13+27.00 TO 17+50.00	394		541	147	
SUBTOTAL	62,627		22,893	4,460	44,194
AREA 3 : PHASE II SUBTOTAL					
	71,192		23,677	4,460	51,975
AREA 3 : PHASE III					
-SRB- DITCH 15+46.00 TO 31+09.00	308		64		244
SUBTOTAL	308		64		244
-Y1- 12+30.00 TO 24+00.00	5,886		824		5,062
SUBTOTAL	5,886		824		5,062
AREA 3 : PHASE III SUBTOTAL					
	65,417		125,470	88,231	28,178

IN CUBIC YARDS

INCOMPLETE PLANS	DO NOT USE FOR R/W ACQUISITION
PRELIMINARY PLANS	DO NOT USE FOR CONSTRUCTION

PROJECT REFERENCE NO.	1-2304AA	RW SHEET NO.
SHEET NO.	3-B	

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

RIGHT OF WAY AREA DATA SHEET



BLYTHE
BARBARA H. MURKIN ENGINEERING, INC.
559 Jones Franklin Road
Suite 104 A
Raleigh, N.C. 27606
(919) 851-1512
(919) 851-1918 (FAX)

PARCEL NO.	PROPERTY OWNERS NAME	TOTAL ACREAGE	AREA TAKEN	AREA REMAINING	RIGHT	LEFT	CONSTR. EASEMENT	PERMANENT DRAINAGE EASEMENT	TEMPORARY DRAINAGE EASEMENT
1	JOHN E. WILLIAMS	8.395	AC	2.373	AC	6.022	AC	AC	AC
2	BILLY G. MITCHELL	1.237	AC	0.506	AC	0.731	AC	AC	AC
3	MARY H. LAMBE	218.610	AC	10.573	AC	118.037	AC	90.000	AC
4	COLOR-TEX FINISHING CO	159.530	AC	10.757	AC	29.943	AC	118.83	AC
5	ALUMINUM COMPANY OF AM	30.400	AC	8.279	AC	22.121	AC	AC	AC
6	YADKIN INC.	AC	5.409	AC	AC	AC	AC	AC	AC
7	ALUMINUM COMPANY OF AM	69.640	AC	6.490	AC	63.150	AC	AC	AC
8	ROBERT L. GRUBB	76.153	AC	10.529	AC	65.624	AC	AC	AC
9	PLEMMONS ENTERPRISE IN	3.872	AC	AC	AC	3.872	AC	0.011	AC
10	MICHAEL D. TAYLOR	18632.540	SF	5.120	SF	18627.420	SF	AC	AC
11	NCDOT	3.568	AC	0.221	AC	3.347	AC	0.119	AC
12	NCDOT	12.010	AC	4.478	AC	4.478	AC	12.01	AC
13	DAVID W. SHELTON	1.039	AC	0.592	AC	0.447	AC	0.042	AC
14	STEVEN E. GOODMAN	1.771	AC	0.100	AC	1.671	AC	AC	AC
15	KATHY C. WILLARD	24160.664	SF	18513.000	SF	5647.664	SF	1785.960	AC
16	KENNETH BLAKE	2.231	AC	0.156	AC	2.075	AC	0.027	AC
17	LUKE H. SHEPHERD	1.027	AC	0.080	AC	0.947	AC	0.021	AC
18	ROBERT C. WILSON, SR.	14949.734	SF	186.660	SF	14763.074	SF	442.51	AC
19	ROBERT C. WILSON, SR.	21854.743	SF	20037.600	SF	1817.143	SF	908.490	AC
20	GEORGE W. KOONTZ	25759.823	SF	4410.010	SF	21349.813	SF	1180.220	AC
21	JOHN A. CHRISLEY	1.689	AC	0.407	AC	1.282	AC	0.011	AC
22	GARY G. BAYNARD	1.245	AC	0.070	AC	1.175	AC	0.025	AC
23	ROBERT L. GRUBB	416.140	AC	43.518	AC	314.102	AC	58.520	AC
24	FALCON DEVELOPMENT GRO	72.729	AC	3.510	AC	69.219	AC	AC	AC
25	ENERGY EFFICIENT HOUSI	7.152	AC	0.700	AC	6.452	AC	AC	AC
26	MOTEL SLEEPERS INC.	5.011	AC	0.752	AC	4.259	AC	AC	AC
27	ROBERT L. GRUBB	59.657	AC	0.267	AC	44.170	AC	15.220	AC
28	NC HISTORICAL COMMISSI	37074.203	SF	11238.480	SF	25835.723	SF	1001.880	AC
29	JOE RAY POOLE	3.206	AC	0.084	AC	3.122	AC	0.048	AC
30	ABNER L. HANES	4.084	AC	0.087	AC	3.997	AC	0.045	AC

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PARCEL INDEX SHEET

BARBARA H. MULKEY ENGINEERING, INC.



559 Jones Franklin Road
Suite 164 A
Raleigh, N.C. 27606
(919) 851-1912
(919) 851-1918 (FAX)




PROJECT REFERENCE NO.

1-2304AA



SHEET NO.

3-D

PARCEL NO.	SHEET NO.	PROPERTY OWNERS NAME	PARCEL NO.	SHEET NO.	PROPERTY OWNERS NAME
1	6	JOHN E. WILLIAMS	31	21	SHELIA GOODMAN LOPP
2	6	BILLY G. & ELIZABETH L. MITCHELL	32	21	DONALD L. & JO S. HALL
3	6, 7, 8	MARY HEDRICK LAMBE	33	21	GARLAND L. YOUNG
4	8, 9, 17	COLOR-TEX FINISHING CORP.	34	21	EVELYN L. & SAMUEL E. DAYTON
5	9	ALUMINUM COMPANY OF AMERICA	35	21	RUBY Y. HANES
6	9, 10	YADKIN INC.	36	21	BEN K., NELSON E., & WILLIS HOPE WHITE
7	10, 11	ALUMINUM COMPANY OF AMERICA	37	21, 24	ROBERT L. GRUBB
8	11, 12, 13, 24	ROBERT L. GRUBB	38	23	DORIS LA NETTE DAVIS
9	12	PLEMMONS ENTERPRISE INC.	39	23	WATSON E. & DARLIN LEE ALLRED
10	12	MICHAEL DALE TAYLOR	40	23, 24	WILBUR & JUDY LOMAX, JR.
11	12, 13	NCDOT	41	24	GLENDA MARLENE KEPLEY
12	12, 13, 24	NCDOT	42	24	DONALD LINFORD LANNING
13	13, 20	DAVID MARTIN SHELTON			
14	13, 20	STEVEN EARLE & JUDY LOFLIN GOODMAN			
15	13, 20	KATHY C. WILLARD			
16	13, 20	KENNETH & BETTY S. BLAKE			
17	14	LUKE H., LEILA ANN, TORN HUGH, & ELLEN REBECCA SHEPHERD			
18	14	ROBERT C. & DORIS J. WILSON, SR.			
19	14	ROBERT C. & DORIS J. WILSON, SR.			
20	14	GEORGE M. & RUTH B. KOONTZ			
21	14	JOHN ALLEN WAYNE CHRISLEY			
22	14	GARY G. & CAROLYN T. BAYNARD			
23	13, 14, 15, 21, 22, 23	ROBERT L. GRUBB			
24	14, 15	FALCON DEVELOPMENT GROUP, INC.			
25	15, 16	ENERGY EFFICIENT HOUSING, INC.			
26	16	MOTEL SLEEPERS INC.			
27	16	ROBERT L. GRUBB			
28	20	NC HISTORICAL COMMISSION			
29	20	JOE RAY POOLE			
30	20	ABNER L. & MARY B. HANES			


$$\begin{array}{r} -SR2- \\ \hline PISta\ 44+58.00 \\ \Delta = 4\ 14\ 16.1\ (RT) \\ D = 0\ 15\ 05.9 \\ L = 1,684.01' \\ T = 842.39' \\ R = 22,768.00' \\ SE = NC \end{array}$$


PROJECT REFERENCE NO.		1-23044A	
SHEET NO.		4	
ROADWAY DESIGN		RW	
ENGINEER		SHEET NO.	
HYDRAULICS			
ENGINEER			
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION			



REVISIONS

FOR -L- PROFILE,SEE SHEET 25
FOR -SR1- PROFILE,SEE SHEET 33
FOR -SR2- PROFILE,SEE SHEET 34

REVISIONS

MATCH TO SHEET 5
-L- STA. 823+00

-SR2- PT Sta. 52+99.62

-SR2- 55+00

-SR2- 60+00

-SR2- 65+00

-L-
PI Sta 821+42.62
 $\Delta = 4' 38" 21.5" (RT)$
 $D = 0' 7" 00.0"$
 $L = 1637.40'$
 $T = 819.5'$
 $R = 20222.04'$
SE = NC




-SR2-
PI Sta 67+01.2
 $\Delta = 4' 14" 16.1" (RT)$
 $D = 0' 15" 05.9"$
 $L = 1684.01'$
 $T = 573.65'$
 $R = 22768.00'$
SE = NC

WOOD REALTY
COMPANY
DB 705 PG 908

830+00

835+00

6+05 TO 62+65 -SR2- RT
EST. DDE = 160 CY
828+93 TO 830+65 -L- RT
EST. DDE = 40 CY



BARBARA H. MULKEY ENGINEERING, INC.
P.O. Box 33027
Raleigh, NC 27634-3027
(919) 851-1932
(919) 851-1938 (FAX)

PROJECT REFERENCE NO.	1-2304AA
SHEET NO.	6
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DO NOT USE FOR CONSTRUCTION	PRELIMINARY PLANS

FOR -L- PROFILE, SEE SHEET 26
FOR -SR2- PROFILE, SEE SHEET 34 & 35
FOR -R/LT- PROFILE, SEE SHEET 48
FOR -R/R- PROFILE, SEE SHEET 48

MATCH TO SHEET 7
-L- STA. 837+00

REVISIONS

MATCH TO SHEET 6
-L- STA 837+00


-SR2- 70+00

END CONSTRUCTION
-SR2- POC STA. 72+45.00

-SR2- PT STA. 72+74.53

-L-
PI STA 889+28.58
 $\Delta = 28' 21" 23.9'$ (RT)
 $D = 0' 18" 00.0'$
 $L = 9' 452.21'$
 $T = 4825.00'$
 $R = 19098.59'$
SE = NC

-SR2-
PI STA 67+01.12
 $\Delta = 2' 53' 11.7"$ (RT)
 $D = 0' 15' 05.9'$
 $L = 1' 47.07'$
 $T = 573.66'$
 $R = 22768.00'$
SE = NC




COLOR-TEX
FINISHING CO.
DB 813 PG 83

BARBARA H. WILKEY ENGINEERING, INC.
P.O. BOX 2307
ROSELAND, N.C. 27068-2307
(919) 881-9800 (FAX)

PROJECT REFERENCE NO.		RW SHEET NO.	
1-2304AA		7	
ROADWAY DESIGN		HYDRAULICS	
ENGINEER		ENGINEER	
PRELIMINARY PLANS			
DO NOT USE FOR CONSTRUCTION			

MATCH TO SHEET 8
-L- STA. 851+00




REVISIONS


MATCH TO SHEET 7
-L- STA. 851+00

MATCH TO SHEET 9
-L- STA. 865+00

PROJECT REFERENCE NO.		1-2304AA
SHEET NO.		8
ROADWAY DESIGN		HYDRAULICS
ENGINEER		ENGINEER
DO NOT USE FOR CONSTRUCTION		PRELIMINARY PLANS



-L-
PI STA 889+28.58
 $\Delta = 28.21' 23.9" (RT)$
 $D = 0' 18" 00.0"$
 $L = 9.452.21'$
 $T = 4.825.00'$
 $R = 19,098.59'$
SE = NC



FOR -L- PROFILE, SEE SHEET 27

REVISIONS

MATCH TO SHEET 9
-L- STA 879+00

880+00

Property Line = 655 ft. Elevation Contour Yodkin, Inc. Datum

YADKIN INCORPORATED
6

YADKIN RIVER

885+00

-L-
PI Sta 889+28.58
 $\Delta = 28' 21" 23.9" (RT)$
 $D = 0' 18" 00.0"$
 $L = 9452.21'$
 $T = 4825.00'$
 $R = 19098.59'$
 $SE = NC$

RBL-143 PINC 115+96.16
-L- POC 885+98.02 (0.63 LT.)

Property Line = 655 ft. Elevation Contour Yodkin, Inc. Datum

ALUMINUM COMPANY
OF AMERICA
DB 541PG 867
7

890+00

BL-12 PINC 122+94.43
5+00.00 SBL POT

RBL-144 PINC 122+10.08
-L- POC 892+11.98 (2.01 RT.)

-RBL- STA 119+45.97
ELEV. 623.20'
BM #12

ALUMINUM COMPANY
OF AMERICA
DB 541PG 867
7

Property Line = 655 ft. Elevation Contour Yodkin, Inc. Datum

YADKIN INCORPORATED
6

5

4

MATCH TO SHEET 11
-L- STA 893+00


YADKIN INCORPORATED

MAD 83

STRUCTURE TO BE REMOVED

blume
BARBARA H. MURPHY ENGINEERING, INC.
P.O. BOX 3302
ROCKFORD, N.C. 27668-3021
(919) 854-9800 (FAX)

PROJECT REFERENCE NO.		1-2304AA
SHEET NO.		10
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER
DO NOT USE FOR CONSTRUCTION		PRELIMINARY PLANS



REVISIONS

DETAIL J

LATERAL BASE DITCH

(NOT TO SCALE)

Natural Ground

Fabric Filter

Min. D = 2.0 Ft.

B = 5.0 Ft.

F/F+1

Slope

Fill

897+35 -L- RT

EST. DDE = 50 CY

EST. 140 TONS CLASS II

EST. 190 SY F.F.

[illegible]

TOE PROTECTION
(Not to Scale)

20'0" FLAT

2'0" SLOPE

FILL

FILTER

FABRIC

1.0' P

54+00 TO 59+00 - SRB- LT
EST, 175 TONS CLASS 'B'
EST, 525 SY F.F.

JAMES KENNETH BERRY
ET UX MARLENE WATSON BERRY
DB 947 PG 1379
DB 947 PG 1378


PATRICIA J. BARBER
DB 534 PG 528

BARBARA H. MULKEY ENGINEERING, INC.
P. O. Box 33127
Raleigh, N.C. 27635-3127
(919) 851-1916 (FAX)
(919) 851-1912

PRELIMINARY PLANS	DO NOT USE FOR CONSTRUCTION
-------------------	-----------------------------


PROJECT REFERENCE NO.	1-2304AA	R/W SHEET NO.	
SHEET N	11		
HADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	



FOR L-PROFILE, SEE SHEET 29
FOR SRB-PROFILE, SEE SHEET 36 & 37



REVISIONS

PROJECT REFERENCE NO.	1-2304AA
SHEET NO.	13




$$\begin{array}{r} 32+88.72 \\ \hline 120.72 \end{array}$$

blume


P.O. Box 33027
Raleigh, N.C. 27635-0227
(919) 851-1912
(919) 851-1910 (FAX)

BARBARA H. MULKKEY ENGINEERING, INC.

REVISIONS

REVISIONS



MATCH TO SHEET 15
-L- STA 975+00



P1 Sta 11+11.33
 $\Delta = 39' 02''$ 55.0' (RT) $\Delta = 4' 19' 10.2''$ (RT)
D = 28' 38' 52.4'
L = 136.31'
T = 70.92'
R = 200.00'
SE = 03
RO = 45'

-SRD-
P1 Sta 58+97.59
 $\Delta = 16' 15' 08.5''$ (RT)
D = 4' 45' 17.4'
L = 34.81'
T = 172.06'
R = 1,205.00'
SE = 08
RO = 208'

RAYMOND GOODMAN
AND WIFE,
DB 305 Pg 591



REVISIONS

Pis	Std	14+86.02
θ s =	47° 25'	
Δ	= 25° 05' (RT)	
D	= 2° 02' 46"	
L	= 12° 41'	
ST	= 58° 34'	
R	= 2° 00'	
Pis	Std	28+44.85
θ s =	1° 47' 25"	
L	= 116.67'	
ST	= 58.34'	

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION


ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
----------------------------	------------------------

PROJECT REFERENCE NO.	1-2304AA
SHEET NO.	17


PROJECT REFERENCE NO.	1-2304AA
SHEET NO.	17

Pfs	Sfd	14+86.02
-Sfb-		
P1	Sd	21+75.82
		Δ = 25° 25' 05.3"
	D	2° 02' 46.6"
L _s	=	175.00'
L _t	=	166.67'
ST	=	58.34'
R	=	2.800000'
Pfs	Sfd	28+44.85
		Θ s = 1° 47' 25.8"
	L _s	= 175.00'
	L _t	= 166.67'
	ST	= 58.34'
	R	= 2.800000'


PROJECT REFERENCE NO.	1-2304AA
SHEET NO.	18
RW SHEET NO.	
HYDRAULICS ENGINEER	ROADWAY DESIGN ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	



MAD + 83




REVISIONS




REVISIONS

REVISIONS




-Y2-
PI Sta 14+28.35
 $\Delta = 12.48' 32.22" (RT)$
 $D = 4' 00" 00.0'$
 $L = 320.22'$
 $T = 160.78'$
 $R = 1,432.39'$
 $SE = 08'$
 $RO = 208'$


-Y6-
PI Sta 14+28.89
 $\Delta = 30' 39" 26.4" (LT)$
 $D = 4' 00" 00.0'$
 $L = 766.43'$
 $T = 392.63'$
 $R = 1,432.39'$



PROJECT REFERENCE NO.		SHEET NO.	
1-2304AA		20	
ROADWAY DESIGN		HYDRAULICS	
ENGINEER		ENGINEER	
DO NOT USE FOR CONSTRUCTION			
PRELIMINARY PLANS			



FOR -Y2- PROFILE, SEE SHEET 39
FOR -Y6- PROFILE, SEE SHEET 39




REVISIONS


-Y5-
PI Sta 21+15.35
D = 12' 00" 00.0
L = 147.31'
R = 471.46'
SE = 06°
RO = 126'

ROBERT L. GRUBB
TRUSTEE OF
JUNE C. LITTLE
DB 698 PG 336

NAD 83



PROJECT REFERENCE NO.		RW SHEET NO.	
1-2304AA			
ROADWAY DESIGN		HYDRAULICS	
ENGINEER		ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION			



MATCH TO SHEET 23
-Y5- STA. 20+50

-Y5- 20+00
-Y5- PC Sta. 19+68.04

-Y5- 15+00

MATCH TO SHEET 13