

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT SECRETARY

February 27, 2003

US Army Corps of Engineers Regulatory Branch 6508 Falls of the Neuse Road Raleigh, NC 27615

ATTENTION:

Mr. John Thomas

NCDOT Coordinator

Subject:

Nationwide 23 and 33 Permit Modification Application for the Replacement of Bridge No. 28 over Big Horse Creek on SR 1358,

Ashe County. Federal Aid Project No. No. BRZ-1358(2), State

Project No. 8.2711702, TIP Project No. B-4014.

Dear Mr. Thomas:

On January 16, 2004 the NCDOT applied for a NW 23 and 33 for the above referenced project. The North Carolina Department of Transportation (NCDOT) proposes to modify the construction plans for the subject project. The purpose of this letter is to request a modification to the original permit. The <u>revised</u> sheets of the original permit drawings are attached.

Temporary jurisdictional impacts to Big Horse Creek have increased from 63 feet of channel impacts or 0.01 acres of fill to 74 feet or 0.03 acres of fill. The increased impact results from the use of three 42" corrugated steel pipes and a rock causeway. Class II Rip Rap will be used for the construction of the rock causeway. The temporary rock causeway will be required due to the steep topography and limited area for staging equipment on the north side of Big Horse Creek.

<u>Restoration Plan</u>: No permanent fill will result from the subject activity. The materials used as temporary fill in the construction of the causeways will be removed. The temporary fill areas will be graded back to the original contours. Elevations and contours in the vicinity of the proposed causeways are available from the field survey notes.

RALEIGH NC 27699-1548

WEBSITE: WWW.NCDOT.ORG

Schedule for Restoration of Temporary Fill Areas: It is assumed that the Contractor will begin construction of the proposed causeway shortly after the date of availability for the project. The Let date is April 20, 2004 with a date of availability of May 30, 2004.

Removal and Disposal: The causeways will be removed within 90 days after it is no longer needed. The temporary rock causeways will be removed by the Contractor using excavating equipment. All materials placed in the stream by the Contractor will be removed. The Class II riprap that is removed will be used as permanent rip rap around end bent 1. All other materials removed by the Contractor will be disposed of at an off site upland location.

If you have any questions or need additional information, please contact Brett Feulner at (919) 715-1488.

Sincerely,

Gregory J. Thorpe, Ph.D.
Environmental Management Director, PDEA

w/ attachment

Mr. John Hennessy, NC Division of Water Quality

Ms. Marella Buncick, USFWS

Ms. Marla Chambers, NCWRC

Mr. Greg Perfetti, P.E., Structure Design

Mr. Jay Bennett, P.E., Roadway Design

Mr. Omar Sultan, Programming and TIP

Mr. Art McMillan, PE, Highway Design

Mr. David Chang, P.E., Hydraulics


Mr. Mark Staley, Roadside Environmental


Mr. Carl McCann, P.E., Division 11

Mr. Heath Slaughter, Division Environmental Officer


Ms. Stacey Baldwin, P.E., Project Planning Engineer

Mr. David Franklin, USACE, Wilmigton





Estimate 682 Tons Class IIRip Rap AREA OF CLASS IIRIP RAP= 0.086 acres VOLUME OF CLASS IIRIP RAP= 481 yds




CLUSEWAY DETAIL SITE #1

NCDOT

BRIDGE #28 ON SR 1358 (LITTLE WINDFALL ROAD) OVER BIG HORSE CREEK DIVISION OF HIGHWAYS
ASHE COUNTY PROJECT: 8.2711702 (B-4014)

4/12/04

SHEET 2



Station Structure Fill in Toury Fill Excavation Carameter Fill in Surface Water Machanical Carameter Fill in Toury Fill Excavation Carameter Fill in Surface Fill in Fill in Surface Fill in Surface Fill in Fill in				>	WETLAND PERMIT IMPACT SUMMARY	RMIT IMPAC	T SUMMARY					٠
Station Structure Fill In Tonip Fill Excavation Clearing Fill In Sw					V . L . LAINE	O DATE			SURFA	CE WATER IN	IPACTS	
From To, Size / Type Wetlands In Wetlands Gac) Gac	Site		Structure	Ē	Temp. Fill			Fill In	Fill In StA	Z mo F	Existing	Natural
1-C Sta 16+40 S5 LONG BRIDGE (T) (4c) (4c) (4c) (4c) (4c) (7d) (4c) (4c) (4c) (4c) (4c) (4c) (4c) (4c	Š		Size / Type	Wetlands (ac)	In Wetlands			(Natural)	(Pond)	In SW	Impacted	Stream
TO 16+95 (36 W)DE) U033 U033	-	-L- Sta 16+40	55' LONG BRIDGE			(25)	(ac)	(90)	(ac)	(ac)	(#)	(
(Temporary Work Bridge during construction) during construction) during construction during construction during construction during construction during construction during the property during the prop		TO 16+95	(36' WIDE)							0.03	74	
during construction Work pad (aggregate Construction Const			(Temporary Work Bridge									
Work pad (aggregate Control causes stream Contro			during construction)									
2 barrier) causes stream			Work pad (aggregate									
impacts		The state of the s	& barrier) causes stream		,							
			impacts	/								
							-					
	-											
					and the state of t							
		The state of the s	,									
	1		The state of the s									
	1											
	TAL	S:		0	0	0	0	C	c	600		,

NC DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS

ASHE COUNTY PROJECT 8.2711702 B-4014

SHEET 9 OF W

2/13/04

torcolo kanaland maga