



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

July 22, 2004

U.S. Army Corps of Engineers
Regulatory Field Office
6508 Falls of the Neuse Road
Suite 120
Raleigh, NC 27615

ATTN: Mr. Eric Alsmeyer
NCDOT Coordinator

Dear Sir:

Subject: **Application for Individual Section 404 and 401 permits**
For NC 109 from north of I-85 Business to north of SR 1798
(Old Greensboro Road), Davidson County, North Carolina
NCDOT Division 9
Federal Aid Project No STP-109(1)
State Project Number 8.1600901
TIP Project R-2568B
\$475.00 Debit work order 8.1600901, WBS Element 34634.1.2

The North Carolina Department of Transportation (NCDOT) proposes to relocate NC 109 from north of I-85 Business in Thomasville to north of SR 1798 (Old Greensboro Road), a distance of 3.51 miles. This section of existing NC 109 is located in the northeastern part of Davidson County. This Urban Principal Arterial is proposed to be a four-lane divided facility with partial access control, and will be constructed partially on new location. The typical section for the proposed facility includes a 46-foot grassed median. This application consists of the cover letter, 8 ½ x 11-inch permit drawings (drawings, impact summary sheets, property owners, and mailing labels), ENG form 4345, Stormwater Management Plan, 4C minutes for permit drawing interagency review, 4C agency comments and post-meeting activities, natural stream design document, SHPO historical architecture concurrence letter, SHPO archaeology concurrence letter, USFWS concurrence request letter, EEP mitigation request letters, USACE Routine Wetland Determination Data Sheets, NCDWQ Wetland Rating Worksheets, USACE Stream Quality Assessment Worksheets, and NCDWQ Stream Classification Forms, and half-size project plan sheets.

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
PROJECT DEVELOPMENT AND ENVIRONMENTAL ANALYSIS
1548 MAIL SERVICE CENTER
RALEIGH NC 27699-1548

TELEPHONE: 919-733-3141
FAX: 919-733-9794

WEBSITE: WWW.NCDOT.ORG

LOCATION:
TRANSPORTATION BUILDING
1 SOUTH WILMINGTON STREET
RALEIGH NC

Purpose and Need

The primary purpose of the proposed project is to upgrade the existing NC 109 corridor from I-85 Business in Thomasville to SR 1798 (Old Greensboro Road). This section of NC 109 has some of the poorest geometric conditions of any section of NC 109 in Davidson County. The proposed project is consistent with the local area's transportation plans and provides needed improvements to an existing transportation corridor within Davidson County. The existing facility is a two lane roadway which is below the current safe design standards and is inadequate to handle the projected traffic volumes within the growing areas of Davidson County.

Several alternatives to improving the NC 109 corridor were considered and evaluated as part of the environmental study. These alternatives include the No Build Alternative, Transportation Management Alternative, and the Mass Transit Alternative. Two Build Alternatives were also considered; Alternative 1, upgrade existing NC 109, and Alternative 2, a combination of upgrading existing NC 109 and constructing a multi-lane highway on new location. Alternative 2 was chosen, since it best fit the purpose and need of the project. A discussion of each alternative considered by NCDOT is detailed in the November 1996 Environmental Assessment (EA).

Project Schedule

The proposed R-2568B project improvements are scheduled in conjunction with four other sections (R-2568A, R-2568C, R-2568D, and R-2568E) of entire R-2568 project. The entire R-2568 project will improve existing NC 109 from Thomasville to the I-40 / US 311 interchange near High Point. Section A of the project includes the NC 109/I-85 Business interchange and has already been constructed. The construction letting date for the R-2568B portion of this project is scheduled for November 2004. Table 1 gives the project limits and projected let dates for each section of the R-2568 project.

Table 1 – R-2568 Project Schedule		
Section	Project Limits	Let Date
R-2568A	South of I-85 Business to South of SR 1800	Completed
R-2568B	South of SR 1800 to North of Ledford J.H.S.	November 2004
R-2568C	North of Ledford J.H.S. to South of SR 1755	Post 2010
R-2568D	South of SR 1755 to North of SR 1723	Post 2010
R-2568E	North of SR 1755 to North of Fiddlers Creek	Post 2010
R-2568F	North of Fiddlers Creek to I-40/US 311	Post 2010

Summary of Impacts

- 0.75 acres of impact to non-riverine wetland, including 0.62 acres of permanent fill, 0.03 acres of excavation, and 0.1 acres of mechanized clearing.
- 0.36 acres of permanent fill in streams
- 0.03 acres of temporary fill in streams
- Permanent stream impacts total 2,987 linear feet, of which 1,405 linear feet require mitigation.

- 182 linear feet of temporary channel impacts associated with pipe/culvert installation
- No impacts to ponds

Summary of Mitigation

The project has been designed to avoid and minimize impacts to jurisdictional areas throughout the National Environmental Policy Act (NEPA) and design processes. Detailed descriptions of these actions are presented elsewhere in this application. Compensatory mitigation for the remaining impacts includes the following:

- 315 linear feet of on-site stream relocation using natural channel design techniques,
- 1,090 linear feet of stream will be mitigated through the use of the North Carolina Department of Environment and Natural Resources Ecosystem Enhancement Program (EEP), and
- 0.75 acres of impacts to non-riverine wetlands will be mitigated through the use of EEP.

NEPA DOCUMENT STATUS

An EA was completed by the NCDOT in compliance with the NEPA. The document addressed both the R-2568A and R-2568B portions of the project, from I-85 Business in Thomasville to just north of SR 1798 (Old Greensboro Road), in Davidson County. The EA explains the purpose and need for the project, provides a description of the alternatives considered and characterizes the social, economic, and environmental effects. After the approval of the EA (November 1996) and Finding of no Significant Impact (FONSI) (August 1997), copies were provided to regulatory review agencies involved in the approval process. Additional copies will be provided upon request.

INDEPENDENT UTILITY

R-2568B is in compliance with 23 CFR Section 771.111(f) which lists the Federal Highway Administration (FHWA) characteristics of independent utility of a project:

- (1) The project connects logical termini and is of sufficient length to address environmental matters on a broad scope;
- (2) The project is usable and a reasonable expenditure, even if no additional transportation improvements are made in the area; and
- (3) The project does not restrict consideration of alternatives for other reasonable foreseeable transportation improvements.

RESOURCE STATUS

History and Identification of Jurisdictional Features

During the preliminary field investigations (1994 and 1995) in preparation for the Natural Resources Technical Report (submitted June 1996) and subsequent EA, stream crossings were identified and wetland determinations were performed by NCDOT biologists. Field work was conducted for the R-2568A and R-2568B portions of the project, and both Alternative 1 and Alternative 2 of the R-2568B section were assessed. Alternative 2 became the selected alternative subsequent to the approval of the EA in November 1996. In 2001, NCDOT biologists returned to the field to delineate jurisdictional features along Alternative 2. At this time, several previously unrecorded jurisdictional features were located. The features identified in 2001 were incorporated into project planning, and minimization and avoidance of these features became part of the design process for R-2568B. Table 2 shows the relationship between the jurisdictional features located during the initial field investigation in 1995 and 1995, and those sites impacted by the current project design, listed from south to north. Detailed descriptions of each impact site are located in the “Wetlands” and “Surface Waters” sections of this letter.

Table 2 – Relationship of R-2568B Jurisdictional Features to EA and Permit Drawings				
Permit Drawing Site and Feature*	EA Stream Site Name	EA Wetland Site Name	Station Number	Comment
---	UT1	---	---	Associated with R-2568A
---	Hunts Fork Creek	---	---	Associated with R-2568A
---	UT2	Wetland 1, Wetland 2	Near 25+60 –L-	Avoided during design
1 (S)	---	---	29+50 to 30+20 –L-	Not presented in EA
2 (W,S)	---	---	33+55 to 33+80 –L-	Not presented in EA
2a (W)	---	---	37+20 –L-	Not presented in EA, avoided during design
3 (W)	---	---	40+40 to 40+60 –L-	Not presented in EA
3a (S)	---	---	43+70 to 44+60 –L-	Not presented in EA
---	UT3	---	---	Associated with Alternative1 (not chosen)
4 (S)	UT5	---	46+60 to 47+80 –L-	
5 (W)	---	---	50+60 to 51+00 –L-	Not presented in EA
6 (S)**	---	---	10+60 to 11+00 –Y10-	Not presented in EA
6 (S)**	---	---	55+60 to 56+00 –L-	Not presented in EA
7 (S)	---	---	56+70 –L-	Not presented in EA
8 (S)	Rich Fork Creek	Wetland 3	61+31.50 –L-	Wetland avoided during design
9 (W,S)	UT4	---	64+00 to 66+00 –L-	
10 (S)	---	---	75+50 to 76+50 –L-	Not presented in EA

* S = Stream, W = Wetland

** At Site 6, one stream will be impacted by the project in two separate locations.

Three wetlands and seven streams were located within the study corridors for R-2568A and R-2568B during the preliminary field investigations. UT1 and Hunt's Fork Creek lie within the R-2568A study area. UT3 is located within the study area associated with R-568B Alternative 1. Therefore, four streams and three wetlands were located within the R-2568B, Alternative 2 corridor. During the 2001 field investigations, five additional streams and five additional wetlands were located. After completion of the project design, a total of nine streams and four wetlands will be impacted by the proposed project.

Delineations

Wetland delineations were conducted by NCDOT biologists on February 1, 2001 using the criteria specified in the 1987 Corps of Engineers Wetland Delineation Manual. Guidance on the jurisdictional status of questionable areas was provided by USACE representative Eric Alsmeyer of the USACE Raleigh Regulatory Field Office during an August 28, 2001 on-site visit. During this field meeting Mr. Alsmeyer verified the jurisdictional wetland delineations.

As part of the on-site field verification meeting on August 28, 2001, stream channel segments were also reviewed by the USACE to confirm intermittent, perennial, or ephemeral status and to determine if mitigation would be required and at what ratio it would be required. During a field meeting on July 9, 2004, Brian Wrenn of NCDWQ, agreed to defer all stream determination and mitigation calls to the USACE.

As previously mentioned, jurisdictional impacts include 0.75 acres of permanent impacts to non-riverine wetlands, 2,987 linear feet of impacts to streams, no temporary wetland impacts, and no permanent impacts to ponds. Detailed descriptions of impacted areas including the type of impact incurred, can be found in the following sections of this letter. Table 3 shows a summary of permanent impacts associated with the proposed R-2568B project.

Of the ten channel segments reviewed, only three unnamed tributaries to Rich Fork Creek require mitigation. The seven stream crossings that do not require mitigation either have a degraded quality or will incur only temporary impacts. Mitigation will be provided for all impacts to streams deemed mitigable. A discussion of permanent impacts to jurisdictional wetlands and streams follows Table 3.

Table 3 – Summary of Permanent Impacts for R-2568B					
Permit Drawing Site	Station Number	Non-Riverine Wetland Impacts (acres)*	Stream Impacts (linear feet)	Stream Impacts Requiring Mitigation & Mitigation Ratios (linear feet)	Natural Channel Design (linear feet)
1	29+50 to 30+20 –L-	0	427	0	0
2	33+55 to 33+80 –L-	0.02	223	0	0
2a**	37+20 –L-	0	0	0	0
3	40+40 to 40+60 –L-	0.05	0	0	0
3a	43+70 to 44+60 –L-	0	437	437 / 1:1	0
4	46+60 to 47+80 –L-	0	617	617 / 2:1	315
5	50+60 to 51+00 –L-	0.15	0	0	0
6	10+60 to 11+00 –Y10-	0	121	0	0
6	55+60 to 56+00 –L-	0	269	0	0
7	56+70 –L-	0	273	0	0
8	61+31.50 –L-	0	98	0	0
9	64+00 to 66+00 –L-	0.13	141	0	0
10	75+50 to 76+50 –L-	0	351	351 / 1:1	0
Total		0.75	2,987	1,405	315

* Includes fill, excavation, and mechanized clearing.

** No impacts will be incurred at Site 2A, however this site has been included with the permit drawings to demonstrate avoidance.

Wetlands

Table 4 shows a list of proposed permanent impacts to verified jurisdictional wetland resources, which include impacts resulting from fill and mechanized clearing. The impacted wetland areas are described in Table 4 by the Cowardin *et al.* classification, NCDWQ Fourth Version of Guidance for Rating the Wetlands in North Carolina, riverine or non-riverine status, and the Schafale and Weakley description. The calculations and drawings by NCDOT Hydraulics Unit are presented in the attached permit drawings. A site by site description of each wetland follows.

Table 4 – Permanent Wetland Impacts and Descriptions

Site	Station	Type of Impact	Wetland Impacts (acres)*	Cowardin <i>et al.</i> description	NCDWQ Wetland Rating	Riverine (R) or Non-riverine (NR)	Schafale and Weakley description
2	33+55 to 33+80 –L-	Fill, 48" pipe	0.02	PFO1C	56	NR	M
2a**	37+20 –L-	None	0	---	---	NR	---
3	40+40 to 40+60 –L-	Fill, Mechanized clearing	0.05	PFO1C/W	44	NR	B
5	50+60 to 51+00 –L-	Fill, 30" pipe, Mechanized clearing	0.15	PFO1B	60	NR	M
9	64+00 to 66+00 –L-	Fill, 42" pipe, Mechanized clearing	0.53	PFO1C	65	NR	B
Total impacts			0.75				

* Indicates total wetland impacts, including fill, excavation and mechanized clearing

** No impacts will be incurred at Site 2A, however this site has been included with the permit drawings to demonstrate avoidance.

USACE Routine Wetland Determination forms and NCDWQ Wetland Rating Worksheets have been completed for all wetlands and copies of these data sheets are included with this application for reference. The Cowardin classification for the wetlands is noted as PFO1, with additional saturation levels found in the project area.

PFO1-Palustrine, forested, broad-leaved deciduous

-B Saturated

-C Seasonally flooded

-W Intermittently flooded/Temporary

Terrestrial community descriptions for these wetland areas (see Table 1) somewhat differ from the Schafale and Weakley descriptions due to their altered conditions. The wetlands within the project study area can be described as the following:

Mesic Oak-Hickory Forest (M) – wetter areas where a mix of oaks and hickories are the dominant tree species

Bottomland Hardwood Forest (B) – broad floodplain forest community

Site 2 (Sheet 7-8 of 40): This non-riverine wetland is located along an intermittent unnamed tributary to Hunt's Fork Creek. The canopy of this wetland is dominated by red maple (*Acer rubrum*), sweetgum (*Liquidambar styraciflua*), tulip poplar (*Liriodendron tulipifera*), and ironwood (*Carpinus caroliniana*). Other dominant species include

Japanese honeysuckle (*Lonicera japonica*) and greenbriar (*Smilax* sp.). Japanese grass (*Microstegium vimineum*) dominates the herbaceous layer. Hydrology is indicated by drainage patterns. The jurisdictional features at Site 2 were not presented in the EA. This wetland will be permanently impacted by a 48-inch pipe and roadway fill.

Site 2a (Sheet 9-10 of 40): This non-riverine wetland will not be impacted by the proposed project, but has been included to exhibit avoidance. It is located north of SR 1800 (Midway School Road). It is dominated by trees and shrubs: black willow (*Salix nigra*), red maple, and sweetgum. The herbaceous layer is dominated by sedges (*Carex* sp.), cattail (*Typha latifolia*), and rush (*Juncus* sp.). Hydrology is indicated by inundation and drainage patterns. The jurisdictional feature at Site 2a was not presented in the EA.

Site 3 (Sheet 11-12 of 40): This non-riverine wetland is located adjacent to a pond north of SR 1800 (Midway School Road). It is dominated by red maple, sweetgum, Japanese honeysuckle, and Japanese grass. Hydrology is indicated by inundation and drainage patterns. The jurisdictional feature at Site 3 was not presented in the EA. This wetland will be permanently impacted by roadway fill and mechanized clearing.

Site 5 (Sheet 22-23 of 40): This is a fairly linear non-riverine wetland located west of NC 109. It is dominated by trees such as red maple, sycamore (*Platanus occidentalis*), sweetgum, black cherry (*Prunus serotina*), box elder (*Acer negundo*), and black gum (*Nyssa sylvatica*). No midstory is present, and the herbaceous layer is a monoculture of Japanese grass. Hydrology is indicated by drainage patterns. The jurisdictional feature at Site 5 was not presented in the EA. This wetland will be permanently impacted by a 30-inch pipe, roadway fill and mechanized clearing.

Site 9 (Sheet 29-33 of 40): This non-riverine wetland is located adjacent to NC 109 along an unnamed tributary to Rich Fork Creek. The canopy is dominated by sycamore, tulip poplar, red maple, sweetgum, and ironwood. The shrub layer is dominated by elderberry (*Sambucus canadensis*) and box elder. The herbaceous layer is a monoculture of Japanese grass. Hydrologic indicators include drainage patterns, oxidized root channels in the upper 12 inches, and buttressed tree trunks. The jurisdictional feature at Site 9 was not presented in the EA. This wetland will be permanently impacted by a 42-inch pipe, roadway fill and mechanized clearing.

Surface Waters

The project crosses through the Yadkin-Pee Dee River Basin (HUC 03040103), within the Piedmont physiographic province. Surface waters crossed by the proposed project include Rich Fork Creek (Index Number 12-119-7), six unnamed tributaries to Rich Fork Creek, and two unnamed tributaries to Hunt's Fork Creek (12-119-7-3). The NCDWQ Best Usage Classification for both these creeks is C. Unnamed tributaries carry the same classification and index number as their receiving stream.

No NCDWQ Stream Classification Forms or USACE Stream Quality Assessment Worksheets were completed for the streams during the initial surveys; however these

forms were completed by H.W. Lochner, Inc. biologists during a subsequent site visit on June 4, 2004. Stream determinations made in 2004 agreed with those determinations made during the August 2001 field verification meeting. During a field inspection on July 9, 2004, Brian Wrenn of NCDWQ, agreed to defer to the USACE for all stream determination and mitigation calls associated with this project. Copies of the USACE Stream Quality Assessment Worksheets and NCDWQ Stream Classification Forms are included with this application for reference.

Table 5 gives the stream name and jurisdictional status, the structure size and type, the fill in surface waters, linear feet of stream impact, and the NCDWQ and USACE scores for the streams at each permanent impact site. The calculations and drawings by NCDOT Hydraulics Unit are presented in the attached permit drawings. A site by site description of each stream follows.

Table 5 – Permanent Stream Impacts and Descriptions						
Site	Stream Name and Jurisdictional Status *	Structure Size and Type	Fill in Stream (acres)	Existing Channel Impacted (Linear feet)	NCDWQ Score	USACE Score
1	UT Hunt's Fork Creek (I)	48" pipe	0.03	427	22.5	48
2	UT Hunt's Fork Creek (I)	48" pipe	0.02	223	18.5	48
3a	UT Rich Fork Creek (P)	66" pipe	0.05	437	31.5	57
4	UT Rich Fork Creek (P)	11' x 8' RCBC	0.14	617	35.5	48
6	UT Rich Fork Creek (I)	24" pipe	0.01	121	21.5	39
6	UT Rich Fork Creek (I)	30" pipe	0.02	289	21.5	39
7	UT Rich Fork Creek (I)	24" pipe	0.01	273	25.5	34
8	Rich Fork Creek (P)	2 @ 85' x 54' P/S Concrete girder bridge	0.05	98	43	60
9	UT Rich Fork Creek (I)	42" pipe	0.01	141	18.5	20
10	UT Rich Fork Creek (I,P)	36" pipe	0.02	351	21.5 (I), 32.5 (P)	33
Total Impacts			0.36	2,987		

* UT = Unnamed Tributary, I = intermittent, P = perennial

Site1 (Sheet 5-6 of 40): This intermittent unnamed tributary to Hunt's Fork Creek is crossed by the project approximately one-half mile northeast of its confluence with

Hunt's Fork Creek. This stream has a wide, forested riparian buffer, and is slightly incised. The jurisdictional feature at Site 1 was not presented in the EA. It will be impacted by a 48-inch pipe and associated roadway fill, and no mitigation will be required for these impacts.

Site 2 (Sheet 7-8 of 40): This intermittent unnamed tributary to Hunt's Fork Creek is crossed by the project approximately one mile northeast of its confluence with Hunt's Fork Creek. This stream has a wide, forested riparian buffer, and has weak geomorphology. A wetland is also associated with the impacts at Site 2. The jurisdictional features at Site 2 were not presented in the EA. The stream will be impacted by a 48-inch pipe and associated roadway fill, and no mitigation will be required for these impacts.

Site 3a (Sheet 13-14 of 40): This perennial unnamed tributary to Rich Fork Creek is crossed by the project approximately one and a half miles southeast of its confluence with Rich Fork Creek. This stream suffers from poor water quality, probably as a result of the numerous septic systems upslope at the stream's headwaters. The channel is also scoured due to stormwater runoff. Household garbage and white goods litter the stream banks. The jurisdictional feature at Site 3a was not presented in the EA. It will be impacted by a 66-inch pipe and associated roadway fill, and mitigation for these impacts will be required at a 1:1 ratio.

Site 4 (Sheet 15-21 of 40): This perennial unnamed tributary to Rich Fork Creek is crossed by the project approximately one and a half miles southeast of its confluence with Rich Fork Creek. This stream receives the drainage from the UT crossed at Site 3a. During the June 4, 2004 site visit, this stream was carrying a large amount of suspended sediment, giving the water a milky appearance. The jurisdictional feature at Site 4 was presented in the EA as UT5. It will be impacted by a 11-foot wide by 8-foot high reinforced concrete box culvert and associated roadway fill, and mitigation for these impacts will be required at a 2:1 ratio.

Approximately 315 linear feet of this impacted channel is targeted for on-site relocation and restoration. The stream design/classification for this stream reach is based on fluvial geomorphic principles and techniques. Existing stream conditions include a substrate of mostly gravel and coarse sand with some bedrock exposed at various locations; a bankfull width of 11.1 feet; a mean depth of 1.6 feet; a cross-sectional area of 5.5 square feet, and a sinuosity of 1.2. The restored channel will be designed for stable pattern, dimension, and profile. More detailed descriptions of existing conditions and the proposed reach can be found on Sheets 19 through 21 of the attached permit drawings. Further detailed information on the existing stream, reference reach, and restoration techniques used can be found in the attached "Natural Stream Design" document.

Site 6 (Sheet 24-25 of 40): Site 6 consists of two crossings of the same intermittent unnamed tributary to Rich Fork Creek. This pair of crossings lies approximately 1,800 feet south of its confluence with Rich Fork Creek. This unnamed tributary shows some

incision and bank failures, but is stable overall. The jurisdictional feature at Site 6 was not presented in the EA. It will be impacted by 30-inch and 24-inch pipes and associated roadway fill, and no mitigation will be required for these impacts.

Site 7 (Sheet 24-25 of 40): This intermittent unnamed tributary to Rich Fork Creek is crossed by the project approximately 1,600 feet south of its confluence with Rich Fork Creek. This tributary receives stormwater from NC 109, and its watershed is composed of primarily residential land use. Consequently, this stream has a large amount of sediment in its bed. The jurisdictional feature at Site 7 was not presented in the EA. It will be impacted by a 24-inch pipe and associated roadway fill, and no mitigation will be required for these impacts.

Site 8 (Sheet 26-28 of 40): Rich Fork Creek is the perennial stream crossed by the project at Site 8. During the June 4, 2004 site visit, this stream was carrying a large amount of suspended sediment, giving the water a milky appearance. The stream channel is 30 to 45 feet in width, and the channel has been straightened in the past. This jurisdictional feature was presented in the EA using the same name (Rich Fork Creek).

The existing 103-foot long bridge on NC 109 over this stream will be removed and replaced with a new two-span bridge 170 feet in length. The bridge will span the water, as the middle pier will be right along the existing bank. A rock causeway will be used to construct the pier due to its close proximity to the water. Temporary channel impacts will be incurred as a result of the temporary rock causeway. A naturally-formed scour hole is present adjacent to the stream channel, and under the existing bridge. This surface water will be permanently filled during construction of the new bridge. No mitigation will be required for the impacts at this site.

Site 9 (Sheet 29-33 of 40): This intermittent unnamed tributary to Rich Fork Creek is crossed by the project approximately 500 feet north of its confluence with Rich Fork Creek. This stream receives a large amount of stormwater runoff from NC 109, and has an incised channel. A wetland is also associated with this impact site. The jurisdictional features at Site 9 were not presented in the EA. This stream will be impacted by 42-inch pipe and associated roadway fill, and no mitigation will be required for these impacts.

Approximately 315 linear feet of this stream channel will be relocated from Station 64+20 to 64+80 left of -L-, which will include both an ephemeral and intermittent portion of the stream. Although natural channel design techniques have been used in the design, the relocated portion of this stream will not be claimed as on-site mitigation. Sheet 31 of 40 depicts the natural channel design details.

Site 10 (Sheet 34-35 of 40): This unnamed tributary to Rich Fork Creek changes from an intermittent to a perennial stream at the culvert near Station 76+10. This stream receives stormwater runoff from NC 109 and SR 1756 (Lexington Avenue). The stream channel is scoured and incised. The intermittent portion of the stream has been straightened, while the perennial portion is fairly sinuous. The jurisdictional feature at Site 9 was presented

in the EA as UT4. It will be impacted by a 36-inch pipe and associated roadway fill, and mitigation for these impacts will be required at a 1:1 ratio.

Temporary Impacts

There are no temporary wetland impacts or ponds; however temporary stream impacts will be necessary for construction of the box culvert at Site 4, pipe installations at Sites 1, 2, 3a, 6, 7, 9 and 10, and for construction of the bridge over Rich Fork Creek. Temporary impacts associated with this project include 182 linear feet of channel impacts, and 0.03 acres of temporary fill.

At Site 4 (Sheet 15-21 of 40) 82 linear feet of temporary impact will be necessary for the installation of the culvert. Temporary impact will also be necessary to tie the newly created stream channel into the existing stream channel near Station 48+00 –L-.

At Sites 1 (Sheet 5-6 of 40), 2 (Sheet 7-8 of 40), 9 (Sheet 29-33 of 40), and 10 (Sheet 34-35 of 40), 10 linear feet of temporary impacts will be necessary for pipe installation at each Site. At Sites 3a (Sheet 11-12 of 40), 6 (Sheet 24-25 of 40), and 7 (Sheet 24-25 of 40), 20 linear feet of temporary impacts will be necessary for pipe installation at each Site. These temporary impacts will allow for any temporary dewatering necessary for installation of the structures, or for any other temporary channel impacts associated with construction. Structure type and locations are listed in Table 5 on page 9 of this letter.

At Site 8 (Site 8, Sheet 26-28 of 40) temporary fill in Rich Fork Creek will result from the construction of a rock causeway, necessary for the construction of the new bridge. More information on temporary impacts associated with this bridge are given below in the proposed project's restoration, removal, and disposal plan for the bridge over Rich Fork Creek.

Restoration Plan: The temporary fill will consist of Class II riprap. No permanent fill in Rich Fork Creek will result from the subject activity. (Permanent fill will be used in a naturally-formed scour hole adjacent to the Rich Fork Creek stream channel.) Following construction of the causeway, the construction of the interior bent will be completed. After the bent is completed all material used in the construction of the temporary causeway will be removed. Reference elevations are available for the area of proposed construction of the temporary causeways. In addition, profiles and cross sections of the streambed have been measured with the data including measurements of the stream thalweg. The NCDOT will restore the stream to its pre-project contours and elevations. The temporary impact area associated with the causeway is expected to recover naturally, since the natural streambed and plant material will not be removed. The NCDOT does not propose any additional planting in this area. The fill will be placed and removed with earth moving equipment.

Removal and Disposal Plan: The contractor will be required to submit a reclamation plan for the removal and disposal of all materials off-site at an upland location. The contractor will use excavating equipment to remove the riprap used for the temporary causeways.

Heavy-duty trucks, bulldozers, cranes and various other pieces of mechanical equipment necessary for construction of roadways and bridges will be used on site. All material placed in the river will be removed from the river at that time. The contractor will have the option of reusing any of the riprap that the engineer deems suitable in the construction of the project. After the temporary causeway is no longer needed all material will become the property of the contractor.

FEDERALLY PROTECTED SPECIES

Plants and animals with a Federal classification of Endangered (E) or Threatened (T) are protected under provisions of Section 7 and Section 9 of the Endangered Species Act of 1973, as amended. At the time of completion of the EA (November 1996) only Schweinitz's sunflower (*Helianthus schweinitzii*) was listed by the U.S. Fish and Wildlife Service (USFWS) as a protected species in Davidson County, NC. However as of January 29, 2003, the USFWS lists three federally protected species for Davidson County. Table 5 lists these species and their federal status. A letter requesting concurrence with these biological conclusions was mailed to USFWS on June 30, 2004, and a copy of this letter is attached with this application package.

Table 5 – Federally Protected Species in Davidson County, NC			
Common Name	Scientific Name	Federal Status*	Biological Conclusion
Bald eagle	<i>Haliaeetus leucocephalus</i>	T (proposed for delisting)	No Effect
Bog turtle	<i>Clemmys muhlenbergii</i>	T(S/A)	Not Required
Schweinitz's sunflower	<i>Helianthus schweinitzii</i>	E	May Affect-Not Likely to Adversely Effect
* E=Endangered, T=Threatened, T(S/A)=Threatened due to similarity of appearance			

A memorandum dated June 7, 2002 from Lynn Smith of the NCDOT Natural Systems Unit, to Jay McInnis, P.E. of the NCDOT Project Development Unit, provided further information on these federally protected species (including a biological conclusion for the bald eagle) as an update to the previously submitted EA.

Bald eagle

There are no large bodies of water or large river systems with a clear flight path to water within a half mile of the proposed project. A review of the North Carolina Natural Heritage Program (NCNHP) database on May 5, 2002 indicated that there are no known occurrences of bald eagle within 1.0 mile of the project study area. Therefore, a biological conclusion of "No Effect" was rendered for this species in the June 7, 2002 memo.

Bog turtle

Any species that is listed by USFWS as “T(S/A)” is a species that is threatened due to similarity of appearance with other rare species and is listed for its protection. These species are not biologically endangered or threatened and are not subject to Section 7 consultation. Therefore, a biological conclusion for this species is not required and no biological conclusion was issued in the June 7, 2002 memo.

Schweinitz’s sunflower

In the EA (November 1996), a biological conclusion of “No Effect” was issued for Schweinitz’s sunflower. However, due to the date of the last survey and the presence of suitable habitat in the project area, this biological conclusion was no longer valid. As a result, new surveys were conducted for this species on June 8 and 9, 2004.

Although these surveys were conducted several months prior to the optimal survey window, Dale Suiter of the USFWS advised that the species could be correctly identified during this time of year. A known population of this species was visited (June 8, 2004) prior to the initiation of field surveys.

Although appropriate habitat is present within the project right-of-way limits in the form of regularly maintained roadside shoulders, field or pasture edges, and utility easements, no individuals of this species or of the *Helianthus* genus were observed during the surveys. A review of the North Carolina Natural Heritage Program occurrence records on May 27, 2004 revealed no records of this species within 1 mile of the proposed project. The nearest known population of Schweinitz’s sunflower is located adjacent to NC 109 in Davidson County approximately 16 miles south of the proposed project. Therefore, a biological conclusion of “May Affect, Not Likely to Adversely Affect” has been issued for this federally protected species. As stated above, a letter requesting concurrence with these biological conclusions was mailed to USFWS on June 30, 2004, and a copy of this letter is attached with this application package.

CULTURAL RESOURCES

Archaeology

1. Archaeological Survey: A survey was conducted to locate existing archaeological resources in the vicinity of the project area and to determine if any of these sites were potentially affected by the project. No additional archaeological investigations for these sites will be required.
2. Properties Identified: During the course of these surveys, several potential archaeological sites were identified; however, none of these sites were determined to meet the criteria for inclusion in the National Register of Historic Places. The N.C. State Historic Preservation Office (SHPO) has concurred with these findings in a letter dated March 21, 1997. A copy of this letter is attached with this application package.

Historic Architecture

Based on architectural surveys, there are no historic properties within the project's area of potential effect (APE) that are listed on the National Register of Historic Places. One property, the John Williams-Hyatt Farm, is located in the APE and was determined by the SHPO to be eligible for the National Register Criterion C in a letter dated November 12, 1996. A copy of this letter is attached with this application package.

Further coordination with the SHPO indicated that the proposed project will have no effect on the property. There will be no right-of-way required from within the designated historic boundaries of the John Williams-Hyatt Farm.

WILD AND SCENIC RIVERS

Rich Fork Creek and Hunts Fork Creek (and their unnamed tributaries) are not listed as a federal or state wild and scenic river.

ESSENTIAL FISH HABITAT

Based on the location, scope, and nature of impacts expected from this project, impacts to Essential Fish Habitat are not anticipated.

303(d) LIST

Section 303(d) of the Clean Water Act (CWA) requires states to develop a list of waters not meeting water quality standards or which have impaired uses. Both Rich Fork Creek and Hunts Fork Creek appear on the April 2004 303(d) Impaired Waters List. Within the project area Rich Fork Creek (Site 8, Sheet 36-38) is listed as impaired for aquatic life due to low dissolved oxygen. This stream will be bridged by the proposed project, and both permanent and temporary impacts to the stream channel will be incurred. Six of the unnamed tributaries to Rich Fork Creek will be directly impacted by culverting (one tributary will be crossed twice).

Hunts Fork Creek, which is crossed by the R-2568A project, is listed as having overall impairment due to impaired biological integrity; the stressors not being identified. This stream will not be directly impacted by the R-2568B project; however two of its unnamed tributaries will be culverted.

UTILITY IMPACTS

No utility relocations will result in additional impacts to wetlands or streams. Utilities will cross aerially at Rich Fork Creek on the east side of the roadway near or between Station 60+80 and Station 61+80.

FEMA COMPLIANCE

Davidson County is currently participating in the National Flood Insurance Regular Program. Rich Fork Creek and Hunt's Fork Creek are included in the detailed flood study, having an established 100-year floodplain and floodway. The unnamed tributaries to these streams are in a designated flood hazard zone. The floodplain of Rich Fork Creek is rural and undeveloped. There are no buildings in the vicinity of the stream crossing with floor elevations below the 100-year floodplain. According to the NCDOT Hydraulics Unit engineers, the NCDOT has achieved compliance with the Federal Emergency Management Agency for this proposed project. None of the drainage accommodations for the bridge replacement at this crossing will have any significant adverse affect on the existing floodplain, nor the associated flood hazard.

INDIRECT AND CUMULATIVE EFFECTS ANALYSIS

The Indirect and Cumulative Effects report dated July 16, 2004 is attached. Conclusions indicate that the proposed project is anticipated to have minimal or no effect on water quality as a result of potential land use changes within the Growth Impact Study Area (GISA).

Potential indirect and cumulative impacts are as follows:

- Based on the analysis, TIP R-2568B is unlikely to stimulate land development having complementary functions and will not serve any explicit economic development purpose or a specific development.
- The change in accessibility and mobility as a result of TIP R-2568B will be minimal, except for those parcels that gain new road frontage.
- Over the next twenty years, population growth within Davidson County should continue at rates just above 1% annually, therefore keeping demand for developable land in the area low.
- A generally weak market for development within the GISA limits the potential for land use change as a result of TIP R-2568B.
- Within the GISA, the most likely area for commercial or residential growth as a result of TIP R-2568B is at the new intersection of NC 109 and Midway School Road.
- Other planned transportation projects, such as the continuation of TIP R-2568 sections C-G, along with TIP U-2537, will improve regional accessibility throughout the eastern portion of Davidson County and the western portion of High Point.

MITIGATION OPTIONS

The NCDOT is committed to incorporating all reasonable and practicable design features to avoid and minimize jurisdictional impacts, and to provide full compensatory mitigation of all remaining, unavoidable jurisdictional impacts. Avoidance measures were taken during the planning and NEPA compliance stages; minimization measures were

implemented during the design phase to include the examination of appropriate and practicable steps to reduce adverse impacts from the project.

Avoidance

All wetland areas not affected by the project will be protected from unnecessary encroachment.

1. No staging of construction equipment or storage of construction supplies will be allowed in wetlands or near surface waters.
2. Aquatic Life Movement: The project was designed to avoid disturbance to aquatic life movements.
3. Site 2A (Sheet 9-10 of 40): Project design has allowed for avoidance of the wetland at Station 37+00 right of -L-. A preformed scour hole was added at the end of the rip rapped ditch at Station 37+15 right of -L- to disperse concentrated flow from the ditch before it enters the wetland.
4. As shown in Table 2 on Page 4 of this letter, two streams (UT2 and UT3) and three wetlands (Wetland 1, Wetland 2, and Wetland 3) that were listed in the EA were avoided during subsequent project design.

Minimization

Minimization includes the examination of appropriate and practicable steps to reduce the adverse impacts. General minimization techniques implemented include the following:

- Slopes: Fill slopes in wetlands are at a 2:1 ratio.
- Ditching: It is the policy of NCDOT to eliminate lateral ditching in wetlands as much as possible, thus preserving the hydrology of adjacent wetlands. There are no ditches in wetlands on this project.
- Pipe Culvert Design: Pipe culvert and box culvert inverts are to be buried 20% of the pipe diameter, up to 1 foot deep. All pipe culverts and box culverts will maintain the normal stream flow and channel characteristics. The design will allow unimpeded passage by fish and other aquatic organisms.
- BMPs: In order to minimize potential adverse impacts to wetlands and streams in the project area, the NCDOT's Best Management Practices for the Protection of Surface Waters and Sedimentation Control Guidelines will be strictly enforced during construction of the project. This will include:
 - Grassed roadway ditches and shoulders as opposed to a curb and gutter roadway system. Rip-rapped ditches were used where warranted to control erosion.
 - Ditches were ended in flat floodplain areas where possible to allow dispersal and infiltration.
 - Preformed scour holes were used to attenuate and disperse flow.
 - No bridge deck drains will be used directly over the surface water.

Site specific minimization efforts that have been employed in the project area include:

- Site 2 (Sheet 7-8 of 40): Rip rap at the outlet of the 48-inch pipe was removed from the streambed and placed only on the channel banks. Fill slopes in wetlands are at a 2:1 ratio.
- Site 3 (Sheet 11-12 of 40): A rock check dam was used to attenuate flow in lieu of preformed scour hole due to steep topography. Fill slopes in wetlands are at a 2:1 ratio.
- Site 4 (Sheet 15-21 of 40): A preformed scour hole was added at the end of the rip rapped ditch at Station 46+80 right of -L- to disperse concentrated flow from the ditch before it enters the floodplain. A preformed scour hole was also added at the outlet of the 16-inch pipe upslope from the restored stream channel at Station 46+80 left of -L- to disperse concentrated flow from the pipe before it enters the stream. Clearing will be limited to 10 feet beyond the top of the cut on the stream relocation. A cross vane rock weir was added to the stream relocation for grade control.
- Site 5 (Sheet 22-23 of 40): A preformed scour hole was added at the end of the rip rapped ditch at Station 50+60 left of -L- to disperse concentrated flow from the ditch before it enters the wetland. In addition, two preformed scour holes were added at Station 51+20 right of -L- to disperse from the base of the fill slope before entering the wetland. Fill slopes in wetlands are at a 2:1 ratio.
- Site 8 (Sheet 26-28 of 40): A preformed scour hole was added at the end of the rip rapped ditches at Station 61+00 left and right of -L- to attenuate and disperse concentrated flow from the ditch before it enters the floodplain.
- Site 9 (Sheet 29-33 of 40): Fill slopes in wetlands are at a 2:1 ratio.

Conservative use of culverts and sensitive placement of drainage structures will minimize further degradation of water quality and reduce adverse impacts on aquatic habitat viability in streams and tributaries.

Compensation

The primary emphasis of the compensatory mitigation is to reestablish a condition similar to what would have existed if the project were not built. Mitigation is limited to reasonable expenditures and practicable considerations related to highway operation. Mitigation is generally accomplished through a combination of methods designed to replace wetland functions and values lost as a result of construction of the project. These methods consist of creation of new wetlands from uplands, borrow pits, and other non-wetland areas; restoration of wetlands; and enhancement of existing wetlands. Where such options may not be available, or when existing wetlands and wetland-surface water complexes are considered to be important resources worthy of preservation, consideration is given to preservation as at least one component of a compensatory mitigation proposal.

Based upon the agreements stipulated in the "Memorandum of Agreement Among the North Carolina Department of Environment and Natural Resources, the North Carolina Department of Transportation, and the U.S. Army Corps of Engineers, Wilmington

District” (MOA), it is understood that the North Carolina Department of Environment and Natural Resources Ecosystem Enhancement Program (EEP) will assume responsibility for satisfying the federal Clean Water Act compensatory mitigation requirements for NCDOT projects that are listed in Exhibit 1 of the subject MOA during the EEP transition period which ends June 30, 2005, or in the additional list of 16 projects to be let during 2004-2005. A request letter dated June 18, 2004 was sent to EEP. However, due to additional project design, which resulted in a reduction of impacts to jurisdictional streams, a revised letter, dated July 21, 2004, has also been sent to EEP. Copies of both letters are attached with the application package.

Since the subject project is listed in Exhibit 1, the necessary compensatory mitigation to offset unavoidable impacts to waters that are jurisdictional under the federal Clean Water Act will be provided by the EEP. The offsetting mitigation will derive from an inventory of assets already in existence within the same 8-digit cataloging unit. The Department has avoided and minimized impacts to jurisdictional resources to the greatest extent possible as described above. The remaining, unavoidable impacts to 0.75 acres of jurisdictional wetlands and to 1,090 linear feet of jurisdictional streams will be offset by compensatory mitigation provided by the EEP program.

Table 2 on page 4 of this letter provides a summary of permanent impacts associated with the R-2568B project. Compensatory mitigation for this project consists of the following:

Wetland Mitigation: Wetland impacts total 0.75 acres to non-riverine wetlands. Compensatory mitigation will be mitigated through the use of EEP for 0.75 acres of wetland impacts.

Stream Mitigation: Stream impacts total 2,987 linear feet of impacts to first- and second-order perennial and intermittent streams. The following combination of on-site relocation and compensatory mitigation is proposed:


1. Mitigation for 1,405 feet of stream impacts will only be required at Site 3a (Sheet 11-12 of 40), Site 4 (Sheet 15-21 of 40), and Site 10 (Sheet 34-35 of 40). Mitigation for 788 feet of impacts at Site 3a and 10 will be required at a 1:1 ratio, while mitigation for 617 feet of impacts at Site 4 will be required at a 2:1 ratio.
2. Natural channel design will create 315 linear feet of new stream channel at a 1:1 mitigation ratio. This on-site mitigation which includes the relocation of a portion of an unnamed tributary to Rich Fork Creek is located at Site 4, Station 47+60 to 47+96 –L-, and is depicted on Sheet 15 of 40. Sheets 18-20 of 40 depict the natural channel design details, and Sheet 21 of 40 shows the morphological measurement table.
3. Compensatory mitigation will be mitigated through the use of EEP for the remaining 1,090 linear feet of stream impacts.

REGULATORY APPROVALS

Application is hereby made for a Department of the Army Individual 404 Permit as required for the above-described activities. We are also hereby requesting a 401 Water Quality Certification from the Division of Water Quality. In compliance with Section 143-215.3D(e) of the NCAC, we will provide \$475.00 to act as payment for processing the Section 401 permit application previously noted in this application (see Subject line). We are providing seven copies of this application to the North Carolina Department of Environment and Natural Resources, Division of Water Quality, for their review.

If you have any questions or need additional information please call Ms. Deanna Riffey, Environmental Specialist at (919) 715-1409.

Sincerely,



Gregory J. Thorpe, Ph.D.,
Environmental Management Director
Project Development and Environmental Analysis Branch

cc: w/attachment

Mr. John Hennessey, NCDWQ (7 copies)
Ms. Marla Chambers, NCWRC
Ms. Becky Fox, USEPA – Whittier, NC
Mr. Ronald Mikulak, USEPA – Atlanta, GA
Ms. Marella Buncick, USFWS
Mr. David Chang, P.E., Hydraulics
Mr. Greg Perfetti, P.E., Structure Design
Mr. S.P. Ivey, P.E., Division Engineer
Ms. Diane Hampton, P.E., DEO
Mr. Ron Hancock, P.E., State Bridge Construction Engineer

w/o attachment

Mr. Jay Bennet, P.E., Roadway Design
Mr. Omar Sultan, Programming and TIP
Ms. Art McMillan, P.E., Highway Design
Mr. Mark Staley, Roadside Environmental
PDEA Project Planning Engineer
Ms. Beth Harmon, EEP
Mr. David Franklin, USACE
Mr. William D. Gilmore, P.E., EEP

APPLICATION FOR DEPARTMENT OF THE ARMY PERMIT
(33 CFR 325)

OMB APPROVAL NO. 0710-0003
Expires December 31, 2004

The Public burden for this collection of information is estimated to average 10 hours per response, although the majority of applications should require 5 hours or less. This includes the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Department of Defense, Washington Headquarters Service Directorate of Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302; and to the Office of Management and Budget, Paperwork Reduction Project (0710-0003), Washington, DC 20503. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to either of those addresses. Completed applications must be submitted to the District Engineer having jurisdiction over the location of the proposed activity.

PRIVACY ACT STATEMENT

Authorities: Rivers and Harbors Act, Section 10, 33 USC 403; Clean Water Act, Section 404, 33 USC 1344; Marine Protection, Research and Sanctuaries Act, 33 USC 1413, Section 103. Principal Purpose: Information provided on this form will be used in evaluating the application for a permit. Routine Uses: This information may be shared with the Department of Justice and other federal, state, and local government agencies. Submission of requested information is voluntary, however, if information is not provided the permit application cannot be evaluated nor can a permit be issued.

One set of original drawings or good reproducible copies which show the location and character of the proposed activity must be attached to this application (see sample drawings and instructions) and be submitted to the District Engineer having jurisdiction over the location of the proposed activity. An application that is not completed in full will be returned.

(ITEMS 1 THRU 4 TO BE FILLED BY THE CORPS)

1. APPLICATION NO.	2. FIELD OFFICE CODE	3. DATE RECEIVED	4. DATE APPLICATION COMPLETED
--------------------	----------------------	------------------	-------------------------------

(ITEMS BELOW TO BE FILLED BY APPLICANT)

5. APPLICANT'S NAME NCDOT-PD&EA	8. AUTHORIZED AGENT'S NAME AND TITLE <i>(an agent is not required)</i>
6. APPLICANT'S ADDRESS 1548 Mail Service Center, Raleigh NC, 27699-1548	9. AGENT'S ADDRESS
7. APPLICANT'S PHONE NOS. W/AREA CODE a. Residence b. Business 919-733-3141	10. AGENT'S PHONE NOS. W/AREA CODE a. Residence b. Business

11. STATEMENT OF AUTHORIZATION

I hereby authorize, _____ to act in my behalf as my agent in the processing of this application and to furnish, upon request, supplemental information in support of this permit application.

APPLICANT'S SIGNATURE

DATE

NAME, LOCATION AND DESCRIPTION OF PROJECT OR ACTIVITY

12. PROJECT NAME OR TITLE <i>(see instructions)</i> NC 109, from north of I-85 Business to just north of SR 1798 (Old Greensboro Road) NCDOT TIP No. R-2568 B	
13. NAME OF WATERBODY, IF KNOWN <i>(if applicable)</i>	14. PROJECT STREET ADDRESS <i>(if applicable)</i>
15. LOCATION OF PROJECT Davidson North Carolina _____ COUNTY STATE	
16. OTHER LOCATION DESCRIPTIONS, IF KNOWN, <i>(see instructions)</i> A four-lane divided facility with partial access control, predominantly on new location.	
17. DIRECTIONS TO THE SITE Exit I-85 Business and head north on NC 109. The southern terminus of the project is on the north side of Hunts Fork Creek.	

18. Nature of Activity (Description of project, include all features)

Improve the NC 109 corridor from north of I-85 Business in Thomasville to SR 1798 (Old Greensboro Rd.) One new bridge, two stream relocations, several culverts installed over stream crossings, and some wetland fill.

19. Project Purpose (Describe the reason or purpose of the project, see instructions)

The purpose of the project is to upgrade the this section of the NC 109 corridor in order to improve safety and serve the future traffic demands required for the growing areas of Davidson County.

USE BLOCKS 20-22 IF DREDGED AND/OR FILL MATERIAL IS TO BE DISCHARGED

20. Reason(s) for Discharge

Roadway fill, pipe/culvert construction, bridge construction (temporary impacts only)

21. Type(s) of Material Being Discharged and the Amount of Each Type in Cubic Yards

roadway fill associated with 8 new pipe culverts, 1 box culvert.

22. Surface Area in Acres of Wetlands or Other Waters Filled (see instructions)

0.75 acres of Wetland impacts; 2,987 lf of stream impacts (1,405 lf of impact to mitigable streams and 1,582 lf of impact to non-mitigable streams)

23. Is Any Portion of the Work Already Complete? Yes ☐ No ☒ IF YES, DESCRIBE THE COMPLETED WORK

24. Addresses of Adjoining Property Owners, Lessees, Etc., Whose Property Adjoins the Waterbody (If more than can be entered here, please attach a supplemental list).


See property owner list in permit drawings

25. List of Other Certifications or Approvals/Denials Received from other Federal, State or Local Agencies for Work Described in This Application.

AGENCY	TYPE APPROVAL*	IDENTIFICATION NUMBER	DATE APPLIED	DATE APPROVED	DATE DENIED

*Would include but is not restricted to zoning, building and flood plain permits

26. Application is hereby made for a permit or permits to authorize the work described in this application. I certify that the information in this application is complete and accurate. I further certify that I possess the authority to undertake the work described herein or am acting as the duly authorized agent of the applicant.



SIGNATURE OF APPLICANT

7/22/04


DATE

SIGNATURE OF AGENT


DATE

The application must be signed by the person who desires to undertake the proposed activity (applicant) or it may be signed by a duly authorized agent if the statement in block 11 has been filled out and signed.

18 U.S.C. Section 1001 provides that: Whoever, in any manner within the jurisdiction of any department or agency of the United States knowingly and willfully falsifies, conceals, or covers up any trick, scheme, or disguises a material fact or makes any false, fictitious or fraudulent statements or representations or makes or uses any false writing or document knowing same to contain any false, fictitious or fraudulent statements or entry, shall be fined not more than \$10,000 or imprisoned not more than five years or both.



VICINITY MAP




N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY

NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.


STATE PROJECT #8J1600901 R-2568B
 SHEET 1 OF 40

12/12/02

MATCHLINE



VICINITY MAP
(HIGH POINT WEST QUADRANGLE)




N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY


**NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.**

STATE PROJECT #8.1600901 R-2568B
SHEET 2 OF 40

060404



VICINITY MAP
MIDWAY AND HIGH POINT WEST QUADRANGLE



N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY

NO. 100 FROM NORTH
OF SR1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT #8.1600901 R-2568B
SHEET 3 OF 40

060404

WETLAND LEGEND


	WETLAND BOUNDARY
	WETLAND
	DENOTES FILL IN WETLAND
	DENOTES FILL IN SURFACE WATER
	DENOTES FILL IN SURFACE WATER (POND)
	DENOTES TEMPORARY FILL IN WETLAND
	DENOTES EXCAVATION IN WETLAND
	DENOTES TEMPORARY FILL IN SURFACE WATER
	DENOTES MECHANIZED CLEARING
	FLOW DIRECTION
	TOP OF BANK
	EDGE OF WATER
	PROP. LIMIT OF CUT
	PROP. LIMIT OF FILL
	PROP. RIGHT OF WAY
	NATURAL GROUND
	PROPERTY LINE
	TEMP. DRAINAGE EASEMENT
	PERMANENT DRAINAGE EASEMENT
	EXIST. ENDANGERED ANIMAL BOUNDARY
	EXIST. ENDANGERED PLANT BOUNDARY
	WATER SURFACE
	LIVE STAKES
	BOULDER
	CORE FIBER ROLLS
	DENOTES TEMPORARY SURFACE WATER IMPACTS

	PROPOSED BRIDGE
	PROPOSED BOX CULVERT
	PROPOSED PIPE CULVERT 12"-48" PIPES 54" PIPES & ABOVE
	(DASHED LINES DENOTE EXISTING STRUCTURES)
	SINGLE TREE
	WOODS LINE
	DRAINAGE INLET
	ROOTWAD
	RIP RAP
	ADJACENT PROPERTY OWNER OR PARCEL NUMBER IF AVAILABLE
	PREFORMED SCOUR HOLE
	LEVEL SPREADER (LS)
	DITCH / GRASS SWALE

N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY
NC 109 FROM NORTH OF
I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT #81600901 R2568B
SHEET 4 OF 40

06/04/04



N.C.D.O.T.

DIVISION OF HIGHWAYS

DAVIDSON COUNTY


NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT #8.1600901 R-2568B
SHEET 5 OF 40

07/14/04

SITE 1


DENOTES TEMPORARY
SURFACE WATER IMPACTS




SCALE



DENOTES FILL IN
SURFACE WATERS





N.C.D.O.T.

DIVISION OF HIGHWAYS

DAVIDSON COUNTY

NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT #8.1600901 R-2568B
SHEET 6 OF 40


07/14/04

SITE 1 IMPACTS

DENOTES FILL IN
SURFACE WATERS




DENOTES TEMPORARY
SURFACE WATER IMPACTS



SCALE





N.C.D.O.T.

DIVISION OF HIGHWAYS

DAVIDSON COUNTY

NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT#8.1600901 R-2568B
SHEET 8 OF 40

07/14/04

SITE 2 IMPACTS


DENOTES TEMPORARY
SURFACE WATER IMPACTS



DENOTES FILL IN
WETLANDS




DENOTES FILL IN
SURFACE WATERS



SCALE

UNNAMED TRIB TO
HUNT'S FORK CREEK



6/4/04




STEELE 2A

NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATB PROJECT#8J600901 R-2568B

SECRET 9 OF 10

060404




N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY

**NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)**

STATE PROJECT#81600901 R-2568B
SECRET 10 OF 40
060404





N.C.D.O.T. **DIVISION OF HIGHWAYS** **DAVIDSON COUNTY**

NC 109 FROM NORTH
 OF I-85 BUSINESS TO
 NORTH OF SR 1756
 (LEXINGTON AVE.)
 NORTH OF LEDFORD M.S.


STATE PROJECT#8J600901 R-2568B
 SHEET 12 OF 40

060404

DENOTES MECHANIZED
 CLEARING IN WETLANDS




DENOTES FILL IN
 WETLANDS



SCALE

SITE 3 IMPACTS




N.C.D.O.T. DIVISION OF HIGHWAYS DAVIDSON COUNTY

NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT #8.160901 R-2568B
SHEET 14 OF 40

07/14/04

SITE 3A IMPACTS



UNNAMED TRIBUTARY
TO RICH FORK CREEK

N.C.D.O.T. DIVISION OF HIGHWAYS DAVIDSON COUNTY

NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.


STATE PROJECT#8J600901 R-2568B

SHEET 16 OF 40



060404

SITE 4 IMPACTS


DENOTES TEMPORARY
SURFACE WATER IMPACTS



DENOTES FILL IN
SURFACE WATERS



Proposed Roadway Grade



SITE 4 PROFILE

N.C.D.O.T.


**DIVISION OF HIGHWAYS
DAVIDSON COUNTY**


NC 109 FROM NORTH OF I-85
BUSINESS TO NORTH OF SR
1756 (LEXINGTON AVE.) NORTH
OF LEDFORD MIDDLE SCHOOL

STATE PROJECT #8.160901 R-2568B


SHEET 17 OF 40

12/20/02





CHANNEL SECTION, IN BEND
(NOT TO SCALE)




CHANNEL TO BE GRADED TO MATCH 'RIFFLE SECTION' AND 'CHANNEL SECTION, IN BEND' THROUGHOUT, PROVIDING A SMOOTH TRANSITION BETWEEN EACH SECTION. EACH BEND SHOULD HAVE A POOL LOCATED ON THE OUTSIDE OF THE BEND.

STA 47+20 TO STA 47+80 - L- LT.


SITE 4

NC 109 FROM NORTH OF I-85
BUSINESS TO NORTH OF SR1756
(LEXINGTON AVE.) NORTH OF
LEDFORD MIDDLE SCHOOL

CHANNEL SECTION, IN BEND
(NOT TO SCALE)




ROOT WAD DIMENSIONS



NATURAL CHANNEL DESIGN DETAILS OUTLET OF CULVERT AT -L- 47 + 20 (LT)

SITE 4

PLAN VIEW




N. C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS

DAVIDSON COUNTY
PROJECT: 8.1600901 (R-2568B)
NC 109 FROM NORTH OF
I-85 BUSINESS TO NORTH
OF SR 1756 (LEXINGTON
AVE.) NORTH OF LEDFORD
MIDDLE SCHOOL


CROSS VANE ROCK WEIR DETAIL

SITE 4

PLAN VIEW




SECTION B-B



Note: Boulders should be native stone or shot rock, angular and oblong with axes approximately 1.2 m in length

Note: Rocks should fit tightly. Trim filter fabric flush with top of rocks.

SECTION A-A



N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY

NC 109 FROM NORTH
 OF I-85 BUSINESS TO
 NORTH OF SR 1756
 (LEXINGTON AVE.)
 NORTH OF LEDFORD M.S.

STATE PROJECT #81600901 R-2563B
 SHEET 20 OF 40
 12/12/02


SITE 4


MORPHOLOGICAL MEASUREMENT TABLE

VARIABLES	EXISTING CHANNEL	PROPOSED REACH	USGS STATION	REFERENCE REACH
1) STREAM TYPE	G4c	C4		E4
2) DRAINAGE AREA	119ha	119ha		78ha
3) BANKFULL WIDTH	3.4m	5.5m		3.7m
4) BANKFULL MEAN DEPTH	0.5m	0.36m		0.45m
5) WIDTH/DEPTH RATIO	6.8	15.3		8.2
6) BANKFULL CROSS-SECTIONAL AREA	1.7m ²	2.12m ²		1.66m ²
7) BANKFULL MEAN VELOCITY	1.5m/s	0.95m/s		1.43m/s
8) BANKFULL DISCHARGE, Q_b	2.6m ³ /s	2.0m ³ /s		1.70m ³ /s
9) BANKFULL MAX. DEPTH	0.57m	0.5m		0.52m
10) WIDTH OF FLOODPRONE AREA	4.0m	14m		8m
11) ENTRENCHMENT RATIO	1.2	2.5		2.2
12) MEANDER LENGTH	30m	27m		24m
13) RATIO OF MEANDER LENGTH TO BANKFULL WIDTH	8.8	4.9		6.5
14) RADIUS OF CURVATURE	11.6m	9m		6m
15) RATIO OF RADIUS OF CURVATURE TO BANKFULL WIDTH	3.4	1.6		1.62
16) BELT WIDTH	6.0m	12m		8m
17) MEANDER WIDTH RATIO	1.7	2.2		2.2
18) SINUOSITY (STREAM LENGTH/VALLEY LENGTH)	1.2	1.2		1.16
19) VALLEY SLOPE	0.0079	0.006		0.0129
20) AVERAGE SLOPE	0.0066	0.005		0.0111
21) POOL SLOPE	0.0022	0.002		0.004
22) RATIO OF POOL SLOPE TO AVERAGE SLOPE	0.33	0.40		0.36
23) MAXIMUM POOL DEPTH	0.15m	0.3m		0.24m
24) RATIO OF POOL DEPTH TO AVERAGE BANKFULL DEPTH	0.3	0.8		0.53
25) POOL WIDTH	2.0m	2.0m		1.8m
26) RATIO OF POOL WIDTH TO BANKFULL WIDTH	0.6	0.4		0.5
27) POOL TO POOL SPACING	17m	13m		15m
28) RATIO OF POOL TO POOL SPACING TO BANKFULL WIDTH	5.0	2.4		4.1
29) RATIO OF LOWEST BANK HEIGHT TO BANKFULL HEIGHT (OR MAX BANKFULL DEPTH)	2.3	1.0		1.8


NCDOT
 DIVISION OF HIGHWAYS
 DAVIDSON COUNTY
 PROJECT: 8.1600901 (R-2568B)
 NC 109 FROM NORTH
 OF I-85 BUSINESS TO
 NORTH OF SR 1756
 (LEXINGTON AVE.)
 NORTH OF LEDFORD M.S.
 SHEET 21 OF 40 12/12/02

060404





SITE 5 IMPACTS



N.C.D.O.T. DIVISION OF HIGHWAYS DAVIDSON COUNTY

NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT#81600901 R-2568B
SHEET 23 OF 40
060404

0.25

50

40


30

20

10

0

10




PROJECT REFERENCE NO.
R-2568B

SHEET 1


40

SITE 5



6-1-2004 00:21
kgp11030


6/4/04



N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY

NC 109 FROM NORTH
 OF I-85 BUSINESS TO
 NORTH OF SR 1756
 (LEXINGTON AVE.)
 NORTH OF LEDFORD M.S.

STATE PROJECT#8.1609001 R-2568B
 SHEET 24 OF 40



SITE 6 AND SITE 7

- DENOTES FILL IN SURFACE WATERS
- DENOTES FILL IN SURFACE WATERS




CHARLES W. HIATT AND WIFE,
DORIS S. HIATT

**NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.**


STATE PROJECT#8.1600901 R-2568B

SHEET 26 OF 40

50170390




DENOTES TEMPORARY FILL IN SURFACE WATER

8
SITTING



2011


SCALE





SITE 8 IMPACTS


 DENOTES FILL IN SURFACE WATER
 DENOTES TEMPORARY FILL IN SURFACE WATER




N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY
 NC 109 FROM NORTH
 OF I-85 BUSINESS TO
 NORTH OF SR 1756
 (LEXINGTON AVE.)
 NORTH OF LEDFORD M.S.
 STATE PROJECT#8J600901 R-2368B
 SHEET 27 OF 40

222
220
218
216
214
212
210

1- STA 61+31.50 LEFT LANE
2 @ 26.0m x 137.2mm P/S CONC. GIRDER BRIDGE
SKEW = 95°



1- STA 61+31.50 RIGHT LANE
2 @ 26.0m x 137.2mm P/S CONC. GIRDER BRIDGE
SKEW = 95°





N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY
NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT #8.1600901 R-2568B
SHEET 28 OF 40

12/2/02


SITE 8 PROFILE

±0.4200%



SCALE

212
210



MATCH SHEET

MATCH SHEET

DENOTES TEMPORARY
SURFACE WATER
IMPACTS



DENOTES EXCAVATION
IN WETLAND



N.C.D.O.T.

**DIVISION OF HIGHWAYS
DAVIDSON COUNTY**


NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.

STATE PROJECT #8.1600901 R-2568B
SHEET 29 OF 40


07/14/04

SITE 9

DENOTES FILL IN
SURFACE WATERS




DENOTES FILL
IN WETLANDS



10m 0 20m

SCALE





MATCH SHEET

MATCH SHEET

DENOTES TEMPORARY
SURFACE WATER
IMPACTS



DENOTES EXCAVATION
IN WETLAND




N.C.D.O.T. DIVISION OF HIGHWAYS DAVIDSON COUNTY

NC 109 FROM NORTH
OF I-85 BUSINESS TO
NORTH OF SR 1756
(LEXINGTON AVE.)
NORTH OF LEDFORD M.S.



STATE PROJECT#8.1600901 R-2568B
SHEET 30 OF 40 07/24/04

SITE 9 IMPACTS

DENOTES FILL IN
SURFACE WATERS




DENOTES FILL
IN WETLANDS




SCALE

RIFFLE SECTION
(NOT TO SCALE)




LOW FLOW CHANNEL IS TO BE SHIFTED WITHIN FLOODPRONE CHANNEL BY VARYING BERM WIDTHS SO THAT LOW FLOW CHANNEL WILL SHIFT TOWARDS THE OUTSIDE OF THE MEANDER. ADDITIONALLY, LOW FLOW CHANNEL SIDE SLOPES ARE TO BE VARIED AS SHOWN BELOW.

CHANNEL SECTION, IN BEND
(NOT TO SCALE)



CHANNEL TO BE GRADED TO MATCH 'RIFFLE SECTION' AND 'CHANNEL SECTION, IN BEND' THROUGHOUT, PROVIDING A SMOOTH TRANSITION BETWEEN EACH SECTION. EACH BEND SHOULD HAVE A POOL LOCATED ON THE OUTSIDE OF THE BEND.



NATURAL CHANNEL DESIGN DETAILS

STA 64+20 TO STA 64+80 -L- LT.

SITE 9

N. C. DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS


DAVIDSON COUNTY

PROJECT: 8.1600901 (R-2568B)

NC 109 FROM NORTH OF I-85
BUSINESS TO NORTH OF SR
1756 (LEXINGTON AVE.) NORTH
OF LEDFORD MIDDLE SCHOOL

SHEET 31 OF 40

12/12/02



N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY
 NC 109 FROM NORTH
 OF I-85 BUSINESS TO
 NORTH OF SR 1756
 (LEXINGTON AVE.)
 NORTH OF LEDFORD M.S.
 STATE PROJECT#8-1600901 R-2568B
 SHEET 33 OF 40

SITE 9 IMPACTS



10m 0 20m

SCALE

* * * *

DENOTES CLEARING
IN WETLANDS


DENOTES FILL
IN WETLANDS



PROJECT REFERENCE NO. R-2568B SHEET NO.

6/4/04

6/4/04




N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY
 NC 109 FROM NORTH
 OF I-85 BUSINESS TO
 NORTH OF SR 1756
 (LEXINGTON AVE.)
 NORTH OF LEDFORD M.S.

STATE PROJECT #8.1600901 R-2568B
 SHEET 34 OF 40
 07/14/04

10m 0 20m SITE 10 SCALE

DENOTES TEMPORARY SURFACE WATER IMPACTS

DENOTES FILL IN SURFACE WATERS



N.C.D.O.T.
DIVISION OF HIGHWAYS
DAVIDSON COUNTY
 NC 109 FROM NORTH
 OF I-85 BUSINESS TO
 NORTH OF SR 1756
 (LEXINGTON AVE.)
 NORTH OF LEDFORD M.S.

STATE PROJECT #8.1600901 R-2568B
 SHEET 35 OF 40 07/14/04

SCALE 10m 0 20m

SITE 10 IMPACTS

DENOTES TEMPORARY SURFACE WATER IMPACTS
 DENOTES FILL IN SURFACE WATERS

WETLAND PERMIT IMPACT SUMMARY

Site No.	Station (From/To)	Structure Size / Type	WETLAND IMPACTS				SURFACE WATER IMPACTS				Natural Stream Design (m)
			Fill In Wetlands (ha)	Temp. Fill In Wetlands (ha)	Excavation In Wetlands (ha)	Mechanized Clearing (Method III) (ha)	Fill In SW (Natural) (ha)	Fill In SW (Pond) (ha)	Temp. Fill In SW (ha)	Existing Channel Impacted (m)	
1	29+50-30+20 -L-	1200mm Pipe					0.0130			130	
2	33+55-33+80 -L-	1200mm Pipe	0.0071				0.0070			71	
2a***	37+20 -L-	no structure									
3	40+40-40+60 -L-	no structure	0.0110			0.0068					
3a	43+70-44+60 -L-	1650mm Pipe					0.0191			133	
4*	46+60-47+80 -L-	3.35 m X 2.44 m RCBC					0.0550			188	96
5	50+60-51+00 -L-	750mm Pipe	0.0585			0.0038					
6	10+60-11+00 -Y10-	600mm Pipe					0.0023			37	
6	55+60-56+00 -L-	750mm Pipe					0.0063			88	
7	56+70 -L-	600mm Pipe					0.0047			83	
8**	61+31-50 -L-	2@26mX1372mm P/S Conc. Girder Bridge					0.0198		0.0102	30	
9	64+00-66+60 -L-	1050mm Pipe	0.1754		0.0136	0.0276	0.0060			43	
10	75+50-76+50 -L-	900mm Pipe					0.0091			107	
TOTALS:			0.252	0	0.0136	0.038	0.142		0.010	910.5	96

NCDOT

DIVISION OF HIGHWAYS
DAVIDSON COUNTY
PROJECT 8.1600901 (R-2568B)
NC 109 FROM NORTH OF I-85
BUSINESS TO NORTH OF SR1756
(LEXINGTON AVE.) NORTH OF
LEDFORD MIDDLE SCHOOL
SHEET 36 OF 40

Sites 1, 2, 9, 10: Includes 3m of Temporary impacts for pipe installation for each site.
Sites 3a, 6 & 7: Includes 6m of Temporary impacts for pipe installation for each site.
* Site 4: Includes 25m of temporary impact for culvert/stream construction.
** Site 8: Channel impacts are temporary only. Permanent impacts at this site are associated with the fill of a natural scour hole adjacent to the stream channel.
*** Site 2a: Although no impacts will occur at this site, it has been included in the permit drawings to demonstrate avoidance.

WETLAND PERMIT IMPACT SUMMARY											
WETLAND IMPACTS				SURFACE WATER IMPACTS							
Site No.	Station (From/To)	Structure Size / Type	Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation In Wetlands (ac)	Mechanized Clearing (Method III) (ac)	Fill In SW (Natural) (ac)	Fill In SW (Pond) (ac)	Temp. Fill In SW (ac)	Existing Channel Impacted (ft)	Natural Stream Design (ft)
1	29+50-30+20 -L-	48" Pipe					0.03			427	
2	33+55-33+80 -L-	48" Pipe	0.02				0.02			233	
2a***	37+20 -L-	no structure									
3	40+40-40+60 -L-	no structure	0.03			0.02					
3a	43+70-44+60 -L-	66" Pipe					0.05			437	
4*	46+60-47+80 -L-	11' X 8' m RCBC					0.14			617	315
5	50+60-51+00 -L-	30" Pipe	0.14			0.01					
6	10+60-11+00 -Y10-	24" Pipe					0.01			121	
6	55+60-56+00 -L-	30" Pipe					0.02			289	
7	56+70 -L-	24" Pipe					0.01			273	
8**	61+31.50 -L-	2@85' X 54" P/S					0.05		0.030	98	
		Conc. Girder Bridge									
9	64+00-66+60 -L-	42" Pipe	0.43		0.03	0.07	0.01			141	
10	75+50-76+50 -L-	36" Pipe					0.02			351	
TOTALS:			0.62		0.03	0.100	0.36		0.03	2987	315

Sites 1, 2, 9, 10: Includes 10ft of Temporary impacts for pipe installation for each site.

Sites 3a, 6 & 7: Includes 20ft of Temporary impacts for pipe installation for each site.

* Site 4: Includes 82 feet of Temporary impact for culvert/stream construction.

** Site 8: Channel impacts are temporary only. Permanent impacts at this site are associated with the fill of a natural scour hole adjacent to the stream channel.

*** Site 2a: Although no impacts will occur at this site, it has been included in the permit drawings to demonstrate avoidance.

NCDOT

DIVISION OF HIGHWAYS
DAVIDSON COUNTY
PROJECT 8.1600901 (R-2568B)
NC 109 FROM NORTH OF I-85
BUSINESS TO NORTH OF SR1756
(LEXINGTON AVE.) NORTH OF
LEDFORD MIDDLE SCHOOL

SHEET 37 OF 40 7/14/04

Site No.	Property Owner Name	Property Owner Address
1	John J. and Catherine E. Seta Edwin Chandler Gable W.D. Talley and wife Kara Lee Talley Terry J. Elledge and wife Dianne E. Elledge	3620 Dunhurst Dr., Pfaftown, NC 27040 PO Box 5393, High Point, NC 27262-5393 257 Reese Road, High Point, NC 27265-9262 PO Box 1535, Welcome, NC 27374
2	Juanita S. Thomas and Wilma S. Brown Terry L. LaBonte and wife Kimberly J. LaBonte Samuel Gordon Myers and David Luther Myers Eddie A. Harmon	1224 Sunset Dr., Asheboro, NC 27203-5126 6810 Colonial Club Dr., Thomasville, NC 27360 514 Garner Towers Lane, Garner, NC 27529 7266 Midway Sch. Rd., Thomasville, NC 27360
2A	Johnny Vernon Gardner and wife, Betty Hinkle Gardner	7157 Midway Sch. Rd., Thomasville, NC 27360
3	Donald L. Saintsing and wife Frances L. Saintsing Lindy M. Leonard	7026 Midway Sch. Rd., Thomasville, NC 27360 6919 Midway Sch. Rd., Thomasville, NC 27360
3A	Loren S. Morris and wife Christine Green Morris	795 Echo Trail, Thomasville, NC 27360
4	Loren S. Morris and wife Christine Green Morris Sherrill Morris and wife Peggy Morris Roger Allen Douglas and wife Linda B. Douglas	795 Echo Trail, Thomasville, NC 27360 123 Von Logan Dr., Thomasville, NC 27360 200 Echo Trail, Thomasville, NC 27360

List of Property Owners

NC Dept. of Transportation
Division of Highways
Davidson County
Project:8.1600901 (R-2568B)

NC 109 From North of I-85 Business to North of
SR 1756 (Lexington Ave.) North of Ledford M.S

Site No.	Property Owner Name	Property Owner Address
5	Steven Douglas Coe Terry Bernard Ferrell	273 Reese Road, High Point, NC 27265-9262 2651 N NC Hwy 109, Thomasville, NC 27360-9804
6 & 7	Troy Lee Curry George C. Beusse Jr. and Derree C. Beusse Burley Logan Black and wife Kimberly Laws Black Kenneth Michael Darr and wife Tamara Ingram Darr	168 Troy's Haven, Thomasville, NC 27360-9804 140 Troy's Haven, Thomasville, NC 27360-9804 2887 N NC Hwy 109, Thomasville, NC 27360-9804 PO Box 7163, High Point, NC 27264
8	Charles W. Hiatt and wife Doris S. Hiatt Marvin G. Woempner and wife Peggy S. Woempner W. C. Bodenheimer	3490 N NC Hwy 109, Thomasville, NC 27360-9255 345 Lloyd Murphy Rd., Thomasville, NC 27360-9243 528 Glenn Drive, Thomasville, NC 27360-9247
9	Marvin G. Woempner and wife Peggy S. Woempner Charles W. Hiatt and wife Doris S. Hiatt Patricia Thomas Sartin Linda Gail H. Aderhold and husband Douglas F. Aderhold E.S. Welborn and wife Frances M. Welborn	345 Lloyd Murphy Rd., Thomasville, NC 27360 3490 N Hwy 109, Thomasville, NC 27360-9255 3475 N Hwy 109, Thomasville, NC 27360 3490 N Hwy 109, Thomasville, NC 27360 4890 W. Lexington Ave., High Point, NC 27265-9238
10	Davidson Co. Board of Education E.S. Welborn and wife Frances M. Welborn	3954 N Hwy 109, Thomasville, NC 27360 4890 W. Lexington Ave., High Point, NC 27265-9238

List of Property Owners

NC Dept. of Transportation
Division of Highways

Davidson County
Project: 8.1600901 (R-2568B)

NC 109 From North of I-85 Business to North of
SR 1756 (Lexington Ave.) North of Ledford M.S

Site No.	Property Owner Name	Property Owner Address
10	<p>Thomas Woodrow Branson</p> <p>George W. Brady and wife Marion K. Brady</p> <p>Terry L. Smith and wife Joni C. Smith</p> <p>J. C. Criddlebaugh Family Limited Partnership</p>	<p>7401 Old Greensboro Rd., Thomasville, NC</p> <p>4043 N Hwy 109, Thomasville, NC 27360</p> <p>4083 N Hwy 109, Thomasville, NC 27360</p> <p>3632 W. Lexington Ave. Extension. High Point, NC 27265</p>

List of Property Owners

NC Dept. of Transportation
Division of Highways


Davidson County
Project: 8.1600901 (R-2568B)

NC 109 From North of I-85 Business to North of
SR 1756 (Lexington Ave.) North of Ledford M.S

TIP PROJECT: R-2568B

CONTRACT: C201069

See Sheet 1-A For Index of Sheets
See Sheet 1-B For Conventional Symbols



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

DAVIDSON COUNTY


LOCATION: NC 109 FROM NORTH OF I-85 BUSINESS TO
NORTH OF SR 1756 (LEXINGTON AVE.) NORTH
OF LEDFORD MIDDLE SCHOOL

TYPE OF WORK: GRADING, DRAINAGE, PAVING, STRUCTURES, AND SIGNALS




ALL DIMENSIONS IN THESE
PLANS ARE IN METERS
AND/OR MILLIMETERS
UNLESS OTHERWISE SHOWN

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	R-2568B	1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
34468.1.3	STP-109(1)	P.E.	
34468.2.3	STP-109(5)	R/W & UTIL	



NOTE: THIS IS A PARTIAL CONTROLLED-ACCESS PROJECT WITH ACCESS BEING LIMITED TO POINTS AS SHOWN ON THE PLANS

GRAPHIC SCALES



DESIGN DATA

ADT 2004 = 8,500 - 12,500
ADT 2030 = 19,900 - 26,000
DHV = 10 %
D = 60 %
T = 11 % *
V = 100 km/h
* TTST 6% DUAL 5%

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT R-2568B = 5.571 km
LENGTH STRUCTURES TIP PROJECT R-2568B = 0.052 km
TOTAL LENGTH OF TIP PROJECT R-2568B = 5.623 km

Prepared In the Office of:
DIVISION OF HIGHWAYS

1000 Birch Ridge Dr.
Raleigh, NC 27610

2002 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
JUNE 26, 2002

LETTING DATE:
NOVEMBER 16, 2004

ROGER D. THOMAS, P.E.
PROJECT ENGINEER

MICHAEL W. LITTLE, P.E.
PROJECT DESIGN ENGINEER

HYDRAULICS ENGINEER


SIGNATURE: _____
ROADWAY DESIGN
ENGINEER
PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION
SIGNATURE: _____
APPROVED
DIVISION ADMINISTRATOR

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

STATE DESIGN ENGINEER
DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION

DATE

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS



PROJ. REFERENCE NO.
R-2568B

SHEET NO.
1 - B

*S.U.E = SUBSURFACE UTILITY ENGINEER

ROADS & RELATED ITEMS

Edge of Pavement	---
Curb	---
Prop. Slope Stakes Cut	---C---
Prop. Slope Stakes Fill	---F---
Prop. Woven Wire Fence	---○---
Prop. Chain Link Fence	---□---
Prop. Barbed Wire Fence	---◇---
Prop. Wheelchair Ramp	---WCP---
Curb Cut For Future Wheelchair Ramp	---CCFR---
Exist. Guardrail	---+---
Prop. Guardrail	---+---
Exist. Cable Guiderail	---+---
Prop. Cable Guiderail	---+---
Equality Symbol	⊕
Pavement Removal	▨

RIGHT OF WAY

Baseline Control Point	◆
Existing Right of Way Marker	△
Exist. Right of Way Line w/Marker	---△---
Prop. Right of Way Line with Proposed	---
R/W marker (Iron Pin & Cap)	▲
Prop. Right of Way Line with Proposed	---
(Concrete or Granite) R/W Marker	▲
Exist. Control of Access Line	---C---
Prop. Control of Access Line	---C---
Exist. Easement Line	---E---
Prop. Temp. Construction Easement Line	---E---
Prop. Temp. Drainage Easement Line	---TDE---
Prop. Perm. Drainage Easement Line	---PDE---

HYDROLOGY

Stream or Body of Water	---
River Basin Buffer	---BZ---
Flow Arrow	→
Disappearing Stream	---
Spring	○
Swamp Marsh	---
Shoreline	---
Falls, Rapids	---
Prop. Lateral, Tail, Head Ditches	---
Prop. Berm Ditches	---

STRUCTURES

MAJOR	
Bridge, Tunnel, or Box Culvert	---CONC---
Bridge Wing Wall, Head Wall	---
and End Wall	---CONC WW---

MINOR

Head & End Wall	---CONC HW---
Pipe Culvert	---=---
Footbridge	---X---
Drainage Boxes	---□CB---
Paved Ditch Gutter	---

UTILITIES

Exist. Pole	●
Exist. Power Pole	●
Prop. Power Pole	○
Exist. Telephone Pole	●
Prop. Telephone Pole	○
Exist. Joint Use Pole	●
Prop. Joint Use Pole	○
Telephone Pedestal	□
Cable TV Pedestal	□
Hydrant	◇
Satellite Dish	◇
Exist. Water Valve	⊗
Sewer Clean Out	⊕
Power Manhole	⊕
Telephone Booth	⊕
Water Manhole	⊕
Light Pole	⊕
H-Frame Pole	⊕
Power Line Tower	⊕
Pole with Base	⊕
Gas Valve	◇
Gas Meter	◇
Telephone Manhole	⊕
Power Transformer	⊕
Sanitary Sewer Manhole	⊕
Storm Sewer Manhole	⊕
Tank; Water, Gas, Oil	⊕
Water Tank With Legs	⊕
Traffic Signal Junction Box	⊕
Fiber Optic Splice Box	⊕
Television or Radio Tower	⊕
Utility Power Line Connects to Traffic	---
Signal Lines Cut Into the Pavement	---

Recorded Water Line	---W---
Designated Water Line (S.U.E.*)	---W---
Sanitary Sewer	---SS---
Recorded Sanitary Sewer Force Main	---FSS---
Designated Sanitary Sewer Force Main(S.U.E.*)	---FSS---
Recorded Gas Line	---G---
Designated Gas Line (S.U.E.*)	---G---
Storm Sewer	---S---
Recorded Power Line	---P---
Designated Power Line (S.U.E.*)	---P---
Recorded Telephone Cable	---T---
Designated Telephone Cable (S.U.E.*)	---T---
Recorded U/G Telephone Conduit	---TC---
Designated U/G Telephone Conduit (S.U.E.*)	---TC---
Unknown Utility (S.U.E.*)	---UTL---
Recorded Television Cable	---TV---
Designated Television Cable (S.U.E.*)	---TV---
Recorded Fiber Optics Cable	---FO---
Designated Fiber Optics Cable (S.U.E.*)	---FO---
Exist. Water Meter	⊕
U/G Test Hole (S.U.E.*)	⊕
Abandoned According to U/G Record	ATTUR
End of Information	E.O.I.

BOUNDARIES & PROPERTIES

State Line	---
County Line	---
Township Line	---
City Line	---
Reservation Line	---
Property Line	---
Property Line Symbol	PL
Exist. Iron Pin	⊕
Property Corner	⊕
Property Monument	⊕
Property Number	123
Parcel Number	6
Fence Line	---X---
Existing Wetland Boundaries	---WLB---
Proposed Wetland Boundaries	---WLB---
Existing Endangered Animal Boundaries	---EAB---
Existing Endangered Plant Boundaries	---EPB---

BUILDINGS & OTHER CULTURE

Buildings	---
Foundations	---
Area Outline	---
Gate	---
Gas Pump Vent or U/G Tank Cap	---
Church	---
School	---
Park	---
Cemetery	---
Dam	---
Sign	---
Well	---
Small Mine	---
Swimming Pool	---

TOPOGRAPHY

Loose Surface	---
Hard Surface	---
Change in Road Surface	---
Curb	---
Right of Way Symbol	R/W
Guard Post	⊕ GP
Paved Walk	---
Bridge	---
Box Culvert or Tunnel	---
Ferry	---
Culvert	---
Footbridge	---
Trail, Footpath	---
Light House	---

VEGETATION

Single Tree	---
Single Shrub	---
Hedge	---
Woods Line	---
Orchard	---
Vineyard	---



RAILROADS

Standard Gauge	---
RR Signal Milepost	---
Switch	---

15-JUN-2004 15:22
R:\proj\2568B\tsb
M:\file At RD203673


PAVEMENT SCHEDULE

C1	PROP. APPROX. 40 mm ASPHALT CONC. SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 96 kg PER SQ. METER	J1	PROP. 150 mm AGGREGATE BASE COURSE.
C2	PROP. APPROX. 80 mm ASPHALT CONC. SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 96 kg PER SQ. METER IN EACH OF TWO LAYERS.	J2	PROP. 200 mm AGGREGATE BASE COURSE.
C3	PROP. VAR. DEPTH ASPHALT CONC. SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 2.40 kg PER SQ. METER PER 1 mm DEPTH, TO BE PLACED IN LAYERS NOT TO EXCEED 40 mm IN DEPTH.	K	BASE TO BE TREATED WITH LIME TO A DEPTH OF 200 mm, AT A RATE OF 11 kg PER SQ. METER AS DIRECTED BY THE ENGINEER. OR BASE TO BE TREATED WITH AGGREGATE AT A RATE OF 135 kg PER SQ. METER AND CEMENT AT A RATE OF 30 kg PER SQ. METER TO A DEPTH OF 180 mm AS DIRECTED BY THE ENGINEER.
C4	PROP. APPROX. 80 mm ASPHALT CONC. SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 96 kg PER SQ. METER IN EACH OF TWO LAYERS.		
C5	PROP. VAR. DEPTH ASPHALT CONC. SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 2.40 kg PER SQ. METER PER 1 mm DEPTH, TO BE PLACED IN LAYERS NOT TO EXCEED 40 mm IN DEPTH.	P1	PRIME COAT AT THE RATE OF 1.58 L PER SQ. METER.
D1	PROP. APPROX. 65 mm ASPHALT CONC. INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 159 kg PER SQ. METER.	R1	750 mm CONCRETE CURB AND GUTTER.
D2	PROP. VAR. DEPTH ASPHALT CONC. INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 2.45 kg PER SQ. METER PER 1 mm DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 55 mm OR GREATER THAN 110 mm IN DEPTH.	R2	SHOULDER BERM GUTTER.
D3	PROP. APPROX. 80 mm ASPHALT CONC. INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 196 kg PER SQ. METER.	T	EARTH MATERIAL.
D4	PROP. VAR. DEPTH ASPHALT CONC. INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 2.45 kg PER SQ. METER PER 1 mm DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 55 mm OR GREATER THAN 110 mm IN DEPTH.	U	EXISTING PAVEMENT.
E1	PROP. APPROX. 100 mm ASPHALT CONC. BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 245 kg PER SQ. METER.	W	VARIABLE DEPTH ASPHALT PAVEMENT. (SEE STANDARD WEDGING DETAIL THIS SHEET)
E2	PROP. APPROX. 120 mm ASPHALT CONC. BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE 294 kg PER SQ. METER.	NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.	
E3	PROP. VAR. DEPTH ASPHALT CONC. BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 2.45 kg PER SQ. METER PER 1 mm DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 75 mm IN DEPTH OR GREATER THAN 140 mm IN DEPTH.		
E4	PROP. APPROX. 90 mm ASPHALT CONC. BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE 221 kg PER SQ. METER.		
E5	PROP. VAR. DEPTH ASPHALT CONC. BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 2.45 kg PER SQ. METER PER 1 mm DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 75 mm IN DEPTH OR GREATER THAN 140 mm IN DEPTH.		



PROJECT REFERENCE NO. R-2568B		SHEET NO. 2
ROADWAY DESIGN ENGINEER		PAVEMENT DESIGN ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION		


PAVEMENT SCHEDULE	
C4	80 mm S9.5C
D3	80 mm I19.0C
E4	90 mm B25.0C
K	200 mm LIME OR 180 mm AGGREGATE
R1	750 mm CONC. C&G
T	EARTH



TYPICAL SECTION NO. 1

USE TYPICAL SECTION NO. 1


- L- STA. 23+20.000 TO -L- STA. 24+77.475 LB = -RTLN1- STA. 24+77.475 LA
- L- STA. 23+20.000 TO -L- STA. 24+99.126 LB = -LTLN1- STA. 24+99.126 LA
- TRANSITION FROM T.S. NO. 1 TO T.S. NO. 2
- * -RTLN1- STA. 24+77.475 LA TO -RTLN1- STA. 28+02.508 LB = -L- STA. 28+03.591 LA
- * -LTLN1- STA. 24+99.126 LA TO -LTLN1- STA. 28+25.243 LB = -L- STA. 28+24.158 LA



TYPICAL SECTION NO. 2

USE TYPICAL SECTION NO. 2

- L- STA. 28+03.591 RT. TO -L- STA. 61+04.890 RT.
- L- STA. 28+24.158 LT. TO -L- STA. 61+06.110 LT.
- L- STA. 61+56.890 RT. TO -L- STA. 75+40.000 LB = -RTLN2- STA. 75+40.000 LA
- L- STA. 61+58.110 LT. TO -L- STA. 75+40.000 LB = -LTLN2- STA. 75+40.000 LA
- TRANSITION FROM T.S. NO. 2 TO EXISTING
- * -RTLN2- STA. 75+40.000 LA TO -RTLN2- STA. 79+43.024
- * -LTLN2- STA. 75+40.000 LA TO -LTLN2- STA. 79+34.562



INSET NO. 1

USE INSET NO. 1 AT THE FOLLOWING LOCATIONS:


- L- STA. 29+00.000 (LT.) TO -L- STA. 29+47.700 (LT.)
- L- STA. 29+25.310 (RT.) TO -L- STA. 29+58.669 (RT.)
- L- STA. 29+99.925 (LT.) TO -L- STA. 30+28.575 (LT.)
- L- STA. 29+99.987 (RT.) TO -L- STA. 30+80.485 (RT.)
- L- STA. 33+09.719 (RT.) TO -L- STA. 34+40.075 (RT.)
- L- STA. 33+19.915 (LT.) TO -L- STA. 34+15.449 (LT.)
- L- STA. 36+67.496 (RT.) TO -L- STA. 37+40.205 (RT.)
- L- STA. 39+76.960 (RT.) TO -L- STA. 40+62.760 (RT.)
- L- STA. 41+19.925 (LT.) TO -L- STA. 44+67.524 (LT.)
- L- STA. 43+93.705 (RT.) TO -L- STA. 44+68.075 (RT.)
- L- STA. 45+67.740 (RT.) TO -L- STA. 46+82.115 (RT.)
- L- STA. 46+88.495 (LT.) TO -L- STA. 48+73.275 (LT.)
- L- STA. 48+00.000 (RT.) TO -L- STA. 49+61.543 (RT.)
- L- STA. 49+87.4548 (LT.) TO -L- STA. 51+49.697 (LT.)
- L- STA. 50+57.940 (RT.) TO -L- STA. 51+61.990 (RT.)
- L- STA. 53+59.330 (LT.) TO -L- STA. 54+04.761 (LT.)
- L- STA. 54+39.925 (LT.) TO -L- STA. 55+47.257 (LT.)
- L- STA. 55+00.541 (RT.) TO -L- STA. 55+60.985 (RT.)
- L- STA. 55+92.743 (LT.) TO -L- STA. 57+31.452 (LT.)
- L- STA. 64+39.925 (LT.) TO -L- STA. 65+43.068 (LT.)
- L- STA. 64+97.740 (RT.) TO -L- STA. 67+00.000 (RT.)
- L- STA. 70+47.647 (RT.) TO -L- STA. 70+88.391 (RT.)
- L- STA. 70+79.945 (LT.) TO -L- STA. 71+62.518 (LT.)
- L- STA. 71+30.018 (RT.) TO -L- STA. 72+24.398 (RT.)
- L- STA. 74+56.885 (RT.) TO -L- STA. 74+78.859 (RT.)
- L- STA. 75+20.933 (RT.) TO -L- STA. 75+40.000 LB = -RTLN2- STA. 75+40.000 LA TO -RTLN2- STA. 76+00.480 (RT.)
- L- STA. 75+22.085 (LT.) TO -L- STA. 75+40.000 LB = -LTLN2- STA. 75+40.000 LA TO -LTLN2- STA. 77+15.396 (LT.)

** See Plans For Shoulder Berm Gutter Locations, use Standard 820.04


PAVEMENT SCHEDULE	
C2	80 mm S9.5B
D1	65 mm I19.0B
E1	100 mm B25.0B
E2	120 mm B25.0B
T	EARTH
U	EXISTING PAVEMENT
W	WEDGING




PROJECT REFERENCE NO.	SHEET NO.
R-2568B	2-B
ROADWAY DESIGN ENGINEER	



USE TYPICAL SECTION NO. 3
 -Y- STA. 10+31.000 TO -Y- STA. 12+12.000 (E2)
 * -Y14A- STA. 10+03.200 TO -Y14A- STA. 11+23.726 (E1)
 TRANSITION FROM T.S. NO. 3 TO EXISTING
 -Y- STA. 12+12.000 TO -Y- STA. 13+20.000



USE TYPICAL SECTION NO. 4
 -Y1- STA. 10+13.600 TO -Y1- STA. 10+66.500 (E2)
 -Y10- STA. 10+32.000 TO -Y10- STA. 11+28.000 (E1)
 -Y10A- STA. 10+13.300 TO -Y10A- STA. 10+50.000 (E1)
 TRANSITION FROM T.S. NO. 4 TO EXISTING
 -Y1- STA. 10+66.500 TO -Y1- STA. 11+60.000
 -Y10- STA. 11+28.000 TO -Y10- STA. 12+00.000
 -Y10A- STA. 10+50.000 TO -Y10A- STA. 11+20.000




USE TYPICAL SECTION NO. 5
 -Y9- STA. 11+40.000 TO -Y9- STA. 11+84.000
 -Y9- STA. 12+90.000 TO -Y9- STA. 13+20.000
 TRANSITION FROM EXISTING TO T.S. NO. 5
 -Y9- STA. 11+20.000 TO -Y9- STA. 11+40.000
 TRANSITION FROM T.S. NO. 5 TO EXISTING
 -Y9- STA. 13+20.000 TO -Y9- STA. 13+40.000

15-JUN-2004 07:02
 PLittle AT 108837-2568B.dwg

PAVEMENT SCHEDULE	
C2	80 mm S9.5B
D1	65 mm I19.0B
E1	100 mm B25.0B
T	EARTH
U	EXISTING PAVEMENT
W	WEDGING




PROJECT REFERENCE NO.	R-2568B	SHEET NO.	2-C
ROADWAY DESIGN ENGINEER			
SEAL			



TYPICAL SECTION NO. 6

USE TYPICAL SECTION NO. 6


- Y11- STA. 10+60.000 TO -Y11- STA. 12+93.000
- * -Y12- STA. 10+23.000 TO -Y12- STA. 11+40.000
- TRANSITION FROM EXISTING TO T.S. NO. 6
- Y11- STA. 10+00.000 TO -Y11- STA. 10+60.000
- TRANSITION FROM T.S. NO. 6 TO EXISTING
- * -Y12- STA. 11+20.000 TO -Y12- STA. 11+40.000



TYPICAL SECTION NO. 6A

USE TYPICAL SECTION NO. 6A


- Y11- STA. 10+20.000 LT. TO -Y11- STA. 10+79.500 LT.
- Y12- STA. 11+40.000 LT. TO -Y12- STA. 12+15.000 LT.



TYPICAL SECTION NO. 7

USE TYPICAL SECTION NO. 7


- Y13- STA. 10+80.000 TO -Y13- STA. 10+87.000
- TRANSITION FROM EXISTING TO T.S. NO. 7
- Y13- STA. 10+60.000 TO -Y13- STA. 10+80.000



TYPICAL SECTION NO. 8

USE TYPICAL SECTION NO. 8

- Y14- STA. 10+33.000 TO -Y14- STA. 10+81.800

	PROJECT REFERENCE NO.	SHEET NO.
	R-2568B	2-D
ROADWAY DESIGN ENGINEER		




Diagram illustrating a typical cross-section of a drainage structure (Typical Section No. 10). The structure is shown in plan view, with dimensions and labels indicating its geometry and components.

Dimensions:

- Overall width: 6.0 m (2.7 m + 0.6 m + 2.7 m + 0.6 m).
- Overall height: 1.0 m.
- Side wall thickness: 0.6 m.
- Central wall thickness: 0.08 m.
- Bottom thickness: 0.08 m.
- Top width: 2.7 m (left of center) and 2.7 m (right of center).
- Bottom width: 0.6 m (left of center) and 0.6 m (right of center).

Labels and Features:

- ℄ - DRI-**: Label at the top center of the structure.
- GRADE TO THIS LINE**: Label at the bottom center of the structure.
- EXIST GROUND**: Label on the left and right sides of the structure.
- 2:1**: Slope indicator on the left and right sides of the structure.
- 140 mm**: Dimension indicating the height of the structure above the ground level.
- T**: Label at the bottom left and bottom right corners of the structure.
- E1**: Label at the bottom center of the structure.
- C1**: Label at the top center of the structure.

TYPICAL SECTION NO. 10

0.6 m

VARIES
SEE PLANS

0.6 m

1.0 m

0.08

0.00

0.15 m

VAR.

0.15 m

0.08

2:1

3:1

EXIST GROUND

EXIST GROUND

GRADE TO THIS LINE

SEE T.S. USAGE


TYPICAL SECTION NO. 11

USE TYPICAL SECTION NO. 10
ALL DRIVES 7% AND UNDER (J1)
ALL DRIVES OVER 7% (J2)







PROJECT REFERENCE NO.		SHEET NO.
R-2568B		2-F
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION		




-L- STA.23+60 TO -L- STA.23+70 (LT.)




-RTLNI- STA.25+40 TO -RTLNI- STA.25+80 (RT.)




-L- STA.28+60 TO -L- STA.28+77 (LT.)
-L- STA.65+35 (LT.)




-L- STA.29+40 TO -L- STA.29+60 (RT.) Reverse Detail
-L- STA.41+20 TO -L- STA.41+60 (LT.)
-L- STA.75+20 TO -RTLNI- STA.76+00 (LT.)




-Y- STA.10+40 TO -Y- STA.10+60 (RT.)
-L- STA.34+00 TO -L- STA.34+40 (RT.)
-L- STA.55+65 TO -L- STA.55+80 (RT.)




-L- STA.30+00 TO -L- STA.30+20 (RT.) Reverse Detail
-L- STA.53+60 TO -L- STA.54+00 (LT.)
-L- STA.75+20 TO -L- STA.75+40 (RT.) Reverse Detail
-RTLNI- STA.76+20 TO -RTLNI- STA.76+40 (LT.)




-L- STA.30+20 TO -L- STA.30+60 (RT.) Reverse Detail
-L- STA.40+20 TO -L- STA.40+40 (RT.) Reverse Detail
-L- STA.48+40 TO -L- STA.48+80 (LT.)




-L- STA.30+00 TO -L- STA.30+20 (LT.)
* -L- STA.39+60 TO -L- STA.40+20 (RT.) Reverse Detail (2:1 Slope)
-L- STA.44+00 TO -L- STA.44+60 (RT.) Reverse Detail




-L- STA.33+40 TO -L- STA.34+00 (RT.)
-L- STA.33+80 TO -L- STA.34+20 (LT.)
-L- STA.41+60 TO -L- STA.42+00 (LT.)
-L- STA.43+70 TO -L- STA.44+40 (LT.)
-L- STA.48+90 TO -L- STA.49+15 (RT.)
-L- STA.50+60 TO -L- STA.51+60 (RT.)
-L- STA.56+80 TO -L- STA.57+20 (RT.)
-L- STA.65+00 TO -L- STA.65+60 (RT.)
-L- STA.66+00 TO -L- STA.66+40 (RT.)




-L- STA.36+80 TO -L- STA.37+10 (RT.)
-L- STA.60+27 TO -L- STA.60+40 (RT.)




-L- STA.39+00 TO -L- STA.40+00 (LT.)
-L- STA.61+60 TO -L- STA.63+00 (LT.)




-L- STA.43+80 TO -L- STA.44+00 (RT.) Reverse Detail
-L- STA.55+80 TO -L- STA.56+80 (RT.) Reverse Detail
-L- STA.60+20 TO -L- STA.60+40 (LT.)
-L- STA.67+40 TO -L- STA.67+80 (RT.) Reverse Detail
-L- STA.71+25 TO -L- STA.71+80 (RT.) Reverse Detail
-RTLNI- STA.75+40 TO -RTLNI- STA.76+00 (RT.) Reverse Detail




-L- STA.46+20 (LT.)
-RTLNI- STA.78+22 TO -RTLNI- STA.78+30 (RT.)




-L- STA.46+20 TO -L- STA.46+70 (LT.)




-L- STA.46+80 TO -L- STA.47+40 (RT.)
-YI2- STA.10+28 TO -YI2- STA.10+60 (RT.)




-L- STA.37+00 TO -L- STA.37+20 (LT.)
-L- STA.47+40 TO -L- STA.47+80 (RT.) Reverse Detail




-L- STA.50+60 TO -L- STA.51+40 (LT.)




-YI0- STA.10+60 TO -YI0- STA.10+80 (RT.)
-L- STA.74+60 TO -L- STA.74+80 (LT.)
-YII- STA.12+85 TO -YII- STA.12+95 (LT. & RT.)




-YI0- STA.10+80 TO -YI0- STA.10+90 (RT.)




-L- STA.60+40 TO -L- STA.61+10 (LT.)
-L- STA.60+40 TO -L- STA.61+10 (RT.) Reverse Detail




-L- STA.71+80 TO -L- STA.72+20 (RT.)
-L- STA.73+80 TO -L- STA.74+80 (RT.)



-L- STA.36+80 TO -L- STA.37+00 (LT.)
-L- STA.51+60 TO -L- STA.52+40 (RT.) Reverse Detail
-RTLNI- STA.78+40 TO -RTLNI- STA.79+00 (RT.) Reverse Detail
-Y- STA.12+20 TO -Y- STA.12+60 (LT.)



SEE PLANS (SHEET 15)



-L- STA.65+00 TO -L- STA.65+20 (LT.)

-L-	-LTLNI-	-RTLNI-
Pis Sta. 25+59.134	Pis Sta. 25+80.786	Pis Sta. 25+37.483
Gs = 2' 56' 47.9"	Gs = 2' 56' 47.9"	Gs = 2' 56' 47.9"
Ls = 90.000	Ls = 90.000	Ls = 90.000
LT = 60.008	LT = 60.008	LT = 60.008
ST = 30.008	ST = 30.008	ST = 30.008

PROJECT REFERENCE NO. R-2568B

R/W SHEET NO. 4

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER

PRELIMINARY PLANS

DO NOT USE FOR CONSTRUCTION

CONST. REV.

R/W REV.

BEGIN PROJECT R-2568B
-L- STA. 23+20.000

DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCGS FOR MONUMENT "WALLBURG RM 2" WITH NAD 83 STATE PLANE GRID COORDINATES OF NORTHING: 251,275.090(m) EASTING: 506,740.831(m)

THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.999919380

THE N.C. LAMBERT GRID BEARING LOCALIZED HORIZONTAL GROUND DISTANCE FROM "WALLBURG RM 2" TO -L- STATION 23+20.000 IS S 18° 26' 14.85" E 12,112.371 m

ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES

VERTICAL DATUM USED IS NGVD 29

NOTES: (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 (2) SEE SHEET 26 FOR -L-, -LTLNI- & -RTLNI- PROFILES

REVISIONS

MATCH TO SHEET NO. 5

-L- STA 25+60

50 10

CONST. REV.

R/W REV.

PROJECT REFERENCE NO.

R-2568B

R/W SHEET NO.


5

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER

PRELIMINARY PLANS

DO NOT USE FOR CONSTRUCTION



-LTLNI-		
Pis Sta. 25+80.786	PI Sta. 26+73.115	Pis Sta. 27+65.250
Os = 2° 56' 47.9"	Δ = 8° 09' 00.4" (RT.)	Os = 2° 56' 47.9"
Ls = 90.000	L = 124.465	Ls = 90.000
LT = 60.008	T = 62.338	LT = 60.008
ST = 30.008	R = 875.000	ST = 30.008
	S.E. = 0.05	

-L-		
Pis Sta. 25+59.134	PI Sta. 26+51.464	Pis Sta. 27+43.599
Os = 2° 56' 47.9"	Δ = 8° 09' 00.4" (RT.)	Os = 2° 56' 47.9"
Ls = 90.000	L = 124.465	Ls = 90.000
LT = 60.008	T = 62.338	LT = 60.008
ST = 30.008	R = 875.000	ST = 30.008



-RTLNI-		
Pis Sta. 25+37.483	PI Sta. 26+29.813	Pis Sta. 27+21.948
Os = 2° 56' 47.9"	Δ = 8° 09' 00.4" (RT.)	Os = 2° 56' 47.9"
Ls = 90.000	L = 124.465	Ls = 90.000
LT = 60.008	T = 62.338	LT = 60.008
ST = 30.008	R = 875.000	ST = 30.008
	S.E. = 0.05	

-YI-	
PI Sta. 12+57.246	Δ = 0° 13' 55.0" (RT.)
L = 176.227	T = 88.114
R = 43,534.314	

- NOTES:
- (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 - (2) SEE SHEET 27 FOR -LTLNI- & -RTLNI- PROFILES
 - (3) SEE SHEET 28 FOR -L- PROFILE

REVISIONS


5-JUN-2004 01:03
R. J. L. 1000000000




PROJECT REFERENCE NO.	SHEET NO.
R-2568B	6
R/W SHEET NO.	6
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS	
DO NOT USE FOR CONSTRUCTION	

-L-
PI Sta. 32+73.213
 $\Delta = 5^\circ 45' 24.5''$ (LT.)
 $L = 351.60$
 $T = 175.728$
 $R = 3,495.000$
 $S.E. = RC$
RUNOFF = 54


NAD 83



- NOTES:
- (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 - (2) SEE SHEET 28 FOR -L- PROFILE
 - (3) SEE SHEET 38 FOR -Y- PROFILE



NOTES:
(1) SEE SHEET 2-E FOR DRAINAGE DETAILS
(2) SEE SHEET 29 FOR -L- PROFILE





5 0 10

CONST. REV.

R/W REV.

PROJECT REFERENCE NO.	R-25688	SHEET NO.	8
R/W SHEET NO.	8		
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS			
DO NOT USE FOR CONSTRUCTION			



- NOTES:
- (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 - (2) SEE SHEET 29 FOR -L- PROFILE
 - (3) SEE SHEET 40 FOR -Y9- PROFILE




-Y9-	-Y9-	-Y9-
PI Sta. 10+74.355	PI Sta. 12+02.573	PI Sta. 14+14.824
$\Delta = 3' 15" 01.4' (RT.)$	$\Delta = 16' 56" 45.4' (LT.)$	$\Delta = 3' 34' 47.1' (RT.)$
L = 27.346	L = 68.321	L = 106.151
T = 13.677	T = 34.412	T = 53.093
R = 482.044	R = 231.000	R = 1,699.000
S.E. = 0.03	S.E. = 0.03	S.E. = 0.03
INCREMENT = 6	INCREMENT = 6	INCREMENT = 6

REVISIONS


MATCH TO SHEET NO. 7

MATCH TO SHEET NO. 9

PROJECT REFERENCE NO.		SHEET NO.	
R-2568B		9	
R/W SHEET NO.		9	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
PRELIMINARY PLANS			
DO NOT USE FOR CONSTRUCTION			
CONST. REV.			
R/W REV.			



NOTES:
 (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 (2) SEE SHEET 30 FOR -L- PROFILE




5 0 10

CONST. REV.

R/W REV.



PROJECT REFERENCE NO.	SHEET NO.
R-2568B	10
R/W SHEET NO.	10
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS	
DO NOT USE FOR CONSTRUCTION	



NOTES:
 (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 (2) SEE SHEET 30 FOR -L- PROFILE

REVISIONS

8-18-2004 01:07
 8-18-2004 01:07
 8-18-2004 01:07



NOTES: (1) SEE SHEETS 2-E & 2-F FOR DRAINAGE DETAILS
(2) SEE SHEET 31 FOR -L- PROFILE

~~NAD - 83~~



54°02'20"E
105.442 (TOTAL)
ROY H. FREEMAN
AND WIFE,
LILLIE LIVINGWOOD
FREEMAN
DB 423 PG 15
N47°52'25"W
105.524 (TOTAL)

TERRY BERNARD FERRELL
DB 781PG 85

DAVID AND MARGARET RIDDLE


-ROGER ALLEN DOUGLAS
AND WIFE,
LINDA B. DOUGLAS
DB 987 PG 1057

-1- STA 48+50


MATCH TO SHEET NO. 13

REVISIONS
R/W REVISION : PARCEL 31A - DRIVEWAY & 20 m ACCESS ADDED - 05-13-04 MWL

5-JUN-2004 07:07
 24 JUN 2004 12:08
 24 JUN 2004 12:08



PROJECT REFERENCE NO.		SHEET NO.	
R-2568B		13	
R/W SHEET NO.		13	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
<div style="border: 1px solid black; padding: 5px; text-align: center;"> PRELIMINARY PLANS <small>DO NOT USE FOR CONSTRUCTION</small> </div>			




NOTES: (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
(2) SEE SHEET 32 FOR -L- PROFILE
(3) SEE SHEET 41 FOR -Y10- & -Y10A- PROFILES

VICTOR RAY MURPHY AND WIFE,-
KATHLEEN J. MURPHY
DB 679 PG 807


REVISIONS

MATCH TO SHEET NO. 14

5-JUN-2004 07:07
4 pr 91-2568013-847
11410 AI R0289673



NOTES: (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
(2) SEE SHEET 32 FOR -L- PROFILE
(3) SEE SHEET 41 FOR -Y10A- PROFILE



-L-
 PI Sta. 59+17.76
 $\Delta = 7' 25'' 17.7''$ (RT.)
 $L = 226.680$
 $T = 113.499$
 $R = 1750.000$
 $S.E. = 0.03$
 RUNOFF = 54

-L-
 PIs Sta. 62+52.675
 $\Theta_s = 2' 58'' 47.9''$
 $L_s = 90.000$
 $LT = 60.008$
 $ST = 30.008$

PROJECT REFERENCE NO.
R-2568B

R/W SHEET NO.
15

ROADWAY DESIGN ENGINEER

SHEET NO.
15

HYDRAULICS ENGINEER


PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

CONST. REV.

R/W REV.

MATCH TO SHEET NO. 14

MATCH TO SHEET NO. 16



- NOTES:
- (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 - (2) SEE SHEET 33 FOR -L- PROFILE
 - (3) SEE SHEET 44 FOR -DRI- PROFILE
 - (4) SEE SHEETS S-1 TO S- FOR STRUCTURE DETAILS

50

0

10

CONST. REV.

R/W REV.

PROJECT REFERENCE NO.

R-2568B

R/W SHEET NO.


16

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER

PRELIMINARY PLANS

DO NOT USE FOR CONSTRUCTION



-DRI-
 PI Sta 10+32.300
 $\Delta = 90^\circ 19' 38.0''$ (LT.)
 L = 315.30
 T = 20.115
 R = 20.000

-L- PIs Sta. 62+52.675 Es = 256' 47.9" Ls = 90.000 LT = 60.008 ST = 30.008	-L- PI Sta. 62+94.337 $\Delta = 1^\circ 31' 41.9''$ (LT.) L = 23.340 T = 11.671 R = 875.000 S.E. = 0.05	PIs Sta. 63+36.014 Es = 256' 47.9" Ls = 90.000 LT = 60.008 ST = 30.008
---	---	--

NOTES:
 (1) SEE SHEETS 2-E & 2-F FOR DRAINAGE DETAILS
 (2) SEE SHEET 33 FOR -L- PROFILE
 (3) SEE SHEET 44 FOR -DRI- PROFILE

REVISIONS

MATCH TO SHEET NO. 15


MATCH TO SHEET NO. 17

50 10


CONST. REV.

R/W REV.

PROJECT REFERENCE NO.	SHEET NO.
R-2568B	17
R/W SHEET NO.	17
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS	
DO NOT USE FOR CONSTRUCTION	



NOTES:
 (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 (2) SEE SHEET 34 FOR -L- PROFILE



PROJECT REFERENCE NO.

R-2568B

SHEET NO.

19

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER

PRELIMINARY PLANS

DO NOT USE FOR CONSTRUCTION

CONST. REV.

R/W REV.

-L-

PI Sta. 71+65.41

$\Delta = 6' 01'' 13.8''$ (RT.)

L = 183.885

T = 92.027

R = 1750.000

S.E. = 0.03

RUNOFF = 54

-YII-

PI Sta. 12+44.647

$\Delta = 25' 14'' 31.1''$ (RT.)

L = 70.489

T = 35.826

R = 160.000

S.E. = 0.06

RUNOFF = 42

-LTLN2-

PI Sta. 76+26.904

$\Delta = 5' 41'' 09.2''$ (RT.)


L = 173.666

T = 86.904

R = 1750.000


S.E. = 0.03

RUNOFF = 54



MATCH TO SHEET NO. 18

MATCH TO SHEET NO. 20



DAVIDSON COUNTY BD. OF ED.

DB 286 PG 80
DB 286 PG 97
DB 83 PG 115
DB 94 PG 541

NOTES:
(1) SEE SHEET 2-E FOR DRAINAGE DETAILS
(2) SEE SHEET 35 FOR -L-, -LTLN2- & -RTLN2- PROFILES
(3) SEE SHEET 42 FOR -YII- & -YI2- PROFILES
(4) SEE SHEET 25 FOR -YI2DET-

MATCH TO SHEET NO. 24

PROJECT REFERENCE NO.

R-2568B

SHEET NO.

20

R/W SHEET NO.

20

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER

PRELIMINARY PLANS


DO NOT USE FOR CONSTRUCTION

CONST. REV.

R/W REV.

-LTLN2-
 PI Sta. 76+26.904
 $\Delta = 5^\circ 41' 09.2''$ (RT.)
 $L = 173.666$
 $R = 86.904$
 $R = 1750.000$
 $S.E. = 0.03$
 RUNOFF = 54

PI Sta. 78+60.159
 $\Delta = 4^\circ 52' 29.8''$ (LT.)
 $L = 148.897$
 $R = 74.493$
 $R = 1750.000$
 $S.E. = 0.03$
 RUNOFF = 54




-RTLN2-
 PI Sta. 77+23.240
 $\Delta = 0^\circ 48' 39.4''$ (RT.)
 $L = 98.934$
 $R = 49.468$
 $R = 6.990.000$

NOTES:
 (1) SEE SHEET 2-E FOR DRAINAGE DETAILS
 (2) SEE SHEET 36 FOR -LTLN2- & -RTLN2- PROFILES


REVISIONS

MATCH TO SHEET NO. 19

MATCH TO SHEET NO. 21



PROJECT REFERENCE NO.	SHEET NO.
R-2568B	21
R/W SHEET NO.	21
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
CONST. REV.	
R/W REV.	



-LTL N2-
PI Sta. 78+60.159
 $\Delta = 4^\circ 52' 29.8''$ (LT.)
L = 148.897
T = 74.493
R = 1750.000
SE = 0.03
RUNOFF = 54

END PROJECT R-2568B
-RTL N2- STA. 79 + 43.042


RICHARD D. CALLICUTT
AND WIFE,
BARBARA F. CALLICUTT
DB 517 PG 750

NOTE: SEE SHEET 37 FOR -LTL N2- & -RTL N2- PROFILES

REVISIONS




PROJECT REFERENCE NO.	SHEET NO.
R-2568B	22
R/W SHEET NO.	22
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
<div style="border: 1px solid black; padding: 5px; text-align: center;"> PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION </div>	



NOTES: (1) SEE SHEET 38 FOR -Y- PROFILE
(2) SEE SHEET 39 FOR -YI- PROFILE


8/17/99

-Y12-
 PI Sta. 11+36.157
 $\Delta = 13^\circ 48' 7" (RT.)$
 $L = 62.513$
 $T = 31.258$
 $R = 2911.508$
 S.E. = NC
 PI Sta. 12+28.334
 $\Delta = 8^\circ 05' 58.2" (RT.)$
 $L = 121.641$
 $T = 60.922$
 $R = 860.484$




CONST. REV.
 R/W REV.

PROJECT REFERENCE NO.	SHEET NO.
R-2568B	24
R/W SHEET NO.	24
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS	
DO NOT USE FOR CONSTRUCTION	



NOTES: (1) SEE SHEET 42 FOR -Y12- PROFILE
 (2) SEE SHEET 25 FOR -Y12DET-



CONST. REV.
R/W REV.

PROJECT REFERENCE NO.	SHEET NO.
R-2568B	25
R/W SHEET NO.	
25	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS	
DO NOT USE FOR CONSTRUCTION	

-Y12- DETOUR

-Y12DET-
PI Sta. 10+60.000
 $\Delta = 10^\circ 21' 14.5''$ (RT)
L = 43.371
T = 21.745
R = 240.000
S.E. = 0.06
R.O. = 30

-L- POT Sta. 75+30.000 =
-Y12DET- POT Sta. 10+00.000

J.C. CRIDLEBAUGH FAMILY
LIMITED PARTNERSHIP

-Y12- POC Sta. 12+40.000 =
-Y12DET- POT Sta. 12+53.560

ROBERT CALICUTT

-Y12- POC Sta. 12+02.525 (EX. LT. EOP) =
-Y12DET- POT Sta. 12+15.832

-L- POT Sta. 75+00.472 =
-Y11- POT Sta. 13+28.310 =
-Y12- POT Sta. 9+89.851

DAVIDSON COUNTY
BOARD OF EDUCATION
DB 286 PG 80
DB 286 PG 97
DB 113 PG 115
DB 94 PG 541

-Y12-
PI Sta. 11+36.157
 $\Delta = 1^\circ 13' 48.7''$ (RT)
L = 62.513
T = 31.258
R = 2,911.508
S.E. = NC

PI Sta. 12+28.334
 $\Delta = 8^\circ 05' 58.2''$ (RT)
L = 121.641
T = 60.922
R = 860.484


NOTE:
SEE SHEET 43 FOR -Y12DET- PROFILE

-LT LNI-

$-L-$

-RT LNI-


FOR -L-, -LTLNI- & -RTLNI- PLAN VIEW
SEE SHEET 4





PROJECT REFERENCE NO.		SHEET NO.
R-2568B		27
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	
PRELIMINARY PLANS		
SEAL 22557		
MICHAEL W. LITTLE		

CONST. REV.
R/W REV.



FOR -LT/LN/- PLAN VIEW
SEE SHEET 5

-LT/LN/-

PI = 26+00.000
EL = 224.935 m
VC = 120 m
K = 31


STATIONING
STATION 26+00.000
STATION 26+120.000
TAN EL 226.460
OR EL 225.162

+60 +80 26 +20 +40 +60 +80 27 +20 +40 +60 +80 28 +20

-RTLNI/-

PI = 25+96.389
EL = 224.848 m
VC = 125 m
K = 32

STATIONING
STATION 25+96.389
STATION 26+121.389
TAN EL 227.215
OR EL 225.162



FOR -RTLNI/- PLAN VIEW
SEE SHEET 5

+60 +80 26 +20 +40 +60 +80 27 +20 +40 +60 +80 28

15-JUN-2004 15:23
D:\PROJECTS\2568B\2568B.dwg
MLittle AL RD203673

6/09/99



PROJECT REFERENCE NO.

R-2568B

ROADWAY DESIGN
ENGINEER

SHEET NO.



28

HYDRAULICS
ENGINEER



CONST. REV.

R/W REV.



28 +20 +40 +60 +80

PI = 29+00.000
EL = 243.000 m
VC = 480 m
K = 100

PIPE HYDRAULIC DATA
DRAINAGE STRUCTURE NO. 36



DRAINAGE AREA = 87 HA
DESIGN FREQUENCY = 50 YRS
DESIGN DISCHARGE = 17 CMS
DESIGN HW ELEVATION = 234.80 m
100 YEAR DISCHARGE = 2.0 CMS
100 YEAR HW ELEVATION = 234.90 m
OVERTOPPING FREQUENCY = 500+ YRS
OVERTOPPING DISCHARGE = N/A
OVERTOPPING ELEVATION = 242.50 m

FOR -L- PLAN VIEW
SEE SHEET 6


15-JUN-2004 15:24
R:\proj\2568B\p1
MLittle AT RD203673


R / W REV.

CHAS. W. LITTLE



15-JUN-2004 15:24
R:\proj\r2568b.pdf
MLtitle AT RD203673






5 0 10

CONST. REV.
R/W REV.

PROJECT REFERENCE NO.
R-2568B
ROADWAY DESIGN
ENGINEER


SHEET NO.
30
HYDRAULICS
ENGINEER



PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

15-JUN-2004 15:25
R:\proj\2568B\cf1
MLittle AI R0203673

15-JUN-2004 15:25
R:\proj\25688\p1\title AT RD 203673




5 0 10



CONST. REV.
R/W REV.



PROJECT REFERENCE NO.
R-25688
ROADWAY DESIGN
ENGINEER

SHEET NO.
3/
HYDRAULICS
ENGINEER



PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION
MICHAEL LITTLE





PROJECT REFERENCE NO.	SHEET NO.
R-2568B	32
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS	
DO NOT USE FOR CONSTRUCTION	
ENGINEER	
MICHAEL W. LITTLE	

CONST. REV.
R/W REV.

FOR -L- PLAN VIEW
SEE SHEET 13

BM *J5 - RR SPIKE IN 24" RED OAK
-BL- 52+48.77 m RT.
-L- 57+48.76 m RT.
EL= 231.46

PIPE HYDRAULIC DATA	
DRAINAGE STRUCTURE NO.122	
DRAINAGE AREA	= 45 HA
DESIGN FREQUENCY	= 50 YRS
DESIGN DISCHARGE	= 0.93 CMS
DESIGN HW ELEVATION	= 226.96 m
100 YEAR DISCHARGE	= 1.0 CMS
100 YEAR HW ELEVATION	= 227.02 m
OVERTOPPING FREQUENCY	= 500+ YRS
OVERTOPPING DISCHARGE	= N/A
OVERTOPPING ELEVATION	= 232.00 m


PIPE HYDRAULIC DATA	
DRAINAGE STRUCTURE NO.126	
DRAINAGE AREA	= 2.2 HA
DESIGN FREQUENCY	= 50 YRS
DESIGN DISCHARGE	= 0.55 CMS
DESIGN HW ELEVATION	= 224.59 m
100 YEAR DISCHARGE	= 0.59 CMS
100 YEAR HW ELEVATION	= 224.45 m
OVERTOPPING FREQUENCY	= 500+ YRS
OVERTOPPING DISCHARGE	= N/A
OVERTOPPING ELEVATION	= 228.40 m

FOR -L- PLAN VIEW
SEE SHEET 14

5-JUN-2004 15:26
C:\proj\2568B\p1
Little A1 RD203673



DESIGN DISCHARGE = 134.0 CMS
DESIGN FREQUENCY = 50 YRS
DESIGN HW ELEVATION = 21497 m
BASE DISCHARGE = 174.0 CMS
BASE FREQUENCY = 100 YRS
BASE HW ELEVATION = 215.35 m
OVERTOPPING DISCHARGE = >242.0CMS
OVERTOPPING FREQUENCY = >500 YRS
OVERTOPPING ELEVATION = 218.46 m




FOR -L- PLAN VIEW
SEE SHEET 16

15-JUN-2004 15:26
R:\proj\2568b.pfl
MLittle AI RD203673




CONST. REV.
R/W REV.

PROJECT REFERENCE NO.		SHEET NO.
R-2568B		34
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	

	PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION
---	---

BM *J6 - RR SPIKE IN 2" RED CEDAR
-BL- 61+68.1042 m LT.
-L- 66+60.51013 m LT.
EL = 228.588


-L-



FOR -L- PLAN VIEW
SEE SHEET 17

PI = 71+80.000
EL = 249.80 m
VC = 590 m
K = 95

-L-



FOR -L- PLAN VIEW
SEE SHEET 18

5 JUN-2004 15:27
C:\proj\2568B\p1
Little A1 RD203673

PROJECT REFERENCE NO.

R-2568B

SHEET NO.

35

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER

SEAL

22557

ENGINEER

MICHAEL W. LITTLE

CONST. REV.

R/W REV.

BM "J8" - RR SPIKE IN 18" DOUBLE WINGED ELM

-BL- 69+82.295.3 m RT.

-L- 75+00.5.299.4 m RT.


EL = 238.482

BM "J9" - RR SPIKE IN 18" BLACK CHERRY

-BL- 70+69.353.7 m LT.

-RTL2- 75+69.3.360.3 m LT.

EL = 250.595



PIPE HYDRAULIC DATA

DRAINAGE STRUCTURE NO.181


DRAINAGE AREA	= 5.0 HA
DESIGN FREQUENCY	= 50 YRS
DESIGN DISCHARGE	= 0.96 CMS
DESIGN HW ELEVATION	= 236.34 m
100 YEAR DISCHARGE	= 1.03 CMS
100 YEAR HW ELEVATION	= 236.38 m
OVERTOPPING FREQUENCY	= 500+ YRS
OVERTOPPING DISCHARGE	= N/A
OVERTOPPING ELEVATION	= 240.70 m

FOR -L-, -LTLN2- & -RTL2- PLAN VIEW
SEE SHEET 19

5/10/25

15-JUN-2025 08:28


FILE: \\msb\projects\2568\plan\2568plan19.dwg




15-JUN-2004 15:28
C:\proj\2004\20040673
M:\proj\2004\20040673



PROJECT REFERENCE NO.	SHEET NO.
R-2568B	37
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER




CONST. REV.
R/W REV.



-LT LN2-

-RT LN2-



FOR -LT LN2- & -RT LN2- PLAN VIEW
SEE SHEET 21

79 + 20 + 40




PROJECT REFERENCE NO.		SHEET NO.
R-2568B		38
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	
PRELIMINARY PLANS		
SEAL 22557		
ENGINEER		



CONST. REV.
R/W REV.

-Y-



PIPE HYDRAULIC DATA	
DRAINAGE STRUCTURE NO.31	
DRAINAGE AREA	= 15 HA
DESIGN FREQUENCY	= 50 YRS
DESIGN DISCHARGE	= 0.38 CMS
DESIGN HW ELEVATION	= 238.59 m
100 YEAR DISCHARGE	= 0.40 CMS
100 YEAR HW ELEVATION	= 238.61 m
OVERTOPPING FREQUENCY	= 500+ YRS
OVERTOPPING DISCHARGE	= N/A
OVERTOPPING ELEVATION	= 242.50 m

FOR -Y- PLAN VIEW
SEE SHEETS 6 & 22


8-1111-2004 B23
M: title A1 11/15/04 12:56:00

5/10/98




PROJECT REFERENCE NO.
R-2568B
ROADWAY DESIGN
ENGINEER


SHEET NO.
39
HYDRAULICS
ENGINEER



CONST. REV.
R/W REV.



-Y/-



5-JUN-2004 05:30
M:\info At\2568B\2568B.p1

15-JUN-2004 15:30
R:\proj\r2568b.pfl
MLittle AT RD203673

6/09/99

BM *J5 - RR SPIKE IN 2" RED OAK
-BL- 52+48.77 m RT.
-L- 57+48.76 m RT.
EL = 231.146

-Y10-

PI = 11+30.000
EL = 239.820 m
VC = 60 m
K = 23

PI = 10+60.000
EL = 235.029 m
VC = 80 m
K = 9

PIPE HYDRAULIC DATA	
DRAINAGE STRUCTURE NO. 114	
DRAINAGE AREA	= 2.2 HA
DESIGN FREQUENCY	= 25 YRS
DESIGN DISCHARGE	= 0.50 CMS
DESIGN HW ELEVATION	= 233.69 m
100 YEAR DISCHARGE	= 0.58 CMS
100 YEAR HW ELEVATION	= 233.80 m
OVERTOPPING FREQUENCY	= 500+ YRS
OVERTOPPING DISCHARGE	= N/A
OVERTOPPING ELEVATION	= 236.30 m

METRIC

5 0 10

CONST. REV.

R/W REV.

PROJECT REFERENCE NO.	SHEET NO.
R-2568B	41
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS	
NOT FOR CONSTRUCTION	

FOR -Y10- PLAN VIEW
SEE SHEET 13


BM *J5 - RR SPIKE IN 2" RED OAK
-BL- 52+48.77 m RT.
-L- 57+48.76 m RT.
EL = 231.146

-Y10A-

PI = 10+15.000
EL = 236.934 m
VC = 23 m
K = 4


FOR -Y10A- PLAN VIEW
SEE SHEETS 13 & 14

15-JUN-2004 15:31
\\proj\proj\2568B\cf1
Little AL RD20673



PI = 10+70.000
EL = 253.046 m
VC = 100 m
K = 14

BM *J8 - RR SPIKE IN 18" DOUBLE WINGED ELM
-BL- 69+82.295.3 m RT.
-L- 75+005.299.4 m RT.
EL = 238.482



5 0 10


CONST. REV.
R/W REV.

PROJECT REFERENCE NO.
R-2568B

SHEET NO.
42

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER



PRELIMINARY PLANS
NOT FOR USE FOR CONSTRUCTION

PIPE HYDRAULIC DATA
DRAINAGE STRUCTURE NO.180

DRAINAGE AREA	= 21	HA
DESIGN FREQUENCY	= 50	YRS
DESIGN DISCHARGE	= 0.54	CMS
DESIGN HW ELEVATION	= 241.05	m
100 YEAR DISCHARGE	= 0.57	CMS
100 YEAR HW ELEVATION	= 241.12	m
OVERTOPPING FREQUENCY	= 500+	YRS
OVERTOPPING DISCHARGE	= N/A	
OVERTOPPING ELEVATION	= 242.50	m

FOR -Y11- PLAN VIEW
SEE SHEETS 19 & 23

BM *J8 - RR SPIKE IN 18" DOUBLE WINGED ELM
-BL- 69+82.295.3 m RT.
-L- 75+005.299.4 m RT.
EL = 238.482

-Y12-

PI = 10+35.000
EL = 242.203 m
VC = 60 m
K = 21

PIPE HYDRAULIC DATA
DRAINAGE STRUCTURE NO.186

DRAINAGE AREA	= 3.2	HA
DESIGN FREQUENCY	= 50	YRS
DESIGN DISCHARGE	= 1.12	CMS
DESIGN HW ELEVATION	= 239.96	m
100 YEAR DISCHARGE	= 1.21	CMS
100 YEAR HW ELEVATION	= 240.07	m
OVERTOPPING FREQUENCY	= 500+	YRS
OVERTOPPING DISCHARGE	= N/A	
OVERTOPPING ELEVATION	= 242.15	m


FOR -Y12- PLAN VIEW
SEE SHEETS 19 & 24

15-JUN-2004 15:31
R:\proj\2568b\pf1
MLittle
At 10203673

BM *J8 - RR SPIKE IN 18" DOUBLE WINGED ELW
-BL- 69+82.295.3 m RT.
-L- 75+00.5,299.4 m RT.
EL = 238.482


-Y13-

-Y14-




PROJECT REFERENCE NO. R-2568B		SHEET NO. 43
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER
PRELIMINARY PLANS NOT TO BE USED FOR CONSTRUCTION		

CONST. REV.
R/W REV.



PIPE HYDRAULIC DATA	
DRAINAGE STRUCTURE NO.	
DRAINAGE AREA	= 2.25 HA
DESIGN FREQUENCY	= 50 YRS
DESIGN DISCHARGE	= 0.50 CMS
DESIGN HW ELEVATION	= 240.03 m
100 YEAR DISCHARGE	= 0.54 CMS
100 YEAR HW ELEVATION	= 240.08 m
OVERTOPPING FREQUENCY	= 500+ YRS
OVERTOPPING DISCHARGE	= N/A
OVERTOPPING ELEVATION	= 242.10 m

-Y12DET-




FOR -Y12DET- PLAN VIEW
SEE SHEET 25

15-JUN-2004 15:32
R:\proj\25686\pf1
M:\file
At R020673



PROJECT REFERENCE NO. R-2568B	SHEET NO. 44
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
PRELIMINARY PLANS NOT FOR USE FOR CONSTRUCTION	
ENGINEER MICHAEL W. LITTLE	




CONST. REV.

R/W REV.

-Y14A-

-DRI-



15-JUN-2004 15:32
B:\proj\1-2568B\MLT\MLT0673

STORMWATER MANAGEMENT PLAN

R-2568B, State Project 8.1600901
Davidson County
Hydraulics Project Manager: Andrew Nottingham, PE

Date: 7/24/02
Revised 6/4/04
Revised 7/15/04

ROADWAY DESCRIPTION

The project involves the construction of NC 109 from north of I-85 Business near Thomasville to north of SR 1756 (Lexington Ave.) north of Ledford Middle School. The overall length of the project is 3.51 miles. R2568B is part of project R2568 which will widen the existing NC 109 from two-lanes to a multi-lane highway from Thomasville to High Point. About half of the project is on new location and the other half approximately follows the existing alignment. The proposed typical section is a four lane divided highway with grass shoulders and ditches and a 46-ft. grass median. The project ties into a 5-lane curb and gutter section at the beginning and a two-lane shoulder section at the end. There are two major stream crossings consisting of a new box culvert and a new bridge.

ENVIRONMENTAL DESCRIPTION

Land Use

The project area is generally rural, but is experiencing increased residential suburban development due to growth in nearby Winston-Salem, High Point, and Thomasville. It is anticipated the suburban growth will continue, with commercial/industrial districts near the southern terminus near Thomasville and at other locations along the project in the future.¹

Topography and Water Resources

The project is located in the Yadkin-PeeDee River Basin in the Piedmont Physiographic Province. In most places a thick layer of soil and soft weathered rock is underlain by bedrock. The terrain is gently to severely rolling. Erosion rates are high for exposed areas. The streams are moderately swift and tend to flow southward and southwestward in fairly broad interstream areas.¹ There are nine stream crossings on this project, which are all classified as Class C waters. Five of the streams are intermittent, three are perennial, and one stream changes from intermittent to perennial within the impact area. The two perennial stream crossings will require a new bridge at Rich Fork Creek (at approximately the same location as the existing bridge crossing) and a new culvert at a Tributary to Rich Fork Creek (on new roadway location). The intermittent streams will utilize pipe culvert crossings. Approximately 2707 ft. of existing stream will be permanently impacted due to the project resulting in 0.36 ac. of fill in surface waters. Temporary stream impacts will total approximately 280 ft. with 0.03 ac. of temporary fill in surface waters. Two sites will require stream relocations. Four wetland sites will be impacted. Approximately 0.75 acres of wetlands will be impacted due to this project which includes 0.62 ac. of fill in wetlands, 0.03 ac. of excavation in wetlands and 0.10 ac. of mechanized clearing in wetlands.

¹ Draft Environmental Assessment, NCDOT

BEST MANAGEMENT PRACTICES AND MAJOR STRUCTURES

Best Management Practices (BMPs) and measures used on the project are an attempt to reduce the stormwater impacts to the receiving streams due to erosion and runoff. The primary BMP is the use of grassed roadway ditches and shoulders, as opposed to a curb and gutter roadway system. Rip rapped ditches were used where warranted to control erosion. Ditches were ended in flat floodplain areas where possible to allow dispersal and infiltration. Preformed scour holes were used to attenuate and disperse flow. The inverts of all new culverts on jurisdictional streams or wetlands will be buried 20% of the pipe diameter up to 1 ft. deep. No bridge deck drains will be used directly over the surface water.

Stream Relocations

Station 47+00 to station 47+80 -L- Lt.

Approximately 315 ft of perennial stream will be relocated using natural stream design.

Station 64+20 to station 65+00 -L- Lt.

Approximately 315 ft of intermittent stream will be relocated.

Bridges

Station 61+31.5 -L- Lt.

The existing 103 ft. long bridge on NC 109 over Rich Fork Creek will be removed and replaced with a new bridge 170 ft. in length. The new bridge will be a two span bridge, which will span the water. The middle pier will be right along the existing bank and a rock causeway will likely be required to construct the pier due to its close proximity to the water.

Culvert

Station 46+85 -L-

The proposed 11-ft wide by 8 ft. high box culvert on a Tributary to Rich Fork Creek will be buried 1 ft. below the stream bed. The stream will be temporarily diverted near the culvert entrance to allow all dry construction.



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

June 18, 2004

Mr. William D. Gilmore, P.E.
EEP Transition Manager
Ecosystem Enhancement Program
1652 Mail Service Center
Raleigh, NC 27699-1652

Dear Sir:

Subject: Improvement of NC 109 from North of I-85 Business to North of SR 1798
(Old Greensboro Road) in Davidson County, Federal Project No. STP-109 (1),
State Project No. 8.1900901, WBS Element 34468.1.1, T.I.P. No.R-2568B.

The purpose of this letter is to request that the North Carolina Ecosystem Enhancement Program (EEP) provide confirmation that the EEP is willing to provide compensatory mitigation for the project in accordance with the Memorandum of Agreement (MOA) signed July 22, 2003 by the USACE, the NCDENR and the NCDOT. This project was one of the 16 additional projects to be let during 2004-2005 that was included on the "Transition List" for the MOA.

The North Carolina Department of Transportation (NCDOT) proposes to relocate NC 109 from north of I-85 Business in Thomasville to north of SR 1798 (Old Greensboro Road), a distance of 3.51 miles. This section of existing NC 109 is located in the northeastern part of Davidson County. This Urban Principal Arterial is a four-lane divided facility with partial access control, and will be constructed partially on new location. The typical section for the proposed facility includes a 46-foot grassed median.

**RESOURCES UNDER THE JURISDICTION OF SECTION 404 AND 401 OF THE
CLEAN WATER ACT.**

We have avoided and minimized the impacts to jurisdictional resources to the greatest extent possible as described in the permit application. A copy of the permit application can be found at <http://www.ncdot.org/planning/pe/naturalunit/Applications.html>. Although there will be 315 feet of onsite mitigation created by a new stream channel, the remaining impacts to jurisdictional resources will be compensated for by mitigation provided by the EEP program.

Wetlands

Table 1 lists the impacts to jurisdictional wetland resources, which include impacts resulting from fill, excavation, and mechanized clearing and wetland descriptions. We estimate 0.75 acres of unavoidable impacts to jurisdictional wetlands for this project. We are requesting compensatory mitigation from EEP for the unavoidable impacts to the wetlands.

Table 1 – Wetland Impacts and Descriptions					
Site	Wetland Impacts (acres)*	Cowardin <i>et al.</i> description	NCDWQ Wetland Rating	Riverine (R) or Non-riverine (NR)	Schafale and Weakley description
2	0.02	PFO1C	56	NR	MO
3	0.05	PFO1C/W	44	NR	B
5	0.15	PFO1B	60	NR	MO
9	0.53	PFO1C	65	NR	B
Total impacts	0.75				
* Indicates total wetland impacts, including fill, excavation and mechanized clearing					

The Cowardin classification for the wetlands is noted as PFO1, with additional saturation levels found in the project area.

PFO1-Palustrine, forested, broad-leaved deciduous

-B Saturated

-C Seasonally flooded

-W Intermittently flooded/Temporary

Schafale and Weakley descriptions:

Mesic Oak-Hickory Forest (MO) – wetter areas where a mix of oaks and hickories are the dominant tree species

Bottomland Hardwood Forest (B) – broad floodplain forest community

Surface Waters

The project is located in the Piedmont Physiographic Province in Davidson County in the Yadkin-Pee Dee River Basin in Hydrological Cataloguing Unit 03040103. Surface waters crossed by the proposed project include Rich Fork Creek (index Number 12-119-7), six unnamed tributaries to Rich Fork Creek, and two unnamed tributaries to Hunt's Fork Creek (12-119-7-3). The North Carolina Division of Water Quality Best Usage Classification for both these creeks is C.


After verification and review by the United States Army Core of Engineers (ACOE) on August 28, 2001, only three unnamed tributaries to Rich Fork Creek require mitigation. The remaining seven channels did not require mitigation based on degraded quality or incurrence to only temporary impacts. There are 1,992 total impacts requiring compensatory mitigation. Natural channel design will create 315 linear feet of new stream channel within the project area and will offset only part of the compensatory mitigation. Therefore, we are requesting compensatory mitigation from EEP for the remaining 1,677 feet of jurisdictional streams impacts.

Please send the letter of confirmation to Mr. Eric Alsmeyer (USACE Coordinator) at U. S. Army Corps of Engineers Raleigh Regulatory Field Office, 6508 Falls of the Neuse Road Suite 120 Raleigh, NC 27615. Mr. Alsmeyer's FAX number (919) 876-5823. The current let date for the project is November 16, 2004 for which the let review date is September 28, 2004.

In order to satisfy regulatory assurances that mitigation will be performed; the NCDWQ requires a formal letter from EEP indicating their willingness and ability to provide the mitigation work requested by NCDOT. The NCDOT requests such a letter of confirmation be addressed to Mr. John Hennessy of NCDWQ, with copies submitted to NCDOT.

If you have any questions or need additional information please call Deanna Riffey at (919) 715-4109.

Sincerely,


For

Gregory J. Thorpe, Ph.D.,

Environmental Management Director

Project Development & Environmental Analysis Branch

cc:

Mr. John Hennessy, Division of Water Quality
Mr. Travis Wilson, NCWRC
Mr. Gary Jordan, USFWS
Mr. David Franklin, USACE, Wilmington
Mr. Eric Alsmeyer, USACE, Raleigh



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

July 22, 2004

Mr. William D. Gilmore, P.E.
EEP Transition Manager
Ecosystem Enhancement Program
1652 Mail Service Center
Raleigh, NC 27699-1652

Dear Sir:

Subject: Mitigation Compensation Change Request for Improvement of NC 109 from North of I-85 Business to North of SR 1798 (Old Greensboro Road) in Davidson County, Federal Project No. STP-109 (1), State Project No. 8.1900901, WBS Element 34468.1.1, T.I.P. No.R-2568B.

The purpose of this letter is to request a change to the compensatory mitigation request letter dated June 18, 2004. According to the June 18th letter, NCDOT requested the Ecosystem Enhancement Program (EEP) provide confirmation for compensatory mitigation for 0.75 acres of wetland impacts and 1,677 feet of jurisdictional stream impacts.


The compensatory mitigation request for the wetland impacts remains unchanged at 0.75 acres. However, the total jurisdictional stream impacts requiring compensatory mitigation has been reduced from 1,992 to 1,405 feet due to design changes. Onsite natural channel design will still create 315 linear feet of new stream channel within the project area and will offset a portion of the required compensatory mitigation. Therefore, we are requesting compensatory mitigation from EEP for the remaining 1,090 feet of jurisdictional stream impacts.

Please send the letter of confirmation to Mr. Eric Alsmeyer (USACE Coordinator) at U. S. Army Corps of Engineers Raleigh Regulatory Field Office, 6508 Falls of the Neuse Road Suite 120 Raleigh, NC 27615. Mr. Alsmeyer's FAX number (919) 876-5823. The current let date for the project is November 16, 2004 for which the let review date is September 28, 2004.

In order to satisfy regulatory assurances that mitigation will be performed; the NCDWQ requires a formal letter from EEP indicating their willingness and ability to provide the mitigation work requested by NCDOT. The NCDOT requests such a letter of confirmation be addressed to Mr. John Hennessy of NCDWQ, with copies submitted to NCDOT.

If you have any questions or need additional information please call Deanna Riffey at (919) 715-4109.

Sincerely,

A handwritten signature in black ink, appearing to read "Gregory J. Thorpe", with a large, stylized "G" to the left of the signature.

Gregory J. Thorpe, Ph.D.,
Environmental Management Director
Project Development & Environmental Analysis Branch

cc:

Mr. John Hennessy, Division of Water Quality
Mr. Travis Wilson, NCWRC
Mr. Gary Jordan, USFWS
Mr. David Franklin, USACE, Wilmington
Mr. Eric Alsmeyer, USACE, Raleigh

Minutes for Permit Drawing Review (Interagency 4C Review) R-2568B

**State Project 8.1600901
NC 109 North of Thomasville, Davidson County**

A Permit Review Meeting was held on Thursday, July 25, 2002 in the Location and Surveys conference room at the NCDOT Century Center Complex, Raleigh.

Team members: Andrew Nottingham-NCDOT Hydraulics (Present)
Eric Alsmeyer-USACE (Present)
Cynthia Van Der Wiele-NCDWQ (Present)
Marella Buncick-USFWS (Present)
David Cox for Marla Chambers-NCWRC (Present)
Chris Miltischer-EPA (Absent)
Lynn Smith-NCDOT PDEA (Present)

Participants: David Chang-NCDOT Hydraulics
Mike Little-NCDOT Roadway Design
Roger Thomas-NCDOT Roadway Design
Stephen Morgan-NCDOT Hydraulics
Karen Gullede-NCDOT Hydraulics

The meeting began at 3:15 with Mr. Nottingham distributing the storm water management plan for the project and presenting a project overview including the Best Management Practices used. He then went through the permit drawings site by site. The discussion and comments for each site are as follows:

Site 1

Mr. Nottingham advised the 1050mm (42") pipe crossing would be upgraded one pipe size to allow burial of the invert in the stream. He stated the new policy for jurisdictional streams in non-CAMA counties with a pipe crossing is that the pipe will be buried 20% of the pipe diameter, up to a maximum burial of one foot. (For a 48" pipe, the invert would be buried 0.8'). He noted the stream, labeled a tributary to Hank's Fork Creek, should be labeled a tributary to Hunt's Fork Creek. There were no further comments.

Site 2

Mr. Nottingham noted the 1050mm (42") pipe crossing would be upgraded to a 48" pipe to allow burial as in Site 1. He also noted a possible concern with rip rap at the pipe outlet. Ms. Buncick, Mr. Cox, and Ms. Van Der Wiele also expresses their concern with rip rap in the stream. Mr. Nottingham recommended investigating the need for rip rap at the outlet of the pipe.

Site 2A

Mr. Nottingham suggested a Preformed Scour Hole at the end of the rip rapped ditch right of 37+15 would attenuate and disperse concentrated flow from the ditch before it enters the wetland. The team members agreed.

Site 3

Mr. Nottingham suggested a Preformed Scour Hole at the end of the rip rapped ditch right of 40+40 would attenuate and disperse concentrated flow from the ditch before it enters the wetland. The team members agreed.

Site 4

Mr. Nottingham suggested a Preformed Scour Hole at the end of the rip rapped ditch right of 46+80 could be added to attenuate and disperse concentrated flow from the ditch before it enters the floodplain. The team members agreed. Ms. Buncick and Ms. Van Der Wiele expressed concern over the potential clearing limits for the stream relocation, noting that many times the entire Right-of-Way is cleared. Mr. Nottingham and Mr. Thomas suggested a note could be added to the plans to limit the clearing to 10' beyond the top of the cut. A revised morphological table was presented to the team members for the stream relocation. Mr. Nottingham noted that he would include documentation addressing sediment transport evaluations with the permit drawings.

Site 5

Ms. Van Der Wiele and Ms. Buncick questioned the linear wetland apparently adjacent to a stream, but no stream impacts were noted. Mr. Alsmeyer related seeing the site and noted no stream was present, but wetland impacts were appropriate. Ms. Buncick expressed concern about erosion at the end of the ditches draining to the site. Mr. Nottingham suggested a Preformed Scour Hole could be added to the ditch left of 50+60. The team members agreed that the 750mm (36") cross pipe did not need to be buried at this site.

Site 6&7

Team members noted the sheet was cluttered. Mr. Morgan commented that the site was a true clipped portion of the latest design, with no "cleanup". He added the Site Impact sheet showing only the existing topography with the proposed centerline, slope stake line, and impacts, was included for this site as well all other sites to clarify any clutter. Team members agreed the concept was helpful, especially for these two sites. Ms. Smith mentioned the sites were streams not requiring mitigation. Mr. Alsmeyer concurred.

Site 8

Mr. Alsmeyer questioned the need for temporary fill (Rock Causeways) at this site. Mr. Nottingham stated that if drilled shafts were recommended, their proximity to the bank would require a temporary rock causeway. Mr. Morgan added the foundation recommendation has not yet been received, but would most likely be drilled shafts based on other projects in the region. Mr. Nottingham suggested the temporary fill could possibly be eliminated should driven piles be recommended. Mr. Nottingham recommended adding Preformed Scour Holes at the end of the ditches left and right of Station 61+00 to attenuate and disperse flow before it enters the floodplain.

Site 9

Ms. Smith mentioned the relocated stream length in English units did not match the converted metric length. Ms. Gulledge said this could be an error in the conversion, and this would be corrected. Mr. Nottingham questioned the need for stream relocation since the impacted stream was only partially intermittent and partially ephemeral. Mr. Alsmeyer, Ms. Van Der Weile and Ms. Buncick indicated natural stream design would not be required. Mr. Nottingham mentioned that natural stream techniques had been used in the design of the channel, and the design would remain the same anyway since it was practicable to do so. Mr. Alsmeyer questioned the alignment in this area, as its location east of the existing road impacts the wetland site. Mr. Little acknowledged the impacted wetland, but added avoidance of a historic property east of the existing road in this area prevented alternative designs. Mr. Alsmeyer inquired as to the relative invert of the 1050mm (42") pipe crossing to the wetland. Mr. Nottingham said the invert of the pipe should match the ground surface, with no burial. Mr. Alsmeyer indicated this would be preferred, as he did not want to drain the remaining wetland system by setting the pipe invert too low. Mr. Alsmeyer noted that the stream at this site would not require mitigation.

Site 10

No comment.

Additional Discussion

Mr. Alsmeyer inquired if the feature crossed at Station 44+00 was also a stream. Ms. Smith noted that the original delineation fact sheet made no mention of the site, but she had recently received correspondence from Mr. Philip Todd, NCDOT PD&EA biologist, that the site was in fact jurisdictional and needed to be added. (verified 7/26/02) Mr. Nottingham said the site will be added. While looking at this additional site, the team members inquired about the hydraulic design- specifically the two pipes (structures 81 and 83) with a junction box. Ms. Gullledge and Mr. Nottingham presented the contour mapping showing the ridge between the two drainages, noting another option would have been a stream relocation, but it would require a cut approximately 15' deep.

The meeting was adjourned at 4:10pm.

Prepared By: Stephen Morgan

August 16, 2002

II. 4C AGENCY COMMENTS AND POST-MEETING ACTIVITIES

Date: 12/12/02 (Revised 06/04/04)

Draft meeting minutes for the 4C meeting on 7/25/2002 were sent out to Team Members on 7/31/2002 for review and comment. No revisions or comments were received as of 12/10/2002.

The following is a summary of the changes made to the permit and plans in response to comments made at the 4C meeting:

Site 1: Changes were made to the permit and plans as recommended in the 4C meeting minutes.

Site 2: Changes were made to the permit and plans as recommended in the 4C meeting minutes. The need for rip rap at the outlet of the 48" pipe was investigated and it was decided that the rip rap will be removed from the streambed at the outlet of the 48" pipe and placed only on the channel banks.

Site 2A: Preformed scour hole added to the permit and plans as noted in the 4C meeting minutes.

Site 3: Rock check dam used to attenuate flow in lieu of Preformed scour hole due to steep topography. Rock check dam added to the permit and plans.

Site 3A: This site was added as noted in the additional discussion section of the 4C meeting minutes.

Site 4: Preformed scour hole added to the permit and plans as noted in the 4C meeting minutes. A note was added to the permit drawings and plans to limit clearing to 10 feet beyond top of the cut on the stream relocation. Natural stream design summary addressing sediment transport and a revised morphological table are included with permit drawings. Also a cross vane rock weir was added to the stream relocation for grade control.

Site 5: Preformed scour holes added to outlet of ditches prior to entering wetlands.

Site 6&7: No revisions requested.

Site 8: Preformed scour holes added to the permit and plans as noted in the 4C meeting minutes.

Site 9: Natural stream design lengths removed from summary table since natural stream design is not being claimed.

Site 10: No revisions requested.

Natural Stream Design
Station 47+20 to 47+88
R-2568B

Existing Stream

The majority of the existing stream is entrenched with a low-to-moderate width to depth ratio, and low-to-moderate sinuosity. The bed consists of mostly gravel and coarse sand with some bedrock exposed at various locations. Old tobacco barns located nearby suggest the area was once used for agriculture. The flood plain is wooded with a valley type X - wide with gentle elevation relief and constructed of alluvial materials by riverine processes. The typical floodplain is 35m to 42m wide. The drainage area near the centerline of the proposed road is 119 hectares (294 acres). There are areas along the existing stream that are characteristic of the stable "E" stream- slightly entrenched with low width to depth ratio but with low sinuosity, or even straight. Other areas are characteristic of a stable "B" stream with moderate entrenchment and sinuosity, but the width to depth ratio is too low. Other areas are more characteristic of a "C" stream with moderate width to depth ratios, sandbar deposition and moderate sinuosity, but the channel is entrenched. The existing stream is best described as a "G4c" stream.

If the width to depth ratio were slightly higher (12 instead of 8), and the entrenchment ratio were slightly higher (2.2 instead of 2.0), the stream would fall in the stable "C" range. The entrenchment ratio is based on a floodprone area that is twice the depth of the maximum bankfull depth. For typical "G" streams, most floods including those greater than 10yr floods are contained within the floodprone area. For the existing stream, a two-year to five-year event would find relief on the floodplain, thus reducing shear stresses along the banks.

"G" streams are most commonly associated with rapid bank erosion. High rates of bank erosion are not occurring along the existing stream. Stability comes from well-established bank vegetation, relatively low bank heights, and interspersed bedrock in the streambed acting as grade control. Two areas where noticeable bank erosion has occurred are near the centerline at station 47+00 and just left of the centerline at station 47+60. A severe bend near station 47+00 and loss of bank vegetation near an old forded stream crossing likely contribute to the erosion. At station 47+60 the stream has migrated close to the edge of the floodplain and formed an escarpment. It is the conclusion that the existing stream with few exceptions is stable.

Reference Reach

The proposed stream relocation is based on a reference reach on the existing stream located upstream of the proposed road and just above a private drive crossing of the creek. The drive crossing consists of a single 60" concrete pipe with two perched 24" concrete pipes. The drainage area is approximately 78 hectares (193 acres). The reference reach parameters are consistent with an "E" classification.

Stream Restoration Techniques Used

The new stream will be considered a Priority 2 restoration since the existing stream is slightly incised. To provide shear stress relief in the newly formed channel, a "C" channel with low bank heights will be designed to provide lower velocities immediately following construction. Natural sandbar deposition is expected following several storm events, which will increase the sinuosity and begin to decrease the width to depth ratio. Theoretically, the channel could eventually form an "E" channel, but if not, the "C" channel will maintain its stability. Relief at bankfull stage will provide additional stability compared to the existing stream. The major floodplain will be available for storms greater than a 10 year event. A stream reforestation schedule will be included with the final construction plans. In addition, the use of root wads at the culvert outlet will aid in bank stability and provide fish habitat. No additional grade control structure is needed at the inlet of the culvert due to exposed bedrock just upstream. A cross-vane rock weir will be added near the end of the stream relocation for grade control.

Sediment Transport

A stable stream is one that will function sufficiently to maintain its dimension, pattern and profile, while neither aggrading nor degrading over time. The wash load is normally composed of fine sands, silts and clay and is transported according to supply limitations. The sediment is composed of larger sized particles that make up the channel bed. The amount of shear stress needed to move these larger particles is an effective measure of stream stability since the process is hydraulically controlled rather than supply limited.

Shear stress for the proposed riffle section was calculated using the Shields Curve. The critical shear stress has to be sufficient to move the D_{84} of the bed material. The computed shear stress for the proposed reach is 0.40 lb/ft^2 . This is sufficient to move particles 35mm in diameter. Since the D_{84} of the proposed stream will be gravel, the stream will have the competency to move its bed load according to Shields curve criteria and design calculations.

Conclusion

The proposed reach is based on a stable reference reach on the same stream. From the reference reach ratios were derived to relate to the proposed stream. The most important feature the proposed stream has versus the existing stream is relief at bankfull stage, which decreases shear stress on the banks until adequate vegetation can be established. Sediment transport in the proposed stream will be sufficient to maintain stability as well. No hard structures will be used in the proposed stream except for one cross-vane rock weir at the tie-in for grade control. A floodplain reforestation schedule will accompany the final construction plans. It is therefore the conclusion that the design meets all the requirements of natural stream design.

Calculations

Shear stress computations

$$\tau = \gamma R s$$

γ = density of water (62.4 lb/ft³)

R = hydraulic radius = Area/Wetted Perimeter
= 21.5 ft²/18.6ft
= 1.16ft

s = slope = 0.0055ft/ft

$$\tau = (62.4 \text{ lb/ft}^3)(1.16\text{ft})(0.0055\text{ft/ft})$$

$$\tau = 0.40\text{lb/ft}^2$$

Friction Factor¹ ; u/u^*

u = mean velocity = 3.31ft/s

u^* = shear velocity = $(gRs)^{1/2}$

s = slope = 0.0055ft/ft

R = hydraulic radius = 1.16ft

g = gravitational constant = 32.2 ft/s²

$$u/u^* = 3.31\text{ft/s} \div (32.2 \text{ ft/s}^2 \times 1.16\text{ft} \times 0.0055\text{ft/ft})^{1/2}$$

$$u/u^* = 7.3$$

Note: the friction factor is consistent with "C4" streams plotted on the graph by Leopold¹; Manning's roughness " n " = 0.035

¹ Rosgen, The Reference Reach Field Book p. 189 (Leopold, 1997)



North Carolina Department of Cultural Resources

James B. Hunt Jr., Governor
Betty Ray McCain, Secretary
November 12, 1996

Division of Archives and History
Jeffrey J. Crow, Director

Nicholas L. Graf
Division Administrator
Federal Highway Administration
Department of Transportation
310 New Bern Avenue
Raleigh, N.C. 27601-1442

Re: NC 109 from I-85 Business to I-40/US 311 in
Winston-Salem, Davidson and Forsyth Counties,
R-2568, Federal Aid Project STP-109(1), State
Project 8.1600901, ER 97-7686



Dear Mr. Graf:

Thank you for your letter of October 28, 1996, transmitting the historic structures survey report by Ed Davis concerning the above project.

For purposes of compliance with Section 106 of the National Historic Preservation Act, we concur that the following property is eligible for the National Register of Historic Places under the criterion cited:

John William Hiatt Farm. This property is significant under Criterion C because its rare collection of outbuildings, particularly the extant "street" of tobacco barns, is exemplary of middle class tobacco farms in Davidson County.

The report in general meets our office's guidelines and those of the Secretary of the Interior.

The above comments are made pursuant to Section 106 of the National Historic Preservation Act and the Advisory Council on Historic Preservation's Regulations for Compliance with Section 106 codified at 36 CFR Part 800.

Thank you for your cooperation and consideration. If you have questions concerning the above comment, please contact Renee Gledhill-Earley, environmental review coordinator, at 919/733-4763.


Sincerely,


David Brook
Deputy State Historic Preservation Officer

DB:slw

cc: H. F. Vick
B. Church





North Carolina Department of Cultural Resources

James B. Hunt Jr., Governor
Betty Ray McCain, Secretary

Division of Archives and History
Jeffrey J. Crow, Director

March 21, 1997

MEMORANDUM

TO: H. Franklin Vick, P.E., Manager
Planning and Environmental Branch
Division of Highways
Department of Transportation

FROM: David Brook
Deputy State Historic Preservation Officer

SUBJECT: NC 109 from I-85 Business in Thomasville
to just north of SR 1798 (Old Greensboro
Road), Davidson County, Federal Aid
Project STP-109(1), State Project
8.1600901, TIP R-2568A&B, 97-E-4220-
0534

We have received information concerning the above project from the State Clearinghouse.

The archaeological survey conducted for this project did not identify potentially significant archaeological sites within the proposed build alternatives. In comments of February 28, 1996, we concurred that none of the identified sites were eligible for nomination to the National Register of Historic Places, but we also cautioned that eleven sites located outside the proposed right-of-way had not been evaluated for National Register eligibility. These sites were 31FY840, 31DV489, 492, 493, 495, 571, 572, 574-577. Should the alignment change, these sites will require additional investigation.

The above comments are made pursuant to Section 106 of the National Historic Preservation Act and the Advisory Council on Historic Preservation's Regulations for Compliance with Section 106 codified at 36 CFR Part 800.

Thank you for your cooperation and consideration. If you have questions concerning the above comment, please contact Renee Gledhill-Earley, environmental review coordinator, at 919/733-4763.

DB:slw

cc: State Clearinghouse
N. Graf
✓ T. Padgett





STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

June 30, 2004

Marella Buncick
US Fish and Wildlife Service
160 Zillicoa Street
Asheville, NC 28801

Dear Ms. Buncick:

Subject: NC 109 from north of I-85 Business to north of SR 1798
(Old Greensboro Road), Davidson County, North Carolina
Federal Aid Project No STP-109(1)
State Project Number 8.1600901
TIP Project R-2568B

This letter is in reference to the proposed improvements to NC 109 in Davidson County (TIP Number R-2568B). The enclosed vicinity map (Figure 1) depicts the R-2568B project right-of-way. The purpose of this letter is to summarize federally protected species surveys that have been conducted to date and to request concurrence from the United States Fish and Wildlife Service (USFWS) pursuant to Endangered Species Act (ESA) §7 (16 U.S.C. 1531 *et seq.*).

The Environmental Assessment (EA) for this project was completed in November 1996; however, subsequent surveys for federally protected species were conducted in 2002 and 2004. At the time of completion of the EA only Schweinitz's sunflower (*Helianthus schweinitzii*) was listed by as a protected species in Davidson County, NC. However as of January 29, 2003, the USFWS lists three federally protected species for Davidson County. The current USFWS listing of protected species (January 29, 2003) and updated Biological Conclusions are listed in the following table:

Federally Protected Species in Davidson County, NC			
Common Name	Scientific Name	Federal Status*	Biological Conclusion
Bald eagle	<i>Haliaeetus leucocephalus</i>	T (proposed for delisting)	No Effect
Bog turtle	<i>Clemmys muhlenbergii</i>	T(S/A)	Not Required
Schweinitz's sunflower	<i>Helianthus schweinitzii</i>	E	May Affect-Not Likely to Adversely Effect
* E=Endangered, T=Threatened, T(S/A)=Threatened due to similarity of appearance			

For each of these species, analysis of the possible presence of and impacts to each species was conducted as an evaluation of existing information and analysis by the primary investigators of the habitat requirements and occurrence of each species in North Carolina.

In a June 7, 2002 internal NCDOT Right-of-Way Consultation memo written by Lynn Smith, NCDOT Natural Systems Specialist, the previously submitted EA was updated for all federally protected species listed in Davidson County. The information given below for bald eagle (*Haliaeetus leucocephalus*) and bog turtle (*Clemmys muhlenbergii*) has been obtained from that memo.

Bog Turtle (*Clemmys muhlenbergii*)

Threatened due to Similarity of Appearance

Family: Emydidae

Date Listed: May 1, 1997

The bog turtle is North Carolina's smallest turtle, measuring 3 to 4 inches in length. It has a dark brown carapace and a black plastron. The bright orange or yellow blotch on each side of the head and neck is a readily identifiable characteristic. The bog turtle inhabits damp grassy fields, bogs, and marshes in the mountains and western Piedmont.

The bog turtle is shy and secretive and will burrow rapidly in mud or debris when disturbed. The bog turtle forages on insects, worms, snails, amphibians and seeds. In June or July, three to five eggs are laid in a shallow nest in moss or loose soil. The eggs hatch in about 55 days.

BIOLOGICAL CONCLUSION:

Not Applicable

The bog turtle is listed as Threatened due to Similarity of Appearance, T(S/A). This is due to its similarity of appearance to another rare species that is listed for protection. Species designated as T(S/A) are not subject to ESA §7 Consultation and a Biological Conclusion for this species is not required.

Bald Eagle (*Haliaeetus leucocephalus*)

Threatened

Family: Accipitridae

Date Listed: March 11, 1967

Adult bald eagles can be identified by their large white head and short white tail. The body plumage is dark-brown to chocolate-brown in color. Immature eagles lack the white head plumage; the body plumage has a uniform brownish to blackish color with blotchy white on the underside of the wings, belly, and tail. In flight bald eagles can be identified by their flat wing soar. Adults range in length from 27-37 inches and have a wingspan ranging from 2.3 - 7.5 ft.

Eagle nests are found in proximity to water (within a half mile) with a clear flight path to water, in the largest living tree in an area, and have an open view of the surrounding land. Human disturbance can cause an eagle to abandon otherwise suitable habitat. Eagle nests are approximately three meters across. The breeding season for the bald eagles begins in December or January. Fish are the major food source for bald eagles. Other sources include coots, herons, and wounded ducks. Food may be live or carrion.

BIOLOGICAL CONCLUSION:**No Effect**

Suitable nesting habitat in the form of large trees with a clear flight path to water is not present within the project study area. There are no large bodies of water or large river systems within a half mile, with a clear flight path to water, of the proposed project. A review of the North Carolina Natural Heritage Program (NCNHP) database on May 5, 2002 indicated that there are no known occurrences of bald eagle within 1.0 mile of the project study area. Therefore, NCDOT renders a Biological Conclusion of No Effect for the bald eagle.

Schweinitz's sunflower (*Helianthus schweinitzii*)

Endangered

Family: Asteraceae

Date Listed: May 7, 1991

Schweinitz's sunflower is a rhizomatous perennial herb that grows from 3 to 6 ft (1 to 2 m) tall from a cluster of carrot-like tuberous roots. Stems are usually solitary, branching only at or above mid-stem. The stem is usually pubescent but can be nearly glabrous; it is often purple. The lanceolate leaves are opposite on the lower stem, changing to alternate above. They are variable in size, being generally larger on the lower stem, and gradually reduced upwards. The pubescence of the underside of the leaves is distinctive and is one of the best characters to distinguish Schweinitz's sunflower from its relatives. The upper surface of the leaves is rough, with the broad-based spinose hairs directed toward the tip of the leaf. From September to frost, Schweinitz's sunflower blooms with comparatively small heads of yellow flowers.

The species occurs in clearings and edges of upland woods on moist to dryish clays, clay-loams, or sandy clay-loams that often have high gravel content and are moderately podzolized. Schweinitz's sunflower usually grows in open habitats not typical of the current general landscape in the piedmont of the Carolinas. Some of the associated species, many of which are also rare, have affinities to glade and prairie habitats of the Midwest. Other species are associated with fire-maintained sandhills and savannas of the Atlantic Coastal Plain and piedmont. The habitat of this sunflower tends to be dominated by members of the aster, pea, and grass families, an association emphasizing affinities of the habitat to both longleaf pine-dominated sandhills and savannas of the southeastern coastal plain and to glades, barrens, and prairies of the Midwest and Plains (Weakley and Houk, 1992).

BIOLOGICAL CONCLUSION: **May Affect-Not Likely to Adversely Affect**
In the Environmental Assessment (November 1996), a biological conclusion of No Effect was issued for Schweinitz's sunflower. However, due to the date of the last survey and the presence of suitable habitat in the project area, this biological conclusion is no longer valid. As a result, new surveys were conducted for this species on June 8 and 9, 2004. Although these surveys were conducted several months prior to the optimal survey window, Dale Suiter of the USFWS advised that the species could be correctly identified during this time of year. A known population of Schweinitz's sunflower in Randolph County was visited (June 8, 2004) prior to the initiation of field surveys.

Although appropriate habitat is present within the project right-of-way limits in the form of regularly maintained roadside shoulders, field or pasture edges, and utility easements, no individuals of this species or individuals of the *Helianthus* genus were observed during the June 2004 surveys. A NCNHP element occurrence records search on May 27, 2004 revealed no element occurrences of this species within 1 mile of the proposed project. The nearest known population of Schweinitz's sunflower is located on NC 109 in Davidson County, approximately 16 miles south of the proposed project. Therefore, it can be concluded that the proposed project will have a Biological Conclusion of May Affect-Not Likely to Adversely Affect for this federally protected species.

SURVEY METHODOLOGY

Field surveys for Schweinitz's sunflower were conducted within the project right-of-way limits, depicted in red on Figure 1. These right-of-way limits range from a width of 225 feet (75 m) to 330 feet (100 m). Aerial photographs were used to aid in identification of appropriate habitat. A walking visual search was conducted by two H.W. Lochner, Inc. biologists trained in identification of this species. The two biologists spent a combined 30 man-hours searching habitat of Schweinitz's sunflower and surveying for the plant where habitat existed.

Qualifications of the Principal Investigators

Investigator: Heather Renninger
Education B.S., Ecology, Appalachian State University
Experience 5 years
Expertise Natural resources surveys, endangered species surveys, wildlife biology, wetlands delineations.

Investigator: Emily Fentress
Education B.S., Biology, University of Tennessee
Experience 2.5 years
Expertise Natural resources surveys, botany, field biology, wetlands delineations.

Investigator: Brian Dustin
Education B.S., Forest Management, North Carolina State University
Experience 1 year
Expertise Natural resources surveys, wetlands delineations, dendrology, endangered species surveys, GPS.




Based on recent field surveys, it is known that the project area contains no federally listed species known to occur in Davidson County. The NCDOT concludes that the proposed project will have Biological Conclusions of May Affect-Not Likely to Adversely Affect for Schweinitz's sunflower and No Effect for bald eagle. We believe that the requirements of Section 7(a)(2) of the ESA have been satisfied and hereby request your concurrence. Please provide a written copy of your conclusions to the United States Army Corps of Engineers-Raleigh District Field Office in order to expedite the Clean Water Act §404 permitting process.


Sincerely,





Deanna Riffey
Environmental Specialist
Office of Natural Environment, PDEA Branch, NCDOT

cc: Mr. Eric Alsmeyer, USACE-Raleigh District Field Office
Mr. Michael Goins, P.E., Project Planning Engineer, NCDOT-PDEA Branch
File



 Right-of-Way for Proposed
 NC 109 New Location / Widening





North Carolina
Department of Transportation

NC 109 From North of I-85 Business
to North of SR 1798 (Old Greensboro Rd)
Davidson County, NC

State Project No. 8.1800901
T.I.P. Project No. R-25888




Figure 1

Project Vicinity

Project/Site: <u>R-2568</u>		Date: <u>2/1/01</u>
Applicant/Owner: <u>NCDOT</u>		County: <u>DAVIDSON</u>
Investigator: <u>Phillip Todd, Jared Gray</u>		State: <u>NC</u>
Do Normal Circumstances exist on the site?		Yes <input checked="" type="radio"/> No <input type="radio"/>
Is the site significantly disturbed (Atypical Situation)?		Yes <input type="radio"/> No <input checked="" type="radio"/>
Is the area a potential Problem Area?		Yes <input type="radio"/> No <input checked="" type="radio"/>
(If needed, explain on reverse.)		Community ID: <u>33180</u>
		Transect ID: <u>wetland</u>
		Plot ID: _____

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>MICROSTEGIUM VININEUM</u>	<u>H</u>	<u>FAC+</u>	9. _____	_____	_____
2. <u>GREEN BRIER</u>	<u>V</u>	<u>FAC</u>	10. _____	_____	_____
3. <u>RED MAPLE</u>	<u>T</u>	<u>FAC</u>	11. _____	_____	_____
4. <u>SWEET GUM</u>	<u>T</u>	<u>FAC+</u>	12. _____	_____	_____
5. <u>TULIP POPLAR</u>	<u>T</u>	<u>FAC</u>	13. _____	_____	_____
6. <u>JAPANESE HONEYSUCKLE</u>	<u>T</u>	<u>FAC-</u>	14. _____	_____	_____
7. <u>IRON WOOD</u>	<u>T</u>	<u>FAC</u>	15. _____	_____	_____
8. _____	_____	_____	16. _____	_____	_____

Percent of Dominant Species that are OBL, FAC+ or FAC (excluding FAC-): 6/7 = 86%

Remarks: prevalence of hydrophytic vegetation at sampling site

HYDROLOGY

<p>Recorded Data (Describe in Remarks):</p> <p>Stream, Lake, or Tide Gauge _____</p> <p>Aerial Photographs _____</p> <p>Other _____</p> <p>No Recorded Data Available _____</p>	<p>Wetland Hydrology Indicators:</p> <p>Primary Indicators:</p> <p>Inundated _____</p> <p>Saturated in Upper 12 Inches _____</p> <p>Water Marks _____</p> <p>Drift Lines _____</p> <p>Sediment Deposits _____</p> <p><input checked="" type="checkbox"/> Drainage Patterns in Wetlands</p> <p>Secondary Indicators (2 or more required):</p> <p>Oxidized Root Channels in Upper 12 Inches _____</p> <p>Water-Stained Leaves _____</p> <p>Local Soil Survey Data _____</p> <p>FAC-Neutral Test _____</p> <p>Other (Explain in Remarks) _____</p>
<p>Field Observations:</p> <p>Depth of Surface Water: _____ (in.)</p> <p>Depth to Free Water in Pit: _____ (in.)</p> <p>Depth to Saturated Soil: _____ (in.)</p>	
<p>Remarks: <u>wet pockets along drainage</u></p> <p><u>Evidence of hydrology is present</u></p>	

SOILS

Map Unit Name

(Series and Phase): Point Lexter + Zims sandy loamsDrainage Class: WD

Taxonomy (Subgroup):

Typic + ultic Hapludalfs

Field Observations

Confirm Mapped Type? Yes No

Profile Description:

Depth (Inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0-4		10YR 4/3	5YR 3/4		clay loam
4-12+		2.5Y 5/2	10YR 4/3		clay loam

Hydric Soil Indicators:

- ☐ Histosol
☐ Histia Epipedon
☐ Sulfidic Odor
☐ Aquic Moisture Regime
☐ Reducing Conditions
☒ Gleyed or Low-Chroma Colors

- ☐ Concretions
☐ High Organic Content in Surface Layer in Sandy Soils
☐ Organic Streaking in Sandy Soils
☐ Listed on Local Hydric Soils List
☐ Listed on National Hydric Soils List
☐ Other (Explain in Remarks)

Remarks:

hydric soils are present

WETLAND DETERMINATION

Hydrophytic Vegetation Present?

Yes

No (Circle)

Wetland Hydrology Present?

Yes

No

Hydric Soils Present?

Yes

No

(Circle)

Is this Sampling Point Within a Wetland?

Yes

No

Remarks:

All 3 parameters are present: site is a wetland

Approved by HQUSACE 3/92

DATA FORM
ROUTINE WETLAND DETERMINATION
 (1987 COE Wetlands Delineation Manual)

Project/Site: <u>R-2568</u> Applicant/Owner: <u>NCDOT</u> Investigator: <u>Phillip Todd, Jared Gray</u>	Date: <u>2/1/01</u> County: <u>Davidson</u> State: <u>NC</u>				
Do Normal Circumstances exist on the site? Is the site significantly disturbed (Atypical Situation)? Is the area a potential Problem Area? (If needed, explain on reverse.)	<table style="width:100%;"> <tr> <td style="text-align: center;">Yes <input checked="" type="radio"/> No <input type="radio"/></td> <td rowspan="3" style="vertical-align: middle; padding-left: 10px;"> Community ID: <u>WY-33+80</u> Transect ID: <u>upland</u> Plot ID: _____ </td> </tr> <tr> <td style="text-align: center;">Yes <input type="radio"/> No <input checked="" type="radio"/></td> </tr> <tr> <td style="text-align: center;">Yes <input type="radio"/> No <input type="radio"/></td> </tr> </table>	Yes <input checked="" type="radio"/> No <input type="radio"/>	Community ID: <u>WY-33+80</u> Transect ID: <u>upland</u> Plot ID: _____	Yes <input type="radio"/> No <input checked="" type="radio"/>	Yes <input type="radio"/> No <input type="radio"/>
Yes <input checked="" type="radio"/> No <input type="radio"/>	Community ID: <u>WY-33+80</u> Transect ID: <u>upland</u> Plot ID: _____				
Yes <input type="radio"/> No <input checked="" type="radio"/>					
Yes <input type="radio"/> No <input type="radio"/>					

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>American Beech</u>	<u>T</u>	<u>NI</u>	9. _____	_____	_____
2. <u>tulip poplar</u>	<u>T</u>	<u>FAC</u>	10. _____	_____	_____
3. <u>White oak</u>	<u>T</u>	<u>FACU</u>	11. _____	_____	_____
4. <u>Japanese honeysuckle</u>	<u>V</u>	<u>FAC-</u>	12. _____	_____	_____
5. <u>greenbrier</u>	<u>V</u>	<u>FAC</u>	13. _____	_____	_____
6. <u>Christmas Fern</u>	<u>H</u>	<u>FAC</u>	14. _____	_____	_____
7. _____	_____	_____	15. _____	_____	_____
8. _____	_____	_____	16. _____	_____	_____

Percent of Dominant Species that are OBL, FACW or FAC (excluding FAC-): 3/6 = 50%

Remarks: hydrophytic vegetation is present at sampling site

HYDROLOGY

<p>___ Recorded Data (Describe in Remarks):</p> <p style="margin-left: 20px;">___ Stream, Lake, or Tide Gauge</p> <p style="margin-left: 20px;">___ Aerial Photographs</p> <p style="margin-left: 20px;">___ Other</p> <p>___ No Recorded Data Available</p> <hr/> <p>Field Observations:</p> <p>Depth of Surface Water: _____ (in.)</p> <p>Depth to Free Water in Pit: _____ (in.)</p> <p>Depth to Saturated Soil: _____ (in.)</p>	<p>Wetland Hydrology Indicators:</p> <p>Primary Indicators:</p> <p style="margin-left: 20px;">___ Inundated</p> <p style="margin-left: 20px;">___ Saturated in Upper 12 Inches</p> <p style="margin-left: 20px;">___ Water Marks</p> <p style="margin-left: 20px;">___ Drift Lines</p> <p style="margin-left: 20px;">___ Sediment Deposits</p> <p style="margin-left: 20px;">___ Drainage Patterns in Wetlands</p> <p>Secondary Indicators (2 or more required):</p> <p style="margin-left: 20px;">___ Oxidized Root Channels in Upper 12 Inches</p> <p style="margin-left: 20px;">___ Water-Stained Leaves</p> <p style="margin-left: 20px;">___ Local Soil Survey Data</p> <p style="margin-left: 20px;">___ FAC-Neutral Test</p> <p style="margin-left: 20px;">___ Other (Explain in Remarks)</p>
Remarks: <u>No evidence of hydrology present</u>	

SOILS

Map Unit Name (Series and Phase): <u>Poinceter + Zion sandy loams</u>		Drainage Class: <u>WB</u>	
Taxonomy (Subgroup): <u>Typic + Udic Hapludolls</u>		Field Observations Confirm Mapped Type? Yes No	

Profile Description:					
Depth (inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0-2		10YR 4/2			sandy loam
2-7		2.5Y 5/4			sandy loam
7-12+		2.5Y 5/4			sandy clay loam

Hydric Soil Indicators:	
<input type="checkbox"/> Histosol <input type="checkbox"/> Histic Epipedon <input type="checkbox"/> Sulfidic Odor <input type="checkbox"/> Aquic Moisture Regime <input type="checkbox"/> Reducing Conditions <input type="checkbox"/> Gleyed or Low-Chroma Colors	<input type="checkbox"/> Concretions <input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils <input type="checkbox"/> Organic Streaking in Sandy Soils <input type="checkbox"/> Listed on Local Hydric Soils List <input type="checkbox"/> Listed on National Hydric Soils List <input type="checkbox"/> Other (Explain in Remarks)

Remarks:

hydric soils not present

WETLAND DETERMINATION

Hydrophytic Vegetation Present? <input checked="" type="radio"/> Yes <input type="radio"/> No (Circle) Wetland Hydrology Present? <input type="radio"/> Yes <input checked="" type="radio"/> No Hydric Soils Present? <input type="radio"/> Yes <input checked="" type="radio"/> No	Is this Sampling Point Within a Wetland? Yes <input checked="" type="radio"/> No
---	--

Remarks:

All 3 parameters not present at sampling site. site is not a wetland

STATION # 33+80

ALONG INTERMITTENT Stream

Site 2

ANNUAL WETLANDS

WETLAND RATING WORKSHEET (4th VERSION)

Project Name: P-2568 B County: DAVIDSON
 Forest Road: _____ Date: 2/1/01
 Wetland Area (ac): _____ Wetland Width (ft): _____
 Name of Evaluator(s): P. Todd (2001), H. Renninger (2004)

Wetland Location:

- ☐ on sound or estuary
 pond or lake
☐ on perennial stream
☒ on intermittent stream
☐ within interstream divide
☐ other _____

Adjacent Land Use:

- (Within 1/2 mi upstream,
 upslope, or radius)
80 forested/natural veg. _____ %
18 agriculture/urbanized _____ %
2 impervious surface _____ %
 Adjacent Special Natural Areas _____

Soils

- Soil Series Poindexter and Zion sandy loam
☐ predominantly organic (humus, muck or peat)
☒ predominantly mineral (non-sandy)
☐ predominantly sandy

Dominant Vegetation

- (1) Microstegium vimineum
 (2) Smilax sp.
 (3) Acer rubrum

Hydraulic Factors

- ☒ freshwater _____ brackish
☐ steep topography
☐ ditched or channelized
☐ total wetland width \geq 100 feet.

Flooding and Wetness

- ☐ semipermanently to
 permanently flooded or
 inundated
☒ seasonally flooded or
 inundated
☐ intermittently flooded or
 temporary surface water
☐ no evidence of flooding or
 surface water

Wetland Type (select one)*

- ☐ Bottomland Hardwood Forest
☐ Swamp Forest ☐ Bog/Fen
☐ Carolina Bay ☐ Headwater Forest
☐ Pocosin ☐ Bog Forest
☐ Pine Savannah ☐ Ephemeral Wetland
☐ Freshwater Marsh ☒ Other: ANNUAL FOREST

*The rating system cannot be applied to salt or brackish marshes or stream channels.

DEM RATING

WATER STORAGE	<u>3</u>	x 4.00 = <u>12</u>
BANK/ShORELINE STABILIZATION	<u>3</u>	x 4.00 = <u>12</u>
POLLUTANT REMOVAL	<u>3</u> *	x 5.00 = <u>15</u>
WILDLIFE HABITAT	<u>2</u>	x 2.00 = <u>4</u>
AQUATIC LIFE VALUE	<u>3</u>	x 4.00 = <u>12</u>
RECREATION/EDUCATION	<u>1</u>	x 1.00 = <u>1</u>

WETLAND SCORE = 56
 (TOTAL)

* Add 1 point if in sensitive watershed and >10% nonpoint disturbance within 1/2 mile upstream, upslope, or radius.

DATA FORM
ROUTINE WETLAND DETERMINATION
(1987 CDE Wetlands Delineation Manual)

Site 2a

Project/Site: <u>R-2568 B</u> Applicant/Owner: <u>NC DOT</u> Investigator: <u>Phillip Todd, Jared Gray</u>		Date: <u>1/31/01</u> County: <u>DAVIDSON</u> State: <u>NC</u>
Do Normal Circumstances exist on the site? Is the site significantly disturbed (Atypical Situation)? Is the area a potential Problem Area? (If needed, explain on reverse.)		Community ID: <u>70+80-R</u> Transect ID: <u>wetland</u> Plot ID: _____

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>Carex sp.</u>	<u>H</u>	<u>-</u>	9. _____	_____	_____
2. <u>Typha</u>	<u>H</u>	_____	10. _____	_____	_____
3. <u>Salix nigra</u>	<u>T</u>	<u>OBL</u>	11. _____	_____	_____
4. <u>Juncus</u>	<u>H</u>	_____	12. _____	_____	_____
5. <u>red maple</u>	<u>S/S</u>	<u>FAC</u>	13. _____	_____	_____
6. <u>sweet gum</u>	<u>S/S</u>	<u>FAC^x</u>	14. _____	_____	_____
7. _____	_____	_____	15. _____	_____	_____
8. _____	_____	_____	16. _____	_____	_____

Percent of Dominant Species that are OBL, FAC^x or FAC (excluding FAC⁻): _____

Remarks: prevalence of hydrophytic vegetation at sampling site

HYDROLOGY

<p>Recorded Data (Describe in Remarks):</p> <p>___ Stream, Lake, or Tide Gauge</p> <p>___ Aerial Photographs</p> <p>___ Other</p> <p>___ No Recorded Data Available</p> <hr/> <p>Field Observations:</p> <p>Depth of Surface Water: _____ (in.)</p> <p>Depth to Free Water in Pit: <u>8</u> (in.)</p> <p>Depth to Saturated Soil: <u>6</u> (in.)</p>	<p>Wetland Hydrology Indicators:</p> <p>Primary Indicators:</p> <p><input checked="" type="checkbox"/> Inundated in Areas</p> <p>___ Saturated in Upper 12 Inches</p> <p>___ Water Marks</p> <p>___ Drift Lines</p> <p>___ Sediment Deposits</p> <p><input checked="" type="checkbox"/> Drainage Patterns in Wetlands</p> <p>Secondary Indicators (2 or more required):</p> <p>___ Oxidized Root Channels in Upper 12 Inches</p> <p>___ Water-Stained Leaves</p> <p>___ Local Soil Survey Data</p> <p>___ FAC-Neutral Test</p> <p>___ Other (Explain in Remarks)</p>
<p>Remarks: <u>old Silt Basin - wet area off 450mm pipe</u> <u>stormwater - drainage below basin</u> <u>Evidence of hydrology is present at sampling site</u></p>	

SOILS

Map Unit Name

(Series and Phase): Powdexter + Zions sandy loams

Drainage Class: W3

Taxonomy (Subgroup): Typic Udic Hapludalfs

Field Observations

Confirm Mapped Type? Yes No

Profile Description:

Depth (Inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
		2.5 YR 4/2			fine sandy loam

Hydric Soil Indicators:

- ☐ Histosol
- ☐ Histosol Epipedon
- ☐ Sulfidic Odor
- ☐ Aquic Moisture Regime
- ☐ Reducing Conditions
- ☐ Gleyed or Low-Chroma Colors

- ☐ Concretions
- ☐ High Organic Content in Surface Layer in Sandy Soils
- ☐ Organic Streaking in Sandy Soils
- ☐ Listed on Local Hydric Soils List
- ☐ Listed on National Hydric Soils List
- ☐ Other (Explain in Remarks)

Remarks:

hydric soils are present

WETLAND DETERMINATION

Hydrophytic Vegetation Present?

☒ Yes No (Circle)

Wetland Hydrology Present?

☒ Yes No

Hydric Soils Present?

☒ Yes No

(Circle)

Is this Sampling Point Within a Wetland?

☒ Yes No

Remarks:

All 3 parameters are present: site is a wetland

Approved by HQUSACE 3/92

DATA FORM
ROUTINE WETLAND DETERMINATION
(1987 COE Wetlands Delineation Manual)

Site 2a

Project/Site: <u>R-2568B</u> Applicant/Owner: <u>NCDOT</u> Investigator: <u>Phillip Todd, Jared Gray</u>	Date: <u>1/31/01</u> County: <u>DAVIDSON</u> State: <u>NC</u>
Do Normal Circumstances exist on the site? <input checked="" type="radio"/> Yes <input type="radio"/> No Is the site significantly disturbed (Atypical Situation)? <input type="radio"/> Yes <input checked="" type="radio"/> No Is the area a potential Problem Area? <input type="radio"/> Yes <input checked="" type="radio"/> No (If needed, explain on reverse.)	Community ID: <u>70180-R</u> Transect ID: <u>Upland</u> Plot ID: _____

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>Tulip poplar</u>	<u>T</u>	<u>FAC</u>	9. _____	_____	_____
2. <u>Sweet gum</u>	<u>T</u>	<u>FAC+</u>	10. _____	_____	_____
3. <u>red maple</u>	<u>T</u>	<u>FAC</u>	11. _____	_____	_____
4. <u>Japanese honeysuckle</u>	<u>V</u>	<u>FAC-</u>	12. _____	_____	_____
5. <u>greenbrier</u>	<u>V</u>	<u>FAC</u>	13. _____	_____	_____
6. _____	_____	_____	14. _____	_____	_____
7. _____	_____	_____	15. _____	_____	_____
8. _____	_____	_____	16. _____	_____	_____

Percent of Dominant Species that are OBL, FACW or FAC (excluding FAC-): 4/5 = 80%

Remarks: prevalence of hydrophytic vegetation at sampling site

HYDROLOGY

<p>Recorded Data (Describe in Remarks):</p> <p><input type="checkbox"/> Stream, Lake, or Tide Gauge</p> <p><input type="checkbox"/> Aerial Photographs</p> <p><input type="checkbox"/> Other _____</p> <p><input type="checkbox"/> No Recorded Data Available</p> <hr/> <p>Field Observations:</p> <p>Depth of Surface Water: _____ (in.)</p> <p>Depth to Free Water in Pit: _____ (in.)</p> <p>Depth to Saturated Soil: _____ (in.)</p>	<p>Wetland Hydrology Indicators:</p> <p>Primary Indicators:</p> <p><input type="checkbox"/> Inundated</p> <p><input type="checkbox"/> Saturated in Upper 12 Inches</p> <p><input type="checkbox"/> Water Marks</p> <p><input type="checkbox"/> Drift Lines</p> <p><input type="checkbox"/> Sediment Deposits</p> <p><input type="checkbox"/> Drainage Patterns in Wetlands</p> <p>Secondary Indicators (2 or more required):</p> <p><input type="checkbox"/> Oxidized Root Channels in Upper 12 Inches</p> <p><input type="checkbox"/> Water-Stained Leaves</p> <p><input type="checkbox"/> Local Soil Survey Data</p> <p><input type="checkbox"/> FAC-Neutral Test</p> <p><input type="checkbox"/> Other (Explain in Remarks) _____</p>
Remarks: <u>Evidence of hydrology is not present</u>	

SOILS -

Map Unit Name

(Series and Phase): Pondexter + Zion sandy loams

Drainage Class: WD

Field Observations

Taxonomy (Subgroup): Typic + Udic Hapludalfs

Confirm Mapped Type? Yes No

Profile Description:

Depth (Inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0-3		10YR3/1			sandy loam
3-12+		2.5 Y 5/3			sandy loam

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol | <input type="checkbox"/> Concretions |
| <input type="checkbox"/> Histia Epipedon | <input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils |
| <input type="checkbox"/> Sulfidic Odor | <input type="checkbox"/> Organic Streaking in Sandy Soils |
| <input type="checkbox"/> Aquic Moisture Regime | <input type="checkbox"/> Listed on Local Hydric Soils List |
| <input type="checkbox"/> Reducing Conditions | <input type="checkbox"/> Listed on National Hydric Soils List |
| <input type="checkbox"/> Gleyed or Low-Chroma Colors | <input type="checkbox"/> Other (Explain in Remarks) |

Remarks:

hydric soils are not present at sampling site

WETLAND DETERMINATION

Hydrophytic Vegetation Present?

Yes No (Circle)

Wetland Hydrology Present?

Yes No (Circle)

Hydric Soils Present?

Yes No (Circle)

(Circle)

Is this Sampling Point Within a Wetland?

Yes No (Circle)

Remarks:

All 3 parameters are not present: site is not a wetland

Approved by HQUSACE 3/92

Project/Site: R-2568BApplicant/Owner: NC DOTInvestigator: Phillip Todd, Jared GrauDate: 10/29/00County: DAVIDSONState: NC

Do Normal Circumstances exist on the site?

Is the site significantly disturbed (Atypical Situation)?

Is the area a potential Problem Area?

(If needed, explain on reverse.)

Yes ☐ No ☒Yes ☐ No ☒Yes ☐ No ☒Community ID: 40+46 (WA)Transect ID: wetland

Plot ID: _____

headwater of pond

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. RED MAPLE	T	FAC	9.		
2. MICROSTEGIUM VINIFLUM	H	FAC+	10.		
3. JAPANESE HONEYSUCKLE	V	FAC-	11.		
4. SWEETGUM	T	FAC+	12.		
5.			13.		
6.			14.		
7.			15.		
8.			16.		

Percent of Dominant Species that are OBL, FACW or FAC (excluding FAC-): 3/4 = 75%

Remarks: prevalence of hydrophytic vegetation at sampling site.

HYDROLOGY

<p>Recorded Data (Describe in Remarks):</p> <p><input type="checkbox"/> Stream, Lake, or Tide Gauge</p> <p><input type="checkbox"/> Aerial Photographs</p> <p><input type="checkbox"/> Other</p> <p><input type="checkbox"/> No Recorded Data Available</p>	<p>Wetland Hydrology Indicators:</p> <p>Primary Indicators:</p> <p><input type="checkbox"/> Inundated</p> <p><input checked="" type="checkbox"/> Saturated in Upper 12 Inches</p> <p><input type="checkbox"/> Water Marks</p> <p><input type="checkbox"/> Drift Lines</p> <p><input type="checkbox"/> Sediment Deposits</p> <p><input checked="" type="checkbox"/> Drainage Patterns in Wetlands</p> <p>Secondary Indicators (2 or more required):</p> <p><input type="checkbox"/> Oxidized Root Channels in Upper 12 Inches</p> <p><input type="checkbox"/> Water-Stained Leaves</p> <p><input type="checkbox"/> Local Soil Survey Data</p> <p><input type="checkbox"/> FAC-Neutral Test</p> <p><input type="checkbox"/> Other (Explain in Remarks)</p>
<p>Field Observations:</p> <p>Depth of Surface Water: _____ (in.)</p> <p>Depth to Free Water in Pit: _____ (in.)</p> <p>Depth to Saturated Soil: _____ (in.)</p>	
<p>Remarks: <u>Evidence of hydrology is present at sampling site.</u></p>	

SOILS

Map Unit Name

(Series and Phase): Powdermill and Zion sandy loam

Drainage Class: WD

Taxonomy (Subgroup): Typic + Ultic Haplustalfs

Field Observations

Confirm Mapped Type? Yes No

Profile Description:

Depth (inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
		2.5 YR 4/1	7.5 YR 4/3		

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol | <input type="checkbox"/> Concretions |
| <input type="checkbox"/> Histosol Epipedon | <input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils |
| <input type="checkbox"/> Sulfidic Odor | <input type="checkbox"/> Organic Streaking in Sandy Soils |
| <input type="checkbox"/> Aquic Moisture Regime | <input type="checkbox"/> Listed on Local Hydric Soils List |
| <input type="checkbox"/> Reducing Conditions | <input type="checkbox"/> Listed on National Hydric Soils List |
| <input type="checkbox"/> Gleyed or Low-Chroma Colors | <input type="checkbox"/> Other (Explain in Remarks) |

Remarks:

Hydric soils are present at sampling site

WETLAND DETERMINATION

Hydrophytic Vegetation Present?	<input checked="" type="radio"/> Yes <input type="radio"/> No (Circle)	(Circle)
Wetland Hydrology Present?	<input checked="" type="radio"/> Yes <input type="radio"/> No	
Hydric Soils Present?	<input checked="" type="radio"/> Yes <input type="radio"/> No	
Is this Sampling Point Within a Wetland?		<input checked="" type="radio"/> Yes <input type="radio"/> No

Remarks:

All 3 parameters are present at sampling site. Site is a wetland.

Approved by HQUSACE 3/92

1-3

at 3

Project/Site: <u>R-2568 B</u>		Date: <u>10/24/00</u>
Applicant/Owner: <u>NC DOT</u>		County: <u>DAVIDSON</u>
Investigator: <u>Phillip Todd, Jared Gray</u>		State: <u>NC</u>
Do Normal Circumstances exist on the site? Is the site significantly disturbed (Atypical Situation)? Is the area a potential Problem Area? (If needed, explain on reverse.)		Yes <input checked="" type="radio"/> No <input type="radio"/> Yes <input checked="" type="radio"/> No <input type="radio"/> Yes <input checked="" type="radio"/> No <input type="radio"/> Community ID: <u>40x40 (3)</u> Transect ID: <u>upland</u> Plot ID: _____

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>Poison Ivy</u>	<u>H/V</u>	<u>FAC</u>	9. _____	_____	_____
2. <u>Japanese honeysuckle</u>	<u>V</u>	<u>FAC</u>	10. _____	_____	_____
3. <u>red maple</u>	<u>T</u>	<u>FAC</u>	11. _____	_____	_____
4. <u>Sycamore</u>	<u>T</u>	<u>FACW</u>	12. _____	_____	_____
5. <u>Loblolly pine</u>	<u>T</u>	<u>FAC</u>	13. _____	_____	_____
6. <u>trumpet creeper</u>	<u>V</u>	<u>FAC</u>	14. _____	_____	_____
7. _____	_____	_____	15. _____	_____	_____
8. _____	_____	_____	16. _____	_____	_____

Percent of Dominant Species that are OBL, FACW or FAC (excluding FAC-): 5/6 = 83%

Remarks: prevalence of hydrophytic vegetation at sampling site

HYDROLOGY

<p><input type="checkbox"/> Recorded Data (Describe in Remarks): <input type="checkbox"/> Stream, Lake, or Tide Gauge <input type="checkbox"/> Aerial Photographs <input type="checkbox"/> Other <input type="checkbox"/> No Recorded Data Available</p> <p>Field Observations:</p> <p>Depth of Surface Water: _____ (in.)</p> <p>Depth to Free Water in Pit: _____ (in.)</p> <p>Depth to Saturated Soil: _____ (in.)</p>	<p>Wetland Hydrology Indicators:</p> <p>Primary Indicators:</p> <ul style="list-style-type: none"><input type="checkbox"/> Inundated<input type="checkbox"/> Saturated in Upper 12 inches<input type="checkbox"/> Water Marks<input type="checkbox"/> Drift Lines<input type="checkbox"/> Sediment Deposits<input type="checkbox"/> Drainage Patterns in Wetlands <p>Secondary Indicators (2 or more required):</p> <ul style="list-style-type: none"><input type="checkbox"/> Oxidized Root Channels in Upper 12 inches<input type="checkbox"/> Water-Stained Leaves<input type="checkbox"/> Local Soil Survey Data<input type="checkbox"/> FAC-Neutral Test<input type="checkbox"/> Other (Explain in Remarks)
Remarks: <u>No evidence of hydrology at sampling site</u>	

SOILS

Map Unit Name (Series and Phase): <u>Powder Mill + Zion sandy loams</u>		Drainage Class: <u>WD</u>
Taxonomy (Subgroup): <u>Typic + Udic Hapludalfs</u>		Field Observations Confirm Mapped Type? Yes No

Profile Description:					
Depth (inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.

Hydric Soil Indicators:	
<input type="checkbox"/> Histosol <input type="checkbox"/> Histos Epipedon <input type="checkbox"/> Sulfide Odor <input type="checkbox"/> Aquic Moisture Regime <input type="checkbox"/> Reducing Conditions <input type="checkbox"/> Gleyed or Low-Chroma Colors	<input type="checkbox"/> Concretions <input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils <input type="checkbox"/> Organic Streaking in Sandy Soils <input type="checkbox"/> Listed on Local Hydric Soils List <input type="checkbox"/> Listed on National Hydric Soils List <input type="checkbox"/> Other (Explain in Remarks)

Remarks:

WETLAND DETERMINATION

Hydrophytic Vegetation Present?	<input checked="" type="radio"/> Yes <input type="radio"/> No (Circle)	
Wetland Hydrology Present?	<input checked="" type="radio"/> Yes <input type="radio"/> No	(Circle)
Hydric Soils Present?	<input checked="" type="radio"/> Yes <input type="radio"/> No	Is this Sampling Point Within a Wetland? Yes No

Remarks:

Approved by HQUSACE 3/92

WET AREA ASSOCIATED W/ HEAD OF POND

WETLAND RATING WORKSHEET (4th VERSION)

Project Name: P-35088 County: DAVIDSON
 Nearest Road: _____ Date: 10/24/00
 Wetland Area (ac): _____ Wetland Width (ft): _____
 Name of Evaluator(s): P. Todd (2000) H. Renninger (2004)

Wetland Location:

- ☒ on sound or estuary
☒ on pond or lake
☐ on perennial stream
☐ on intermittent stream
☐ within interstream divide
☐ other _____

Adjacent Land Use:

- (Within 1/2 mi upstream,
 upslope, or radius)
☒ 70 forested/natural veg. _____ %
☒ 20 agriculture/urbanized _____ %
☒ 10 impervious surface _____ %
 Adjacent Special Natural Areas _____

Soils

- Soil Series Poindexter and Ziem Sandy
☐ predominantly organic (humus, muck or peat) loam
☒ predominantly mineral (non-sandy)
☐ predominantly sandy

Dominant Vegetation

- (1) Acer rubrum
 (2) Microstegium vimineum
 (3) Lonicera japonica

Hydraulic Factors

- ☒ freshwater _____ brackish
☐ steep topography
☐ ditched or channelized
☐ total wetland width \geq 100 feet.

Flooding and Wetness

- ☐ semipermanently to
 permanently flooded or
 inundated
☒ seasonally flooded or
 inundated
☒ intermittently flooded or
 temporary surface water
☐ no evidence of flooding or
 surface water

Wetland Type (select one)*

- ☐ Bottomland Hardwood Forest
☐ Swamp Forest
☐ Carolina Bay
☐ Pocosin
☐ Pine Savannah
☐ Freshwater Marsh
☐ Bog/Fen
☒ Headwater Forest @ head of pond
☐ Bog Forest
☐ Ephemeral Wetland
☐ Other: _____

*The rating system cannot be applied to salt or brackish marshes or stream channels.

DEM RATING

WATER STORAGE	<u>3</u>	x 4.00 = <u>12</u>
BANK/ShORELINE STABILIZATION	<u>3</u>	x 4.00 = <u>12</u>
POLLUTANT REMOVAL	<u>1</u> *	x 5.00 = <u>5</u>
WILDLIFE HABITAT	<u>3</u>	x 2.00 = <u>6</u>
AQUATIC LIFE VALUE	<u>2</u>	x 4.00 = <u>8</u>
RECREATION/EDUCATION	<u>1</u>	x 1.00 = <u>1</u>

WETLAND SCORE = 44

(TOTAL)

* Add 1 point if in sensitive watershed and >10% nonpoint disturbance within 1/2 mile upstream, upslope, or radius.

P12

Project/Site: <u>R-2568B</u>		Date: <u>10/24/00</u>
Applicant/Owner: <u>NRDOT</u>		County: <u>DAVIDSON</u>
Investigator: <u>Phillip Todd, Jared Gray</u>		State: <u>NC</u>
Do Normal Circumstances exist on the site?		Yes <input checked="" type="radio"/> No <input type="radio"/>
Is the site significantly disturbed (Atypical Situation)?		Yes <input type="radio"/> No <input checked="" type="radio"/>
Is the area a potential Problem Area? (If needed, explain on reverse.)		Yes <input type="radio"/> No <input checked="" type="radio"/>
		Community ID: <u>50+70.6-</u>
		Transect ID: <u>Wetland</u>
		Plot ID: _____

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>Microstegium vimineum</u>	<u>H</u>	<u>FAC+</u>	9. _____	_____	_____
2. <u>Red Maple</u>	<u>T</u>	<u>FAC</u>	10. _____	_____	_____
3. <u>Sycamore</u>	<u>T</u>	<u>FACW</u>	11. _____	_____	_____
4. <u>sweetgum</u>	<u>T</u>	<u>FAC+</u>	12. _____	_____	_____
5. <u>black cherry</u>	<u>T</u>	<u>FACW</u>	13. _____	_____	_____
6. <u>box elder</u>	<u>T</u>	<u>FACW</u>	14. _____	_____	_____
7. <u>black gum</u>	<u>T</u>	<u>FAC</u>	15. _____	_____	_____
8. _____	_____	_____	16. _____	_____	_____

Percent of Dominant Species that are OBL, FACW or FAC (excluding FAC+): 6/7 = 86%

Remarks: prevalence of hydrophytic vegetation at sampling site

HYDROLOGY

<p>Recorded Data (Describe in Remarks):</p> <p><input type="checkbox"/> Stream, Lake, or Tide Gauge</p> <p><input type="checkbox"/> Aerial Photographs</p> <p><input type="checkbox"/> Other</p> <p><input checked="" type="checkbox"/> No Recorded Data Available</p>	<p>Wetland Hydrology Indicators:</p> <p>Primary Indicators:</p> <p><input type="checkbox"/> Inundated</p> <p><input type="checkbox"/> Saturated in Upper 12 Inches</p> <p><input type="checkbox"/> Water Marks</p> <p><input type="checkbox"/> Drift Lines</p> <p><input type="checkbox"/> Sediment Deposits</p> <p><input checked="" type="checkbox"/> Drainage Patterns in Wetlands</p> <p>Secondary Indicators (2 or more required):</p> <p><input type="checkbox"/> Oxidized Root Channels in Upper 12 Inches</p> <p><input type="checkbox"/> Water-Stained Leaves</p> <p><input type="checkbox"/> Local Soil Survey Data</p> <p><input type="checkbox"/> FAC-Neutral Test</p> <p><input type="checkbox"/> Other (Explain in Remarks)</p>
<p>Field Observations:</p> <p>Depth of Surface Water: <u>0</u> (in.)</p> <p>Depth to Free Water in Pit: _____ (in.)</p> <p>Depth to Saturated Soil: _____ (in.)</p>	<p>Remarks: <u>20 ft wide swath along drainage channel (10 ft either side)</u> <u>-groundwater discharge</u> <u>Evidence of hydrology is present</u></p>

SOILS

Map Unit Name

(Series and Phase): Dandexter and Zion sandy loams

Drainage Class:

WD

Taxonomy (Subgroup): Typic + Udic Hapludalfs

Field Observations

Confirm Mapped Type? Yes No

Profile Description:

Depth (inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0-12		2.5 YR 6/2	7.5 YR 3/4		sandy loam

Hydric Soil Indicators:

- ☐ Histosol
- ☐ Histia Epipedon
- ☐ Sulfidic Odor
- ☐ Aquic Moisture Regime
- ☐ Reducing Conditions
- ☒ Gleyed or Low-Chroma Colors

- ☐ Concretions
- ☐ High Organic Content in Surface Layer in Sandy Soils
- ☐ Organic Streaking in Sandy Soils
- ☐ Listed on Local Hydric Soils List
- ☐ Listed on National Hydric Soils List
- ☐ Other (Explain in Remarks)

Remarks:

hydric soils are present

WETLAND DETERMINATION

Hydrophytic Vegetation Present?

☒ Yes No (Circle)

Wetland Hydrology Present?

☒ Yes No

Hydric Soils Present?

☒ Yes No

(Circle)

Is this Sampling Point Within a Wetland?

☒ Yes No

Remarks:

All 3 parameters are present: site is a wetland

Approved by HQUSACE 3/92

Project/Site: <u>R-2568B</u>		Date: <u>10/24/00</u>
Applicant/Owner: <u>NC DOT</u>		County: <u>DAVIDSON</u>
Investigator: <u>Phillip Todd, Jared Gray</u>		State: <u>NL</u>
Do Normal Circumstances exist on the site?		Yes <input type="radio"/> No <input checked="" type="radio"/>
Is the site significantly disturbed (Atypical Situation)?		Yes <input type="radio"/> No <input checked="" type="radio"/>
Is the area a potential Problem Area?		Yes <input type="radio"/> No <input checked="" type="radio"/>
(If needed, explain on reverse.)		Community ID: <u>50+90-L</u>
		Transect ID: <u>upland</u>
		Plot ID: _____

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>AMERICAN BEECH</u>	<u>T</u>	<u>NI</u>	9. _____	_____	_____
2. <u>Red Maple</u>	<u>T</u>	<u>FAC</u>	10. _____	_____	_____
3. <u>NORTHERN RED OAK</u>	<u>T</u>	<u>FACU</u>	11. _____	_____	_____
4. <u>WHITE OAK</u>	<u>T</u>	<u>FACU</u>	12. _____	_____	_____
5. <u>SOUR WOOD</u>	<u>SIS</u>	<u>NI</u>	13. _____	_____	_____
6. <u>JAPANESE HONEYSUCKLE</u>	<u>V</u>	<u>FAC-</u>	14. _____	_____	_____
7. _____	_____	_____	15. _____	_____	_____
8. _____	_____	_____	16. _____	_____	_____

Percent of Dominant Species that are OBL, FACW or FAC (excluding FAC-): 1/5 = 20%

Remarks: hydrophytic vegetation is not prevalent at sampling site

HYDROLOGY

<p>Recorded Data (Describe in Remarks):</p> <p>____ Stream, Lake, or Tide Gauge</p> <p>____ Aerial Photographs</p> <p>____ Other</p> <p>____ No Recorded Data Available</p>	<p>Wetland Hydrology Indicators:</p> <p>Primary Indicators:</p> <p>____ Inundated</p> <p>____ Saturated in Upper 12 Inches</p> <p>____ Water Marks</p> <p>____ Drift Lines</p> <p>____ Sediment Deposits</p> <p>____ Drainage Patterns in Wetlands</p> <p>Secondary Indicators (2 or more required):</p> <p>____ Oxidized Root Channels in Upper 12 Inches</p> <p>____ Water-Stained Leaves</p> <p>____ Local Soil Survey Data</p> <p>____ FAC-Neutral Test</p> <p>____ Other (Explain in Remarks)</p>
<p>Field Observations:</p> <p>Depth of Surface Water: _____ (in.)</p> <p>Depth to Free Water in Pit: _____ (in.)</p> <p>Depth to Saturated Soil: _____ (in.)</p>	
<p>Remarks: <u>No evidence of hydrology at sampling site</u></p>	

SOILS

Map Unit Name

(Series and Phase):

Poinderter + Zion sandy loams

Drainage Class:

WD

Taxonomy (Subgroup):

Typic + Ultic Hapludalfs

Field Observations

Confirm Mapped Type? Yes No

Profile Description:

Depth (inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0-12		2.5 YR 5/3		SAND	

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol | <input type="checkbox"/> Concretions |
| <input type="checkbox"/> Histosol Epipedon | <input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils |
| <input type="checkbox"/> Sulfidic Odor | <input type="checkbox"/> Organic Streaking in Sandy Soils |
| <input type="checkbox"/> Aquic Moisture Regime | <input type="checkbox"/> Listed on Local Hydric Soils List |
| <input type="checkbox"/> Reducing Conditions | <input type="checkbox"/> Listed on National Hydric Soils List |
| <input type="checkbox"/> Gleyed or Low-Chroma Colors | <input type="checkbox"/> Other (Explain in Remarks) |

Remarks:

hydric soils not present

WETLAND DETERMINATION

Hydrophytic Vegetation Present?

Yes ☒ No (Circle)

Wetland Hydrology Present?

Yes ☒ No (Circle)

Hydric Soils Present?

Yes ☒ No (Circle)

Is this Sampling Point Within a Wetland?

Yes ☒ No (Circle)

Remarks:

All 3 parameters not present: site is not a wetland

Approved by HQUSACE 3/92

STATION # 50+90

ALONG DRAINAGE CHANNEL

Site 5

WETLAND RATING WORKSHEET (4th VERSION)

P-2568 B

Project Name: _____

County: Davidson

Nearest Road: _____

Date: 10/24/00

Wetland Area (ac): _____

Wetland Width (ft): _____

Name of Evaluator(s): P. Todd (2000)H. Renninger (2004)Wetland Location:

- ☐ on sound or estuary
☐ pond or lake
☐ on perennial stream
☐ on intermittent stream
☐ within interstream divide
☒ other ephemeral drainage

Adjacent Land Use:

(Within 1/2 mi upstream, upslope, or radius)

- 75 forested/natural veg. _____ %
20 agriculture/urbanized _____ %
5 impervious surface _____ %
 Adjacent Special Natural Areas _____

Soils

- Soil Series Poindexter and Zion sandy loam
☐ predominantly organic (humus, muck or peat)
☒ predominantly mineral (non-sandy)
☐ predominantly sandy

Dominant Vegetation

- (1) Microstegium vimineum
 (2) Acer rubrum
 (3) Platanus occidentalis

Hydraulic Factors

- ☐ freshwater ☐ brackish
☐ steep topography
☐ ditched or channelized
☐ total wetland width \geq 100 feet.

Flooding and Wetness

- ☐ semipermanently to permanently flooded or inundated
☐ seasonally flooded or inundated
☒ intermittently flooded or temporary surface water
☐ no evidence of flooding or surface water

Wetland Type (select one)*

- ☐ Bottomland Hardwood Forest
☐ Swamp Forest ☐ Bog/Fen
☐ Carolina Bay ☒ Headwater Forest
☐ Pocosin ☐ Bog Forest
☐ Pine Savannah ☐ Ephemeral Wetland
☐ Freshwater Marsh ☐ Other: _____

*The rating system cannot be applied to salt or brackish marshes or stream channels.

DEM RATING

WATER STORAGE

2x 4.00 = 8

BANK/ShORELINE STABILIZATION

3x 4.00 = 12

POLLUTANT REMOVAL

4 *x 5.00 = 20

WILDLIFE HABITAT

4x 2.00 = 8

AQUATIC LIFE VALUE

3x 4.00 = 12

RECREATION/EDUCATION

0x 1.00 = 0

WETLAND SCORE = 60
(TOTAL)

* Add 1 point if in sensitive watershed and >10% nonpoint disturbance within 1/2 mile upstream, upslope, or radius.

DATA FORM
ROUTINE WETLAND DETERMINATION
(1987 COE Wetlands Delineation Manual)

Site 7

Project/Site: R. 2569B
 Applicant/Owner: NC DOT
 Investigator: Phillip Todd, Jared Gray
 Date: 1/31/01
 County: DAVIDSON
 State: NC
 Do Normal Circumstances exist on the site? Yes No
 Is the site significantly disturbed (Atypical Situation)? Yes No
 Is the area a potential Problem Area? Yes No
 (If needed, explain on reverse.)
 Community ID: W2 6440
 Transect ID: wetland
 Plot ID: _____

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>Microstegium vimineum</u>	<u>H</u>	<u>FAC+</u>	9. _____	_____	_____
2. <u>Sycamore</u>	<u>T</u>	<u>FACW-</u>	10. _____	_____	_____
3. <u>Tulip poplar</u>	<u>T</u>	<u>FAC</u>	11. _____	_____	_____
4. <u>red maple</u>	<u>T</u>	<u>FAC</u>	12. _____	_____	_____
5. <u>Sweet gum</u>	<u>T</u>	<u>FAC+</u>	13. _____	_____	_____
6. <u>elderberry</u>	<u>S/S</u>	<u>FACW-</u>	14. _____	_____	_____
7. <u>ironwood</u>	<u>T</u>	<u>FAC</u>	15. _____	_____	_____
8. <u>box elder</u>	<u>S/S</u>	<u>FACW</u>	16. _____	_____	_____

Percent of Dominant Species that are OBL, FACW or FAC (excluding FAC+): 8/8 = 100%

Remarks: prevalence of hydrophytic vegetation at sampling site

HYDROLOGY

Recorded Data (Describe in Remarks):
 _____ Stream, Lake, or Tide Gauge
 _____ Aerial Photographs
 _____ Other
 _____ No Recorded Data Available

Field Observations:
 Depth of Surface Water: _____ (in.)
 Depth to Free Water in Pit: _____ (in.)
 Depth to Saturated Soil: _____ (in.)

Wetland Hydrology Indicators:
 Primary Indicators:
 _____ Inundated
 _____ Saturated in Upper 12 Inches
 _____ Water Marks
 _____ Drift Lines
 _____ Sediment Deposits
X Drainage Patterns in Wetlands
 Secondary Indicators (2 or more required):
X Oxidized Root Channels in Upper 12 Inches
 _____ Water-Stained Leaves
 _____ Local Soil Survey Data
 _____ FAC-Neutral Test
 _____ Other (Explain in Remarks)
X buttressed trunks

Remarks: There is evidence of hydrology at sampling site

SOILS

Map Unit Name

(Series and Phase): Painter + Zion sandy loam

Drainage Class: WD

Taxonomy (Subgroup): Typic + Ultic Hapludalfs

Field Observations

Confirm Mapped Type? Yes No

Profile Description:

Depth (inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
<u>0-1</u>		<u>10YR 4/3</u>	<u>10YR 5/6</u>	<u>M2D</u>	<u>FINE SANDY LOAM</u>
<u>1-8</u>		<u>10YR 4/3</u>			<u>SANDY LOAM</u>
<u>8-12+</u>		<u>2.5Y 5/2</u>	<u>5YR 4/6</u>		<u>SANDY CLAY LOAM</u>

Hydric Soil Indicators:

- | | |
|---|---|
| <input type="checkbox"/> Histosol | <input type="checkbox"/> Concretions |
| <input type="checkbox"/> Histosol Epipedon | <input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils |
| <input type="checkbox"/> Sulfide Odor | <input type="checkbox"/> Organic Streaking in Sandy Soils |
| <input type="checkbox"/> Aquic Moisture Regime | <input type="checkbox"/> Listed on Local Hydric Soils List |
| <input type="checkbox"/> Reducing Conditions | <input type="checkbox"/> Listed on National Hydric Soils List |
| <input checked="" type="checkbox"/> Gleyed or Low-Chroma Colors | <input type="checkbox"/> Other (Explain in Remarks) |

Remarks:

Hydric soils are present at sampling site

WETLAND DETERMINATION

Hydrophytic Vegetation Present?	<input checked="" type="radio"/> Yes No (Circle)	(Circle)
Wetland Hydrology Present?	<input checked="" type="radio"/> Yes No	
Hydric Soils Present?	<input checked="" type="radio"/> Yes No	
Is this Sampling Point Within a Wetland?		<input checked="" type="radio"/> Yes No

Remarks:

All 3 parameters are present: site is a wetland

Approved by HQUSACE 3/92

Project/Site: R-2568B
 Applicant/Owner: NC DOT
 Investigator: Phillip Todd, Jared Gray
 Date: 1/31/01
 County: DAVIDSON
 State: NC
 Do Normal Circumstances exist on the site? Yes No
 Is the site significantly disturbed (Atypical Situation)? Yes No
 Is the area a potential Problem Area? Yes No
 (If needed, explain on reverse.)
 Community ID: W2 64+40
 Transect ID: upland
 Plot ID: _____

VEGETATION

Dominant Plant Species	Stratum	Indicator	Dominant Plant Species	Stratum	Indicator
1. <u>Vitis rotundifolia</u>	<u>V</u>	<u>FAC</u>	9. _____	_____	_____
2. <u>red oak</u>	<u>T</u>	<u>FACU</u>	10. _____	_____	_____
3. <u>white oak</u>	<u>T</u>	<u>FACU</u>	11. _____	_____	_____
4. <u>japanese honeysuckle</u>	<u>V</u>	<u>FAC-</u>	12. _____	_____	_____
5. <u>red cedar</u>	<u>T</u>	<u>FACU-</u>	13. _____	_____	_____
6. _____	_____	_____	14. _____	_____	_____
7. _____	_____	_____	15. _____	_____	_____
8. _____	_____	_____	16. _____	_____	_____

Percent of Dominant Species that are OBL, FACU or FAC (excluding FAC-): 1/5 = 20%

Remarks: hydrophytic vegetation is not prevalent at sampling site

HYDROLOGY

Recorded Data (Describe in Remarks):
 _____ Stream, Lake, or Tide Gauge
 _____ Aerial Photographs
 _____ Other
 _____ No Recorded Data Available

Field Observations:
 Depth of Surface Water: _____ (in.)
 Depth to Free Water in Pit: _____ (in.)
 Depth to Saturated Soil: _____ (in.)

Wetland Hydrology Indicators:
 Primary Indicators:
 _____ Inundated
 _____ Saturated in Upper 12 Inches
 _____ Water Marks
 _____ Drift Lines
 _____ Sediment Deposits
 _____ Drainage Patterns in Wetlands
 Secondary Indicators (2 or more required):
 _____ Oxidized Root Channels in Upper 12 Inches
 _____ Water-Stained Leaves
 _____ Local Soil Survey Data
 _____ FAC-Neutral Test
 _____ Other (Explain in Remarks)

Remarks: No evidence of hydrology at sampling site

SOILS

Map Unit Name

(Series and Phase): Poinexter + Zion sandy loams

Drainage Class: WD

Taxonomy (Subgroup): Typic + ultic Hapludalfs

Field Observations

Confirm Mapped Type? Yes No

Profile Description:

Depth (inches)	Horizon	Matrix Color (Munsell Moist)	Mottle Colors (Munsell Moist)	Mottle Abundance/Contrast	Texture, Concretions, Structure, etc.
0-1		10YR 3/2			sandy loam
1-10		7.5YR 4/6	7.5YR 5/3		sandy clay loam
10-12+		7.5YR 4/6			sandy clay loam

Hydric Soil Indicators:

- | | |
|--|---|
| <input type="checkbox"/> Histosol | <input type="checkbox"/> Concretions |
| <input type="checkbox"/> Histia Epipedon | <input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils |
| <input type="checkbox"/> Sulfidic Odor | <input type="checkbox"/> Organic Streaking in Sandy Soils |
| <input type="checkbox"/> Aquic Moisture Regime | <input type="checkbox"/> Listed on Local Hydric Soils List |
| <input type="checkbox"/> Reducing Conditions | <input type="checkbox"/> Listed on National Hydric Soils List |
| <input type="checkbox"/> Gleyed or Low-Chroma Colors | <input type="checkbox"/> Other (Explain in Remarks) |

Remarks:

WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes <input checked="" type="radio"/> No <input type="radio"/> (Circle)	(Circle)
Wetland Hydrology Present?	Yes <input checked="" type="radio"/> No <input type="radio"/>	
Hydric Soils Present?	Yes <input checked="" type="radio"/> No <input type="radio"/>	
Is this Sampling Point Within a Wetland?		Yes <input checked="" type="radio"/> No <input type="radio"/>

Remarks:

All 3 parameters are not present: site is not a wetland

Approved by HQUSACE 3/92

STATION # 64+40

ALONG DRAINAGE CHANNEL
(STORMWATER DRAINAGE)

Site 9

WETLAND RATING WORKSHEET (4th VERSION)

Project Name: P-25033 County: Davidson
 Forest Road: FAIR W2 Date: 1/31/01
 Wetland Area (ac): _____ Wetland Width (ft): _____
 Name of Evaluator(s): P. Todd (2001) H. Renninger (2004)

Wetland Location:

- ☐ on sound or estuary
 pond or lake
☐ on perennial stream
☒ on intermittent stream
☐ within interstream divide
☐ other _____

Adjacent Land Use:

(Within 1/2 mi upstream,
 upslope, or radius)

- 40 forested/natural veg. _____ %
40 agriculture/urbanized _____ %
20 impervious surface _____ %
 Adjacent Special Natural Areas _____

Soils

- Soil Series Poindexter and Zion sandy
☐ predominantly organic loam
 (humus, muck or peat)
☒ predominantly mineral (non-sandy)
☐ predominantly sandy

Dominant Vegetation

- (1) Microstegium vimineum
 (2) Platanus occidentalis
 (3) Liriodendron tulipifera

Hydraulic Factors

- ☒ freshwater _____ brackish
☐ steep topography
☐ ditched or channelized
☐ total wetland width \geq 100 feet.

Flooding and Wetness

- ☐ semipermanently to
 permanently flooded or
 inundated
☐ seasonally flooded or
 inundated
☒ intermittently flooded or
 temporary surface water
☐ no evidence of flooding or
 surface water

Wetland Type (select one)*

- ☐ Bottomland Hardwood Forest
☐ Swamp Forest ☐ Bog/Fen
☐ Carolina Bay ☒ Headwater Forest
☐ Pocosin ☐ Bog Forest
☐ Pine Savannah ☐ Ephemeral Wetland
☐ Freshwater Marsh ☐ Other:

*The rating system cannot be applied to salt or brackish marshes or stream channels.

DEM RATING

WATER STORAGE

3x 4.00 = 12

BANK/ShORELINE STABILIZATION

3x 4.00 = 12

POLLUTANT REMOVAL

4 *x 5.00 = 20

WILDLIFE HABITAT

4x 2.00 = 8

AQUATIC LIFE VALUE

3x 4.00 = 12

RECREATION/EDUCATION

1x 1.00 = 1WETLAND SCORE = 65

(TOTAL)

* Add 1 point if in sensitive watershed and >10% nonpoint disturbance within 1/2 mile upstream, upslope, or radius.



STREAM QUALITY ASSESSMENT WORKSHEET



Provide the following information for the stream reach under assessment:

- Applicant's name: NC DOT
- Evaluator's name: A. Renninger
- Date of evaluation: 6-4-04
- Time of evaluation: 9:45
- Name of stream: UT Hunt's Fork Creek
- River basin: Yadkin
- Approximate drainage area:
- Stream order: 1st
- Length of reach evaluated: ~75'
- County: Davidson
- Site coordinates (if known):
- Subdivision name (if any):
- Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location): Site 1, Station 29+50 -> 30+20
- Proposed channel work (if any): 48" pipe
- Recent weather conditions: Rain this AM
- Site conditions at time of visit: cloudy, 70's, slight drizzle
- Identify any special waterway classifications known: Section 10 Tidal Waters Essential Fisheries Habitat Trout Waters Outstanding Resource Waters Nutrient Sensitive Waters Water Supply Watershed (I-IV)
- Is there a pond or lake located upstream of the evaluation point? YES (NO) If yes, estimate the water surface area:
- Does channel appear on USGS quad map? YES (NO)
- Does channel appear on USDA Soil Survey? (YES) NO
- Estimated watershed land use: 10 % Residential 10 % Commercial % Industrial 10 % Agricultural 70 % Forested % Cleared / Logged % Other ()
- Bankfull width: 4'
- Bank height (from bed to top of bank): 3'
- Channel slope down center of stream: Flat (0 to 2%) ☒ Gentle (2 to 4%) Moderate (4 to 10%) Steep (>10%)
- Channel sinuosity: Straight Occasional bends ☒ Frequent meander Very sinuous Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Total Score (from reverse): 48

Comments: Intermittent

Evaluator's Signature

This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a particular mitigation ratio or requirement. Form subject to change - version 06/03. To Comment, please call 919-876-8441 x 26.

Date 6-4-04

STREAM QUALITY ASSESSMENT WORKSHEET

	CHARACTERISTICS	Ecoregion Point Range			SCORE
		Coastal	Piedmont	Mountain	
HYDROLOGY	1. Presence of flow, persistent pools, instream flow or saturation = 0 (stream flow = max points)				2
	2. Evidence of past human alteration (erosive channel = 0, stable channel = max points)				4
	3. Riparian zone				4
	4. Incision = 0 (continuous, wide, open, no pools)				4
	5. Evidence of human or animal activity (e.g., debris, structures, etc.)				4
	6. Groundwater discharge				1
	7. Evidence of impact on stream (e.g., debris, structures, etc.)				2
	8. Evidence of human or animal activity (e.g., debris, structures, etc.)				1
	9. Evidence of human or animal activity (e.g., debris, structures, etc.)				0
	10. Evidence of human or animal activity (e.g., debris, structures, etc.)				4
STABILITY	11. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
	12. Evidence of channel incision or widening (e.g., debris, structures, etc.)				2
	13. Evidence of channel incision or widening (e.g., debris, structures, etc.)				2
	14. Evidence of channel incision or widening (e.g., debris, structures, etc.)				4
	15. Evidence of channel incision or widening (e.g., debris, structures, etc.)				2
	16. Evidence of channel incision or widening (e.g., debris, structures, etc.)				4
	17. Evidence of channel incision or widening (e.g., debris, structures, etc.)				4
	18. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
	19. Evidence of channel incision or widening (e.g., debris, structures, etc.)				3
	20. Evidence of channel incision or widening (e.g., debris, structures, etc.)				5
HABITAT	21. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
	22. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
	23. Evidence of channel incision or widening (e.g., debris, structures, etc.)				0
	24. Evidence of channel incision or widening (e.g., debris, structures, etc.)				0
	25. Evidence of channel incision or widening (e.g., debris, structures, etc.)				0
	26. Evidence of channel incision or widening (e.g., debris, structures, etc.)				0
	27. Evidence of channel incision or widening (e.g., debris, structures, etc.)				0
	28. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
	29. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
	30. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
BIOLOGY	31. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
	32. Evidence of channel incision or widening (e.g., debris, structures, etc.)				1
Total Points Possible					100
TOTAL SCORE (also enter on last page)					48

* These characteristics are not assessed in coastal streams.

NCDWQ Stream Classification Form

Project Name: R-2568B River Basin: Yadkin

County: Dawson Evaluator: Jim Buggs

DWQ Project Number:

Nearest Named Stream: Huntsfork Creek

Latitude:

Signature: Jim Buggs

Date: 6-4-04

USGS QUAD: High Point West

Longitude:

Location/Directions: Site 1, St. 29+50

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	1	2	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	1	2	3
3) Are Natural Levees Present?	0	1	2	3
4) Is The Channel Sinuous?	0	1	2	3
5) Is There An Active (Or Relic) Floodplain Present?	0	1	2	3
6) Is The Channel Braided?	0	1	2	3
7) Are Recent Alluvial Deposits Present?	0	1	2	3
8) Is There A Bankfull Bench Present?	0	1	2	3
9) Is A Continuous Bed & Bank Present?	0	1	2	3
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	No=0		

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 9

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	1	2	3

PRIMARY HYDROLOGY INDICATOR POINTS: 1

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	0	1	2	3
2) Are Rooted Plants Present In Streambed?	0	1	2	3
3) Is Periphyton Present?	0	1	2	3
4) Are Bivalves Present?	0	1	2	3

PRIMARY BIOLOGY INDICATOR POINTS: 6

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Head Cut Present In Channel?	0	.5	1	1.5
2) Is There A Grade Control Point In Channel?	0	.5	1	1.5
3) Does Topography Indicate A Natural Drainage Way?	0	.5	1	1.5

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 3

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf litter Present In Streambed?	1.5	1	.5	0
2) Is Sediment On Plants (Or Debris) Present?	0	.5	1	1.5
3) Are Wrack Lines Present?	0	.5	1	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	0	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	.5	1	1.5
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5	No=0		

SECONDARY HYDROLOGY INDICATOR POINTS: 4


rain < 1 hr ago

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fish Present?	0	.5	1	1.5
2) Are Amphibians Present?	0	.5	1	1.5
3) Are Aquatic Turtles Present?	0	.5	1	1.5
4) Are Crayfish Present?	0	.5	1	1.5
5) Are Macroinvertebrates Present?	0	.5	1	1.5
6) Are Iron Oxidizing Bacteria/Fungus Present?	0	.5	1	1.5
7) Is Filamentous Algae Present?	0	.5	1	1.5
8) Are Wetland Plants In Streambed?	SAV 2	Mostly OBL 1	Mostly FACW .75	Mostly FACU 0
(*NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)				

SECONDARY BIOLOGY INDICATOR POINTS: 2

N/A

TOTAL POINTS (Primary + Secondary) = 22.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).



STREAM QUALITY ASSESSMENT WORKSHEET



Provide the following information for the stream reach under assessment:

1. Applicant's name: NCDOT
2. Evaluator's name: H. Penninger
3. Date of evaluation: 6-4-04
4. Time of evaluation: 11:30
5. Name of stream: UT Hunts Fork Creek
6. River basin: Jackson
7. Approximate drainage area: _____
8. Stream order: 1st
9. Length of reach evaluated: 200'
10. County: Davidson
11. Site coordinates (if known): _____
12. Subdivision name (if any): _____
13. Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location):
Site 2, Station 33+55 → 33+80
14. Proposed channel work (if any): 48" pipe
15. Recent weather conditions: drizzle all morning
16. Site conditions at time of visit: raining
17. Identify any special waterway classifications known: _____ Section 10 _____ Tidal Waters _____ Essential Fisheries Habitat
_____ Trout Waters _____ Outstanding Resource Waters _____ Nutrient Sensitive Waters _____ Water Supply Watershed _____ (I-IV)
18. Is there a pond or lake located upstream of the evaluation point? YES (NO) If yes, estimate the water surface area: _____
19. Does channel appear on USGS quad map? YES (NO)
20. Does channel appear on USDA Soil Survey? (YES) NO
21. Estimated watershed land use: 10% Residential _____ % Commercial _____ % Industrial _____ % Agricultural
80% Forested 10% Cleared / Logged _____ % Other (_____)
22. Bankfull width: 2'
23. Bank height (from bed to top of bank): 1 - 3'
24. Channel slope down center of stream: _____ Flat (0 to 2%) X Gentle (2 to 4%) _____ Moderate (4 to 10%) _____ Steep (>10%)
25. Channel sinuosity: _____ Straight X Occasional bends _____ Frequent meander _____ Very sinuous _____ Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Total Score (from reverse): 48

Comments: Intermittent

Evaluator's Signature: Heath Penninger

Date: 6-4-04

This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a particular mitigation ratio or requirement. Form subject to change - version 06/03. To Comment, please call 919-876-8441 x 26.

STREAM QUALITY ASSESSMENT WORKSHEET

	CHARACTERISTICS	SCORE/POINT RANGE			SCORE
		Coastal	Piedmont	Mountain	
PHYSICAL	Presence of flow persisting pools in stream (no flow or saturation = 0, slow flow = max points)				1
	Presence of patchiness of stream (extensive channelization = 0, no channelization = max points)				4
	Rap/run zone (no rap/run = 0, continuous rap/run = max points)				4
	Presence of riffles or scour holes (evidence of riffles or scour holes = 0, no riffles or scour holes = max points)				4
	Groundwater discharge (no discharge = 0, some discharge = 1, full discharge = max points)				2
	Presence of adjacent floodplain (no floodplain = 0, extensive floodplain = max points)				3
	Extent of adjacent floodplain access (no access = 0, some access = 1, full access = max points)				3
	Presence of adjacent wetlands (no wetlands = 0, some wetlands = 1, full wetlands = max points)				1
	Channel sinuosity (extensive channelization or natural channel = 0, no sinuosity = max points)				3
	SEDIMENT	Sediment input (no sediment input = 0, little sediment = 1, max sediment = max points)			
Natural riparian channel bed material (no riparian bed material = 0, some riparian bed material = 1, max riparian bed material = max points)					1
Evidence of channel incision or widening (no incision or widening = 0, some incision or widening = 1, max incision or widening = max points)					2
Presence of large boulders (no boulders = 0, some boulders = 1, max boulders = max points)					4
Root depth and density of banks (no roots = 0, some roots = 1, max roots = max points)					2
Impact by agriculture, livestock, or timber production (no impact = 0, some impact = 1, max impact = max points)					0
Presence of stable pool/multi-pool complex (no stable pool/multi-pool complex = 0, some stable pool/multi-pool complex = 1, max stable pool/multi-pool complex = max points)					1
Habitat complexity (no habitat complexity = 0, some habitat complexity = 1, max habitat complexity = max points)					2
Canopy cover over streambed (no canopy cover = 0, some canopy cover = 1, max canopy cover = max points)					5
BIOLOGY		Substrate embeddedness (no embeddedness = 0, some embeddedness = 1, max embeddedness = max points)			
	Presence of stream invertebrates (see page 4) (no evidence = 0, common invertebrates = 1, max invertebrates = max points)				0
	Presence of amphibians (no evidence = 0, common invertebrates = 1, max invertebrates = max points)				0
	Presence of fish (no evidence = 0, common invertebrates = 1, max invertebrates = max points)				0
	Evidence of wildlife use (no evidence = 0, abundant evidence = 1, max evidence = max points)				1
	Total Points Possible	100	100	100	
TOTAL SCORE (also enter on first page)					48

* These characteristics are not assessed in coastal streams.

(2) **NCDWQ Stream Classification Form**

Project Name: R-2568B

River Basin: Yadkin

County: Davidson Evaluator:

DWQ Project Number:

Nearest Named Stream: Hunters Creek

Latitude:

Signature: Tim Bassette

Date: 6-4-04

USGS QUAD:

Longitude:

Location/Directions:

HighPoint West

SI. 33+55

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology

	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	1	2	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	1	2	3
3) Are Natural Levees Present?	0	1	2	3
4) Is The Channel Sinuous?	0	1	2	3
5) Is There An Active (Or Relic) Floodplain Present?	0	1	2	3
6) Is The Channel Braided?	0	1	2	3
7) Are Recent Alluvial Deposits Present?	0	1	2	3
8) Is There A Bankfull Bench Present?	0	1	2	3
9) Is A Continuous Bed & Bank Present?	0	1	2	3
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	No=0		

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 5

II. Hydrology

	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	1	2	3

PRIMARY HYDROLOGY INDICATOR POINTS: 1

III. Biology

	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	0	2	1	0
2) Are Rooted Plants Present In Streambed?	0	2	1	0
3) Is Periphyton Present?	0	1	2	3
4) Are Bivalves Present?	0	1	2	3

PRIMARY BIOLOGY INDICATOR POINTS: 6

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology

	Absent	Weak	Moderate	Strong
1) Is There A Head Cut Present In Channel?	0	.5	1	1.5
2) Is There A Grade Control Point In Channel?	0	.5	1	1.5
3) Does Topography Indicate A Natural Drainage Way?	0	.5	1	1.5

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 3

II. Hydrology

	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf Litter Present In Streambed?	1.5	1	.5	0
2) Is Sediment On Plants (Or Debris) Present?	0	.5	1	1.5
3) Are Wrack Lines Present?	0	.5	1	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	0	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	.5	1	1.5
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5	No=0		

SECONDARY HYDROLOGY INDICATOR POINTS: 3.0

III. Biology

	Absent	Weak	Moderate	Strong
1) Are Fish Present?	0	.5	1	1.5
2) Are Amphibians Present?	0	.5	1	1.5
3) Are Aquatic Turtles Present?	0	.5	1	1.5
4) Are Crayfish Present?	0	.5	1	1.5
5) Are Macroinvertebrates Present?	0	.5	1	1.5
6) Are Iron Oxidizing Bacteria/Fungus Present?	0	.5	1	1.5
7) Is Filamentous Algae Present?	0	.5	1	1.5
8) Are Wetland Plants In Streambed?	SAV 2	Mostly OBL 1	Mostly FACW .75	Mostly FAC .5
(*NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)				
			Mostly FACU 0	Mostly UPL 0

SECONDARY BIOLOGY INDICATOR POINTS: 0.5

TOTAL POINTS (Primary + Secondary) = 18.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).



STREAM QUALITY ASSESSMENT WORKSHEET



Provide the following information for the stream reach under assessment:

1. Applicant's name: NC DOT
2. Evaluator's name: H. Renninger
3. Date of evaluation: 6-4-04
4. Time of evaluation: 12:30
5. Name of stream: UT Rich Fork Creek
6. River basin: Yadkin
7. Approximate drainage area: —
8. Stream order: 1st
9. Length of reach evaluated: ~ 300'
10. County: Davidson
11. Site coordinates (if known): —
12. Subdivision name (if any): —
13. Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location): Site 3A, Station 43+70 → 44+60
14. Proposed channel work (if any): 66" pipe
15. Recent weather conditions: rain all AM
16. Site conditions at time of visit: raining
17. Identify any special waterway classifications known: ☐ Section 10 ☐ Tidal Waters ☐ Essential Fisheries Habitat ☐ Trout Waters ☐ Outstanding Resource Waters ☐ Nutrient Sensitive Waters ☐ Water Supply Watershed ☐ (I-IV)
18. Is there a pond or lake located upstream of the evaluation point? YES NO If yes, estimate the water surface area: —
19. Does channel appear on USGS quad map? YES ☒ NO
20. Does channel appear on USDA Soil Survey? YES ☒ NO
21. Estimated watershed land use: 60% Residential —% Commercial —% Industrial 25% Agricultural 25% Forested —% Cleared / Logged —% Other (—)
22. Bankfull width: 2-4'
23. Bank height (from bed to top of bank): 2-4'
24. Channel slope down center of stream: ☐ Flat (0 to 2%) ☐ Gentle (2 to 4%) ☒ Moderate (4 to 10%) ☐ Steep (>10%)
25. Channel sinuosity: ☐ Straight ☐ Occasional bends ☒ Frequent meander ☐ Very sinuous ☐ Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Score (from reverse): 57 Comments: low water quality; many septic systems uphill; scoured channel downstream
Perennial

Evaluator's Signature

H. Renninger

Date

6-4-04

This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a final mitigation ratio or requirement. Form subject to change – version 06/03. To Comment, please call 919-876-8441 x 26.

STREAM QUALITY ASSESSMENT WORKSHEET

#	CHARACTERISTICS	ECOREGION POINT RANGE			SCORE
		Coastal	Piedmont	Mountain	
1	Presence of flow (persistent pools in stream) (no flow or saturation = 0; strong flow = max points)		0-2	0-5	3
2	Evidence of past human alteration (extensive alteration = 0; no alteration = max points)	0-16	0-5	0-5	4
3	Riparian zone (no buffer = 0; continuous wide buffer = max points)	0-16	0-4	0-15	3
4	Evidence of nutrient or chemical discharges (extensive discharges = 0; no discharges = max points)	0-5	0-4	0-5	1
5	Groundwater discharge (no discharge = 0; springs, seeps, wells, etc. = max points)	0-5	0-2	0-4	2
6	Presence of adjacent floodplain (no floodplain = 0; extensive floodplain = max points)	0-1	0-4	0-2	1
7	Entrenchment/floodplain access (deeply entrenched = 0; frequent flooding = max points)	0-5	0-4	0-2	2
8	Presence of adjacent wetlands (no wetlands = 0; large adjacent wetlands = max points)	0	0-2	0-5	0
9	Channel sinuosity (extensive channelization = 0; natural meander = max points)	0-5	0-2	0-2	2
10	Sediment input (extensive deposition = 0; little or no sediment = max points)	0	0-4	0-4	4
11	Size & diversity of channel bed substrate (fine, homogenous = 0; large, diverse sizes = max points)	0	0-4	0-5	4
12	Evidence of channel incision or widening (deeply incised = 0; stable bank & banks = max points)	0-5	0-4	0-5	1
13	Presence of major bank failures (severe erosion = 0; no erosion, stable banks = max points)	0-5	0-5	0-5	3
14	Root depth and density on banks (no visible roots = 0; dense roots throughout = max points)	0-3	0-4	0-5	2
15	Impact by agriculture, livestock, or timber production (substantial impact = 0; no evidence = max points)	0-5	0-4	0-5	4
16	Presence of riffle-pool/ripple-pool complexes (no riffles/pools or pools = 0; well developed = max points)	0-3	0-5	0-5	4
17	Habitat complexity (little or no habitat = 0; frequent varied habitats = max points)	0-6	0-4	0-6	4
18	Canopy coverage over streambed (no shading vegetation = 0; continuous canopy = max points)	0-5	0-5	0-5	5
19	Substrate embeddedness (deeply embedded = 0; loose structure = max)	N/A	0-15	0-4	3
20	Presence of stream invertebrates (see page 4) (no evidence = 0; common, numerous types = max points)	0-4	0-5	0-5	2
21	Presence of amphibians (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	3
22	Presence of fish (no evidence = 0; common, numerous types = max points)	0	0-4	0-4	0
23	Evidence of wildlife use (no evidence = 0; abundant evidence = max points)	0-6	0-5	0-2	0
Total Points Possible		100	100	100	
TOTAL SCORE (also enter on first page)					57

* These characteristics are not assessed in coastal streams.

NCDWQ Stream Classification Form

Project Name: R-2568B River Basin: Yadkin
 DWQ Project Number: _____
 Date: 6-4-04 Nearest Named Stream: Richfork Creek
 USGS QUAD: Highpoint West

County: Davidson Evaluator: Tim Bassette
 Latitude: _____ Signature: Tim Bassette
 Longitude: _____ Location/Directions: St. 43 + 70

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	1	(2)	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	(0)	1	2	(3)
3) Are Natural Levees Present?	(0)	1	2	3
4) Is The Channel Sinuous?	0	1	(2)	3
5) Is There An Active (Or Relic) Floodplain Present?	0	1	(2)	3
6) Is The Channel Braided?	(0)	1	2	3
7) Are Recent Alluvial Deposits Present?	(0)	1	2	3
8) Is There A Bankfull Bench Present?	0	1	2	(3)
9) Is A Continuous Bed & Bank Present?	0	1	2	(3)
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	No=0		
PRIMARY GEOMORPHOLOGY INDICATOR POINTS: <u>15</u>				

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	(1)	2	3
PRIMARY HYDROLOGY INDICATOR POINTS: <u>1</u>				

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	(3)	2	1	0
2) Are Rooted Plants Present In Streambed?	(3)	2	1	0
3) Is Periphyton Present?	(0)	1	2	3
4) Are Bivalves Present?	(0)	1	2	3
PRIMARY BIOLOGY INDICATOR POINTS: <u>6</u>				

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
w/in ROW → 1) Is There A Head Cut Present In Channel?	(0)	.5	1	1.5
2) Is There A Grade Control Point In Channel?	0	.5	1	(1.5)
3) Does Topography Indicate A Natural Drainage Way?	0	.5	1	(1.5)
SECONDARY GEOMORPHOLOGY INDICATOR POINTS: <u>3</u>				

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf litter Present In Streambed?	1.5	(1)	.5	0
2) Is Sediment On Plants (Or Debris) Present?	(0)	.5	1	1.5
3) Are Wrack Lines Present?	0	(.5)	1	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	(0)	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	.5	(1)	1.5
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5	No=0		
SECONDARY HYDROLOGY INDICATOR POINTS: <u>4</u>				

2/A

III. Biology	Absent	Weak	Moderate	Strong		
1) Are Fish Present?	0	.5	1	1.5		
2) Are Amphibians Present?	0	.5	1	1.5		
3) Are Aquatic Turtles Present?	0	.5	1	1.5		
4) Are Crayfish Present?	0	.5	1	1.5		
5) Are Macroinvertebrates Present?	0	.5	1	1.5		
6) Are Iron Oxidizing Bacteria/Fungus Present?	0	.5	1	1.5		
7) Is Filamentous Algae Present?	0	.5	1	1.5		
8) Are Wetland Plants In Streambed?	SAV	Mostly OBL	Mostly FACW	Mostly FAC	Mostly FACU	Mostly UPL
(* NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)	2	1	.75	.5	0	0

SECONDARY BIOLOGY INDICATOR POINTS: 2.5

TOTAL POINTS (Primary + Secondary) = 31.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).



STREAM QUALITY ASSESSMENT WORKSHEET



Provide the following information for the stream reach under assessment:

1. Applicant's name: NCDOT
2. Evaluator's name: H. Renninger
3. Date of evaluation: 6-4-04
4. Time of evaluation: 1:30
5. Name of stream: UT Rock Fork Creek
6. River basin: Yadkin
7. Approximate drainage area: _____
8. Stream order: 2nd
9. Length of reach evaluated: ~200'
10. County: Davidson
11. Site coordinates (if known): _____
12. Subdivision name (if any): _____
13. Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location):
Site 4; Station 46+60 → 47+80
14. Proposed channel work (if any): 11' x 8' RCBC
15. Recent weather conditions: no rain past 24h rain all AM
16. Site conditions at time of visit: raining
17. Identify any special waterway classifications known: _____ Section 10 _____ Tidal Waters _____ Essential Fisheries Habitat
_____ Trout Waters _____ Outstanding Resource Waters _____ Nutrient Sensitive Waters _____ Water Supply Watershed _____ (I-IV)
18. Is there a pond or lake located upstream of the evaluation point? YES NO If yes, estimate the water surface area: _____
19. Does channel appear on USGS quad map? YES NO
20. Does channel appear on USDA Soil Survey? YES NO
21. Estimated watershed land use: 20 % Residential _____ % Commercial _____ % Industrial 5 % Agricultural
60 % Forested 15 % Cleared / Logged _____ % Other (_____)
22. Bankfull width: 7-8'
23. Bank height (from bed to top of bank): 3-4'
24. Channel slope down center of stream: _____ Flat (0 to 2%) X Gentle (2 to 4%) _____ Moderate (4 to 10%) _____ Steep (>10%)
25. Channel sinuosity: _____ Straight _____ Occasional bends X Frequent meander _____ Very sinuous _____ Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Total Score (from reverse): 48 Comments: lots of suspended sediment in water; milky appearance since from adjacent dirt road
Perennial

Evaluator's Signature Heath Henry

Date 6-4-04

This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a particular mitigation ratio or requirement. Form subject to change – version 06/03. To Comment, please call 919-876-8441 x 26.

STREAM QUALITY ASSESSMENT WORKSHEET

#	CHARACTERISTICS	ECOREGION POINT RANGE			SCORE
		Coastal	Piedmont	Mountain	
PHYSICAL	1. Presence of flow / persistent pools in stream (no flow or saturation = 0; strong flow = max points)	0-5	0-4	0-5	4
	2. Evidence of past human alteration (extensive alteration = 0; no alteration = max points)	0-6	0-5	0-5	2.2
	3. Riparian zone (no buffer = 0; continuous, wide buffer = max points)	0-6	0-4	0-5	2
	4. Evidence of nutrient or chemical discharges (extensive discharges = 0; no discharges = max points)	0-5	0-4	0-4	3
	5. Groundwater discharge (no discharge = 0; springs, seeps, wetlands, etc. = max points)	0-5	0-4	0-4	3
	6. Presence of adjacent floodplain (no floodplain = 0; extensive floodplain = max points)	0-4	0-4	0-2	4
	7. Entrenchment / floodplain access (deeply entrenched = 0; frequent flooding = max points)	0-5	0-4	0-2	2
	8. Presence of adjacent wetlands (no wetlands = 0; large adjacent wetlands = max points)	0-6	0-4	0-2	0
	9. Channel sinuosity (extensive channelization = 0; natural meander = max points)	0-5	0-4	0-3	2
	10. Sediment input (extensive deposition = 0; little or no sediment = max points)	0-5	0-4	0-4	0
	STABILITY	11. Size & diversity of channel bed substrate (fine, homogenous = 0; large, diverse sizes = max points)	N/A	0-4	0-5
12. Evidence of channel incision or widening (deeply incised = 0; stable bed & banks = max points)		0-5	0-4	0-5	2
13. Presence of major bank failures (severe erosion = 0; no erosion, stable banks = max points)		0-5	0-5	0-5	2
14. Root depth and density on banks (no visible roots = 0; dense roots throughout = max points)		0-5	0-4	0-5	1
15. Impact by agriculture, livestock for timber production (substantial impact = 0; no evidence = max points)		0-5	0-4	0-5	1
HABITAT	16. Presence of riffle-pool-ripple-pool complexes (no riffles, ripples or pools = 0; well developed = max points)	0-2	0-5	0-6	3
	17. Habitat complexity (little or no habitat = 0; frequent, varied habitats = max points)	0-6	0-6	0-6	4
	18. Canopy coverage over streambed (no shading vegetation = 0; continuous canopy = max points)	0-5	0-5	0-5	5
BIOLOGY	19. Substrate embeddedness (deeply embedded = 0; loose structure = max)	N/A	0-4	0-4	2
	20. Presence of stream invertebrates (see page 4) (no evidence = 0; common, numerous types = max points)	0-4	0-5	0-5	3
	21. Presence of amphibians (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	1
	22. Presence of fish (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
	23. Evidence of wildlife use (no evidence = 0; abundant evidence = max points)	0-6	0-5	0-5	1
Total Points Possible		100	100	100	
TOTAL SCORE (also enter on first page)					48

* These characteristics are not assessed in coastal streams.

(4) **NCDWQ Stream Classification Form**

Project Name: R2568B

River Basin: Yadkin

County: Davidson

Evaluator: Tim Bassette

DWQ Project Number:

Nearest Named Stream: Rich Fork Creek

Latitude:

Signature: Tim Bassette

Date: 6-4-04

USGS QUAD: High Point West

Longitude:

Location/Directions:

St. 46+60

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	1	(2)	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	1	(2)	3
3) Are Natural Levees Present?	(0)	1	2	3
4) Is The Channel Sinuous?	0	1	(2)	3
5) Is There An Active (Or Relic) Floodplain Present?	0	1	2	(3)
6) Is The Channel Braided?	(0)	1	2	3
7) Are Recent Alluvial Deposits Present?	0	1	(2)	3
8) Is There A Bankfull Bench Present?	0	1	2	(3)
9) Is A Continuous Bed & Bank Present?	0	1	2	(3)
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3		No=0	

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 17

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	1	(2)	3

PRIMARY HYDROLOGY INDICATOR POINTS: 2

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	(3)	2	1	0
2) Are Rooted Plants Present In Streambed?	(3)	2	1	0
3) Is Periphyton Present?	(0)	1	2	3
4) Are Bivalves Present?	(0)	1	2	3

PRIMARY BIOLOGY INDICATOR POINTS: 6

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Head Cut Present In Channel?	(0)	.5	1	1.5
2) Is There A Grade Control Point In Channel?	0	.5	(1)	1.5
3) Does Topography Indicate A Natural Drainage Way?	0	.5	1	(1.5)

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 2.5

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf litter Present In Streambed?	(1.5)	1	.5	0
2) Is Sediment On Plants (Or Debris) Present?	0	.5	1	(1.5)
3) Are Wrack Lines Present?	0	(.5)	1	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	0	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	.5	1	(1.5)
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5		No=0	

SECONDARY HYDROLOGY INDICATOR POINTS: 6.5

III. Biology	Absent	Weak	Moderate	Strong		
1) Are Fish Present?	0	.5	1	1.5		
2) Are Amphibians Present?	0	.5	1	1.5		
3) Are Aquatic Turtles Present?	0	.5	1	1.5		
4) Are Crayfish Present?	0	.5	1	1.5		
5) Are Macroinvertebrates Present?	0	.5	1	1.5		
6) Are Iron Oxidizing Bacteria/Fungus Present?	0	.5	1	1.5		
7) Is Filamentous Algae Present?	0	.5	1	1.5		
8) Are Wetland Plants In Streambed?	SAV	Mostly OBL	Mostly FACW	Mostly FAC	Mostly FACU	Mostly UPL
(* NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)						
	2	1	.75	.5	0	0

SECONDARY BIOLOGY INDICATOR POINTS: 1.5

TOTAL POINTS (Primary + Secondary) = 35.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).



STREAM QUALITY ASSESSMENT WORKSHEET

6



Provide the following information for the stream reach under assessment:

1. Applicant's name: NCDOT
2. Evaluator's name: Tim Bassette
3. Date of evaluation: 6-4-04
4. Time of evaluation: 2:00pm
5. Name of stream: UT Rich Fork Creek
6. River basin: Yadkin
7. Approximate drainage area: _____
8. Stream order: 1st
9. Length of reach evaluated: 500ft
10. County: Dawson
11. Site coordinates (if known): _____
12. Subdivision name (if any): _____
13. Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location): Sto 6 (2 aftern); Stations 10+60 → 11+00 - Y10 and 55+60 → 56+00 - L
14. Proposed channel work (if any): 24" Pipe and 30" pipe
15. Recent weather conditions: no rain for 24 h. just rained
16. Site conditions at time of visit: drizzly, cloudy, 80°F.
17. Identify any special waterway classifications known: _____ Section 10 _____ Tidal Waters _____ Essential Fisheries Habitat _____ Trout Waters _____ Outstanding Resource Waters _____ Nutrient Sensitive Waters _____ Water Supply Watershed _____ (I-IV)
18. Is there a pond or lake located upstream of the evaluation point? YES ☒ NO ☐ If yes, estimate the water surface area: _____
19. Does channel appear on USGS quad map? YES ☒ NO ☐
20. Does channel appear on USDA Soil Survey? YES ☒ NO ☐
21. Estimated watershed land use: 20% Residential _____ % Commercial _____ % Industrial 10% Agricultural 70% Forested _____ % Cleared / Logged _____ % Other (_____)
22. Bankfull width: 1ft - 3ft
23. Bank height (from bed to top of bank): 6 in - 2 ft
24. Channel slope down center of stream: ☒ Flat (0 to 2%) ☒ Gentle (2 to 4%) ☒ Moderate (4 to 10%) ☐ Steep (>10%)
25. Channel sinuosity: ☐ Straight ☒ Occasional bends ☐ Frequent meander ☐ Very sinuous ☐ Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Total Score (from reverse): 39 Comments: intermittent
The same stream is crossed twice by the project.

Evaluator's Signature

Tim Bassette

Date 6-4-04

This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a particular mitigation ratio or requirement. Form subject to change – version 06/03. To Comment, please call 919-876-8441 x 26.

STREAM QUALITY ASSESSMENT WORKSHEET

#	CHARACTERISTICS	ECOREGION POINT RANGE			SCORE
		Coastal	Piedmont	Mountain	
PHYSICAL	1. Presence of flow / persistent pools in stream (no flow or saturation = 0; strong flow = max points)	0-5	0-4	0-5	2
	2. Evidence of past human alteration (extensive alteration = 0; no alteration = max points)	0-6	0-5	0-5	1
	3. Riparian zone (no buffer = 0; contiguous, wide buffer = max points)	0-6	0-4	0-5	3
	4. Evidence of nutrient or chemical discharges (extensive discharges = 0; no discharges = max points)	0-5	0-4	0-4	1
	5. Groundwater discharge (no discharge = 0; springs, seeps, wetlands, etc. = max points)	0-3	0-4	0-4	2
	6. Presence of adjacent floodplain (no floodplain = 0; extensive floodplain = max points)	0-4	0-4	0-2	2
	7. Entrenchment / floodplain access (deeply entrenched = 0; frequent flooding = max points)	0-5	0-4	0-2	2
	8. Presence of adjacent wetlands (no wetlands = 0; large adjacent wetlands = max points)	0-6	0-4	0-2	0
	9. Channel sinuosity (extensive channelization = 0; natural meander = max points)	0-2	0-4	0-3	1
	10. Sediment input (extensive deposition = 0; little or no sediment = max points)	0-5	0-4	0-4	2
	11. Size & diversity of channel bed substrate (fine, homogenous = 0; large, diverse sizes = max points)	NA*	0-4	0-5	2
STABILITY	12. Evidence of channel incision or widening (deeply incised = 0; stable bed & banks = max points)	0-5	0-4	0-5	2
	13. Presence of major bank failures (severe erosion = 0; no erosion, stable banks = max points)	0-5	0-5	0-5	2
	14. Root depth and density on banks (no visible roots = 0; dense roots throughout = max points)	0-3	0-4	0-5	3
	15. Impact by agriculture, livestock or timber production (substantial impact = 0; no evidence = max points)	0-5	0-4	0-5	3
	16. Presence of riffle-pool/ripple-pool complexes (no riffles/ripples or pools = 0; well developed = max points)	0-3	0-5	0-6	0
HABITAT	17. Habitat complexity (little or no habitat = 0; frequent, varied habitats = max points)	0-6	0-6	0-6	1
	18. Canopy coverage over streambed (no shading vegetation = 0; continuous canopy = max points)	0-3	0-5	0-5	2
	19. Substrate embeddedness (deeply embedded = 0; loose structure = max)	NA*	0-4	0-4	2
BIOLOGY	20. Presence of stream invertebrates (See page 4) (no evidence = 0; common, numerous types = max points)	0-4	0-5	0-5	4
	21. Presence of amphibians (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
	22. Presence of fish (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
	23. Evidence of wildlife use (no evidence = 0; abundant evidence = max points)	0-6	0-5	0-5	2
Total Points Possible		100	100	100	
TOTAL SCORE (also enter on first page)					39

* These characteristics are not assessed in coastal streams.

NCDWQ Stream Classification Form

Project Name: R-2568B

River Basin: Yadkin

County: Davidson

Evaluator: Tim Bassett

DWQ Project Number:

Nearest Named Stream:

Latitude:

Signature: Tim Bassett

Date: 6-4-04

USGS QUAD:

Longitude:

Location/Directions:

Rich Fork Creek
High Point West

SF. 10+60-Y10
and SF+60-L-

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	1	2	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	1	2	3
3) Are Natural Levees Present?	0	1	2	3
4) Is The Channel Sinuous?	0	1	2	3
5) Is There An Active (Or Relic) Floodplain Present?	0	1	2	3
6) Is The Channel Braided?	0	1	2	3
7) Are Recent Alluvial Deposits Present?	0	1	2	3
8) Is There A Bankfull Bench Present?	0	1	2	3
9) Is A Continuous Bed & Bank Present?	0	1	2	3
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	No=0		

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 6

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	1	2	3

PRIMARY HYDROLOGY INDICATOR POINTS: 2

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	3	2	1	0
2) Are Rooted Plants Present In Streambed?	3	2	1	0
3) Is Periphyton Present?	0	1	2	3
4) Are Bivalves Present?	0	1	2	3

PRIMARY BIOLOGY INDICATOR POINTS: 4

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Head Cut Present In Channel?	0	.5	1	1.5
2) Is There A Grade Control Point In Channel?	0	.5	1	1.5
3) Does Topography Indicate A Natural Drainage Way?	0	.5	1	1.5

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 3.5

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf litter Present In Streambed?	1.5	1	.5	0
2) Is Sediment On Plants (Or Debris) Present?	0	.5	1	1.5
3) Are Wrack Lines Present?	0	.5	1	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	0	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	.5	1	1.5
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5	No=0		

SECONDARY HYDROLOGY INDICATOR POINTS: 2.5

III. Biology	Absent	Weak	Moderate	Strong		
1) Are Fish Present?	0	.5	1	1.5		
2) Are Amphibians Present?	0	.5	1	1.5		
3) Are Aquatic Turtles Present?	0	.5	1	1.5		
4) Are Crayfish Present?	0	.5	1	1.5		
5) Are Macroinvertebrates Present?	0	.5	1	1.5		
6) Are Iron Oxidizing Bacteria/Fungus Present?	0	.5	1	1.5		
7) Is Filamentous Algae Present?	0	.5	1	1.5		
8) Are Wetland Plants In Streambed?	SAV 2	Mostly OBL 1	Mostly FACW .75	Mostly FAC .5	Mostly FACU 0	Mostly UPL 0

SECONDARY BIOLOGY INDICATOR POINTS: 2.5

TOTAL POINTS (Primary + Secondary) = 21.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).



STREAM QUALITY ASSESSMENT WORKSHEET



Provide the following information for the stream reach under assessment:

1. Applicant's name: NCDOT
2. Evaluator's name: H. Runniger
3. Date of evaluation: 6-4-04
4. Time of evaluation: 2:00
5. Name of stream: OT Rich Fork Creek
6. River basin: Yadkin
7. Approximate drainage area: —
8. Stream order: 1st
9. Length of reach evaluated: 2100'
10. County: Davidson
11. Site coordinates (if known): —
12. Subdivision name (if any): —
13. Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location): Site 7; Station 516+70
14. Proposed channel work (if any): 24" pipe
15. Recent weather conditions: no rain past 24h. rain all AM
16. Site conditions at time of visit: raining
17. Identify any special waterway classifications known: ☐ Section 10 ☐ Tidal Waters ☐ Essential Fisheries Habitat ☐ Trout Waters ☐ Outstanding Resource Waters ☐ Nutrient Sensitive Waters ☐ Water Supply Watershed ☐ (I-IV)
18. Is there a pond or lake located upstream of the evaluation point? YES ☒ NO ☐ If yes, estimate the water surface area: _____
19. Does channel appear on USGS quad map? YES ☒ NO ☐
20. Does channel appear on USDA Soil Survey? YES ☒ NO ☐
21. Estimated watershed land use: 80 % Residential ☐ % Commercial ☐ % Industrial ☐ % Agricultural ☐ % Cleared / Logged 10 % Other (NC 109)
22. Bankfull width: 2.5'
23. Bank height (from bed to top of bank): 1'
24. Channel slope down center of stream: ☐ Flat (0 to 2%) ☒ Gentle (2 to 4%) ☐ Moderate (4 to 10%) ☐ Steep (>10%)
25. Channel sinuosity: ☐ Straight ☒ Occasional bends ☐ Frequent meander ☐ Very sinuous ☐ Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Total Score (from reverse): 34

Comments: receives a lot of stormwater

Intermittent

Evaluator's Signature

H. Runniger

Date 6-4-04

This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a particular mitigation ratio or requirement. Form subject to change – version 06/03. To Comment, please call 919-876-8441 x 26.

STREAM QUALITY ASSESSMENT WORKSHEET

	#	CHARACTERISTICS	ECOREGION POINT RANGE			SCORE
			Coastal	Piedmont	Mountain	
PHYSICAL	1	Presence of flow / persistent pools in stream (no flow or saturation = 0; strong flow = max points)	0-5	0-4	0-5	1
	2	Evidence of past human alteration (extensive alteration = 0; no alteration = max points)	0-6	0-5	0-5	1
	3	Riparian zone (no buffer = 0; contiguous wide buffer = max points)	0-6	0-4	0-5	2
	4	Evidence of nutrient or chemical discharges (extensive discharges = 0; no discharges = max points)	0-5	0-4	0-4	2
	5	Groundwater discharge (no discharge = 0; springs, seeps, wetlands, etc. = max points)	0-5	0-4	0-4	1
	6	Presence of adjacent floodplain (no floodplain = 0; extensive floodplain = max points)	0-4	0-4	0-2	3
	7	Entrenchment / floodplain access (deeply entrenched = 0; frequent flooding = max points)	0-5	0-4	0-2	3
	8	Presence of adjacent wetlands (no wetlands = 0; large adjacent wetlands = max points)	0-6	0-4	0-3	0
	9	Channel sinuosity (extensive channelization = 0; natural meander = max points)	0-5	0-4	0-3	1
	10	Sediment input (extensive deposition = 0; little or no sediment = max points)	0-5	0-4	0-2	1
STABILITY	11	Size & diversity of channel bed substrate (fine, homogenous = 0; large, diverse sizes = max points)	NA	0-4	0-5	1
	12	Evidence of channel incision or widening (deeply incised = 0; stable bed & banks = max points)	0-5	0-4	0-5	2
	13	Presence of major bank failures (severe erosion = 0; no erosion, stable banks = max points)	0-5	0-5	0-5	4
	14	Root depth and density on banks (no visible roots = 0; dense roots throughout = max points)	0-5	0-4	0-5	1
HABITAT	15	Impact by agriculture, livestock, or timber production (substantial impact = 0; no evidence = max points)	0-5	0-4	0-5	3
	16	Presence of riffle-pool/ripple-pool complexes (no riffles/ripples or pools = 0; well-developed = max points)	0-5	0-5	0-6	1
	17	Habitat complexity (little or no habitat = 0; frequent varied habitats = max points)	0-6	0-6	0-6	1
	18	Canopy coverage over streambed (no shading vegetation = 0; continuous canopy = max points)	0-5	0-5	0-5	3
BIOLOGY	19	Substrate embeddedness (deeply embedded = 0; loose structure = max)	NA	0-4	0-4	2
	20	Presence of stream invertebrates (see page 4) (no evidence = 0; common, numerous types = max points)	0-4	0-5	0-5	0
	21	Presence of amphibians (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
	22	Presence of fish (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
	23	Evidence of wildlife use (no evidence = 0; abundant evidence = max points)	0-6	0-5	0-5	1
Total Points Possible			100	100	100	
TOTAL SCORE (also enter on first page)						34

* These characteristics are not assessed in coastal streams.

(7)

NCDWQ Stream Classification Form

Project Name: R-2568B River Basin: Yadkin County: Davidson Evaluator: H. Renninger
DWQ Project Number: _____ Nearest Named Stream: Rich Fork Creek Latitude: _____ Signature: [Signature]
Date: 6-4-04 USGS QUAD: High Point West Longitude: _____ Location/Directions: St 56+70

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	(1)	2	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	(1)	2	3
3) Are Natural Levees Present?	(0)	1	2	3
4) Is The Channel Sinuous?	0	(1)	2	3
5) Is There An Active (Or Relic) Floodplain Present?	0	1	(2)	3
6) Is The Channel Braided?	0	(1)	2	3
7) Are Recent Alluvial Deposits Present?	0	1	(2)	3
8) Is There A Bankfull Bench Present?	0	1	(2)	3
9) Is A Continuous Bed & Bank Present?	0	1	(2)	3
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	No=0		

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 12

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	(1)	2	3

PRIMARY HYDROLOGY INDICATOR POINTS: 1

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	(3)	2	1	0
2) Are Rooted Plants Present In Streambed?	(3)	2	1	0
3) Is Periphyton Present?	(0)	1	2	3
4) Are Bivalves Present?	0	1	2	3

PRIMARY BIOLOGY INDICATOR POINTS: 6

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Head Cut Present In Channel?	0	.5	(1)	1.5
2) Is There A Grade Control Point In Channel?	0	.5	(1)	1.5
3) Does Topography Indicate A Natural Drainage Way?	0	(3)	1	1.5

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 2.5

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf litter Present In Streambed?	(1.5)	1	.5	0
2) Is Sediment On Plants (Or Debris) Present?	0	.5	(1)	1.5
3) Are Wrack Lines Present?	0	.5	(1)	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	0	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	(.5)	1	1.5
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5	No=0		

SECONDARY HYDROLOGY INDICATOR POINTS: 4

III. Biology	Absent	Weak	Moderate	Strong		
1) Are Fish Present?	(0)	.5	1	1.5		
2) Are Amphibians Present?	(0)	.5	1	1.5		
3) Are AquaticTurtles Present?	(0)	.5	1	1.5		
4) Are Crayfish Present?	(0)	.5	1	1.5		
5) Are Macrobenethos Present?	(0) -	.5	1	1.5		
6) Are Iron Oxidizing Bacteria/Fungus Present?	(0)	.5	1	1.5		
7) Is Filamentous Algae Present?	(0)	.5	1	1.5		
8) Are Wetland Plants In Streambed?	SAV	Mostly OBL	Mostly FACW	Mostly FAC	Mostly FACU	Mostly UPL
(* NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)	2	1	.75	.5	0	0

SECONDARY BIOLOGY INDICATOR POINTS: 0

TOTAL POINTS (Primary + Secondary) = 25.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).



STREAM QUALITY ASSESSMENT WORKSHEET



Provide the following information for the stream reach under assessment:

1. Applicant's name: NCDOT
2. Evaluator's name: Tim Bassette
3. Date of evaluation: 6-4-04
4. Time of evaluation: 2:30 pm
5. Name of stream: Rich Fork Creek
6. River basin: Yadkin
7. Approximate drainage area: _____
8. Stream order: at least third order
9. Length of reach evaluated: 400 linear ft
10. County: Davidson
11. Site coordinates (if known): _____
12. Subdivision name (if any): _____
13. Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location): Site 8; Station 61+31.5
14. Proposed channel work (if any): 2 @ 85' x 54' P/S Conc. girder bridge
15. Recent weather conditions: Rained post 24h - (couple hrs. ago)
16. Site conditions at time of visit: cloudy; no rain; creek relatively fast flowing + sediment laden
17. Identify any special waterway classifications known: _____ Section 10 _____ Tidal Waters _____ Essential Fisheries Habitat
 _____ Trout Waters _____ Outstanding Resource Waters _____ Nutrient Sensitive Waters _____ Water Supply Watershed _____ (I-IV)
18. Is there a pond or lake located upstream of the evaluation point? YES ☒ NO ☐ If yes, estimate the water surface area: N/A
19. Does channel appear on USGS quad map? ☒ YES ☐ NO
20. Does channel appear on USDA Soil Survey? ☒ YES ☐ NO
21. Estimated watershed land use: 30 % Residential _____ % Commercial _____ % Industrial 10 % Agricultural
70 % Forested _____ % Cleared / Logged _____ % Other (_____)
22. Bankfull width: 55 ft
23. Bank height (from bed to top of bank): unknown
24. Channel slope down center of stream: ☒ Flat (0 to 2%) _____ Gentle (2 to 4%) _____ Moderate (4 to 10%) _____ Steep (>10%)
25. Channel sinuosity: _____ Straight ☒ Occasional bends _____ Frequent meander _____ Very sinuous _____ Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Total Score (from reverse): 60 Comments: perennial; receives lots of sediment inputs

Evaluator's Signature

Tim Bassette

Date 6-4-04

This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a particular mitigation ratio or requirement. Form subject to change - version 06/03. To Comment, please call 919-876-8441 x 26.

STREAM QUALITY ASSESSMENT WORKSHEET

	#	CHARACTERISTICS	ECOREGION POINT RANGE			SCORE
			Coastal	Piedmont	Mountain	
PHYSICAL	1	Presence of flow / persistent pools in stream (no flow or saturation = 0; strong flow = max points)	0-5	0-4	0-5	4
	2	Evidence of past human alteration (extensive alteration = 0; no alteration = max points)	0-5	0-5	0-5	3
	3	Riparian zone (no buffer = 0; contiguous, wide buffer = max points)	0-6	0-4	0-5	4
	4	Evidence of nutrient or chemical discharges (extensive discharges = 0; no discharges = max points)	0-5	0-4	0-4	0
	5	Groundwater discharge (no discharge = 0; springs, seeps, wetlands, etc. = max points)	0-5	0-4	0-5	4
	6	Presence of adjacent floodplain (no floodplain = 0; extensive floodplain = max points)	0-4	0-4	0-5	4
	7	Entrenchment / floodplain access (deeply entrenched = 0; frequent flooding = max points)	0-5	0-4	0-2	1
	8	Presence of adjacent wetlands (no wetlands = 0; large adjacent wetlands = max points)	0-5	0-4	0-5	0
	9	Channel sinuosity (extensive channelization = 0; natural meander = max points)	0-5	0-4	0-3	1
	10	Sediment input (extensive deposition = 0; little or no sediment = max points)	0-5	0-4	0-4	0
STABILITY	11	Size & diversity of channel bed substrate (fine, homogenous = 0; large, diverse sizes = max points)	NA	0-4	0-5	0
	12	Evidence of channel incision or widening (deeply incised = 0; stable bed & banks = max points)	0-5	0-4	0-5	2
	13	Presence of major bank failures (severe erosion = 0; no erosion, stable banks = max points)	0-5	0-5	0-5	2
	14	Root depth and density on banks (no visible roots = 0; dense roots throughout = max points)	0-3	0-4	0-5	4
	15	Impact by agriculture, livestock, or timber production (substantial impact = 0; no evidence = max points)	0-5	0-4	0-5	2
HABITAT	16	Presence of riffle-pool/ripple-pool-complexes (no riffles/ripples or pools = 0; well-developed = max points)	0-3	0-5	0-6	0
	17	Habitat complexity (little or no habitat = 0; frequent varied habitats = max points)	0-6	0-6	0-6	6
	18	Canopy coverage over streambed (no shading vegetation = 0; continuous canopy = max points)	0-2	0-5	0-6	5
	19	Substrate embeddedness (deeply embedded = 0; loose structure = max)	NA	0-4	0-4	0
BIOLOGY	20	Presence of stream invertebrates (see page 4) (no evidence = 0; common, numerous types = max points)	0-4	0-5	0-5	5
	21	Presence of amphibians (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	4
	22	Presence of fish (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	4
	23	Evidence of wildlife use (no evidence = 0; abundant evidence = max points)	0-6	0-5	0-5	5
Total Points Possible			2-100	0-100	100	
TOTAL SCORE (also enter on first page)					60	

* These characteristics are not assessed in coastal streams.

NCDWQ Stream Classification Form

Project Name: R-2568

River Basin: Yadkin

County: Davidson Evaluator: H. Runniger

DWQ Project Number:

Nearest Named Stream:

Latitude:

Signature: HJR

Date: 6-4-04

USGS QUAD:

Longitude:

Location/Directions:

Rich Fork Creek
High Point West

S. 61+31.5

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong	
1) Is There A Riffle-Pool Sequence?	0	1	2	3	<u>Flooded</u>
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	1	2	3	<u>Can't See</u>
3) Are Natural Levees Present?	0	1	2	3	
4) Is The Channel Sinuous?	0	1	2	3	
5) Is There An Active (Or Relic) Floodplain Present?	0	1	2	3	
6) Is The Channel Braided?	0	1	2	3	
7) Are Recent Alluvial Deposits Present?	0	1	2	3	
8) Is There A Bankfull Bench Present?	0	1	2	3	
9) Is A Continuous Bed & Bank Present?	0	1	2	3	
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)					
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	No=0			

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 18

II. Hydrology	Absent	Weak	Moderate	Strong	
1) Is There A Groundwater Flow/Discharge Present?	0	1	2	3	

PRIMARY HYDROLOGY INDICATOR POINTS: 3

III. Biology	Absent	Weak	Moderate	Strong	
1) Are Fibrous Roots Present In Streambed?	0	2	1	0	
2) Are Rooted Plants Present In Streambed?	0	2	1	0	
3) Is Periphyton Present?	0	1	2	3	
4) Are Bivalves Present?	0	1	2	3	

PRIMARY BIOLOGY INDICATOR POINTS: 6

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong	
1) Is There A Head Cut Present In Channel?	0	.5	1	1.5	<u>not w/</u>
2) Is There A Grade Control Point In Channel?	0	.5	1	1.5	<u>Row</u>
3) Does Topography Indicate A Natural Drainage Way?	0	.5	1	1.5	

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 1.5

II. Hydrology	Absent	Weak	Moderate	Strong	
1) Is This Year's (Or Last's) Leaf litter Present In Streambed?	0	.5	1	1.5	
2) Is Sediment On Plants (Or Debris) Present?	0	.5	1	1.5	
3) Are Wrack Lines Present?	0	.5	1	1.5	
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	0	.5	1	1.5	<u>raining</u>
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	.5	1	1.5	
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5	No=0			<u>flooded</u>

SECONDARY HYDROLOGY INDICATOR POINTS: 6

III. Biology	Absent	Weak	Moderate	Strong		
1) Are Fish Present?	0	.5	1	1.5		
2) Are Amphibians Present?	0	.5	1	1.5		
3) Are Aquatic Turtles Present?	0	.5	1	1.5		
4) Are Crayfish Present?	0	.5	1	1.5		
5) Are Macroinvertebrates Present?	0	.5	1	1.5		
6) Are Iron Oxidizing Bacteria/Fungus Present?	0	.5	1	1.5		
7) Is Filamentous Algae Present?	0	.5	1	1.5		
8) Are Wetland Plants In Streambed?	SAV	Mostly OBL	Mostly FACW	Mostly FAC	Mostly FACU	Mostly UPL
(*NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)						

SECONDARY BIOLOGY INDICATOR POINTS: 7.5

TOTAL POINTS (Primary + Secondary) = 43 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).



STREAM QUALITY ASSESSMENT WORKSHEET



Provide the following information for the stream reach under assessment:

1. Applicant's name: NC DOT
2. Evaluator's name: H. Renninger
3. Date of evaluation: 6-4-04
4. Time of evaluation: 2:54
5. Name of stream: UT Rich Fork Creek
6. River basin: Tuckahoe
7. Approximate drainage area: _____
8. Stream order: 1st
9. Length of reach evaluated: ~100'
10. County: Davidson
11. Site coordinates (if known): _____
12. Subdivision name (if any): _____
13. Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location):
Site 9; Station 64+00 → 66+60
14. Proposed channel work (if any): 42" pipe
15. Recent weather conditions: raining all AM
16. Site conditions at time of visit: drizzle
17. Identify any special waterway classifications known: _____ Section 10 _____ Tidal Waters _____ Essential Fisheries Habitat
_____ Trout Waters _____ Outstanding Resource Waters _____ Nutrient Sensitive Waters _____ Water Supply Watershed _____ (I-IV)
18. Is there a pond or lake located upstream of the evaluation point? YES ☒ NO ☐ If yes, estimate the water surface area: _____
19. Does channel appear on USGS quad map? YES ☒ NO ☐
20. Does channel appear on USDA Soil Survey? YES ☒ NO ☐
21. Estimated watershed land use: 50% Residential _____ % Commercial _____ % Industrial 20% Agricultural
30% Forested _____ % Cleared / Logged _____ % Other (_____)
22. Bankfull width: 2'
23. Bank height (from bed to top of bank): 1'
24. Channel slope down center of stream: _____ Flat (0 to 2%) _____ Gentle (2 to 4%) ☒ Moderate (4 to 10%) _____ Steep (>10%)
25. Channel sinuosity: _____ Straight ☒ Occasional bends _____ Frequent meander _____ Very sinuous _____ Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Total Score (from reverse): 20 Comments: receives stormwater from
Nc109; lots of trash in channel
Intermittent

Evaluator's Signature H. Renninger Date 6-4-04
This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a particular mitigation ratio or requirement. Form subject to change – version 06/03. To Comment, please call 919-876-8441 x 26.

STREAM QUALITY ASSESSMENT WORKSHEET

		CHARACTERISTICS	SCORE/REGION POINT RANGE			SCORE
			Coastal	Piedmont	Mountain	
PHYSICAL	1	Presence of flow / persistent pools in stream (no flow or saturation = 0; strong flow = max points)	0-5	0-4	0-5	1
	2	Evidence of past human alteration (extensive alteration = 0; no alteration = max points)	0-6	0-5		2
	3	Riparian zone (no buffer = 0; contiguous, wide buffer = max points)	0-6	0	0-5	1
	4	Evidence of nutrient or chemical discharges (extensive discharges = 0; no discharges = max points)	0-5	0		1
	5	Groundwater discharge (no discharge = 0; springs, seeps, wetlands etc. = max points)		1	0	1
	6	Presence of adjacent floodplain (no floodplain = 0; extensive floodplain = max points)	0	0	0-2	0
	7	Entrenchment / floodplain access (deeply entrenched = 0; frequent flooding = max points)		0		1
	8	Presence of adjacent wetlands (no wetlands = 0; large adjacent wetlands = max points)	0-6	0	0-2	0
	9	Channel sinuosity (extensive channelization = 0; natural meander = max points)	0-5	0	0-5	1
	10	Sediment input (extensive deposition = 0; little or no sediment = max points)	0	0	0	1
STABILITY	11	Size & diversity of channel bed substrate (fine, homogeneous = 0; large, diverse sizes = max points)	0-5	0-4	0	0
	12	Evidence of channel incision or widening (deeply incised = 0; stable bed & banks = max points)	0-5	0-4	0-5	1
	13	Presence of major bank failures (severe erosion = 0; no erosion, stable banks = max points)	0	0	0	1
	14	Root depth and density on banks (no visible roots = 0; dense roots throughout = max points)	0	0-4	0-5	1
	15	Impact by agriculture, livestock, or timber production (substantial impact = 0; no evidence = max points)	0-4	0-4	0-5	4
HABITAT	16	Presence of riffle/pool/ripple pool complexes (no riffles/ripples or pools = 0; well developed = max points)	0	0-5	0-5	1
	17	Habitat complexity (little or no habitat = 0; frequently varied habitats = max points)	0-6	0-6	0-6	1
	18	Canopy coverage over streambed (no shading vegetation = 0; continuous canopy = max points)	0-5	0-5	0-5	1
	19	Substrate embeddedness (deeply embedded = 0; loose structure = max)	NA	0-4	0-20	1
BIOLOGY	20	Presence of stream invertebrates (see page 4) (no evidence = 0; common, numerous types = max points)	0-4	0-5	0-5	0
	21	Presence of amphibians (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
	22	Presence of fish (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
	23	Evidence of wildlife use (no evidence = 0; abundant evidence = max points)	0-6	0-2	0-5	0
	24	Total Points Possible	100	100	100	
TOTAL SCORE (also enter on first page)					20	

* These characteristics are not assessed in coastal streams.

NCDWQ Stream Classification Form

Project Name: R-2568B

River Basin: Yadkin

County: Davidson

Evaluator: Tim Bassett
Signature: Tim Bassett

DWQ Project Number:

Nearest Named Stream: Rich Fork Creek
USGS QUAD: High Point West

Latitude:

Longitude:

Location/Directions:

St. 64100

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	1	2	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	1	2	3
3) Are Natural Levees Present?	0	1	2	3
4) Is The Channel Sinuous?	0	1	2	3
5) Is There An Active (Or Relic) Floodplain Present?	0	1	2	3
6) Is The Channel Braided?	0	1	2	3
7) Are Recent Alluvial Deposits Present?	0	1	2	3
8) Is There A Bankfull Bench Present?	0	1	2	3
9) Is A Continuous Bed & Bank Present?	0	1	2	3
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	No=0		

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 6

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	1	2	3

PRIMARY HYDROLOGY INDICATOR POINTS: 2

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	3	2	1	0
2) Are Rooted Plants Present In Streambed?	3	2	1	0
3) Is Periphyton Present?	0	1	2	3
4) Are Bivalves Present?	0	1	2	3

PRIMARY BIOLOGY INDICATOR POINTS: 6

Secondary Field Indicators: (Circle One Number Per Line)

w/ia Rowley

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Head Cut Present In Channel?	0	.5	1	1.5
2) Is There A Grade Control Point In Channel?	0	.5	1	1.5
3) Does Topography Indicate A Natural Drainage Way?	0	.5	1	1.5

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 1

just rain

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf Litter Present In Streambed?	1.5	1	.5	0
2) Is Sediment On Plants (Or Debris) Present?	0	.5	1	1.5
3) Are Wrack Lines Present?	0	.5	1	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	0	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	.5	1	1.5
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5	No=0		

SECONDARY HYDROLOGY INDICATOR POINTS: 3.5

n/A

III. Biology	Absent	Weak	Moderate	Strong		
1) Are Fish Present?	0	.5	1	1.5		
2) Are Amphibians Present?	0	.5	1	1.5		
3) Are Aquatic Turtles Present?	0	.5	1	1.5		
4) Are Crayfish Present?	0	.5	1	1.5		
5) Are Macroinvertebrates Present?	0	.5	1	1.5		
6) Are Iron Oxidizing Bacteria/Fungus Present?	0	.5	1	1.5		
7) Is Filamentous Algae Present?	0	.5	1	1.5		
8) Are Wetland Plants In Streambed?	SAV	Mostly OBL	Mostly FACW	Mostly FAC	Mostly FACU	Mostly UPL
(*NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)						
	2	1	.75	.5	0	0

SECONDARY BIOLOGY INDICATOR POINTS: 0

TOTAL POINTS (Primary + Secondary) = 18.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).



STREAM QUALITY ASSESSMENT WORKSHEET



Provide the following information for the stream reach under assessment:

1. Applicant's name: NC DOT
2. Evaluator's name: H. Renninger
3. Date of evaluation: 6-4-04
4. Time of evaluation: 3:30
5. Name of stream: UT Rich Fork Creek
6. River basin: Yadkin
7. Approximate drainage area: _____
8. Stream order: 1st
9. Length of reach evaluated: 250'
10. County: Davidson
11. Site coordinates (if known): _____
12. Subdivision name (if any): _____
13. Location of reach under evaluation (note nearby roads and landmarks and attach map identifying stream(s) location): Site 10; Station 75+50 → 76+50
14. Proposed channel work (if any): 36" pipe
15. Recent weather conditions: rain all AM
16. Site conditions at time of visit: drizzle
17. Identify any special waterway classifications known: _____ Section 10 _____ Tidal Waters _____ Essential Fisheries Habitat
_____ Trout Waters _____ Outstanding Resource Waters _____ Nutrient Sensitive Waters _____ Water Supply Watershed _____ (I-IV)
18. Is there a pond or lake located upstream of the evaluation point? YES ☒ NO ☐ If yes, estimate the water surface area: _____
19. Does channel appear on USGS quad map? YES ☒ NO ☐
20. Does channel appear on USDA Soil Survey? ☒ YES ☐ NO
21. Estimated watershed land use: 40% Residential _____ % Commercial _____ % Industrial _____ % Agricultural
25% Forested 5% Cleared / Logged 30% Other (impervious sur.)
22. Bankfull width: 4'
23. Bank height (from bed to top of bank): 2-4'
24. Channel slope down center of stream: _____ Flat (0 to 2%) ☒ Gentle (2 to 4%) _____ Moderate (4 to 10%) _____ Steep (>10%)
25. Channel sinuosity: _____ Straight ☒ Occasional bends ☒ Frequent meander _____ Very sinuous _____ Braided channel

Instructions for completion of worksheet (located on page 2): Begin by determining the most appropriate ecoregion based on location, terrain, vegetation, stream classification, etc. Every characteristic must be scored using the same ecoregion. Assign points to each characteristic within the range shown for the ecoregion. Page 3 provides a brief description of how to review the characteristics identified in the worksheet. Scores should reflect an overall assessment of the stream reach under evaluation. If a characteristic cannot be evaluated due to site or weather conditions, enter 0 in the scoring box and provide an explanation in the comment section. Where there are obvious changes in the character of a stream under review (e.g., the stream flows from a pasture into a forest), the stream may be divided into smaller reaches that display more continuity, and a separate form used to evaluate each reach. The total score assigned to a stream reach must range between 0 and 100, with a score of 100 representing a stream of the highest quality.

Total Score (from reverse): 33 Comments: intermittent upstream of culvert at St. 76+10; perennial downstream

Evaluator's Signature Heather J. Renninger

Date 6-4-04

This channel evaluation form is intended to be used only as a guide to assist landowners and environmental professionals in gathering the data required by the United States Army Corps of Engineers to make a preliminary assessment of stream quality. The total score resulting from the completion of this form is subject to USACE approval and does not imply a particular mitigation ratio or requirement. Form subject to change – version 06/03. To Comment, please call 919-876-8441 x 26.

STREAM QUALITY ASSESSMENT WORKSHEET

#	CHARACTERISTICS	ECOREGION POINT RANGE			SCORE
		Coastal	Piedmont	Mountain	
1	Presence of flow / persistent pools in stream (no flow or saturation = 0; strong flow = max points)	0-5	0-4	0-5	3
2	Evidence of past human alteration (extensive alteration = 0; no alteration = max points)	0-6	0-5	0-5	0
3	Riparian zone (no buffer = 0; contiguous, wide buffer = max points)	0-6	0-4	0-5	1
4	Evidence of nutrient or chemical discharges (extensive discharges = 0; no discharges = max points)	0-5	0-4	0-4	2
5	Groundwater discharge (no discharge = 0; springs, seeps, wetlands, etc. = max points)	0-5	0-4	0-4	1
6	Presence of adjacent floodplain (no floodplain = 0; extensive floodplain = max points)	0-4	0-4	0-2	0
7	Entrenchment / floodplain access (deeply entrenched = 0; frequent flooding = max points)	0-5	0-4	0-2	1
8	Presence of adjacent wetlands (no wetlands = 0; large adjacent wetlands = max points)	0-6	0-4	0-2	0
9	Channel sinuosity (extensive channelization = 0; natural meander = max points)	0-5	0-4	0-5	2
10	Sediment input (extensive deposition = 0; little or no sediment = max points)	0-5	0-2	0-4	2
11	Size & diversity of channel bed substrate (fine, homogenous = 0; large, diverse sizes = max points)	NA	0-4	0-5	2
12	Evidence of channel incision or widening (deeply incised = 0; stable bed & banks = max points)	0-5	0-4	0-5	1
13	Presence of major bank failures (severe erosion = 0; no erosion, stable banks = max points)	0-5	0-3	0-5	1
14	Root depth and density on banks (no visible roots = 0; dense roots throughout = max points)	0-5	0-4	0-5	1
15	Impact by agriculture, livestock, or timber production (substantial impact = 0; no evidence = max points)	0-5	0-4	0-5	4
16	Presence of riffle, pool, rap, or pool complexes (no riffles, rapids or pools = 0; well-developed = max points)	0-3	0-5	0-6	2
17	Habitat complexity (little or no habitat = 0; frequent, varied habitats = max points)	0-6	0-6	0-6	3
18	Canopy coverage over streambed (no shading, vegetation = 0; continuous canopy = max points)	0-5	0-5	0-5	2
19	Substrate embeddedness (deeply embedded = 0; loose structure = max)	NA	0-4	0-4	2
20	Presence of stream invertebrates (see page 4) (no evidence = 0; common, numerous types = max points)	0-4	0-5	0-5	3
21	Presence of amphibians (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
22	Presence of fish (no evidence = 0; common, numerous types = max points)	0-4	0-4	0-4	0
23	Evidence of wildlife use (no evidence = 0; abundant evidence = max points)	0-6	0-5	0-5	0
Total Points Possible		100	100	100	
TOTAL SCORE (also enter on first page)					33

* These characteristics are not assessed in coastal streams.

NCDWQ Stream Classification Form

Project Name: R 25686

River Basin: Yadkin

County: Davidson

Evaluator: Tim Bassett

DWQ Project Number:

Nearest Named Stream:

Latitude:

Signature: Tim Bassett

Date: 6-4-04

Rich Fork Creek
USGS QUAD:
High Point West

Longitude:

Location/Directions:

S+ 75+50

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	<u>1</u>	2	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	<u>1</u>	2	3
3) Are Natural Levees Present?	<u>0</u>	1	2	3
4) Is The Channel Sinuous?	<u>0</u>	1	2	3
5) Is There An Active (Or Relic) Floodplain Present?	<u>0</u>	<u>1</u>	2	3
6) Is The Channel Braided?	<u>0</u>	1	2	3
7) Are Recent Alluvial Deposits Present?	<u>0</u>	1	2	3
8) Is There A Bankfull Bench Present?	0	1	<u>2</u>	3
9) Is A Continuous Bed & Bank Present?	0	1	<u>2</u>	3
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	<u>No=0</u>		

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 7

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	<u>1</u>	2	3

PRIMARY HYDROLOGY INDICATOR POINTS: 1

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	<u>0</u>	2	1	0
2) Are Rooted Plants Present In Streambed?	<u>0</u>	2	1	0
3) Is Periphyton Present?	<u>0</u>	1	2	3
4) Are Bivalves Present?	<u>0</u>	1	2	3

PRIMARY BIOLOGY INDICATOR POINTS: 6

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Head Cut Present In Channel?	0	<u>.5</u>	1	1.5
2) Is There A Grade Control Point In Channel?	0	.5	<u>1</u>	1.5
3) Does Topography Indicate A Natural Drainage Way?	0	<u>.5</u>	1	1.5

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 2

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf litter Present In Streambed?	<u>1.5</u>	1	.5	0
2) Is Sediment On Plants (Or Debris) Present?	<u>0</u>	.5	1	1.5
3) Are Wrack Lines Present?	0	.5	<u>1</u>	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	<u>0</u>	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	<u>.5</u>	1	1.5
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	<u>Yes=1.5</u>		<u>No=0</u>	

SECONDARY HYDROLOGY INDICATOR POINTS: 4.5

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fish Present?	<u>0</u>	.5	1	1.5
2) Are Amphibians Present?	<u>0</u>	.5	1	1.5
3) Are Aquatic Turtles Present?	<u>0</u>	.5	1	1.5
4) Are Crayfish Present?	<u>0</u>	.5	1	1.5
5) Are Macroinvertebrates Present?	0	.5	<u>1</u>	1.5
6) Are Iron Oxidizing Bacteria/Fungus Present?	<u>0</u>	.5	1	1.5
7) Is Filamentous Algae Present?	<u>0</u>	.5	1	1.5

8) Are Wetland Plants In Streambed? SAV 2 Mostly OBL 1 Mostly FACW .75 Mostly FAC .5 Mostly FACU 0 Mostly UPL 0
(*NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)

SECONDARY BIOLOGY INDICATOR POINTS: 1

TOTAL POINTS (Primary + Secondary) = 21.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).

10
upstream
of
driveway
culvert
intermittent

just
rained →

N/A →

NCDWQ Stream Classification Form

Project Name: R-2568B River Basin: Yadkin County: Davidson Evaluator: Tim Bassette
 DWQ Project Number: Nearest Named Stream: Rich Fork Creek Latitude: Signature: Tim Bassette
 Date: 6/4/2004 USGS QUAD: High Point West Longitude: Location/Directions: St. 75+50

Primary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Riffle-Pool Sequence?	0	1	(2)	3
2) Is The USDA Texture In Streambed Different From Surrounding Terrain?	0	1	2	(3)
3) Are Natural Levees Present?	(0)	1	2	3
4) Is The Channel Sinuous?	0	(1)	2	3
5) Is There An Active (Or Relic) Floodplain Present?	0	1	(2)	3
6) Is The Channel Braided?	(0)	1	2	3
7) Are Recent Alluvial Deposits Present?	0	(0)	2	3
8) Is There A Bankfull Bench Present?	0	1	2	(3)
9) Is A Continuous Bed & Bank Present?	0	1	2	(3)
(*NOTE: If Bed & Bank Caused By Ditching And WITHOUT Sinuosity Then Score=0*)				
10) Is A 2 nd Order Or Greater Channel (As Indicated On Topo Map And/Or In Field) Present?	Yes=3	(No=0)		

PRIMARY GEOMORPHOLOGY INDICATOR POINTS: 15

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is There A Groundwater Flow/Discharge Present?	0	1	(2)	3

PRIMARY HYDROLOGY INDICATOR POINTS: 2

III. Biology	Absent	Weak	Moderate	Strong
1) Are Fibrous Roots Present In Streambed?	(3)	2	1	0
2) Are Rooted Plants Present In Streambed?	(3)	2	1	0
3) Is Periphyton Present?	(0)	1	2	3
4) Are Bivalves Present?	(0)	1	2	3

PRIMARY BIOLOGY INDICATOR POINTS: 6

Secondary Field Indicators: (Circle One Number Per Line)

I. Geomorphology	Absent	Weak	Moderate	Strong
1) Is There A Head Cut Present In Channel?	(0)	.5	1	1.5
2) Is There A Grade Control Point In Channel?	0	.5	1	(1.5)
3) Does Topography Indicate A Natural Drainage Way?	0	.5	(1)	1.5

SECONDARY GEOMORPHOLOGY INDICATOR POINTS: 2.5

II. Hydrology	Absent	Weak	Moderate	Strong
1) Is This Year's (Or Last's) Leaf litter Present In Streambed?	(1.5)	1	.5	0
2) Is Sediment On Plants (Or Debris) Present?	(0)	.5	1	1.5
3) Are Wrack Lines Present?	0	.5	(1)	1.5
4) Is Water In Channel And >48 Hrs. Since Last Known Rain? (*NOTE: If Ditch Indicated In #11 Above Skip This Step And #5 Below*)	(0)	.5	1	1.5
5) Is There Water In Channel During Dry Conditions Or In Growing Season?	0	.5	1	(1.5)
6) Are Hydric Soils Present In Sides Of Channel (Or In Headcut)?	Yes=1.5	No=0		

SECONDARY HYDROLOGY INDICATOR POINTS: 5.5

III. Biology	Absent	Weak	Moderate	Strong		
1) Are Fish Present?	0	.5	1	1.5		
2) Are Amphibians Present?	0	.5	1	1.5		
3) Are Aquatic Turtles Present?	0	.5	1	1.5		
4) Are Crayfish Present?	0	.5	1	1.5		
5) Are Macroinvertebrates Present?	0	.5	1	1.5		
6) Are Iron Oxidizing Bacteria/Fungus Present?	0	.5	1	1.5		
7) Is Filamentous Algae Present?	0	.5	1	1.5		
8) Are Wetland Plants In Streambed?	SAV	Mostly OBL	Mostly FACW	Mostly FAC	Mostly FACU	Mostly UPL
(* NOTE: If Total Absence Of All Plants In Streambed As Noted Above Skip This Step UNLESS SAV Present*)						
	2	1	.75	.5	0	0

SECONDARY BIOLOGY INDICATOR POINTS: 1.5

TOTAL POINTS (Primary + Secondary) = 32.5 (If Greater Than or = 19 Points The Stream Is At Least Intermittent).

FINAL

**QUALITATIVE INDIRECT AND
CUMULATIVE EFFECTS ASSESSMENT
NC 109 RELOCATION AND WIDENING
TIP R-2568B
Davidson County, North Carolina**

Prepared for
North Carolina Department of Transportation
Office of Human Environment

Prepared by:

HNTB North Carolina, PC

*2108 South Boulevard
Suite 108
Charlotte, North Carolina 28203*

July 16, 2004



TABLE OF CONTENTS

I. EXECUTIVE SUMMARY	1
II. PROJECT DOCUMENTATION AND BACKGROUND.....	2
III. STUDY AREA BOUNDARIES	3
IDENTIFICATION OF THE GROWTH IMPACT STUDY AREA	3
IDENTIFICATION OF DEMOGRAPHIC AREA	4
IV. STUDY AREA DIRECTION AND GOALS.....	4
REGIONAL LOCATION INFLUENCES AND IMPLICATIONS	4
LOCAL INFLUENCES AND DEVELOPMENT PATTERNS	5
POPULATION AND EMPLOYMENT TRENDS.....	7
TRANSPORTATION PLANS	10
LOCAL LAND USE PLANS AND ZONING.....	11
ENVIRONMENTAL REGULATIONS	13
<i>State Regulations</i>	13
<i>Local Regulations</i>	14
V. INVENTORY OF NOTABLE FEATURES.....	14
VI. ACTIVITIES THAT CAUSE EFFECTS	14
PREVIOUS CONCLUSIONS	14
<i>Environmental Assessment (EA), November 1996.....</i>	<i>14</i>
<i>Finding of No Significant Impact (FONSI), August 1997.....</i>	<i>15</i>
DEVELOPMENT TRENDS	15
VII. POTENTIAL INDIRECT AND CUMULATIVE EFFECTS	15
VIII. ANALYSIS OF INDIRECT AND CUMULATIVE EFFECTS	17
AMOUNT OF POTENTIAL LAND USE CHANGE	18
LOCATION OF POTENTIAL LAND USE CHANGE	19
IX. EVALUATION OF ANALYSIS RESULTS	20
CONSIDERATION OF INDIRECT EFFECTS	20
CONSIDERATION OF CUMULATIVE EFFECTS.....	21
APPENDIX.....	22
BIBLIOGRAPHY	24

**North Carolina Department of Transportation
Office of Human Environment**

**Qualitative Indirect and Cumulative Effects Assessment
TIP R-2568B, Davidson County, NC**

I. EXECUTIVE SUMMARY

TIP R-2568B is a 3.7-mile relocation and widening of NC 109 to a four-lane facility from south of Midway Road (SR 1800) to north of SR 1798 (Old Greensboro Road) in Davidson County. The purpose of the project is to straighten roadway alignment, increase roadway capacity, and to improve roadway safety. NC 109 is an important link between Winston-Salem and Thomasville, and the widening will improve access to I-85 Business in Thomasville. A 250-foot right-of-way with a 46-foot median is proposed. Existing right-of-way is generally 40 feet. Construction of R-2568B is scheduled to begin in 2005.

This report is intended to provide a preliminary analysis of the potential for indirect and cumulative effects (particularly land use change) associated with TIP R-2568B. The analysis will also provide information to the North Carolina Department of Environment and Natural Resources (DENR), Division of Water Quality (DWQ) relating to potential downstream water quality impacts, which will assist them in their determination of Section 401 Water Quality Certification.

Existing Conditions

- Population in the Demographic Area grew by 14.8% between 1990 and 2000. This percentage is lower than Davidson County (16.2%) and the State of North Carolina (21.4%).
- Davidson County employment grew slightly with a 0.05% increase between 1990 and 2002. The health care and social assistance industry experienced the largest employment increase with 1,391 new jobs, and the government industry experienced the second largest increase with 1,135 new jobs. The largest decrease was in the manufacturing industry, which lost 5,503 jobs.
- According to the North Carolina Natural Heritage Program database, the USGS Quads that encompass the Growth Impact Study Area (GISA) include five state or federally protected species.
- There are several 303(d) impaired water bodies within the GISA; Rich Creek, Hunts Fork Creek, and North Hamby Creek. TIP R-2568B crosses both Rich Creek and Hunts Fork Creek.
- Water and sewer are available in the southern portion of the GISA, mainly within the City of Thomasville, and is planned for expansion in those areas close to Thomasville and west of High Point.
- The existing character around TIP R-2568B is mainly rural with agriculture, open fields, forests and some residential subdivisions.

- Abbots Creek Water Supply (WS) III Watershed covers around one-third of the GISA. Stricter than State regulations, Davidson County allows an overall density of one unit per acre and a minimum of 40,000-square foot lots within both the critical area and the balance of WS-III Watersheds. The built-upon area cannot exceed 24% for multi-family and non-residential development. Within the critical area, the built-upon area cannot exceed 12% for multi-family and non-residential.

Potential Indirect and Cumulative Effects

- Based on the analysis, TIP R-2568B is unlikely to stimulate land development having complementary functions and will not serve any explicit economic development purpose or a specific development.
- The change in accessibility and mobility as a result of TIP R-2568B will be minimal, except for those parcels that gain new road frontage.
- Over the next twenty years, population growth within Davidson County should continue at rates just above 1% annually, therefore keeping demand for developable land in the area low.
- A generally weak market for development within the GISA limits the potential for land use change as a result of TIP R-2568B.
- Within the GISA, the most likely area for commercial or residential growth as a result of TIP R-2568B is at the new intersection of NC 109 and Midway School Road.
- Other planned transportation projects, such as the continuation of TIP R-2568 sections C-G, along with TIP U-2537, will improve regional accessibility throughout the eastern portion of Davidson County and the western portion of High Point.
- Based on this assessment, TIP R-2568B is anticipated to have minimal or no effect on water quality as a result of potential land use changes within the GISA.

II. PROJECT DOCUMENTATION AND BACKGROUND

TIP R-2568B is a proposed relocation and widening of NC 109 to a four-lane facility from south of Midway School Road (SR 1800) to north of Old Greensboro Road (SR 1798) in northeastern Davidson County (see Figure 1). The purpose of the project is to increase roadway capacity and improve roadway safety by strengthening the roadway alignment. The proposed right-of-way for TIP R-2568B is 250 feet with four, 12-foot lanes, a 46-foot median, and two, 10-foot paved shoulders. Access will be partially controlled with left turn lane breaks within the median. The majority of the project will be on new location. The project will be posted with a speed limit of 55 miles per hour.



NC 109 Looking North From Old Greensboro Road

III. STUDY AREA BOUNDARIES

Identification of the Growth Impact Study Area

The North Carolina DOT's and North Carolina Department of Environment and Natural Resources' (DENR) *Guidance for Assessing Indirect and Cumulative Impacts of Transportation Projects in North Carolina* indicates that the development effects of a new roadway facility are most often found up to one mile around an interchange, and up to two to five miles along major feeder roadways to the interchange. Based on this guidance and an initial review of project area conditions, it was determined that the potential for growth impact as a result of this project would primarily be within a three-mile radius of the project. This three-mile radius, referred to as the Growth Impact Study Area (GISA), determines the data collection and analysis area, but is not necessarily the extent to which growth impacts are expected to occur (see Figure 2).

More specific areas within the GISA that are most likely to experience land use changes over the next 20-25 years as a result of the roadway improvements will be identified later in this report. The *Guidance* indicates that this timeframe is reasonable since it is used in most Metropolitan Planning Organization (MPO) and local transportation plans.




FIGURE 2 - DEMOGRAPHIC AREA

- TIP R-2568B
- HIGHWAYS
- ROADS
- RAILROADS
- RIVERS
- WATER BODIES
- COUNTY BOUNDARIES
- MUNICIPALITIES
- GROWTH IMPACT STUDY AREA

2 1 0 2 Miles

MAP SOURCES:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
ENVIRONMENTAL SYSTEMS RESEARCH INSTITUTE (ESRI)
US CENSUS BUREAU
DAVIDSON COUNTY
HIGH POINT
HNTB NORTH CAROLINA, P.C.



Identification of Demographic Area

The Demographic Area for TIP R-2568B is partially located within Davidson County, the City of Thomasville, and the City of High Point. It was created to assess the socioeconomic growth trends within the GISA, which the Demographic Area encompasses (see Figure 2). This area is generally bounded by Old Thomasville Road, Abbotts Creek, Tom-A-Lex Lake, and Hamby Creek to the west, the Davidson/Forsyth County Line to the north, the Davidson/Randolph County Line and Rich Creek to the east, and North Carolina Railroad (NCRR), SR 2031, Cunningham Road, SR 2118, and SR 2010 to the south. The following 2000 US Census Bureau Census Tracts (CT) and Block Groups (BG) are included in the Demographic Area for TIP R-2568B:

- CT 601, BG 1
- CT 601, BG 2
- CT 601, BG 3
- CT 601, BG 4
- CT 602, BG 3
- CT 605, BG 1
- CT 605, BG 2
- CT 605, BG 3
- CT 605, BG 4
- CT 606, BG 1
- CT 606, BG 2
- CT 606, BG 3
- CT 606, BG 4
- CT 607, BG 1
- CT 607, BG 2
- CT 607, BG 3
- CT 607, BG 4
- CT 608, BG 1
- CT 608, BG 2
- CT 608, BG 3

IV. STUDY AREA DIRECTION AND GOALS

The study area directions and goals were determined by analyzing existing conditions and trends of the area surrounding TIP R-2568B. Information was gathered from the US Census Bureau, the Employment Security Commission of North Carolina, a site visit to the project area, and interviews with planners from Davidson County, the City of Thomasville, and the High Point Urban Area Metropolitan Planning Organization (HPMPO). Research gathered from these sources, as well as from NCDOT project staff and local staff, was used to help determine the potential for and nature of any indirect or cumulative impacts of the project on the surrounding community.

Regional Location Influences and Implications

The City of Thomasville is located within the Piedmont Triad of North Carolina and continues to grow at a steady pace. Most of the population growth has occurred within or near the City of Thomasville, but has also started to spread to the northern and western peripheries. Growth has also occurred to the west of High Point, with sewer lines being extended to those land owners that sign voluntary annexation agreements with the City of High Point.

Thomasville is a small working class city that is known for its furniture industry. Thomasville Furniture Industries is the leading employer with over 2,500 employees. Besides the furniture industry, one of the leading employers in Davidson County is the



Community General Hospital in Thomasville. The area to the north of Thomasville where TIP R-2538B is located is more rural with houses on larger lots. There is a mixture of farmland, open fields, forested areas, and houses. The further away from Thomasville, the more rural the area becomes with houses spread farther apart. Land to the north of Thomasville is generally hilly with steep slopes, making development more difficult.



Farmland on Jacob Street

Local Influences and Development Patterns

Key roads in the vicinity besides NC 109 include the following: Business 85, NC 68, W. Lexington Road, Main Street in Thomasville, and I-85. Based on the site visit, most local traffic utilizing NC 109 either is traveling to Thomasville or accessing Business 85. NC 109 is a main commuter route between Thomasville and Winston-Salem and NC 109 also serves as a main access route for I-85. The area along TIP R-2568B is mainly rural with agriculture, open fields, forests and some scattered residential uses. Ledford Middle School is located at the southeast corner of NC 109 and W. Lexington Road, across from Old Greensboro Road. There are two larger subdivisions on the east side of NC 109, one of which is just south of Ledford Middle School. A gas station/convenience store is located at the southwest corner of NC 109 and Midway School Road.



Ledford Middle School Located On NC 109, Just North of Old Greensboro Road

The first major intersection to the south of TIP R-2568B is the recently completed TIP R-2568A, which is the Business 85 and NC 109 interchange. The southeast quadrant of the interchange includes a gas station/convenience store. The northeast corner has the most potential for future development because new road access was created for this parcel when the interchange was built. However, most of this development will be a result of the interchange construction of TIP R-2568A and not from R-2568B. The City of Thomasville's golf course is just west of NC 109 and north of Business 85.

Property within the GISA is very hilly with steep slopes, making development more difficult. Also, there are poor soils for septic tanks, which makes the availability of sewer key for development. TIP R-2568B will provide some new access to undeveloped land, although local planners indicated that growth is still more dependent upon sewer availability. Sewer service expansion is planned as development occurs, and will be dependent upon voluntary annexation agreements.



NC 109 Looking South, Just South of Old Greensboro Road

Population and Employment Trends

Table 1 below indicates population growth trends between 1990 and 2000 for the Demographic Area, as well as for the City of Thomasville, Davidson County, and North Carolina. The Demographic Area grew by 14.8%, slightly less than Davidson County (16.2%) during this timeframe. The Demographic Area and Davidson County both grew at a slower rate than North Carolina (21.4%), but the City of Thomasville grew at a faster rate (24.3%) than the State. Thomasville government staff indicated that a lot of their growth was due to annexation of unincorporated county land, which may explain why Thomasville's growth rate was higher than Davidson County and the Demographic Area.

Table 1. Population Growth, 1990-2000

Area	Population		Growth 1990-2000	
	1990	2000	#	% Change
Demographic Area	24,256	27,855	3,599	14.8%
City of Thomasville	15,915	19,788	3,873	24.3%
Davidson County	126,677	147,246	20,569	16.2%
North Carolina	6,628,637	8,049,313	1,420,676	21.4%

Source: US Census Bureau

The North Carolina Office of State Budget and Management indicates that in 1980, the population of Davidson County was 113,162, and the population grew by 30.1% to 147,246 in 1990 (see Table 2). In comparison, the population of North Carolina was 5,880,095 in 1980, and it grew 36.9% between 1980 and 2000.

Overall growth is expected to be less during the next twenty years (2000–2020) for both geographies, with the growth rate in Davidson County being less than that of North Carolina. The North Carolina Office of State Budget and Management forecasts that the population of Davidson County will be approximately 166,833 in 2010 and 186,335 in 2020. That equates to a 26.5% growth rate for Davidson County. Comparatively, the population of North Carolina is expected to be approximately 9,491,374 in 2010 and 10,966,138 in 2020, translating into a growth rate of 36.2%.

Table 2. Population Growth
Trends and Projections, 1980-2020

Population	Davidson County	North Carolina
1980	113,162	5,880,095
1990	126,677	6,632,448
Percentage Growth 1980-1990	11.9%	12.8%
2000	147,246	8,049,313
Percentage Growth 1990-2000	16.2%	21.4%
Population Projections*	Davidson County	North Carolina
2010	166,833	9,491,374
Percentage Growth 2000-2010	13.3%	17.9%
2020	186,335	10,966,138
Percentage Growth 2010-2020	11.7%	15.5%

Source: US Census Bureau, *North Carolina State Demographics, May 30, 2002,
Internet accessed 6/7/04, <http://demog.state.nc.us/>

Traffic Analysis Zone (TAZ) data shows slow residential and commercial growth throughout Davidson County, except in the areas closer to I-85. Due to High Point's annexation policies, residential growth is increasing in eastern Davidson County while residential growth in western Davidson County continues at a relatively slower pace.

Table 3 shows employment growth figures by industry sector for Davidson County between 1990 and 2002. According to data from the North Carolina Employment Security Commission, Davidson County gained only 23 jobs between 1990 and 2002, resulting in a 0.05% growth rate. This was predominantly due to a loss of more than 5,500 manufacturing sector jobs and over 650 management of companies and enterprise sector jobs. The health care and social assistance sector, similar to most counties throughout North Carolina, is showing steady growth within Davidson County. The sector that experienced the largest percentage increase was arts, entertainment, and recreation, with a 425.7% increase in employment from 1990 to 2002. According to local planners, this growth was mainly a result of increased tourism activity.

**Table 3. Employment By Sector Growth, Davidson County**

Sector	Employment		Change, '90-'02	
	1990	2002	#	%
Agriculture, Forestry, Fishing & Hunting	24	37	13	54.2%
Mining	53	41	-12	-22.6%
Utilities	167	129	-38	-22.8%
Construction	1,693	2,196	503	29.7%
Manufacturing	21,932	16,429	-5,503	-25.1%
Wholesale Trade	1,339	1,641	302	22.6%
Retail Trade	4,575	5,022	447	9.8%
Transportation and Warehousing	1,018	1,248	230	22.6%
Information	376	407	31	8.2%
Finance and Insurance	748	646	-102	-13.6%
Real Estate and Rental and Leasing	235	357	122	51.9%
Professional and Technical Services	658	671	13	2.0%
Management of Companies and Enterprises	1,726	1,048	-678	-39.3%
Administrative and Waste Services	561	1,407	846	150.8%
Educational Services	*	189	N/A	N/A
Health Care and Social Assistance	2,752	4,143	1,391	50.5%
Arts, Entertainment, and Recreation	105	552	447	425.7%
Accommodation and Food Services	2,455	2,998	543	22.1%
Other Services, Ex. Public Administration	732	922	109	26.0%
Unclassified	*	43	N/A	N/A
Government	5,301	6,436	1,135	21.4%
Total**	46,496	46,519	23	0.05%

Source: North Carolina Employment Security Commission (NCESC)

* - Indicates disclosure suppression

N/A - Not Applicable

** - 1990 total includes data for * sectors

Table 5 illustrates that North Carolina only lost employment in two industry sectors (manufacturing and utilities) between 1990 and 2002. As stated earlier, the loss in manufacturing for the State was less than that for Davidson County, but the utilities sector loss for the State was a larger percentage (-46.1%) than that of Davidson County (-22.8%). North Carolina employment sectors grew more rapidly (higher percent growth) than Davidson County in two-thirds of the industry sectors, with the most notable exceptions being Arts, Entertainment, and Recreation and Administrative and Waste Services.

Table 4. Employment By Sector Growth, North Carolina

Sector	Employment		Change, 1990-2002	
	1990	2002	#	%
Agriculture, Forestry, Fishing & Hunting	21,827	31,376	9,549	43.7%
Mining	3,993	4,203	210	5.3%
Utilities	26,626	14,342	-12,284	-46.1%
Construction	166,733	219,036	52,303	31.4%
Manufacturing	820,239	643,963	-176,276	-21.5%
Wholesale Trade	139,697	162,233	22,536	16.1%
Retail Trade	377,026	437,775	60,749	16.1%
Transportation and Warehousing	82,772	108,388	25,616	30.9%
Information	57,615	79,124	21,509	37.3%
Finance and Insurance	102,412	137,441	35,029	34.2%
Real Estate and Rental and Leasing	32,488	47,195	14,707	45.3%
Professional and Technical Services	89,618	146,022	56,404	62.9%
Management of Companies and Enterprises	35,104	63,565	28,461	81.1%
Administrative and Waste Services	108,590	207,329	98,739	90.9%
Educational Services	22,091	44,507	22,416	101.5%
Health Care and Social Assistance	203,641	350,934	147,293	72.3%
Arts, Entertainment, and Recreation	27,952	45,590	17,638	63.1%
Accommodation and Food Services	205,943	287,393	81,450	39.5%
Other Services, Ex. Public Administration	77,172	97,728	20,556	26.6%
Unclassified	*	9,515	N/A	N/A
Government	476,906	619,456	142,550	29.9%
Total**	3,079,017	3,757,115	678,098	22.0%

Source: North Carolina Employment Security Commission (NCESC)

* - Indicates disclosure suppression

N/A - Not Applicable

** - 1990 total includes data for * sectors

Transportation Plans

North Carolina Department of Transportation's Transportation Improvement Program projects in the GISA include (see Figure 1):

- **R-2568A** – Recently constructed interchange at NC 109 and Business 85.
- **R-2568C-F** – NC 109 widening to multi-lane facility from north of Old Greensboro Road to I-40/US 311 in Forsyth County. A bypass of Wallburg on new location is included. This project is currently in the planning phase, with construction to start in Post Years.
- **R-2808** – US 29-70 and I-85 Business. Upgrade, safety improvements, and replacement of 3 bridges. Bridges projects include B-2163 at SR 1627, B-3159 at US 29-64-70/I-85 Business Loop, and B-2832 at SR 1480 (Vickery Chapel Road). Construction to start in Post Years.
- **U-2537** – Westside Thoroughfare, I-85 to US 311 Bypass multi-lanes on new location. There is a Feasibility Study that was done in May of 1999, and an Environmental Impact Study is being prepared. Construction to start in Post Years.



The 2001 HPMPO Thoroughfare Plan shows TIP R-2568B as a proposed project. It also includes recommendations for the following projects, all of which are within the GISA:

- **NC 109 Connector** – an unfunded project that would connect NC 109 to the future Westside Thoroughfare via a new road that would follow Rich Creek.
- **West Loop** – an unfunded project that would start from the same intersection of the NC 109 Connector and NC 109; it would then loop to the west connecting to the intersection of Business 85 and Pilot School Road.
- **Midway School and Hasty School Connection** – unfunded and would realign Midway School Road to intersect with Hasty School Road.
- **Ballpark Road Extension** – unfunded project that would extend Ballpark Road to intersect with NC 109.
- **Unity Street Extension** – unfunded project to extend Unity Street to the intersection of Jacobs Street and Business 85.


Local Land Use Plans and Zoning

Existing Land Use

Most of the existing land use within the unincorporated portion of the GISA is either vacant or rural homesite (see Figure 3). There are several single family residential subdivisions along and near the area of Shady Grove Church Road and NC 109. Two newer residential subdivisions are on either side of Ledford Middle School at NC 109 and West Lexington Avenue. Several churches are located along NC 109 and scattered throughout the area. The larger industrial land uses are within the City of Thomasville and in the Jacob Street area. (Jacob Street is located north of Business 85 and west of NC 109). A few commercial land uses are located in the unincorporated portion of the GISA. Most of the commercial land uses are within the City of Thomasville along NC 68 or Main Street. A gas station/convenience store is located at the southwest corner of NC 109 and Midway School Road. Just north of Business 85 and west of NC 190 is a large parcel that is shown as an institutional land use, this is the city's golf course. Another golf course is located in the northeast portion of the GISA at Dorado Drive.

Davidson Forward, Davidson County Land Development Plan, November 2001

The Davidson Forward plan was developed because of the steady growth that Davidson had seen in the past 20 years and because of the continued anticipated growth for the future. The County is hoping to “foster and maintain a favorable business climate” and to help plan for how the community will grow. TIP R-2568B is identified in the Davidson Forward Plan as part of future improvements to transportation. A Development Area Suitability Map shows areas to the west of NC 109 and south of Old Greensboro Road as having the potential for future sewer service. Development in that area could be limited as a result of flood prone areas along Rich Fork Creek. The Abbotts Creek Water Supply Watershed III will also limit development densities to the north of Old Greensboro Road. The area east of NC 109 and south of Old Greensboro Road is shown as an existing sewer service area for the City of High Point, which has sewer trunk lines along Rich Creek, Rich Fork Creek, and Kennedy Mill Creek. Extension of these lines depends on



property owners signing voluntary annexation agreements with the City of High Point, and they must be located within their annexation boundary.

The plan includes a Land Development Strategy Map. It shows the area south of Old Greensboro Road and north of Thomasville as an Area of Traditional or Greenspace Development. This category is defined as allowing for a “traditional post war pattern” with 30,000-square foot suburban lots. It also provides an opportunity for greenspace preservation, where the overall development density remains at 30,000-square feet of land per dwelling unit, but the units are clustered on lots smaller than 30,000 square feet in order to preserve the remaining land as open space.

A Preferred Conservation area is shown along Rich Creek and Rich Fork Creek. The Preferred Conservation area is defined as “best left in a condition as close as possible to their natural state.” Lastly, the area north of Old Greensboro Road is shown as Preferred Rural/Agricultural Areas. This category is defined as an area that does not currently have water and sewer services, nor are there plans on providing these services within the next 20 years. Therefore, it is best “suited for rural and agricultural preservation.” Since the area north of Old Greensboro Road is also within Abbots Creek Water Supply Watershed III, the minimum lot size required is 40,000 square feet, and larger lot sizes are encouraged to help protect farming and prime farmland areas.

The Davidson Forward Plan also identifies Development Centers and Corridors. There is only one center within the GISA, a Commercial Service Center surrounding the intersection of NC 68 (National Highway) and Hasty School Road. This area already has commercial services with the potential to add more.

Northeast Davidson Area Plan, December, 2002

This plan covers the area east of Joe Morris Road and Chestnut Street in Davidson County. The plan identifies most of the land within this portion of the GISA as Future Growth. This category is for those areas that are too far away from existing utilities to consider them for future utilities or annexation. Densities within the Future Growth area would be very low. A small amount of Residential Low Density is within the GISA, just east of the Future Growth area and west of the future Westside Thoroughfare.

City of Thomasville Zoning, June 2004

Zoning along NC 109 within the Thomasville jurisdiction just south of R-2568B is residential with 15,000 square foot lots, the lowest density zoning category for Thomasville (see Figure 4). Land further west of NC 109 is zoned as Industrial, both to the north and south of Business 85. Land to the east of NC 109 is mostly zoned as R-10, except for the areas along Ball Park Road, which are zoned as Industrial, and the areas along NC 68, which are zoned as Commercial.

Davidson County Zoning, June 2004

Most of the zoning within the unincorporated Davidson County portion of the GISA is designated as Rural Agriculture, with some Low Density Residential districts and small pockets of Medium to High Density Residential districts (see Figure 4). There is some





FIGURE 4 - ZONING

- TIP R-2568B
- RIVERS
- WATER BODIES
- COUNTY BOUNDARIES
- GROWTH IMPACT STUDY AREA
- MUNICIPALITIES
- RURAL AGRICULTURE
- LOW DENSITY RESIDENTIAL
- MEDIUM-HIGH DENSITY RESIDENTIAL
- R-15 (15,000 SQUARE FOOT LOTS)
- R-10 (10,000 SQUARE FOOT LOTS)
- R-8 (8,000 SQUARE FOOT LOTS)
- R-6 (6,000 SQUARE FOOT LOTS)
- COMMERCIAL
- INDUSTRIAL
- OFFICE/INSTITUTIONAL

1 0.5 0 1 Miles

MAP SOURCES:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
ENVIRONMENTAL SYSTEMS RESEARCH INSTITUTE (ESRI)
US CENSUS BUREAU
DAVIDSON COUNTY
HIGH POINT
THOMASVILLE
HNTB NORTH CAROLINA, P.C.



Office/Institutional zoning along John Green Road, W. Lexington Avenue and NC 109, as well as Hasty School Road and Roselynn Lane. Commercial zoning is scattered on mostly small sites throughout the GISA, with the largest cluster along NC 68 near the county border.

Environmental Regulations

State Regulations

North Carolina Division of Land Resources - Sediment and Erosion Control Act

This act requires that any person planning to disturb more than one acre of land within the State of North Carolina must submit a Sedimentation and Erosion Control Plan to the Division of Land Resources. Local governments may review and enforce the program within their jurisdiction, but the program has to be as strict as the Division of Land Resources program.

The TIP R-2568B GISA falls within the Yadkin River Basin. A search using NCDOT Statewide Planning GIS information reveals that the Abbotts Creek Water Supply (WS) III Watershed is within the GISA (see Figure 5). According to State regulations, within WS-III Watersheds, development regulations allow for a residential density of approximately two dwelling units per acre. For other residential (multi-family) and non-residential development, the built-upon area cannot exceed 50%. The 10/70 provision is permitted within this classification of water supply watershed, which allows 10% of the balance of the watershed to be developed at a 70% built-upon rate.

A small portion of Abbotts Creek WS III Watershed critical area is within the GISA, just west of R-2568B. Residential development can take place within the critical area at one unit per acre for single family dwellings (40,000 square feet excluding roadway right-of-way). For other residential (multi-family) and non-residential development, the built-upon area cannot exceed 30%.

According to the National Wetland Inventory GIS information, there are wetlands along Rich Creek, Rich Fork Creek, Kennedy Mill Creek, Hunts Fork Creek, and Abbotts Creek. Other small wetland areas are scattered throughout the GISA (see Figure 5). According to the March 1997 NCDOT Best Management Practices For Protection of Surface Waters report, BMPs include activities, practices, and procedures undertaken to prevent or reduce water pollution, such as: on-site detention areas, vegetative buffers, culverts, and erosion control.

The 303(d) list is a product of the Clean Water Act, which requires states to identify those waters that do not meet water quality standards, or those that have impaired uses. If control strategies for point and non-point source pollution exist for impaired waters, they may be excluded from the 303(d) list.

There are three 303(d) waterbodies within the GISA for TIP R-2568B. NCDOT Transportation Planning Branch GIS information shows Rich Fork as a 303d impaired





FIGURE 5 - ENVIRONMENTAL FEATURES

- TIP R-2568B
- RIVERS
- WATER BODIES
- COUNTY BOUNDARIES
- MUNICIPALITIES
- GROWTH IMPACT STUDY AREA
- 303D LIST
- ▨ 100 YEAR FLOOD ZONE
- WETLANDS
- WATER SUPPLY WATERSHED IV**
 - DEEP RIVER (RANDLEMAN LAKE)
 - EAST FORK DEEP RIVER (HIGH POINT LAKE)
 - WEST FORK DEEP RIVER
- WATER SUPPLY WATERSHED III**
 - ABBOTTS CREEK
 - LEONARD CREEK
 - UWHARRIE RIVER (LAKE REESE)
 - CRITICAL AREA

1 0.5 0 1 Miles

MAP SOURCES:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
ENVIRONMENTAL SYSTEMS RESEARCH INSTITUTE (ESRI)
US CENSUS BUREAU
DAVIDSON COUNTY
HIGH POINT
HNTB NORTH CAROLINA, P.C.
NATIONAL WETLANDS INVENTORY



water from its source to Abbotts Creek (see Figure 5). It is considered Class C with a low priority. The cause for impairment is listed as fecal coliform, and the length of the impaired water is 20.7 miles. Hunts Fork Creek is also a 303(d) water from its source to Rich Fork Creek, and is Class C with a low priority. The cause for impairment is listed as unknown, and the length of the impaired water is 7.5 miles. Lastly, North Hamby Creek is also a 303(d) water from its source to Hamby Creek, and is considered a Class C with a low priority. The cause for impairment is unknown, and the length of the impaired water is 6.1 miles.

Local Regulations

In addition to State regulations, Davidson County only allows one dwelling unit per acre for a single family residential development with no lots less than 40,000 square feet for those areas within the WS-III Watersheds. For other residential and non-residential development the built-upon area cannot exceed 24%. Although, 10% of the balance watershed can be developed at a 70% built-upon rate when the County approves a special non-residential intensity allocation (SNIA). A small portion of Abbotts Creek Critical area is within the GISA, to the west of R-2568B. Development can take place within the critical area at one unit per acre for single family residential (40,000 square feet excluding roadway right-of-way) and for other residential and non-residential the built-upon area cannot exceed 12%.

Future development within the City of Thomasville and Davidson County which might result from the completion of the project will be governed by the provisions of the Davidson County Watershed Protection Ordinances. Mechanisms included in this ordinance are 50-foot vegetative buffer along all perennial waters, impervious surface limits, density limits, storm water management regulations, and other Best Management Practices (BMP's). Furthermore, the City of Thomasville requires that a small amount of open space be dedicated per residential subdivision

V. INVENTORY OF NOTABLE FEATURES

This section is based on review of the Geographic Information System (GIS) data provided by the Transportation Planning Branch of the NCDOT, and a database search of the TIP R-2568B GISA (see Appendix). Among other things, the inventory identifies federally-protected species and natural communities that are found within the USGS Quads that encompass the GISA.

VI. ACTIVITIES THAT CAUSE EFFECTS

Previous Conclusions

Environmental Assessment (EA), November 1996

According to the EA for R-2568 A and B, a No Build Alternative Transportation System Management Alternative, Mass Transit Alternative, and two Build Alternatives (1 & 2)

were analyzed. Alternate 1 was a widening of existing NC 109 to four-lanes with a center turn lane, while Alternative 2 was a combination of widening existing NC 109 to four-lanes with a center median and partial construction on new location. Alternative 2 had less impacts to the urban environment than Alternative 1, but Alternative 2 had more impacts to the natural environment. Alternative 2 was chosen as the Preferred Alternative because “it will provide the operational advantages of a four-lane divided roadway while its cost and impacts are very similar to Alternative 1.” Specific indirect and cumulative effects were not disclosed.

According to the EA, the Schweinitz’s sunflower is the only federally-protected species found in Davidson County, and the initial biological conclusion was no effect for the TIP R-2568 A & B project area. After further discussions with NCDOT Natural Systems staff, a request was submitted to change the “no effect” to “may effect, but not likely to adversely effect.”

Finding of No Significant Impact (FONSI), August 1997

The FONSI for TIP R-2568 A and B stated that there would be 1.14 acres of wetland impacts and there would be no effect upon archaeological or historic architecture resources within the TIP project corridor. The removal of two underground storage tanks would also be required. The relocation of 21 residences and 1 business will occur from the project. Prime farmland should not be impacted, but 16.6 acres of farmland that is considered statewide or of local importance will be converted within the TIP project area. Direct impacts to natural resources within the TIP corridor will affect 45.1 acres of maintained habitat, 61.1 acres of dry mesic oak-hickory forest, 2.4 acres of bottomland hardwood forest, and 2.7 acres of alluvial forest. Specific indirect and cumulative effects were not disclosed.

Development Trends

According to local planners, there are no new major developments planned within the GISA. New residential growth is occurring in the western portion of Thomasville where sewer lines have recently been extended. Recent residential development also has been occurring on the northern edge of Thomasville in the area of Hasty School Road. Unilin, a large flooring manufacturer, is building a new plant outside of the GISA on land bounded by I-85 and NC 62 just west of the Randolph County border. This development could influence additional commercial as well as residential growth within the GISA.

VII. POTENTIAL INDIRECT AND CUMULATIVE EFFECTS

The North Carolina DOT, in their April 2001 handbook titled “*Guidance for Assessing Indirect and Cumulative Impacts of Transportation Projects in North Carolina*,” outline a set of factors that need to be evaluated to determine whether or not a more detailed indirect and cumulative impact analysis (ICI) may be necessary for specific projects. The following is an assessment of those factors as they relate to TIP R-2568B.

Conflict with local plan:

TIP R-2568B is consistent with the HPMPO's High Point Urbanized Area Thoroughfare Plan, the Northeast Davidson Area Plan, and the Davidson Forward Plan, all of which indicate the project as being needed.

Explicit economic development purpose:

There is no explicit economic development purpose associated with TIP R-2568B. According to local planners, the project serves more of a safety purpose. The project will improve the geometrics, alignment, and blind intersections to reduce the number of accidents along NC 109.

Planned to serve specific development:

As stated above, the purpose for TIP R-2568B is to improve safety and increase capacity. The project is not planned to serve a specific development.

Likely to stimulate land development having complementary functions:

The assessment of this factor involves the evaluation of a subset of factors related to location and infrastructure. This subset includes:

- Distance to a major urban center
- Traffic volumes on intersecting roadways
- Presence of frontage roads
- Availability of water/sewer

This project is located near several major urban centers, including the City of Winston-Salem, which is located about 18 miles to the northwest, the City of High Point, which is approximately six miles to the east, the City of Greensboro, which is 20 miles to the east, and the City of Thomasville, which borders the southern terminus of the project. NCDOT Transportation Planning Branch indicates that 2020 traffic volumes on Midway School Road are projected to be 11,000 Average Daily Trips (ADT), while Hasty School Road will be 6,500 ADT, Burton Road will be 1,300 ADT, and Old Greensboro Road will be 7,600 ADT.

There are no plans to include frontage roads as part of TIP R-2568B.

Water and sewer services are provided within the southern portion of the GISA, predominantly within Thomasville or just outside of its city limits (see Figure 6). A voluntary annexation agreement is required for those parcels to receive sewer service outside of the city boundaries. Sewer is also available from High Point, which has existing sewer trunk lines along Rich Creek, Rich Fork Creek, and Kennedy Mill Creek all starting from the Westside Sewer Treatment Plant on Kennedy Mill Creek. The city is willing to extend services to the edge of its annexation boundary and a voluntary annexation agreement is also required for connection.

Based on this assessment, even though there are several major urban centers nearby, water and sewer service is only available in the already developed areas of Thomasville,





FIGURE 6 - NOTABLE FEATURES

- TIP R-2568B
- HIGHWAYS
- ROADS
- RAILROADS
- RIVERS
- WATER BODIES
- COUNTY BOUNDARIES
- GROWTH IMPACT STUDY AREA
- USGS QUADS
- NATIONAL REGISTER STRUCTURES
- NATIONAL REGISTER DISTRICT
- HIGH POINT ANNEXATION BOUNDARY
- ▲ WESTSIDE SEWER TREATMENT PLANT
- THOMASVILLE UTILITIES**
- SEWER LINES
- WATER LINES

1 0.5 0 1 Miles

MAP SOURCES:
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
ENVIRONMENTAL SYSTEMS RESEARCH INSTITUTE (ESRI)
US CENSUS BUREAU
DAVIDSON COUNTY
HIGH POINT
THOMASVILLE
HNTB NORTH CAROLINA, P.C.





and there are low traffic volumes on intersecting roadways. Thus, TIP R-2568B has a low potential to stimulate complementary land development.

Likely to influence intraregional land development location decisions:

Typically, if the conditions are favorable for development and/or a region is currently undergoing urbanization, an improvement in the transportation infrastructure is likely to influence where development will occur. In this case, land to the south of TIP R-2568B within Thomasville is already developed, but in the immediate vicinity of the project and to the north, land is less developed. Thomasville and Davidson County planners indicated that they do not believe TIP R-2568B will influence growth for the area. They see the project more as a safety improvement and believe that where sewer is extended will be much more influential upon new growth.

Notable feature present in Growth Impact Study Area:

There are five state or federally protected species present in the two USGS quadrants (Midway and High Point West) that encompass the GISA and there is one species that is mentioned within the EA (see Figure 6). There are no superfund sites. There are six National Register structures, and two National Register districts within the GISA including Brummel's Inn, a former stage coach stop. Also, there are three 303(d) streams, which include Rich Creek, Hunts Fork Creek, and North Hamby Creek. A small portion of Abbotts Creek WS III Watershed critical area is within the GISA

Notable feature impacted:

Since minimal induced development growth is anticipated from R-2568B, and the exact location of federally protected species within the GISA is unknown, it is difficult to assess impacts to federally protected species at this time. The National Register structures and districts are not anticipated to be affected because they are not within anticipated growth areas. It is unlikely that the 303(d) streams or the critical area of Abbotts Creek WS III Watershed will be impacted from the small amount of indirect growth that may occur from TIP R-2568B.

VIII. ANALYSIS OF INDIRECT AND CUMULATIVE EFFECTS

To further determine what the potential extent of indirect and cumulative effects will be as a result of TIP R-2568B, an analysis of a set of environmental and economic conditions was completed. This analysis attempts to somewhat quantify the potential for land use change over the 20-year timeframe. A strong rating indicates a high likelihood of land use change related to transportation investments. Table 6 indicates the results of this rating analysis.



Table 6. Potential for Land Use Change, 2000-2020

Rating	Change in Accessibility	Change in Property Values	Forecasted Growth	Land Supply vs. Demand	Water/Sewer Availability	Market For Development	Public Policy
Strong	Travel Time Savings > 10 min.	> 50% Increase	> 3% Annual Pop. Growth	< 10-Year Supply of Land	Current Services Exist	Extremely High Potential	Less Stringent; No Growth Management
^							
"							X
"							
"	X	X	X		X	X	
"				X			
Weak	Travel Time Savings < 2 min.	No Change	< 1% Annual Pop. Growth	> 20-Year Supply of Land	No Plans For Future Service	Extremely Low Potential	More Stringent; Growth Management

Amount of Potential Land Use Change

Travel time savings as a result of TIP R-2568B is anticipated to be low, much closer to two minutes than five minutes for the duration of the project length. Any existing or future development on the parcels fronting the new location portion of the project should experience the largest improvement in accessibility, since previously they would have not had direct access to a major thoroughfare. Property values may increase for parcels fronting the new alignment; otherwise, little change is anticipated. The projected annual growth rate for Davidson County from 2000 to 2010 is 1.3%, which is considered weak. The Demographic Area and GISA should continue to experience low growth rates whether R-2568B is built or not. Since growth has been relatively slow over the last decade, developable land is abundant.

Water and sewer service is available within the southern portion of the GISA, mostly within the City of Thomasville. Water and sewer will most likely be extended to those areas closest to Thomasville as development occurs and they are annexed. High Point could also potentially extend their water and sewer lines to the western portion of their annexation boundary (see Figure 6).

Local planners and population/employment growth trends indicate that the market for development is relatively low within the GISA. Local government zoning and land use plans support growth, but do limit development densities in certain areas, particularly within the water supply watershed. Furthermore, as mentioned before, the City of Thomasville requires that a small amount of open space be dedicated per residential subdivision.

Location of Potential Land Use Change

The majority of the land within the GISA north of Midway School Road (SR 1800) is agriculture, open fields, forests, or residential in nature, while south of Midway School Road in Thomasville land is a mixture of industrial, commercial, office, and residential uses. Because of the large amount of agriculture, open fields, and forests, a majority of the land north of the City of Thomasville is available for future development, (see Figure 3). There are some larger residential subdivisions that are along Shady Grove Church Road, a few along NC 109, and a few others scattered throughout the GISA. But mainly there are scattered houses along the main roadways.



Midway School Road, Looking East Where The New NC 109 Will Cross

The greatest potential for induced commercial growth is at the new intersection of NC 109 and Midway School Road. This location is the only major new intersection created by the portion of NC 109 that is on new alignment, and developable land will be available at this intersection. Midway School Road is also a main route to the west, and will connect to existing NC 109 to the east as well. Both sides of Midway School Road, just west of existing NC 109 are designated as potential Sewer Service Area.

Development throughout the area is restricted by very hilly terrain with steep slopes and poor soils for septic tanks. Therefore, potential for induced residential growth is minimal, with most development still dependent upon sewer service. Areas along the periphery of Thomasville where sewer can be extended are the most likely candidates for any type of residential development resulting from the new project.



Example of Rural Housing North of Midway School Road

IX. EVALUATION OF ANALYSIS RESULTS

Consideration of Indirect Effects

Change in accessibility and mobility as a result of TIP R-2568B will be minimal, except for those parcels that gain new road frontage. Population growth within Davidson County should continue at rates just above 1% annually, therefore keeping demand for developable land in the area low. A generally weak market for development within the GISA limits the potential for land use change as a result of TIP R-2568B.

The most likely area for commercial or residential growth as a result of TIP R-2568B is at the new intersection of NC 109 and Midway School Road. Any growth surrounding this intersection is unlikely to have indirect effects on water quality and/or National Register structures or districts within the GISA. Since little induced growth is anticipated



from R-2568B, it is also unlikely that the federally protected species and 303(d) streams will be impacted. In addition, the aforementioned state and local environmental regulations would mitigate any potential effects incurred.

TIP R-2568B may induce some residential development on land that is provided new road access along the project corridor, particularly within the northern portion of the GISA closer to Winston-Salem. Future commercial growth is more likely to develop in the southern portion of the GISA closer to Thomasville and the Business 85 and I-85 corridors.

Consideration of Cumulative Effects

TIP R-2568's proximity to two major urban centers (High Point and Winston-Salem) solidifies its potential as a future residential/commercial development corridor, particularly when considered with the fact that expansion of public sewer service within portions of the GISA is possible. TIP R-2568B, when combined with all of the other transportation projects within or partially within the GISA, may improve access to the regional interstate network (I-85, I-40, future I-73/74 corridor), creating opportunities for industrial/distribution-related development.

The cumulative impact of TIP R-2568B increases when considered along with TIP R-2568 C-G and TIP U-2537 (Westside Thoroughfare). By improving regional accessibility throughout the eastern portion of Davidson County and the western portion of High Point and serving commuters with destinations of employment centers in Winston-Salem, an increase in residential development may result in northern Davidson County.

Factors used to evaluate indirect and cumulative impacts indicate that the potential for land use change resulting from Tip R-2568B alone is relatively weak. Therefore, it is unlikely that TIP R-2568B will cause substantial indirect impacts to water quality. Some development is already occurring within the GISA, and this project is unlikely to induce new development without other contributing factors, such as public utility extensions or connecting roadway improvements.

APPENDIX
Notable Features Tables
Davidson County / R-2568B

State and Federally-Protected Species

Common Name	Scientific Name	Federal Status	State Status	USGS Quad Map
Plant:				
Dissected Toothwort	<i>Cardamine dissecta</i>	-	SR-P	Midway
Heller's Rabbit Tobacco	<i>Gnaphalium helleri</i> var <i>helleri</i>	-	SR-P	Midway
Carolina Birdfoot-trefoil	<i>Lotus helleri</i>	FSC	SR-T	Midway
Schweinitz's sunflower*	<i>Helianthus schweinitzii</i>	E	N/A	N/A
Reptile:				
Bog Turtle	<i>Glyptemys muhlenbergii</i>	T (S/A)	T	Midway
Crustacean				
Greensboro Burrowing Crayfish	<i>Cambarus catagius</i>	-	SC	High Point West

Source: North Carolina National Heritage Program, Midway and High Point West USGS topographic quadrangles (June 2004) <http://ils.unc.edu/parkingproject/nhp>

*North Carolina Department of Transportation, Planning and Environmental Branch, Environmental Assessment, Davidson County, North Carolina, TIP No. R-2568A and B, November, 1996.

Natural Communities

Name	USGS Quad Map
Basic Mesic Forest (Piedmont Subtype)	Midway
Piedmont/Low Mountain Alluvial Forest	Midway

Source: North Carolina National Heritage Program, Midway and High Point West USGS topographic quadrangles (June 2004) <http://ils.unc.edu/parkingproject/nhp>

**Architectural Features and Historic Sites
in Growth Impact Study Area**

Name	Address	Status
Bethany Reformed & Lutheran Church Cemetery	Old Thomasville Road & Bethany Church Road	National Register Structure
Brummel's Inn	West Lexington Avenue, east of NC 109	National Register District
Church Street School	Jasper Street, west of Church Street	National Register Structure
Mitchell House	411 Biggs Avenue, Thomasville	National Register
Smith Clinic	17 Randolph Street, Thomasville	National Register Structure
Adam Spach Rock House Site (Archaeology)	Friedberg Vicinty (near Winston-Salem)	National Register
Thomasville Railroad Passenger Depot	West Main Street, Thomasville	National Register Structure
Thomasville Historic District		

Source: NCDOT – Transportation Planning Branch (Last updated June 2003).

North Carolina State Office of Historic Preservation (May 2003), <http://www.hpo.dcr.state.nc.us/>



**Solid Waste Facilities
Davidson County in Growth Impact Study Area**

Permit	Name	Type	Location	Contact
29A	Hill & Sons Demo Site	LCID	Midway Township	Phillip Hill Route 11 Box 297 B Winston-Salem, NC 27107

Source: North Carolina Department of Environmental and Natural Resources, Davidson County (Last updated October 2003), http://wastenot.enr.state.nc.us/DATARPTS2003_3ColA.HTM.

Streams and Water Quality in Growth Impact Study Area

Stream	Affected Portion	Water Classification	Cause of Impairment	Priority
Rich Fork	From its source to Abbotts Creek	C	Fecal coliform	Low
Hunts Fork	From its source to Rich Ford	C	Unknown	Low
North Hamby Creek	From its source to Hamby Creek	C	Unknown	Low

Source: North Carolina Department of Transportation – Transportation Planning Branch (August 2001)

**Potential Hazardous Material Sites
Underground Storage Tank (UST) Locations
Davidson County**

UST Name	Location
Big R North	1269 N. NC Highway 109, Thomasville, NC
Big R Pilot - B	4279 Old Highway 29, Thomasville, NC
Coastal Mart #441	1032 Randolph Street, Thomasville, NC
Country Food Mart	610 Jacob Street, Thomasville, NC
Etna #491	705 National Hwy., Thomasville, NC
Henderson Property, Tyrone	622 Nance Drive, Thomasville, NC
Hicks Grocery And Service	10693 E. Highway 64, Thomasville, NC
Leonard Block Company	2390 Midway School
Thomasville - Public Works Building	512 Doak Street, Thomasville, NC
Wilson Property, Robert	622 Nance Drive, Thomasville, NC

Source: North Carolina Department of Environmental and Natural Resources, October 2003,
<http://www.enr.state.nc.us/>

BIBLIOGRAPHY

Davidson County, Davidson Forward, Davidson County Land Development Plan, Adopted November 2001.

Davidson County, Watershed Protection Ordinance, Adopted December 1993.

Davidson County, Zoning Ordinance, Adopted December 1993, Last Amended December 8, 2003.

High Point Urban Area Metropolitan Planning Organization, High Point Urbanized Area Thoroughfare Plan, <http://www.hpdot.net/HPMPO/plans/thoroughfare.htm>, internet accessed June 2004.

National Cooperative Highway Research Program, Guidebook for Assessing the Social and Economic Effects of Transportation Projects, NCHRP Report 456, Washington, D.C., 2001.

North Carolina Department of Environment and Natural Resources, Division of Water Quality, Water Quality Section, Total Maximum Daily Loads for Fecal Coliform for Rich Fork Creek and Hamby Creek, North Carolina [Waterbody ID 12-119-7 and Waterbody ID 12-119-7-4], Final Report April 2004, Yadkin-Pee Dee River Basin, <http://h2o.enr.state.nc.us/tmdl/documents/RichForkCreekandHambyCreekFecalColiformTMDLsApprovedFinalReport.pdf>, approved April 2004.

North Carolina Department of Environment and Natural Resources (DENR), Water Supply Watersheds and 303d List of Impaired Water Bodies, available from www.enr.state.nc.us

North Carolina Employment Security Commission, www.ncesc.com, 1990 and 2002.

North Carolina Department of Transportation, Planning and Environmental Branch, Environmental Assessment for NC 109 from I-85 Business to just North of SR 1798, Davidson County, North Carolina, TIP No. R-2568A and B, State Project No. 8.160901, November, 1996.

North Carolina Department of Transportation, Planning and Environmental Branch, Finding of No Significant Impact for NC 109 from I-85 Business to just North of SR 1798, Davidson County, North Carolina, TIP No. R-2568A and B, State Project No. 8.160901, August, 1997.

North Carolina State Demographics, <http://demog.state.nc.us/>, 2010, 2020 County and State Population Data/Forecasts.



The Louis Berger Group, Inc., Volume II Practitioner's Handbook "Guidance for Assessing Indirect and Cumulative Impacts of Transportation Projects in North Carolina", p. III-56–III-64, issued November 2001.

US Census Bureau, www.census.gov, 1990 and 2000.

U.S. Fish and Wildlife Service, National Wetlands Inventory; Available from <http://www.nwi.fws.gov/index.html> , accessed June, 2004.

